DOCKETED	
Docket Number:	25-OPT-02
Project Title:	Prairie Song Reliability Project
TN #:	264401
Document Title:	App 3-4A Geological Appendix
Description:	N/A
Filer:	Erin Phillips
Organization:	Dudek
Submitter Role:	Applicant Consultant
Submission Date:	6/20/2025 1:36:07 PM
Docketed Date:	6/20/2025

Appendix 3.4A Geotechnical Engineering Report

Prairie Song Reliability Project Geotechnical Engineering Report

May 14, 2025 | Terracon Project No. LA245085

Prepared for:

Prairie Song Reliability Project, LLC



Nationwide Terracon.com Facilities
Environmental
Geotechnical
Materials



145 W Walnut St. Gardena, CA 90248 P (949) 261-0051 Terracon.com

March 25, 2025, revised April 11, 2025, May 14, 2025

Prairie	Song	g Relia	ability	, LLC	_	
Attn:	-					
	E:					

Re: Geotechnical Engineering Report Prairie Song Reliability Project Acton, Los Angeles County, California Terracon Project No. LA245085

Dear Mr. Lehman:

We have completed the scope of Geotechnical Engineering services for the above referenced project in general accordance with Terracon Proposal No. PLA245085 dated May 15, 2024, between Prairie Song Reliability, LLC and Terracon Consultants, Inc. (Terracon). This report presents the findings of the subsurface exploration and provides geotechnical recommendations concerning earthwork and the design and construction of pavements and foundations for the proposed Battery Energy Storage Systems (BESS) and substation facility.

We appreciate the opportunity to be of service to you on this project. If you have any questions concerning this report or if we may be of further service, please contact us.

Sincerely,

Terracon

-anna Valdez

Janna Valdez, E.I.T. Senior Staff Engineer

Joshua R. Morgan, P.E. Department Regional Manager





Table of Contents

Introduction1
Project Description
Site Conditions
Geotechnical Characterization
Subsurface Conditions
Lab Results
Groundwater
Seismic Site Class
Faulting and Estimated Ground Motions10
Liquefaction
Corrosivity
Electrical Resistivity Testing
Thermal Resistivity Testing
Geotechnical Overview
Earthwork
Site Preparation
Subgrade Preparation
Excavation
Site Slopes
Fill Material and Placement
Compaction Requirements19
Utility Trench Backfill
Grading and Drainage
Exterior Slab Design and Construction
Earthwork Construction Considerations
Construction Observation and Testing
Shallow Foundations
Shallow Foundation Design Recommendations
Lateral Earth Pressures
Design Parameters
Deep Foundations
Drilled Shaft Design Recommendations
Drilled Shaft Axial Loading
Drilled Shaft Lateral Loading - LPILE Parameters
Drilled Shaft Construction Considerations
Driven Pile Design Parameters
Driven Piles Construction Considerations
Gravel-Surfaced Drives and Parking
Roadway Subgrades
Design Parameters
Access Road Sections



Roadway Design and Construction Considerations	32
Pavements	33
General Pavement Comments	33
Pavement Design Parameters	33
Pavement Section Thicknesses	33
Pavement Drainage	34
Pavement Maintenance	34
General Comments	35

Figures

GeoModel

Attachments

Exploration and Testing Procedures Site Location and Exploration Plans Exploration and Laboratory Results Supporting Information

Note: This report was originally delivered in a web-based format. Blue Bold text in the report indicates a referenced section heading. The PDF version also includes hyperlinks which direct the reader to that section and clicking on the **pierracon** logo will bring you back to this page. For more interactive features, please view your project online at client.terracon.com.

Refer to each individual Attachment for a listing of contents.



Introduction

This report presents the results of our subsurface exploration and Geotechnical Engineering services performed for the proposed Battery Energy Storage System (BESS) and Substation facility to be located north and south of Soledad Canyon Road in Acton, Los Angeles County, California. The purpose of these services was to provide information and geotechnical engineering recommendations relative to:

- Subsurface soil conditions
- Groundwater conditions
- Seismic site classification per CBC
- Site preparation and earthwork
- Foundation design and construction
- Access roadway design and construction
- Infiltration design rates

The geotechnical engineering Scope of Services for this project included the advancement of test borings, electrical resistivity testing, laboratory testing, engineering analysis, and preparation of this report. The geotechnical engineering Scope of Services for our current scope of work included the following:

- Fifteen (15) soil test borings to approximately 21 to 51.5 below ground surface (bgs) in the proposed BESS areas
- Two (2) soil test borings to approximately 51.5 feet bgs in the proposed substation area
- Two (2) soil test borings to approximately 21.5 feet bgs in the proposed Operations and Maintenance (O&M) building area
- Seven (7) soil test borings to approximately 51.5 feet bgs along the transmission line
- Four (4) percolation tests at approximately 3 and 5 feet bgs in the proposed basin area
- Corrosion testing on soil samples obtained from seven (7) locations
- Field electrical resistivity tests at seven (7) locations
- Lab thermal resistivity testing on soil samples obtained from four (4) locations.

Drawings showing the site, borings, percolation testing, and electrical resistivity locations are shown on the Site Location and Exploration Plan, respectively. The results of the laboratory testing performed on soil samples obtained from the site during our field exploration are included on the boring logs and/or as separate graphs in the Exploration Results section.



Project Description

Our initial understanding of the project was provided in our proposal and was discussed during project planning. A period of collaboration has transpired since the project was initiated, and our final understanding of the project conditions is as follows:

Item	Description
Previous Submittals	A letter titled "Geotechnical Percolation Test Letter Prairie Song Reliability Project " was provided to Prairie Song Reliability Project, LLC by Terracon on January 22, 2025. The letter describes the percolation test procedures and results that was conducted by Terracon for the design of the proposed basin. Recommendations and limitations for stormwater management provided in the referenced letter remain valid and applicable for the proposed project except where superseded or identified herein.
Information Provided	An email request for proposal was provided by Matt McCaffrey on March 29, 2024. A site boundary Google Earth file and a conceptual site plan for the proposed BESS and substation was provided at the time of the request. Subsequently, a Google Earth file of the proposed overhead transmission line was provided on November 22, 2024.
Project Description	The project consists of a proposed BESS, substation, stormwater basin, O&M Building, two 40k gal water tanks (estimated to be 16 feet tall by 33 feet in diameter), and transmission line. Based on our review of the conceptual site plan, the project parcel will encompass an approximate footprint of 65 acres. The BESS and substation facility will encompass an approximate footprint of 35 and 6 acres, respectively. Furthermore, an approximately 2 miles overhead 500 kV transmission line will connect with the proposed substation.
Proposed Foundation Structure	We anticipate that the proposed BESS will consist of battery storage units supported by mat foundations, driven piles, or drilled shafts. We anticipate the substation will include control room building, self- contained structures, and other substation elements to be supported on shallow spread footings, equipment slabs-on-grade/mat foundations, and/or drilled shafts. We anticipate that the proposed O&M building and water tanks will be supported by a spread footing foundation system with concrete slabs on grade. We anticipate that the overhead transmission line will be supported on drilled shaft foundations.

Prairie Song Reliability Project | Acton, Los Angeles County, California





Item	Description		
Item	 Structural loads for the BESS, substation, and O&M structures were provided and are listed below: BESS: BESS enclosure pads: 1000 to 1200 psf contact pressure BESS Axial Load: 94 kips BESS Shear Load: 79 kips Substation: GSU Foundation: 2,000 to 2,500 psf Control Room: 1 to 3 kips per linear foot (klf) Tubular steel (A-frames) - drilled piers: Substation Axial Load: 120 kips Substation Shear Load: 30 kips Other steel - drilled piers: Substation Axial Load: 15 kips Substation Shear Load: 5 kips O&M Building Walls: 1 to 3 kips klf O&M columns: 30 to 60 kips Structural loads for the transmission line and water tank structures were not provided and have been estimated below: Transmission Line: Axial: less than 10 kips Shear: less than 5 kips 		
	 <u>Water tanks:</u> 1,000 psf contact pressure 		

Prairie Song Reliability Project | Acton, Los Angeles County, California

May 14, 2025 | Terracon Project No. LA245085



Item	Description
Grading/Slopes	 The site has a slight slope, on the order of 5%. We assume that the site will be terraced, and minimal grading will be used to level the site. We anticipate that the battery containers, water tanks, and O&M building will generally follow the existing site grades with cut/fill on the order of 1 to 2 feet to bring the site to finished grades. We anticipate cut/fill on the order of 3 to 4 feet to bring the substation area to finish grade Furthermore, a 3H: 1V to 5H: 1V slope is located south of the southern perimeter of the site descending towards the existing train tracks and W Carson Mesa Road. We assume that the proposed structures will have a set setback distance, sufficient enough that slope stability analysis is not required for the site. Details of required setbacks are included in this report.
Infiltration System	We understand that an infiltration system consisting of an underground retention/detention basin will be planned on-site. A percolation test letter was provided previously.
Access Roadways	We understand that access road cross sections used for construction of the project will be the responsibility of Prairie Song Reliability Project. We anticipate low-volume access roads will have a maximum vehicle load of 10,000 lbs. and will travel over the access roads only once per week during operation. Moreover, we anticipate all-weather access roads will be required to access the project substation. Such roads should be designed to support a firetruck weighing approximately 75,000 lbs. Furthermore, based on input from the client, approximately 80,000 to 90,000 lbs trucks and cranes will travel through the access roads every 5 years.

Terracon should be notified if any of the above information is inconsistent with the planned construction, especially the grading limits, as modifications to our recommendations may be necessary.

Site Conditions

The following description of site conditions is derived from our site visit in association with the field exploration and our review of publicly available geologic and topographic maps.

Prairie Song Reliability Project | Acton, Los Angeles County, California May 14, 2025 | Terracon Project No. LA245085



Item	Description
Parcel Information	The project is located north and south of Soledad Canyon Road in Acton, Los Angeles County, California. The project site encompasses a total area of approximately 65 acres. The coordinates of the approximate center of the site are 34.4858° N, 118.1383° W.
Existing Improvements	The site is primarily in an undeveloped state, with several residential properties dispersed across the area. Located approximately 100 feet from the proposed BESS development, an existing railroad traverses parallel to the southern perimeter of the property.
Current Ground Cover	The majority of the surface of the site is covered by exposed soils with dense desert vegetation.
Existing Topography	The parcels north and south of Soledad Canyon Rd have an approximately 4% slope increasing from the southwest to the northeast direction. The approximate elevations of the site range from 2,980 to 3,140. The proposed transmission line will traverse flat terrains and rolling hill topographies and the elevation at the proposed towers ranges from 3010 to 3125 feet.

Geotechnical Characterization

Subsurface Conditions

We have developed a general characterization of the subsurface conditions based upon our review of the subsurface exploration, laboratory data, geologic setting and our understanding of the project. This characterization, termed GeoModel, forms the basis of our geotechnical calculations and evaluation of the site. Conditions observed at each exploration point are indicated on the individual logs. The individual logs can be found in the Exploration Results and the GeoModel can be found in the Figures attachment of this report.

As part of our analyses, we identified the following model layers within the subsurface profile. For a more detailed view of the model layer depths at each boring location, refer to the GeoModel.

Prairie Song Reliability Project | Acton, Los Angeles County, California May 14, 2025 | Terracon Project No. LA245085



Model Layer	Layer Name	Consistency/Density
1	Sand with varying amounts of silt, clay, and gravel	loose to medium dense
2	Sand with varying amounts of silt, clay, and gravel	medium dense to very dense

The geotechnical characterization forms the basis of our geotechnical calculations and evaluation of site preparation and foundation options. As noted in General Comments, the characterization is based upon widely spaced exploration points across the site, and variations are likely.

Lab Results

Laboratory tests were conducted on selected soil samples and the test results are presented in the Exploration Results section and on the boring logs. Atterberg limit test results indicate that the on-site soils generally have low plasticity or are non-plastic. Consolidation tests indicated that the silty sand soils encountered at an approximate depth of 5 feet bgs have a moderate collapse potential when saturated under normal footing loads of 2,000 psf. Maximum density/optimum moisture content testing conducted in accordance with ASTM D1557 (Modified Proctor) indicate that near surface soils tested have maximum dry densities ranging from 133.3 to 136.3 pounds per cubic feet (pcf) and optimum water contents ranging from 7.8 to 8.4 percent. California Bearing Ratio (CBR) testing of the near surface soils indicated a CBR value of 10. Direct shear testing results on sandy samples are tabulated below:

Boring I D	Depth (feet)	Description	Peak Friction Angle (°)	Peak Cohesion (psf)
BESS-4	5	Silty Sand	32°	130
BESS-8	10	Silty Sand	27°	600
BESS-14	5	Poorly Graded Sand with Silt	27°	260
TL-2	10	Silty Sand	42°	0
TL-3	2.5	Silty Sand	27°	350
TL-5	7.5	Silty Sand	35°	220
TL-6	5	Silty Sand	31°	240



Groundwater

The borings were advanced using a hollow-stem-auger technique that allowed short term groundwater observations to be made while drilling. Groundwater seepage was not encountered during drilling or for the short duration the boring remained open. These observations represent groundwater conditions at the time of field exploration and may not be indicative of other times, or at other locations.

Groundwater level fluctuations occur due to seasonal variations in the amount of rainfall, runoff and other factors not evident at the time the borings were performed. Therefore, groundwater levels during construction or at other times in the life of the structure may be higher or lower than expected.

According to data collected from the Water Data Library for the State of California from a nearby well, located approximately 0.5 miles north of the site in State Well Number 05N12W28F001S, historic groundwater levels around November 30, 1965, were recorded at greater than 100 feet bgs.¹ Recent publicly available data (within the last 20 years) is not available within a 1-mile radius from the site boundary. As such, groundwater is not anticipated to occur within the depth of excavations or foundation installations at the site.

Seismic Site Class

The seismic design requirements for buildings and other structures are based on Seismic Design Category. Site Classification is required to determine the Seismic Design Category for a structure. The Site Classification is based on the upper 100 feet of the site profile defined by a weighted average value of either shear wave velocity, standard penetration resistance, or undrained shear strength in accordance with Section 20.4 of ASCE 7.

Description	Value
BESS Area	
2022 California Building Code Site Classification (CBC) ¹	C ²
Site Latitude (°N)	34.4834
Site Longitude (°W)	118.1383
S₅ Spectral Acceleration for a 0.2-Second Period	1.689

¹ California Department of Water Resources.

⁽https://wdl.water.ca.gov/WaterDataLibrary/GroundWaterLevel.aspx?StateWellNumber=05N12W28F001S&SiteCode=344881N1181435W001)



Description	Value		
S1 Spectral Acceleration for a 1-Second Period	0.698		
Fa Site Coefficient for a 0.2-Second Period	1.2		
Fv Site Coefficient for a 1-Second Period	1.4		
TL-1			
2022 California Building Code Site Classification (CBC) ¹	C ²		
Site Latitude (°N)	34.4818		
Site Longitude (°W)	118.1378		
S _s Spectral Acceleration for a 0.2-Second Period	1.677		
S1 Spectral Acceleration for a 1-Second Period	0.692		
Fa Site Coefficient for a 0.2-Second Period	1.2		
Fv Site Coefficient for a 1-Second Period	1.4		
TL-2			
2022 California Building Code Site Classification (CBC) ¹	C ²		
Site Latitude (°N)	34.4808		
Site Longitude (°W)	118.1379		
S _s Spectral Acceleration for a 0.2-Second Period	1.668		
S1 Spectral Acceleration for a 1-Second Period	0.688		
Fa Site Coefficient for a 0.2-Second Period	1.2		
F _v Site Coefficient for a 1-Second Period	1.4		
TL-3			
2022 California Building Code Site Classification (CBC) ¹	C ²		
Site Latitude (°N)	34.4802		
Site Longitude (°W)	118.1350		
S _s Spectral Acceleration for a 0.2-Second Period	1.672		
S1 Spectral Acceleration for a 1-Second Period	0.69		
Fa Site Coefficient for a 0.2-Second Period	1.2		
Fv Site Coefficient for a 1-Second Period	1.4		
TL-4			
2022 California Building Code Site Classification (CBC) ¹	C ²		
Site Latitude (°N)	34.4802		
Site Longitude (°W)	118.1328		
S _s Spectral Acceleration for a 0.2-Second Period	1.681		



Description	Value
S1 Spectral Acceleration for a 1-Second Period	0.694
Fa Site Coefficient for a 0.2-Second Period	1.2
Fv Site Coefficient for a 1-Second Period	1.4
TL-5	
2022 California Building Code Site Classification (CBC) ¹	C ²
Site Latitude (°N)	34.4832
Site Longitude (°W)	118.1322
S _s Spectral Acceleration for a 0.2-Second Period	1.71
S1 Spectral Acceleration for a 1-Second Period	0.707
Fa Site Coefficient for a 0.2-Second Period	1.2
F _v Site Coefficient for a 1-Second Period	1.4
TL-6	
2022 California Building Code Site Classification (CBC) ¹	C ²
Site Latitude (°N)	34.4823
Site Longitude (°W)	118.1278
S _s Spectral Acceleration for a 0.2-Second Period	1.719
S1 Spectral Acceleration for a 1-Second Period	0.711
Fa Site Coefficient for a 0.2-Second Period	1.2
F _v Site Coefficient for a 1-Second Period	1.4
TL-7	
2022 California Building Code Site Classification (CBC) ¹	C ²
Site Latitude (°N)	34.4846
Site Longitude (°W)	118.1332
S _s Spectral Acceleration for a 0.2-Second Period	1.719
S1 Spectral Acceleration for a 1-Second Period	0.711
Fa Site Coefficient for a 0.2-Second Period	1.2
Fv Site Coefficient for a 1-Second Period	1.4

1. Seismic site classification in general accordance with the 2022 California Building Code.

2. The 2022 California Building Code (CBC) requires a site soil profile determination extending to a depth of 100 feet for seismic site classification. The current scope does not include the 100-foot soil profile determination. Borings were extended to a maximum depth of 51½ feet, and this seismic site class definition considers that similar or denser soils continue below the maximum depth of the subsurface exploration. It is an acceptable practice in Southern California to analyze the upper 50 feet and assume the lower 50 feet to be similar. Additional exploration to deeper depths would be required to confirm the conditions below the current depth of exploration.



Faulting and Estimated Ground Motions

The site is located in Southern California, which is a seismically active area. The type and magnitude of seismic hazards affecting the site are dependent on the distance to causative faults, the intensity, and the magnitude of the seismic event. As calculated using the USGS Unified Hazard Tool, the fault which is considered to have the most significant effect at the site from a design standpoint and its maximum credible earthquake and proximity to the site are tabulated below:

Location	Fault	Magnitude	Distance (kilometers)
BESS and substation areas		7.82	8.71
TL-1A		7.92	7.96
TL-2			
TL-3	San Andreas (Mojave S)	7.94	8.02
TL-4		7.93	7.60
TL-5		7.93	8.60
TL-6		7.93	7.50
TL-7		7.93	7.51

Based on the USGS Design Maps Summary Report, using the American Society of Civil Engineers (ASCE 7-16) standard, the peak ground acceleration (PGA_M) at the project site is shown in the table below. In addition, based on the USGS Unified Hazard Tool, the mean magnitude at the project is also shown in the table below. Furthermore, the site is not located within an Alquist-Priolo Earthquake Fault Zone based on our review of the State Fault Hazard Maps.²

² California Geological Survey.

https://maps.conservation.ca.gov/cgs/informationwarehouse.

Prairie Song Reliability Project | Acton, Los Angeles County, California May 14, 2025 | Terracon Project No. LA245085



Location	PGAM	Mean Magnitude
BESS and substation areas	0.883	7.81
TL-1A	0.877	7.76
TL-2	0.873	7.76
TL-3	0.875	7.81
TL-4	0.879	7.9
TL-5	0.893	7.82
TL-6	0.898	7.82
TL-7	0.898	7.82

Liquefaction

Liquefaction is a mode of ground failure that results when a saturated soil loses substantial strength in response to earthquake shaking. Liquefaction is typically a hazard where loose sand or non-plastic silt soils exist below groundwater but may also occur with sensitive plastic silt or clay below groundwater. The California Geological Survey (CGS) has designated certain areas within the state as potential liquefaction hazard zones. These are areas considered at a risk of liquefaction-related ground failure during a seismic event, based upon mapped surficial deposits and the presence of relatively shallow groundwater.

The proposed BESS and substation are not located within a liquefaction hazard zone as designated by the CGS. However, a portion of the proposed transmission line is located within a liquefaction hazard zone. In particular, borings TL-1, TL-2, TL-3, TL-4 and TL-6 are located within a liquefaction hazard zone. As such liquefaction hazard analysis is included for the proposed T-line locations in the following section.

Liquefaction Analysis

Our explorations indicate the native soils encountered in exploratory borings generally consisted of loose to very dense sand to the maximum exploration depth of 51½ feet bgs. Groundwater was not encountered in borings while drilling and the recorded historical groundwater depth is more than 100 feet bgs.

To evaluate the presence of liquefiable soils and determine the amount of settlement of saturated/unsaturated soils during seismic shaking, we performed liquefaction analysis in accordance with the DMG Special Publication 117.

We utilized the software "LiquefyPro" by CivilTech Software, using soil from boring TL-2. A Peak Ground Acceleration (PGAM) of 0.873g and assumed a magnitude of 7.76 were used. Settlement analysis used the Tokimatsu, M-correction method. The fines percentage were corrected for liquefaction using the Idriss/Seed method. For this analysis a groundwater depth of 100 feet has been utilized.



Based on the depth to groundwater liquefaction hazard risk is considered low. Results and calculations for the liquefaction analysis are included in the Supporting Documents section of this report.

Seismic Settlement

Based on the calculation results, the seismically induced settlement of dry sands which typically occurred in the upper 5 to 10 feet is estimated to be on the order of 1¼ inch. Differential seismic settlement can be taken as one-half of the total seismic settlement.

Corrosivity

The table below lists the results of laboratory soluble sulfate, soluble chloride, electrical resistivity, and pH testing. The values may be used to estimate potential corrosive characteristics of the on-site soils with respect to contact with the various underground materials which will be used for project construction.

Boring	Sample Depth (feet)	Soluble Sulfate (mg/kg)	Sulfides (mg/kg)	Chloride (mg/kg)	Red-Ox Potential (mV)	Electrical Resistivity (Ω -cm)	рН
BESS-2	0-2	1.6	Nil	5.8	+278	10,250	7.1
BESS-8	0-2.5	9.7	Nil	7.7	+290	8,140	7.4
BESS-14	0-2.5	6.5	Nil	6.2	+282	5,230	7.7
SUB-2	0-2.5	4.1	Nil	6.6	+291	6,840	7.3
TL-1	0-5	9.2	Nil	6.5	+288	18,100	7.7
TL-3	0-5	2.4	Nil	6.5	+288	13,070	7.1
TL-6	0-5	0.2	Nil	5.4	+293	21,110	7.0

Results of soluble sulfate testing indicate samples of the on-site soils tested possess negligible sulfate concentrations when classified in accordance with Table 19.3.1.1 of the ACI Design Manual. Concrete should be designed in accordance with the exposure class S0 provisions of the ACI Design Manual, Section 318, Chapter 19.

Electrical Resistivity Testing

Terracon performed field measurements of soil electrical resistivity for the support of grounding design. Soil resistivity data was obtained from two test arrays at three (3)



locations each in the proposed BESS, one (1) location in the substation area, and at three (3) locations along the proposed transmission line for a total of seven (7) locations. At one of the test locations, ER-7, Terracon attempted to collect soil electrical resistivity readings, but the soil was too loose for electrode contact, and no repeatable readings were collected. The client was notified that no testing was obtained at this location. The approximate locations of the test arrays are shown in the Exploration Plan. Each testing was performed in general accordance with Wenner Array (4-pin) method per ASTM G57. This method was performed in with IEEE Standard 81, IEEE Guide for Measuring Earth Resistivity, Ground Impedance and Earth Surface Potentials of a Ground System. The test in the proposed locations included perpendicular arrays, North-South and East-West, with **"a" spacings** 2, 4, 6, 8, 12, 20, 30, 50, 70, 100, and 150 feet. For test locations in the BESS and substation areas, soil resistivity readings were also collected at 300 feet "a" spacing. The "a" spacing is generally considered to be the depth of influence of the test. The electrical resistivity test results are presented in Exploration Results.

Thermal Resistivity Testing

Terracon subcontracted Geotherm USA to perform laboratory thermal resistivity testing. Testing was conducted on four (4) bulk samples at the project site from a depth of 0 to 5 feet bgs. Three (3) samples were collected from the proposed BESS and one (1) sample was collected from the substation area. The tests were conducted on soil samples remolded to 90% (as determined by ASTM D1557) of the material's maximum dry density. Dry out curves targeted the higher of either the in-situ moisture content of the optimum moisture content as determined by ASTM D1557, totally dry condition, and two intermediate points. The thermal resistivity test results are presented in Exploration Results.

Geotechnical Overview

The site appears suitable for the proposed construction based upon geotechnical conditions encountered in the test borings, provided that the recommendations provided in this report are implemented in the design and construction phases of this project.

We anticipate that the proposed BESS will consist of battery storage units supported by driven steel piles or mat foundations and other appurtenant electrical equipment supported on mat or drilled shaft foundations. We anticipate the substation structures will be supported on drilled piers or mat foundations. We anticipate that the proposed O&M building and water tanks will be supported on shallow concrete foundations.

We anticipate that the proposed transmission line will be supported by drilled shaft foundations.

To create a uniform bearing stratum, shallow concrete footings should bear on engineered fill extending to a minimum depth of 1 foot below the bottom of foundations, or 3 feet below existing grades, whichever is greater within the BESS, substation, and water tank areas. Grading should incorporate the limits of the overexcavation plus a lateral distance of 1 feet beyond the outside edge of perimeter footings.

Ierracon

The majority of the site indicates medium dense to very dense soils near the surface. However, potentially compressible soils, which show significant tendency for hydrocompaction when elevated in moisture content, will require particular attention in the design and construction near the O&M Building location. Within the O&M area we recommend engineered fill extend to a minimum depth of 3 feet below bottom of foundations or 5 feet below existing site grades.

Overexcavation and replacement is not required for support of drilled shaft or driven pile foundations.

Estimated movements described in this report are based on effective drainage for the life of the structure and cannot be relied upon if effective drainage is not maintained. Exposed ground, extending at least 10 feet from the perimeter, should be sloped a minimum of 5% away from the building to provide positive drainage away from the structure. Grades around the structure should be periodically inspected and adjusted as part of the **structure's maintenance program**.

Based on the findings summarized in this report, it is our professional opinion that the proposed construction will not be subjected to a hazard from settlement, slippage, or landslide, provided the recommendations of our report are incorporated into the proposed construction. It is also our opinion that the proposed construction will not adversely affect the geologic stability of the site or adjacent properties provided the recommendations contained in our report are incorporated into the proposed construction.

Geotechnical engineering recommendations for foundation systems and other earth connected phases of the project are outlined below. The recommendations contained in this report are based upon the results of field and laboratory testing (presented in the Exploration Results), engineering analyses, and our current understanding of the proposed project. The General Comments section provides an understanding of the report limitations.

Earthwork

The following presents recommendations for site preparation, excavation, subgrade preparation, and placement of engineered fills on the project. The recommendations presented for the design and construction of foundations are contingent upon following the recommendations outlined in this section.



Earthwork on the project should be observed and evaluated by a geotechnical engineer. If a geotechnical engineer other than Terracon is selected to perform the observations and testing during construction, they will assume the role of Geotechnical Engineer of Record. The evaluation of earthwork should include observation and testing of engineered fill, subgrade preparation, foundation of bearing soils, and other geotechnical conditions exposed during construction of the project.

An on-site, pre-job meeting with the owner, the contractor and the Geotechnical Engineer should occur prior to all grading-related operations. Observation, testing, documentation, and reporting of the grading operation should be performed by the Geotechnical Engineer of Record. A final compaction report should be issued by the Geotechnical Engineer of Record at the completion of the grading operation. Interim reports may be issued according to project requirements. Operations undertaken at the site without the Geotechnical Engineer present may result in exclusions of affected areas from compaction reports for the project.

Grading of the subject site should be performed, at a minimum, in accordance with these recommendations and with applicable portions of the current version of CBC. The following recommendations are presented for your assistance in establishing proper grading criteria.

Site Preparation

Prior to placing fill, existing vegetation, debris, and other deleterious materials should be removed from proposed foundation and roadway areas. Exposed surfaces within these areas should be free of mounds and depressions which could prevent uniform compaction. The site should be initially graded to create a relatively level surface to receive fill and provide for a relatively uniform thickness of fill beneath proposed structures.

We recommend stripping topsoil to depths that expose soils with less than 3 percent organics and no roots having a diameter greater than 1/8 inch. While the depth of the unsuitable soils should be expected to vary, the thickness of the top soil layer may be estimated to range between 6 and 12 inches for construction budgeting purposes. The thickness of the top soil layer was not determined during our field exploration. Therefore, the actual depth of stripping should be verified by engineering observations made during the grading operations at the project. Exposed surfaces should be free of mounds and depressions which could prevent uniform compaction.

Stripped materials consisting of vegetation and organic materials should be wasted from the site or used to revegetate landscaped areas or exposed slopes after completion of grading operations. If it is necessary to dispose of organic materials on site, they should be placed in non-structural areas, and in fill sections not exceeding 5 feet in height.

Although no evidence of fills, utilities, or underground facilities such as septic tanks, cesspools, or basements was observed during the site reconnaissance, such features could

ierracon

be encountered during construction. If unexpected fills, utilities, or underground facilities are encountered, such features should be removed, and the excavation thoroughly cleaned prior to backfill placement and/or construction.

Subgrade Preparation

The proposed structures may be supported by a shallow concrete foundation system bearing on engineered fill, driven piles, or drilled shafts foundation.

To create a uniform bearing stratum, shallow concrete footings should bear on engineered fill extending to a minimum depth of 1 foot below the bottom of foundations, or 3 feet below existing grades, whichever is greater within the BESS, substation, and water tank areas. Grading should incorporate the limits of the overexcavation plus a lateral distance of 1 feet beyond the outside edge of perimeter footings.

The majority of the site indicates medium dense to very dense soils near the surface. However, potentially compressible soils, which show significant tendency for hydrocompaction when elevated in moisture content, will require particular attention in the design and construction near the O&M Building location. Within the O&M area we recommend engineered fill extend to a minimum depth of 3 feet below bottom of foundations or 5 feet below existing site grades.

Overexcavation and replacement is not required for support of drilled shaft or driven pile foundations.

Large gravels and cobble materials may be encountered at proposed excavation depths. If such conditions are encountered, any cobbles or boulders should be removed and be replaced a minimum of 12 inches below foundation bearing depths with engineered fill.

Subgrade soils beneath proposed exterior slabs and roadways should be scarified to a minimum depth of 12 inches, moisture conditioned, and compacted. The moisture content and compaction of subgrade soils should be maintained until slab or roadway construction.

All exposed areas which will receive fill, once properly cleared and benched where necessary, should be scarified to a minimum depth of 10 inches, moisture conditioned as necessary, and compacted per the compaction requirements in this report. Compacted structural fill soils should then be placed to the proposed design grade and the moisture content and compaction of subgrade soils should be maintained until foundation or pavement construction.

Based upon the subsurface conditions determined from the geotechnical exploration, subgrade soils exposed during construction are anticipated to be relatively workable; however, the workability of the subgrade may be affected by precipitation, repetitive construction traffic or other factors. If unworkable conditions develop, workability may be improved by scarifying and drying.



Excavation

We anticipate that excavations for the proposed construction can be accomplished with conventional earthmoving equipment. However, as excavations extend deeper into very dense soils additional excavation effort and larger equipment may be required. Very dense and gravelly soils was encountered in multiple borings. The owner should consider obtaining unit pricing for difficult excavations prior to the start of the project

The subgrade soils exposed during construction are expected to be relatively stable. However, the stability of the subgrade may also be affected by precipitation, repetitive construction traffic or other factors.

The bottom of excavations should be thoroughly cleaned of loose soils and disturbed materials prior to backfill placement and/or construction.

Onsite soils consist of cohesionless sandy soils. Such soils have the tendency to cave and slough during excavations. Therefore, formwork may be needed for foundation excavations.

Individual contractors are responsible for designing and constructing stable, temporary excavations. Excavations should be sloped or shored in the interest of safety following local, and federal regulations, including current OSHA excavation and trench safety standards.

Site Slopes

Based on the existing site grades, we expect that up to 10 feet of cut:fill with 2H:1V (horizontal:vertical) slopes will be placed around the site interior and boundary.

These new fill materials should possess a minimum friction angle of 32 degrees and cohesion of 100 psf from slope stability standpoint. For permanent slopes in compacted fill areas, recommended maximum configurations for on-site materials are as follows.

Maximum Slope Configuration (Height equal or less than 10 feet)		
Inclination Slope Treatment		
5:1 to 2:1 Re-vegetate		
More steep than 2:1 Stability analysis or structural retaining wall required		

We expect slopes with this configuration to be resistant to erosion and stable against circular failure. The face of all slopes should be compacted to the minimum specification for fill embankments. No tracking of fill material on the slope is allowed. Fill slopes can be over-built with compacted material and trimmed to final configurations. If any slope in

fill will exceed 20 feet in height, the grading design should include mid-height benches to intercept surface drainage and divert flow from the face of the embankment.

erracor

The Geotechnical Engineer of Record should be provided with proposed grading plans and cross sections and the anticipated height of fills and cuts for review prior to the start of construction. Based on preliminary analysis, placing up to 10 feet of new fill above the existing site soils to construct the BESS/Substation pads will result in estimated settlements of less than 1/2 inch. The majority of this settlement is expected to occur over a short period of time during the construction.

If fill is placed in areas of the site where existing slopes are steeper than 5H: 1V, the area should be benched to reduce the potential for slippage between existing slopes and fills. Benches should be wide enough to accommodate compaction and earth moving equipment, and to allow placement of horizontal lifts of fill.

If foundations are determined to be setback a distance less than H/2 or 15 feet (whichever is less for structures located below slope) or H/3 or 40 feet (whichever is less for structures located atop slopes), then the Geotechnical Engineer of Record should be notified as additional evaluations may be required.

Fill Material and Placement

All fill materials should be inorganic soils free of vegetation, debris, and fragments larger than six inches in size. Pea gravel or other open-graded materials should not be used as fill or backfill without the prior approval of the geotechnical engineer.

Clean on-site soils (provided they are screened for oversized particles with dimensions larger than 3 inches) or approved imported materials may be used as fill materials for the following:

- general site grading
- foundation backfill
- foundation areas
- roadway areas
- exterior slab areas

Imported soils for use as fill material within proposed structure areas should conform to low volume change materials as indicated in the following specifications:

	Percent Finer by Weight
Gradation	<u>(ASTM C 136)</u>
3"	
No. 4 Sieve	
No. 200 Sieve	40(max)
Liquid Limit	30 (max)



Plasticity Index 10 (max)
Maximum Expansion Index*
*ASTM D4829

The contractor shall notify the Geotechnical Engineer of import sources sufficiently ahead of their use so that the sources can be observed and approved as to the physical characteristic of the import material. For all import material, the contractor shall also submit current verified reports from a recognized analytical laboratory indicating that the import has a "not applicable" (Class SO) potential for sulfate attack based upon current ACI criteria and is "mildly corrosive" to ferrous metal and copper. The reports shall be accompanied by a written statement from the contractor that the laboratory test results are representative of all import material that will be brought to the job.

Engineered fill should be placed and compacted in horizontal lifts, using equipment and procedures that will produce recommended moisture contents and densities throughout the lift. Fill lifts should not exceed 10 inches loose thickness.

Compaction Requirements

	Per the Modified Proctor Test (ASTM D 1557)			
Material Type and Location	Minimum Compaction	Range of Moisture Contents for Compaction Above Optimum		
	Requirement		Maximum	
Approved on-site or imported fill soils:				
Beneath foundations ¹ :	90%	0%	+3%	
Utility trenches (structural areas) ¹ :	90%	0%	+3%	
Utility trenches (landscape areas):	90%	0%	+3%	
Fill greater than 5 feet in depth	95%	0%	+3%	
Exterior Slabs:	90%	0%	+3%	
Miscellaneous backfill:	90%	0%	+3%	
Aggregate base:	95%	0%	+3%	

Recommended compaction and moisture content criteria for engineered fill materials are as follows:

1. Upper 12 inches should be compacted to 95% beneath foundation, pavement, and structural areas. Low-volume change imported soils should be used in lightly loaded equipment areas.



Utility Trench Backfill

We anticipate that the on-site soils will provide suitable support for underground utilities and piping that may be installed. Any soft and/or unsuitable material encountered at the bottom of excavations should be removed and be replaced with an adequate bedding material.

Trench excavation should not be conducted below a downward 1:1 projection from existing foundations without engineering review of shoring requirements and geotechnical observation during construction.

A non-expansive granular material with a sand equivalent greater than 30 should be used for bedding and shading of utilities, unless allowed or specified otherwise by the utility manufacturer.

On-site materials are considered suitable for backfill of utility and pipe trenches from 1 foot above the top of the pipe to the final ground surface, provided the material is free of organic matter and deleterious substances. Imported low volume change soils should be used for trench backfill in structural areas.

Trench backfill should be mechanically placed and compacted as discussed earlier in this report. Compaction of initial lifts should be accomplished with hand-operated tampers or other lightweight compactors. Where trenches are placed beneath footings, the backfill should satisfy the gradation and expansion index requirements of engineered fill discussed in this report. Flooding or jetting for placement and compaction of backfill is not recommended.

Grading and Drainage

All grades must provide effective drainage away from the proposed structures during and after construction and should be maintained throughout the life of the structure. Water retained next to the structures result in soil movements greater than those discussed in this report. Greater movements can result in unacceptable differential foundation movements causing cracked slabs and walls.

We recommend a minimum horizontal setback distance of 10 feet from the perimeter of any structure and the high-water elevation of the nearest storm-water retention basin.

Exterior Slab Design and Construction

Exterior slabs-on-grade, exterior architectural features, and utilities founded on, or in backfill may experience some movement due to the volume change of the backfill. To reduce the potential for damage caused by movement, we recommend:



- minimizing moisture increases in the backfill;
- controlling moisture-density during placement of backfill;
- using designs which allow vertical movement between the exterior features and adjoining structural elements;
- placing effective control joints on relatively close centers

Earthwork Construction Considerations

Upon completion of filling and grading, care should be taken to maintain the subgrade water content prior to construction of roadways. Construction traffic over the completed subgrades should be avoided to the extent practical. The site should also be graded to prevent ponding of surface water on the prepared subgrades or in excavations. Water collecting over or adjacent to construction areas should be removed. If the subgrade desiccates, saturates, or is disturbed, the affected material should be removed, or the materials should be scarified, moisture conditioned, and recompacted prior to roadway construction.

Construction site safety is the sole responsibility of the contractor who controls the means, methods, and sequencing of construction operations. Under no circumstances shall the information provided herein be interpreted to mean Terracon is assuming responsibility for construction site safety, or the contractor's activities; such responsibility shall neither be implied nor inferred.

Should unstable subgrade conditions develop stabilization measures will need to be employed. Stabilization measures may include placement of aggregate base and multiaxial geogrid. Use of lime, fly ash, kiln dust or cement could also be considered as a stabilization technique. Laboratory evaluation is recommended to determine the effect of chemical stabilization on subgrade soils prior to construction.

We recommend that the earthwork portion of this project be completed during extended periods of dry weather if possible. If earthwork is completed during the wet season (typically November through April) it may be necessary to take extra precautionary measures to protect subgrade soils. Wet season earthwork operations may require additional mitigative measures beyond that which would be expected during the drier summer and fall months. This could include diversion of surface runoff around exposed soils and draining of ponded water on the site. Once subgrades are established, it may be necessary to protect the exposed subgrade soils from construction traffic.

The individual contractor(s) is responsible for designing and constructing stable, temporary excavations as required to maintain stability of both the excavation sides and bottom. Excavations should be sloped or shored in the interest of safety following local, and federal regulations, including current Occupational Safety and Health Administration (OSHA) excavation and trench safety standards.



Construction Observation and Testing

The geotechnical engineer should be retained during the construction phase of the project to observe earthwork and to perform necessary tests and observations during subgrade preparation, proof-rolling, placement and compaction of controlled compacted fills, backfilling of excavations to the completed subgrade.

The exposed subgrade and each lift of compacted fill should be tested, evaluated, and reworked, as necessary, as recommended by the Geotechnical Engineer prior to placement of additional lifts. Each lift of fill should be tested for density and water content at a frequency of at least one test for every 2,500 square feet of compacted fill in the structure areas and 5,000 square feet in roadway areas. Where not specified by local ordinance, one density and water content test should be performed for every 50 linear feet of compacted utility trench backfill. This testing frequency criteria may be adjusted during construction as specified by the geotechnical engineer of record.

In areas of foundation excavations, the bearing subgrade should be evaluated by the Geotechnical Engineer. If unanticipated conditions are observed, the Geotechnical Engineer should prescribe mitigation options.

In addition to the documentation of the essential parameters necessary for construction, the continuation of the Geotechnical Engineer into the construction phase of the project **provides the continuity to maintain the Geotechnical Engineer's evaluation of** subsurface conditions, including assessing variations and associated design changes.

Shallow Foundations

We anticipate that the proposed BESS and substation equipment, water tanks, and O&M building may be supported on either spread footings, slab-on grade, or mat foundations.

Recommendations for foundation for the proposed structures and related structural elements are presented in the following paragraphs.

If the site has been prepared in accordance with the requirements noted in Earthwork, the following design parameters are applicable for shallow foundations.

Item	Description
Foundation System	Spread footings, slab on grade, mat foundation
Maximum Net Allowable	3,000 psf up to 8 feet wide
Bearing Pressure	2,000 psf up to 14 feet wide

Shallow Foundation Design Recommendations

Prairie Song Reliability Project | Acton, Los Angeles County, California

May 14, 2025 | Terracon Project No. LA245085



Item	Description
(1-inch settlement) ^{1, 2}	1,500 psf up to 22 feet wide 1,250 psf up to 32 feet wide 1,200 psf up to 35 feet wide
Required Bearing Stratum ³	 Engineered fill extending to a minimum of 1 foot below the bottom of foundations, or 3 feet below existing grade, whichever is greater for the BESS, substation, and water tank areas. Engineered fill extending to a minimum of 3 feet below the bottom of foundations, or 5 feet below existing grade, whichever is greater for the O&M building area.
Design Modulus of Subgrade Reaction, k ³	200 pounds per square inch per inch (psi/in) The modulus was obtained on estimates obtained from NAVFAC 7.1 design charts. This value is for a small-loaded area (1 sq.ft. or less) such as for forklift wheel loads or point loads and should be adjusted for larger loaded areas.
Modulus Correction Factor ³	$k_c = k [(B+1)/2B)]^2$
Minimum Embedment Below Finished Grade	18 inches
Minimum Dimensions	Square footings and mats: 24 inches Strip footings: 18 inches
Ultimate Passive Resistance ⁴	360 pcf
Ultimate Coefficient of Sliding Friction ⁵	0.4
Estimated Total Settlement from Structural Loads	About 1 inch
Estimated Differential Settlement	About 1/2 of total settlement over a horizontal distance of 40 feet

- The maximum net allowable bearing pressure is the pressure in excess of the minimum surrounding overburden pressure at the footing base elevation. An appropriate factor of safety has been applied. These bearing pressures can be increased by 1/3 for transient loads unless those loads have been factored to account for transient conditions.
- 2. Unsuitable or soft soils should be overexcavated and replaced per the recommendations presented in Earthwork.
- 3. k values should be reduced to account for dimensional effects of largely loaded areas. Where k_c is the corrected or design modulus value and B is the mat width in feet.



Item

Description

- 4. Use of passive earth pressures requires the footing forms be removed and compacted structural fill be placed against the vertical footing face. A factor of safety of 2.0 is recommended.
- Can be used to compute sliding resistance where foundations are placed on suitable soil/materials. Should be neglected for foundations subject to net uplift conditions. A factor of safety of 1.5 is recommended.

Settlement calculations were performed utilizing Westergaard and Hough's methods³ to estimate the static settlement for various foundations widths with an allowable settlement of 1-inch.

Finished grade is defined as the lowest adjacent grade within five feet of the foundation for perimeter (or exterior) footings.

The allowable foundation bearing pressure applies to dead loads plus design live load conditions. The design bearing pressure may be increased by one-third when considering total loads that include wind or seismic conditions. The weight of foundation concrete below grade may be neglected in dead load computations.

Foundation should be reinforced as necessary to reduce the potential for distress caused by differential foundation movement. Foundation excavations should be observed by the geotechnical engineer. If the soil conditions encountered differ significantly from those presented in this report, supplemental recommendation will be required.

Lateral Earth Pressures

Design Parameters

For engineered fill comprised of on-site soils or imported low volume change materials above any free water surface, recommended equivalent fluid pressure of unrestrained foundation elements are:

Item	Recommended Value
Active Case	31 psf/ft
Passive Case	390 psf/ft
At-Rest Case	47 psf/ft

³ FHWA Geotechnical Engineering Circular No. 6 – Shallow Foundations, FHWA – SA-02-054

Geotechnical Engineering Report Prairie Song Reliability Project | Acton, Los Angeles County, California

May 14, 2025 | Terracon Project No. LA245085



Coefficient of Friction

0.35

- 1. The values are based on engineered fill materials used as backfill.
- 2. Uniform, horizontal backfill, compacted to at least 90% of the ASTM D 1557 maximum dry density, rendering a maximum unit weight of 125 pcf.
- 3. Use of passive earth pressures require the sides of the excavation for the foundation to be nearly vertical and the concrete placed neat against these vertical faces or that the foundation forms be removed and compacted engineered fill be placed against the vertical foundation face.
- 4. Can be used to compute sliding resistance where foundations are placed on suitable soil/materials. Should be neglected for foundations subject to net uplift conditions.
- 5. Passive pressure and sliding friction may be combined to resist sliding provided that either the passive pressure or frictional resistance (adhesion) is reduced by 50 percent.

The lateral earth pressures herein do not include any factor of safety and are not applicable for submerged soils/hydrostatic loading. Additional recommendations may be necessary if such conditions are to be included in the design.

Fill against foundation walls should be compacted to densities specified in the Earthwork section of this report. Compaction of each lift adjacent to walls should be accomplished with hand-operated tampers of other lightweight compactors.

Deep Foundations

Drilled Shaft Design Recommendations

Proposed substation and BESS electrical equipment and transmission line poles may be supported on drilled shaft piers. Total required embedment of the drilled shaft should be determined by the structural engineer based on structural loading and parameters provided in this report.

It should be noted that the transmission line borings were located in accessible areas, however there are rolling hills between the test locations. Subsurface conditions in these hills are anticipated to be more dense than what was encountered in the lower flat areas and may contain cobbles or shallow bedrock outcrops. The owner should consider getting unit rates for rock coring or difficult drilling costs associated with tower locations sited in the hills.

Drilled Shaft Axial Loading

Allowable skin friction and total capacity charts are attached to our Supporting Information section at the end of this report. The values presented for allowable side friction and end bearing include a factor of safety of 2.5.

Drilled piers should have a minimum (center-to-center) spacing of three diameters. Closer spacing may require a reduction in axial load capacity. Axial capacity reduction can be determined by comparing the allowable axial capacity determined from the sum of



individual piers in a group versus the capacity calculated using the perimeter and base of the pier group acting as a unit. The lesser of the two capacities should be used in design.

The allowable uplift capacities should only be based on the side friction of the shaft; however, the weight of the foundation should be added to these values to obtain the actual allowable uplift capacities for drilled shafts. Tensile reinforcement should extend to the bottom of shafts subjected to uplift loading.

Drilled Shaft Lateral Loading – LPILE Parameters

Based on our review of the subsurface conditions in the area of the substation, BESS and transmission line, our laboratory testing, and the Standard Penetration Test (SPT) results, engineering properties have been estimated for the soils conditions as shown in the following table. A depth of neglect based on anticipated disturbance, shrinkage, or scour during the design life off the piers should be considered due to utilities construction and grading around the piers. Due to potential for disturbance within the upper soils around the shaft, lateral and axial capacity of soils within the upper 2 feet should be neglected. This depth of neglect should be provided by the designer and verified by the civil engineer.

Recommended geotechnical parameters for lateral load analyses by others of drilled shaft foundations have been developed for use in the LPILE computer program. The following table summarizes input values for use in LPILE analyses. LPILE estimated values of kh and

 \mathcal{E}_{50} may be used. Since deflection or a service limit criterion will most likely control lateral capacity design, no safety/resistance factor is included with the parameters.


	Stratigraphy ¹	L-Pile Soil		MFAD Modulus of Deformation (po (ksi)	γ″
Layer	Depth Below Finished Grade (feet)	Model	¢ (°) ²		(pcf) ²
1	2	Sand 32	1.35	120	
	10				
2	10	Caral	34	1.98	110
2	20	Sand			
2	20		Sand 40 3.60	100	
3	50	Sand		3.60	120
2.	See Subsurface Profile in Geotec Definition of terms: φ: Internal friction angle γ: Effective unit weight	chnical Characterizat	ion for mo	re details on Strati	graphy.

The load capacities provided herein are based on the stresses induced in the supporting soil strata. The structural capacity of the shafts/piles should be checked to assure they can safely

accommodate the combined stresses induced by axial and lateral forces. Lateral deflections of shafts/piles should be evaluated using an appropriate analysis method, and will depend **upon the pile's diameter, length, configuration, stiffness and "fixed head" or "free head"** condition. We can provide additional analyses and estimates of lateral deflections for specific loading conditions upon request. The load-carrying capacity of shafts/piles may be increased by increasing the diameter and/or length.

ierracor

When piers are used in groups, the lateral capacities of the piers in the second, third, and subsequent rows of the group should be reduced as compared to the capacity of a single, independent pier. Guidance for applying p-multiplier factors to the p values in the p-y curves for each row of pier foundations within a pier group are as follows:



- 1. Front row: Pm = 0.8
- 2. Second row: Pm = 0.4
- 3. Third and subsequent row: Pm = 0.3

For the case of a single row of piers supporting a laterally loaded grade beam, group action for lateral resistance of piers would need to be considered when spacing is less than five pier diameters (measured center-to-center). However, spacing closer than 3D (where D is the diameter of the pier) is not recommended due to the potential for the installation of a new pier disturbing an adjacent installed pier, likely resulting in axial capacity reduction.

Drilled Shaft Construction Considerations

Due to presence of sandy soils, caving of soils within the drilled shaft excavations should be anticipated. We do not anticipate drilled shafts to extend below the depth of groundwater. However, if foundation concrete cannot be placed in dry conditions, a tremie should be used for concrete placement. Temporary steel casing will likely be required to properly drill and clean shafts prior to concrete placement. Gravelly soils were encountered in multiple borings on-site. Therefore, as drilled shafts extend below 10 feet, heavy duty rock bit or coring may be required to advance drilled shafts



The drilling speed should be reduced as necessary to minimize vibration and caving of the silty sand materials. The contractor should be prepared to use casing or other approved means to prevent caving. The contractor should review the boring logs to make sure they are familiar with the anticipated subsurface conditions prior to beginning construction of the deep foundations.

In the event drilled hole walls slough during drilling, temporary steel casing may be required to properly drilled shafts prior to concrete placement. We recommend the use of slurry drilling methods with polymers method to keep the solids in suspension during the drilling. Drilled shaft foundation concrete should be placed within 6 inches of the shaft base of the slurry-filled excavation immediately after completion of drilling and cleaning. The tremie should remain inserted several feet into the fresh concrete as it displaces the slurry upward and until placement is complete. The slurry should have a sand content no greater than 1% at the time concrete placement commences. The maximum unit weight of the slurry should be established in consultation with the Geotechnical Engineer.

As an alternative to temporary casing, the shaft excavation may be backfilled with a slurry mix in order to help stabilize sloughing sidewalls of the excavation, allowed to dry, and re-drilled through the backfill. The slurry mix design should be submitted to the Geotechnical Engineer for review and approval.

Drilled shaft foundation concrete should be placed immediately after completion of drilling and cleaning. Due to potential sloughing and raveling, foundation concrete quantities may exceed calculated geometric volumes.

If casing is used for drilled shaft construction, it should be withdrawn in a slow continuous manner maintaining a sufficient head of concrete to prevent infiltration of water or the creation of voids in shaft concrete. Shaft concrete should have a relatively high fluidity when placed in cased shaft holes or through a tremie. Shaft concrete with slump in the range of 6 to 8 inches is recommended.

Foundation concrete should be placed immediately after completion of drilling and cleaning. Closely spaced shafts should be drilled and filled alternatively, allowing the concrete to set at least eight hours before drilling the adjacent shaft. All excavations should be filled with concrete as soon after drilling as possible. In no event should shaft holes be left open overnight.

We recommend that all drilled shaft installations be observed on a full-time basis by an experienced geotechnical engineer in order to evaluate that the soils encountered are consistent with the recommended design parameters. If the subsurface soil conditions encountered differ significantly from those presented in this report, supplemental recommendations will be required. The Geotechnical Engineer should observe the installation of drilled piers to verify the soil conditions and the diameter and depth of piers. Drilled piers should be constructed true and plumb.



Free-fall concrete placement in drilled piers will only be acceptable if provisions are taken to avoid striking the concrete on the sides of the hole or reinforcing steel. The use of a bottom-**dump hopper, or an "elephant's trunk" discharging near the botto**m of the hole where concrete segregation will be minimized, is recommended.

Drilled pier end bearing surfaces must be thoroughly cleaned prior to concrete placement. A representative of the Geotechnical Engineer should inspect the bearing surface and foundation pier configuration. If the subsurface soil conditions encountered differ significantly from those presented in this report, supplemental recommendations will be required.

The contractor should check for gas and/or oxygen deficiency before any workers enter the excavation for observation and manual cleanup. All necessary monitoring and safety precautions as required by OSHA, State or local codes should be strictly enforced.

Driven Pile Design Parameters

Proposed battery storage units can be supported on driven steel W-section foundations (assumed to be W6x9 or similar) in general accordance with the following sections.

The design capacity of a single-driven pile is a function of several factors including:

- Size and type of pile;
- Type and capacity of pile installation equipment;
- Pile integrity after installation; and
- Engineering properties of the subsurface soils.

Based on specific conditions encountered on site, the soils are generally considered drivable for pile installation. The most effective means of verifying pile drivability and capacities for either tension or lateral loads is through pile load tests. Pile foundation design parameters have been based upon correlated capacities utilizing soil strength criteria determined from the soil borings and laboratory testing.

The tables below neglect a depth of 2 feet for axial and lateral resistance. This neglect is estimated based on our experience and accounts for depth of scour and/or disturbance from utilities near the piles. Depth of neglect should be verified and adjusted by the design engineer based on the scour analysis. Allowable capacities were based on a minimum factor-of-safety (FOS) of 2.0 for skin friction and 3.0 for end bearing

Description	<u>Top Depth</u> Bottom Depth	Total Unit Weight (pcf)	Allowable Compression Unit Skin friction (psf) ¹	Allowable Bearing Pressure (psf) ²
Stratum 1	2	120	90	8,000
	10			

Geotechnical Engineering Report

Prairie Song Reliability Project | Acton, Los Angeles County, California May 14, 2025 | Terracon Project No. LA245085



Description	<u>Top Depth</u> Bottom Depth	Total Unit Weight (pcf)	Allowable Compression Unit Skin friction (psf) ¹	Allowable Bearing Pressure (psf) ²
Stratum 2	10	110	200	25.000
Stratum 2	20	110	300	25,000

- 1. Allowable uplift capacity is on the order of 70% of the compression capacity values in the table. The values provided should be multiplied by the box perimeter of the pile times the depth. The box perimeter is considered two times the width of the flange plus two times the depth of the web.
- 2. The values provided should be multiplied by the box area of the pile and be used for compression resistance only.

Recommended soil parameters for lateral load analysis of driven pile foundations have been developed for use in LPILE computer programs. Engineering properties have been estimated as outlined below:

Description	<u>Top Depth</u> Bottom Depth	Effective Unit Weight (pcf)	L-PILE/ GROUP Soil Type	φ (°)
Stratum 1	1 10	120	Sand	32
Stratum 2	10 20	110	Sand	34

Driven Piles Construction Considerations

Based on the field exploration and laboratory testing, it is our opinion that the soils on the site are suitable for pile installation into native soils.

A geotechnical engineer should be engaged to make periodic observations of pile driving operations during construction. Each pile should be observed and checked for buckling, crimping and alignment in addition to recording penetration resistance, depth of embedment, and general pile driving operations.

As part of the overall quality control program, the time rate of installation (seconds per foot of embedment) should be recorded during production post driving. As a direct **extension of the design process, additional "proof" testing should be performed on** a representative number of production posts that do not meet the minimum installation rate criteria outlined in this report.



Gravel-Surfaced Drives and Parking

Roadway designs are provided for the traffic conditions and pavement life conditions as noted in the Project Description and in the following sections of this report. A critical aspect of pavement performance is site preparation. Roadway sections noted in this section are contingent upon the site being adequately prepared. Additionally, our recommendations are based on Chapter 4 Low-Volume Road Design found in AASHTO 1993.

Roadway Subgrades

For this analysis, the laboratory CBR value result of 10 was used.

Design Parameters

We understand unpaved access roads are planned throughout the site. The unpaved road sections for post-construction use have been developed under the following assumptions:

	Aggregate Roadway Design P	Parameters		
Parameter	Design Value	Comments		
Traffic Loading	5,000 ESALs ¹	Assumed		
Design Life	40 years	Assumed		
Design CBR	10	Assumed		
Resilient Modulus	11,150 psi (all-weather)	Based on CBR of 10		
Aggregate Base Elastic Modulus	36,000 psi	Assumed		
Allowable Rut Depth	2.0 inches	Assumed		
Design Serviceability Loss	2.5	Assumed		
Vehicle Tire Pressure	80 psi	Assumed		

1. ESAL = 18 kips Equivalent Single Axle Load



Access Road Sections

As a minimum, we recommend the following options for unpaved access roads:

Typical Unpaved Road Section	on – Post Construction Traffic
Base Course Thickness (inches)	Traffic (ESALs)
5 ^{1, 2}	5,000

1. Minimum section thickness is anticipated to support fire trucks and pick-up trucks associated with on-going maintenance. Trucks containing heavy equipment may require localized repairs.

2. Base materials shall consist of Class II Base meeting requirements of the Caltrans Standard Specifications.

Roadway section should be constructed over a minimum of 12 inches of scarified, moisture conditioned, and compacted native soils to 95% of the maximum dry density using ASTM D1557. The recommended thicknesses should be measured after full compaction. The width of the roadway should extend a minimum distance of 1 foot on each side of the desired surface width.

Aggregate materials should conform to the specifications of Class II aggregate base in accordance with the requirements and specifications of the State of California Department of Transportation (Caltrans), or other approved local governing specifications.

Positive drainage should be provided during construction and maintained throughout the life of the roadways. Proposed roadway design should maintain the integrity of the road and eliminate ponding.

Roadway Design and Construction Considerations

Regardless of the design, un-surfaced roadways will display varying levels of wear and deterioration. We recommend an implementation of a site inspection program at a frequency of at least once per year to verify the adequacy of the roadways. Preventative measures should be applied as needed for erosion control and re-grading. An initial site inspection should be completed approximately three months following construction.

Preventative maintenance should be planned and provided for through an on-going management program to enhance future roadway performance. Preventative maintenance activities are intended to slow the rate of deterioration, and to preserve the roadway investment.

Surfacing materials should not be placed when the surface is wet. Surface drainage should be provided away from the edge of roadways to reduce lateral moisture transmission into the subgrade.



If rut depths become excessive as construction work progresses, re-grading and recompaction should be performed as necessary. Care should be taken to reduce or eliminate trafficking of the unpaved access road when the subgrade is wet as this will result in accelerated rutting conditions. Scarification, moisture treatment as necessary, and re-compaction of the roadways will likely be necessary as the roadways deteriorate.

Materials and construction of roadways for the project should be in accordance with the requirements and specifications of the California Department of Transportation or the applicable local governing body.

Pavements

General Pavement Comments

Based on input from the design team, the entrance to the substation will be paved with asphalt. Asphalt pavement designs are provided for the traffic conditions and pavement life conditions as noted in Project Description and in the following sections of this report. A critical aspect of pavement performance is site preparation. Pavement designs noted in this section must be applied to the site which has been prepared as recommended in the Earthwork section.

Pavement Design Parameters

A sample was tested for CBR at the site and resulted in a CBR value of 10. An equivalent R-value of 48 was considered and used to calculate the asphalt concrete pavement thickness sections. R-value testing should be completed prior to pavement construction to verify the design R-value.

The structural sections are predicated upon proper compaction of the utility trench backfills and the subgrade soil preparation as prescribed by in Earthwork, with the upper 12 inches of subgrade soils and all aggregate base material brought to a minimum relative compaction of 95 percent in accordance with ASTM D 1557 prior to paving. The aggregate base should meet Caltrans requirements for Class 2 base.

Assuming the pavement subgrades will be prepared as recommended within this report, the following pavement sections should be considered minimums for this project for the traffic indices assumed in the table below. As more specific traffic information becomes available, we should be contacted to reevaluate the pavement calculations.

Pavement Section Thicknesses

The following table provides our opinion of minimum thickness for AC sections:

Geotechnical Engineering Report

Prairie Song Reliability Project | Acton, Los Angeles County, California May 14, 2025 | Terracon Project No. LA245085



	Recommended Pavement Section	on Thickness ¹ (inches)
Pavement Type	TI = 5	TI = 7
Asphaltic Concrete ²	3 inches	4 inches
Asphantic Concrete-	3 inches Class II Aggregate Base	5 inches Class II Aggregate Base

1. The individual and total material thickness values presented herein represent minimum thickness values, not averages.

2. All materials should meet the Caltrans Standard Specifications for Highway Construction.

These pavement sections are considered minimal sections based upon the expected traffic and the existing subgrade conditions. However, they are expected to function with periodic maintenance and overlays if good drainage is provided and maintained.

Subsequent to clearing, grubbing, and removal of topsoil, subgrade soils beneath all pavements should be scarified, moisture conditioned, and compacted to a minimum depth of 10 inches. All materials should meet the CALTRANS Standard Specifications for Highway Construction. Aggregate base materials should meet the gradation and quality requirement of Class 2 Aggregate Base (³/₄ inch maximum) in Caltrans Standard Specifications, latest edition, Sections 25 through 29.

Parking areas for heavy vehicles, concentrated turn areas, and start/stop maneuvers could require thicker pavement sections. Edge restraints (i.e. concrete curbs or aggregate shoulders) should be planned along curves and areas of maneuvering vehicles.

Pavement Drainage

Pavements should be sloped to provide rapid drainage of surface water. Water allowed to pond on or adjacent to the pavements could saturate the subgrade and contribute to premature pavement deterioration. In addition, the pavement subgrade should be graded to provide positive drainage within the granular base section. Appropriate sub-drainage or connection to a suitable daylight outlet should be provided to remove water from the granular subbase.

Pavement Maintenance

The pavement sections represent minimum recommended thicknesses and, as such, periodic upkeep should be anticipated. Preventive maintenance should be planned and provided for through an on-going pavement management program. Maintenance activities are intended to slow the rate of pavement deterioration and to preserve the pavement investment. Pavement care consists of both localized (e.g., crack and joint sealing and



patching) and global maintenance (e.g., surface sealing). Additional engineering consultation is recommended to determine the type and extent of a cost-effective program. Even with periodic maintenance, some movements and related cracking may still occur, and repairs may be required.

Pavement performance is affected by its surroundings. In addition to providing preventive maintenance, the civil engineer should consider the following recommendations in the design and layout of pavements:

- Final grade adjacent to paved areas should slope down from the edges at a minimum 2%.
- Subgrade and pavement surfaces should have a minimum 2% slope to promote proper surface drainage.
- Install pavement drainage systems surrounding areas anticipated for frequent wetting.
- Seal cracks immediately.

General Comments

Our analysis and opinions are based upon our understanding of the project, the geotechnical conditions in the area, and the data obtained from our site exploration. Variations will occur between exploration point locations or due to the modifying effects of construction or weather. The nature and extent of such variations may not become evident until during or after construction. Geotechnical contractor should be retained as the Geotechnical Engineer, where noted in this report, to provide observation and testing services during pertinent construction phases. If variations appear, we can provide further evaluation and supplemental recommendations. If variations are noted in the absence of our observation and testing services on-site, we should be immediately notified so that we can provide evaluation and supplemental recommendations.

Our Scope of Services does not include either specifically or by implication any environmental or biological (e.g., mold, fungi, bacteria) assessment of the site or identification or prevention of pollutants, hazardous materials, or conditions. If the owner is concerned about the potential for such contamination or pollution, other studies should be undertaken.

Our services and any correspondence are intended for the sole benefit and exclusive use of our client for specific application to the project discussed and are accomplished in accordance with generally accepted geotechnical engineering practices with no third-party beneficiaries intended. Any third-party access to services or correspondence is solely for information purposes to support the services provided by Terracon to our client. Reliance upon the services and any work product is limited to our client and is not intended for



third parties. Any use or reliance of the provided information by third parties is done solely at their own risk. No warranties, either express or implied, are intended or made.

Site characteristics as provided are for design purposes and not to estimate excavation cost. Any use of our report in that regard is done at the sole risk of the excavating cost estimator as there may be variations on the site that are not apparent in the data that could significantly effect excavation cost. Any parties charged with estimating excavation costs should seek their own site characterization for specific purposes to obtain the specific level of detail necessary for costing. Site safety and cost estimating including excavation support and dewatering requirements/design are the responsibility of others. Construction and site development have the potential to affect adjacent properties. Such impacts can include damages due to vibration, modification of groundwater/surface water flow during construction, foundation movement due to undermining or subsidence from excavation, as well as noise or air quality concerns. Evaluation of these items on nearby properties are commonly associated with contractor means and methods and are not addressed in this report. The owner and contractor should consider a preconstruction/precondition survey of surrounding development. If changes in the nature, design, or location of the project are planned, our conclusions and recommendations shall not be considered valid unless we review the changes and either verify or modify our conclusions in writing.




Figures

Contents:

GeoModel







This is not a cross section. This is intended to display the Geotechnical Model only. See individual logs for more detailed conditions.


Model Layer	Layer Name	General Description	Legend
1	Sand	Sand with varying amounts of silt, clay, and gravel; loose to medium dense	Silty Sand Poorly-graded Sand with Silt and Gravel
2	Sand	Sand with varying amount of silt, clay, and gravel; medium dense to very dense	Poorly-graded Sand Clayey Sand

NOTES:

Layering shown on this figure has been developed by the geotechnical engineer for purposes of modeling the subsurface conditions as required for the subsequent geotechnical engineering for this project. Numbers adjacent to soil column indicate depth below ground surface.



GeoModel



This is not a cross section. This is intended to display the Geotechnical Model only. See individual logs for more detailed conditions.


Model Layer	Layer Name	General Description	Legend			
1	Sand	Sand with varying amounts of silt, clay, and gravel; loose to medium dense	Silty Sand	Poorly-graded Sand		
2	Sand	Sand with varying amount of silt, clay, and gravel; medium dense to very dense	Poorly-graded Sand with Gravel Poorly-graded Sand with Silt	Poorly-graded Sand with Silt and Gravel		
			🔀 Silty Clayey Sand	💋 Clayey Sand		

NOTES:

Layering shown on this figure has been developed by the geotechnical engineer for purposes of modeling the subsurface conditions as required for the subsequent geotechnical engineering for this project. Numbers adjacent to soil column indicate depth below ground surface.



GeoModel



This is not a cross section. This is intended to display the Geotechnical Model only. See individual logs for more detailed conditions.

Model Layer	Layer Name	General Description	Legend
1	Sand	Sand with varying amounts of silt, clay, and gravel; loose to medium dense	Poorly-graded Sand Silty Sand
2	Sand	Sand with varying amount of silt, clay, and gravel; medium dense to very dense	Poorly-graded Sand

NOTES:

Layering shown on this figure has been developed by the geotechnical engineer for purposes of modeling the subsurface conditions as required for the subsequent geotechnical engineering for this project. Numbers adjacent to soil column indicate depth below ground surface.



Attachments

Geotechnical Engineering Report

Prairie Song Reliability Project | Acton, Los Angeles County, California Terracon Project No. LA245085



Exploration and Testing Procedures

Field Exploration

Number of Borings	Approximate Boring Depth (feet)	Location
15	21 to 51.5	Proposed BESS Area
2	51.5	Proposed Substation Area
2	21.5	Proposed O&M Building Area
4	3 and 5	Proposed Infiltration Area
7	50.5 and 51.5	Proposed Transmission Line

Boring Layout and Elevations: Terracon personnel provided the boring layout using handheld GPS equipment (estimated horizontal accuracy of about ± 10 feet) and referencing existing site features. Approximate ground surface elevations were estimated using Google Earth. If elevations and a more precise boring layout are desired, we recommend borings be surveyed.

Subsurface Exploration Procedures: We advanced the borings with a track-mounted drill rig using continuous hollow stem flight. Four samples were obtained in the upper 10 feet of each boring and at intervals of 5 feet thereafter. Test samples were collected during drilling in general accordance with the appropriate ASTM methods using Standard Penetration Testing (SPT) and sampling using either standard split-spoon or Modified California samplers. A sampling spoon was driven into the ground by a 140-pound automatic hammer falling a distance of 30 inches. The number of blows required to advance the sampling spoon the last 12 inches of a normal 18-inch penetration was recorded as the Standard Penetration Test (SPT) resistance value, also referred to as N-values. The N-values are indicated on the boring logs at the test depths. The samples were placed in appropriate containers, taken to our soil laboratory for testing, and classified by a geotechnical engineer.

For safety purposes and as required by Los Angeles County, all borings were backfilled with grout after their completion.

We also observed the boreholes while drilling and at the completion of drilling for the presence of groundwater. Groundwater was not encountered at the time of drilling.

The sampling depths, penetration distances, and other sampling information was recorded on the field boring logs. The samples were placed in appropriate containers and taken to our soil laboratory for testing and classification by a Geotechnical Engineer. Our



exploration team prepared field boring logs as part of the drilling operations. These field logs included visual classifications of the materials observed during drilling and our interpretation of the subsurface conditions between samples. Final boring logs were prepared from the field logs. The final boring logs represent the Geotechnical Engineer's interpretation of the field logs and include modifications based on observations and tests of the samples in our laboratory.

Electrical Resistivity Testing: Soil electrical resistivity data was be obtained in accordance with ASTM G57 Standard Test Method for Field Measurement of Soil Resistivity Using the Wenner Four-Electrode Method. At the test location, two near perpendicular lines was tested. Electrode "a" spacings are summarized in the following table. Electrode spacing was adjusted to conform to site conditions.

No. of Test Locations	Electrode "a" Spacing (feet)	Planned Location
7	2, 4, 6, 8, 12, 20, 30, 50, 70, 100, 150 and 300 feet	Proposed BESS and Substation Areas

Laboratory Testing

The project engineer reviewed the field data and assigned laboratory tests. The laboratory testing program included the following types of tests:

- Moisture Content
- Dry Unit Weight
- Atterberg Limits
- Compaction
- Swell Consolidation Test
- Direct Shear
- Corrosivity
- Thermal Resistivity
- California Bearing Ratio

The laboratory testing program often included examination of soil samples by an engineer. Based on the results of our field and laboratory programs, we described and classified the soil samples in accordance with the Unified Soil Classification System.



Site Location and Exploration Plans

Contents:

Site Location Plan Exploration Plan

Site Location

een Valley

Ν

> bing

Elizabeth Lake



Agua Dulce

14


MAP PROVIDED BY MICROSOFT BING MAPS

© 2025 Microsoft Corporation © 2025 TomTom Earthstar Geographics SIQ

5 miles



Exploration Plan




Geotechnical Engineering Report

Prairie Song Reliability Projectl Acton, Los Angeles County, California Terracon Project No. LA245085



Sheet 1 Exploration Plan - BESS and Substation Locations




Geotechnical Engineering Report

Prairie Song Reliability Projectl Acton, Los Angeles County, California Terracon Project No. LA245085




Sheet 2 Exploration Plan - BESS and Substation Locations





Sheet 3 - Exploration Plan - T-Line Exploration Locations



Exploration and Laboratory Results

Contents:

Boring Logs Atterberg Limits Full Sieve Compaction Graphs Direct Shear Graphs Consolidation Results Corrosivity Results California Bearing Ratio Thermal Resistivity Testing Results Electrical Resistivity Results



	Atterberg Limits	t cf)	(%	, st	be	ns el		Location: See Exploration Plan	bo:	-el	/er
Percent	LL-PL-PI	Dry Unit Weight (pcf)	Water Content (%)	Field Test Results	Sample Type	Water Level Observations	Depth (Ft.)	Latitude: 34.4829° Longitude: -118.1491°	Graphic Log	модет сауег	Model La
		_			+			Depth (Ft.) SILTY SAND (SM), trace gravel, light brown	340	-	
32		119	<u>2.3</u> 3.3	15-50/4"	÷			very dense			
			5.5	10 00,1	î						
-				15-39-30			5 —				
				N=69	Ą		-				
		_	-		-			dense			
		123	2.0	16-28-31	Å.						
		-		16-23-30			10-	very dense			
3 25	20-17-3			16-23-30 N=53	Ă,					-	
					-		15–	medium dense			
		109	0.9	10-21-33	à.		-				
							2				
				14-25-26	\downarrow	1	20-	very dense			
				N=51	Ą		8				
				17-29-35	\downarrow		25–	brown			
				N=64	Ą						
							-				
							30	30.0	-		
	Drill Rig D-50		Water Level Observations Groundwater not encountered					ee Exploration and Testing Procedures for a description of field and laboratory rocedures used and additional data (If any). ee Supporting Information for explanation of symbols and abbreviations.			
Hammer Type Automatic											
	Terracon						Advancement M Hollow Stem Auge	lotes			
	AT										
24	12-24-2024		entonite	Cuttings and/or B			Abandonment M Boring backfilled				
tic n b 02	Hamme Automat Driller Terracor Logged AT Boring S		entonite		1	letho o Jer Methoo	Advancement M Hollow Stem Aug Abandonment M	See Supporting Information for explanation of symbols and abbreviations. Elevation Reference: Elevations obtained from Google Earth Notes			




Model Layer	Graphic Log	Location: See Exploration Plan Latitude: 34.4829° Longitude: -118.1491° Depth (Ft.) <u>SILTY SAND (SM)</u> , brown, very dense	Depth (Ft.)	Water Level Observations	Sample Type	Tield Test N=90 N=90	Water Content (%)	Dry Unit Weight (pcf)	Atterberg Limits	Percent Fines
2	11	 35.0 POORLY GRADED SAND WITH SILT (SP-SM), trace gravel and clay light brown, very dense 40.0 SILTY SAND (SM), trace gravel, brown, very dense 	,, 35- - - - - 40-		X	22-29-36 N=65 20-25-26				
See	Explo	ration and resting ribectaries for a description of nera and laboratory	er Level Ob						Drill Rig	
See Supporting Information for explanation of symbols and abbreviations. Elevation Reference: Elevations obtained from Google Earth Notes		orting Information for explanation of symbols and abbreviations. Reference: Elevations obtained from Google Earth Adv Holio	Groundwa ancement N w Stem Aug ndonment I 19 backfilled	lethoo er Metho	i d	untered Cuttings and/or Bo	entonite		D-50 Hammer Typ Automatic Driller Terracon Logged by AT Boring Start 12-24-2024 Boring Comp 12-24-2024	ed



Model Layer	Graphic Log	Location: See Exploration Plan Latitude: 34.4823° Longitude: -118.1484° Depth (Ft.)	Depth (Ft.)	Water Level Observations	Sample Type	Field Test Results	Water Content (%)	Dry Unit Weight (pcf)	Atterberg Limits LL-PL-PI	Percent Fines
1		<u>SILTY SAND (SM)</u> , reddish brown medium dense			res (6-8-8 N=16	-			
		brown 7.5	5		X	11-17-20	2.1	119		
		dense	10-		X	9-14-18 N=32 28-38-42	0.7	118		26
2					A	20 30 42		110		
			- 15 - -		X	9-15-17 N=32				
		very dense 21.0 Boring Terminated at 21 Feet	20-		X	34-50/6"	1.8	106		
See	Suppo	ation and Testing Procedures for a description of field and laboratory s used and additional data (If any). rting Information for explanation of symbols and abbreviations. Reference: Elevations obtained from Google Earth	Water Level Ob Groundwa			untered			Drill Rig D-50 Hammer Typ Automatic Driller	e
Not	es		Advancement M Hollow Stem Aug Abandonment M Boring backfilled	er 1etho	d	Cuttings and/or B	entonite		Terracon Logged by JB Boring Start 01-08-2025 Boring Comp 01-08-2025	








Rodel Layer	Graphic Log	Location: See Exploration Plan Latitude: 34.4828° Longitude: -118.1475° Depth (Ft.) SILTY SAND (SM), brown, very dense 35.0 POORLY GRADED SAND WITH SILT (SP-SM), trace gravel, brown, dense	(:-:) Debth (:-:) 	Water Level Observations	Sample Type	ts st Plane 19-28-38 N=66 23-25-27 N=52	Water Content (%)	Dry Unit Weight (pcf)	Atterberg Limits	Percent Fines
		41.5 Boring Terminated at 41.5 Feet	40-		X	26-36-46 N=82				
proo See	edures Suppo ation I	s used and additional data (If any). prting Information for explanation of symbols and abbreviations. Reference: Elevations obtained from Google Earth Hollo Abar	er Level Ob Groundwa mcement M w Stem Aug donment I g backfilled	ter not lethoo jer Methoo	t enco 1 d	untered Cuttings and/or Be	entonite		Drill Rig D-50 Hammer Typ Automatic Driller Terracon Logged by AT Boring Start 12-24-2024	ed







2 Model Layer	Graphic Log	Location: See Exploration Plan Latitude: 34.4836° Longitude: -118.1464° Depth (Ft.) <u>SILTY SAND (SM)</u> , trace gravel, brown, very loose	- Depth (F.) - - - - - - - - - - - - - - - - - - -	Water Level Observations	Sample Type	17-34-37 N=71 32-50/6"	Water Content (%)	Dry Unit Weight (pcf)	Atterberg Limits	Percent
	211	40.0 POORLY GRADED SAND WITH SILT (SP-SM), brown, very de 41.0 Boring Terminated at 41 Feet			X	28-50/6"				
See	Explor edures	ation and Testing Procedures for a description of field and laboratory s used and additional data (If any).	Water Level Ob Groundwa						Drill Rig CME-75	
See	Suppo ation F	rting Information for explanation of symbols and abbreviations. Reference: Elevations obtained from Google Earth	Advancement N Hollow Stem Aug Abandonment I Boring backfilled	jer Metho	d	Cuttings and/or Be	entonite		Hammer Typ Automatic Driller 2R Logged by JB Boring Starte 01-08-2025 Boring Comp 01-08-2025	ed



Model Layer	Graphic Log	Location: See Exploration Plan Latitude: 34.4839° Longitude: -118.1454° Depth (Ft.)	Depth (Ft.)	Water Level Observations	Sample Type	Field Test Results	Water Content (%)	Dry Unit Weight (pcf)	Atterberg Limits LL-PL-PI	Percent Fines
1		SILTY SAND (SM), brown medium dense 10.0 very dense dense	5			8-16-19 6-9-10 N=19 6-9-17 20-32-35 N=67 18-26-29	1.5 1.6 1.9 2.8	104		17
		21.5 Boring Terminated at 21.5 Feet			X	12-15-17 N=32				
proc See	edures Suppo ation f	ation and Testing Procedures for a description of field and laboratory s used and additional data (If any). rting Information for explanation of symbols and abbreviations. Reference: Elevations obtained from Google Earth	Water Level Ob Groundwa Advancement M Hollow Stem Aug Abandonment I Boring backfilled	ter not lethoo er Methoo	encou I	untered Cuttings and/or Be	entonite		Drill Rig 6-Tech Hammer Typ Automatic Driller Terracon Logged by JB Boring Start 01-06-2025 Boring Comp 01-06-2025	ed



Aer	Log	Location: See Exploration Plan	(;;)	vel	ype	s	r (%)	hit pcf)	Atterberg Limits	
модеі цауег	Graphic Log	Latitude: 34.4828° Longitude: -118.1444°	Depth (Ft.)	Water Level Observations	Sample Type	Field Test Results	Water Content (%)	Dry Unit Weight (pcf)	LL-PL-PI	Percent
_	111	Depth (Ft.)					-			
		SILTY SAND (SM), light brown, trace gravel			m					
			-							
1		medium dense	-		M	5-9-13 N=22				
		5.0	5 -			50/6"	6.2	106		
2		brown, dense	-			50/0	0.2	100		
-		7.5 light brown, medium dense			V	6-8-10 N=18	-			
			-			N=10	-			
1			10-		X	11-18-20	1.0			
			-							
		15.0	L							
		dense	15-		X	16-21-22 N=43				
			-							
			20-		X	16-21-24 N=45			NP	16
2			-							
			25-		X	24-50/6"	1.4	111		
			-							
		30.0	30-							
ee roc	Explor edures	ation and Testing Procedures for a description of field and laboratory sused and additional data (If any).	Water Level Ob Groundwa						Drill Rig 6-Tech	
		rting Information for explanation of symbols and abbreviations. Reference: Elevations obtained from Google Earth							Hammer Typ Automatic	be
lote			Advancement N	latho	d				Driller Terracon	
.010			Hollow Stem Aug						Logged by JB	
									Boring Start	



A Model Layer	Graphic Log	Location: See Exploration Plan Latitude: 34.4828° Longitude: -118.1444° Depth (Ft.) SILTY SAND (SM), light brown, very dense	- Depth (F.) - - - - - - - - - - - - - - - - - - -	Water Level Observations	Sample Type	ts ss Pail ss 18-35-36 N=71 20-29-22 N=51	Water Content (%)	Dry Unit Weight (pcf)	Atterberg Limits	Fines
		41.5 Boring Terminated at 41.5 Feet	40-			13-13-19 N=32				
proc See	edures Suppo ation F	ation and Testing Procedures for a description of field and laboratory s used and additional data (If any). rting Information for explanation of symbols and abbreviations. Reference: Elevations obtained from Google Earth	Water Level Ob Groundwar Advancement M Hollow Stem Aug Abandonment M Boring backfilled	ter not lethoo er letho	encoi I	untered Cuttings and/or Be	entonite		Drill Rig 6-Tech Hammer Typ Automatic Driller Terracon Logged by JB Boring Starts 01-06-2025 Boring Comp 01-06-2025	ed



-	D	Location: See Exploration Plan			e			6	Atterberg	
Model Layer	Graphic Log	Latitude: 34.4834° Longitude: -118.1434°	Depth (Ft.)	Water Level Observations	Sample Type	Field Test Results	Water Content (%)	Dry Unit Weight (pcf)	Limits	Percent Fines
del I	aphi		bth	ter L serva	mple	eld ⁻	Wat	Jry L ight	LL-PL-PI	Fine
β	ŭ		De	Åå	Sa	Ē,	Ō	8		-
-	171	Depth (Ft.) CLAYEY SAND (SC), trace gravel, light brown		-						-
	11									
1		medium dense			4	_	-		27-15-12	31
		medium dense			X	19-23-33	2.2	125		
				1	-		-	-		
	44	5.0 <u>SILTY SAND (SM)</u> , trace gravel, brown, dense	5-				-			-
		SILTY SAND (SM), trace graver, brown, dense			X	18-21-29 N=50				
					$\langle +$		-	-	-	
		medium dense		1	-		-		<	
		medium dense		1	X.	10-26-25	1.1	106		
			-		-		-			
		4	10-				_			
		dense			X	15-19-23 N=42				
					$\langle \cdot \rangle$	11-12	-			
				1						
			-	1						
			1	-						
			15-		_		-			
		very dense	120		X	31-50/5"	2.1	118		
				1						
2										
			-	-						
			2							
			20-				_			
			20		M	21-31-38 N=69	1.1			
			- I I I	1	$\langle \gamma \rangle$	N=69				
				1						
			-	1						
			-	1						
			25-							
			25		M	26-28-38				
				1	\wedge	N=66	-			
			-							
				-						
		30.0	30-							
See	Explor	I ation and Testing Procedures for a description of field and laboratory	Water Level Ob	serva	tions				Drill Ria	-
prod	cedures	s used and additional data (If any).	Groundwa	ter not	enco	untered			Drill Rig D-50	
		rting Information for explanation of symbols and abbreviations. Reference: Elevations obtained from Google Earth							Hammer Typ Automatic	be
									Driller	
Not	es		Advancement N Hollow Stem Aug		1				Terracon Logged by	
			Ab						AT Boring Start	ed
			Abandonment Boring backfilled	with A	u uger (Cuttings and/or B	entonite		12-23-2024 Boring Comp 12-23-2024	



Model Layer	Graphic Log	Location: See Exploration Plan Latitude: 34.4834° Longitude: -118.1434° Depth (Ft.) <u>SILTY SAND (SM)</u> , trace gravel, brown, very dense	Depth (Ft.)	Water Level Observations	Sample Type	Field Test Results N=95	Water Content (%)	Dry Unit Weight (pcf)	Atterberg Limits	Percent Fines
2			- 35- - - 40-	-		20-35-38 N=73 30-37-45 N=82	-			
proc See	Exploredures	41.5 Boring Terminated at 41.5 Feet Boring Terminated at 41.5 Feet Sector 100 - 100	Water Level Ob Groundwa						Drill Rig D-50 Hammer Typ Automatic	Pe
Not		Server, Lievations obtained from Google Edith	Advancement M Hollow Stem Aug Abandonment M Boring backfilled	er 4etho	d	Cuttings and/or Be	entonite		Automatic Driller Terracon Logged by AT Boring Start 12-23-2024 Boring Comp 12-23-2024	



L	б	Location: See Exploration Plan	1		φ			Ð	Atterberg Limits	
Model Layer	Graphic Log	Latitude: 34.4831° Longitude: -118.1427°	Depth (Ft.)	Water Level Observations	Sample Type	Field Test Results	Water Content (%)	Dry Unit Weight (pcf)	LIITIIUS	Percent Fines
del	aphi		pth	ater I	mple	ield Resu	Wat	Dry I eight	LL-PL-PI	Perc
Σ	Ģ		Ĕ	j≥g	ů	LL I	Ŭ	-»		
		Depth (Ft.) SILTY SAND (SM), brown		-				-	_	
1				-	SWA					
				_						
		medium dense			1	11 10 11				-
					М	11-10-11 N=21			19-16-3	26
4				7						
1		trace gravel	5		W		-			
				-	À	8-15-16	2.4	115		
				-		1				
4		medium dense		_	M	9-10-16				
					M	9-10-16 N=26				
		10.0		7			1.00			
		dense	10		W	12 27 40	27	110	5	
				-	à	12-37-48	2.7	116		
				-						
				-						
				4						
		15.0	15							
2		POORLY GRADED SAND (SP), trace gravel and silt, light brown dense	, very		M	19-28-33				
				1	\square	N=61				
				-						
				-						
				_						
		20.0	20	_	_					
		POORLY GRADED SAND WITH SILT (SP-SM), brown, dense	20		Y	20-48-40	1.4			
		21.5 Boring Terminated at 21.5 Feet		-			-	-		
		bonny reminated at 21.5 reet								1
	_									
See	Explor	ation and Testing Procedures for a description of field and laboratory used and additional data (If any).	Water Level C Groundw						Drill Rig D-50	
		rting Information for explanation of symbols and abbreviations.	c. oundw						Hammer Typ)e
Elev	ation F	Reference: Elevations obtained from Google Earth							Automatic	
Not	es		Advancement	Metho	d				Driller Terracon	
			Hollow Stem Au						Logged by	
									OW Boring Start	od
			Abandonment Boring backfille			Cuttings and/or B	entonite		Boring Start 12-20-2024	ea
						2			Boring Comp 12-20-2024	leted



Model Layer	Graphic Log	Location: See Exploration Plan Latitude: 34.4838° Longitude: -118.1424° Depth (Ft.)	Depth (Ft.)	Water Level Observations	Sample Type	Field Test Results	Water Content (%)	Dry Unit Weight (pcf)	Atterberg Limits LL-PL-PI	Percent Fines
		 SILTY SAND (SM), brown to light brown very dense 7.5 POORLY GRADED SAND (SP), trace silt, trace gravel, brown, de light brown	ense 10-			33-37-50/5" 30-49-50/4" 24-49-46 11-14-24	3.2	125		
2			prown, 15-			24-48-50/4" 32-35-35 N=70	2.1	117		
		21.5 Boring Terminated at 21.5 Feet								
proo See	edures Suppo ation f	ation and Testing Procedures for a description of field and laboratory s used and additional data (If any). rrting Information for explanation of symbols and abbreviations. Reference: Elevations obtained from Google Earth	Water Level Ot Groundwa Advancement I Hollow Stem Aug	iter not	: enco				Drill Rig D-50 Hammer Typ Automatic Driller Terracon	e
			Abandonment	Metho	d luger	Cuttings and/or Be	ntonite		Logged by OW Boring Start 12-20-2024 Boring Comp 12-20-2024	



Model Layer	Graphic Log	Location: See Exploration Plan Latitude: 34.4835° Longitude: -118.1417° Depth (Ft.)	Depth (Ft.)	Water Level Observations	Sample Type	Field Test Results	Water Content (%)	Dry Unit Weight (pcf)	Atterberg Limits LL-PL-PI	Percent Fines
	00000	SILTY SAND WITH GRAVEL (SM), brown medium dense			ens.	8-11-11				36
1	000000		5 -		Å	N=22 13-23-25	2.2	115		
	000	7.5 <u>SILTY SAND (SM)</u> , trace gravel, brown, very dense					_			
		dense	- 10-			18-32-42 N=74			NP	26
		uense	-	-	Ă	23-28-33	3.3	111		
		15.0 POORLY GRADED SAND WITH GRAVEL (SP), trace silt, light very dense	- 			12-28-39				
	0.00000000					N=67				
2	00000000	dense	- 20- -		X	24-35-48	1.3	6		
	0000000									
	000000		25-		X	43-28-34 N=62	-			
	00	30.0								
prod See	Explor cedures Suppo	ation and Testing Procedures for a description of field and laboratory s used and additional data (If any). rting Information for explanation of symbols and abbreviations. Reference: Elevations obtained from Google Earth	Water Level Ob Groundwa			untered	1		Drill Rig D-50 Hammer Typ Automatic	e
Not	es		Advancement M Hollow Stem Aug		1				Driller Terracon Logged by OW	
			Abandonment I Boring backfilled			Cuttings and/or B	entonite		OW Boring Start 12-20-2024 Boring Comp 12-20-2024	



Model Layer	Graphic Log	Location: See Exploration Plan Latitude: 34.4835° Longitude: -118.1417° Depth (Ft.) <u>POORLY GRADED SAND WITH GRAVEL (SP)</u> , trace silt, light brow very dense	, u, Depth (Ft.)	Water Level Observations	Sample Type	Field Test Results 50-46-20/4.	Water Content (%)	Dry Unit Weight (pcf)	Atterberg Limits LL-PL-PI	Percent Fines
2		41.3	35- - 40-		X	28-33-38 N=71 31-48-50/4"				
proc	Explor	Boring Terminated at 41.3 Feet	ater Level Obs Groundwat						D-50	
	ation F	Hoi Ab	vancement M Ilow Stem Aug andonment M ring backfilled	er letho d	d	Cuttings and/or Be	ntonite		Hammer Typ Automatic Driller Terracon Logged by OW Boring Start 12-20-2024 Boring Comp 12-20-2024	ed



-	Ď	Location: See Exploration Plan			_ v	ø		(0)	Ę.	Atterberg Limits	
Model Layer	Graphic Log	Latitude: 34.4838° Longitude: -118.1409°		Depth (Ft.)	Water Level Observations	Sample Type	Field Test Results	Water Content (%)	Dry Unit Weight (pcf)	LL-PL-PI	Percent Fines
		Depth (Ft.)				-		-		-	-
1	0000000	SILTY SAND WITH GRAVEL (SM), light brown medium dense				X	9-23-24	1.1	124	NP	19
	0			5	1	Т	n n				
	1000000000	medium dense 5.0 very dense		5 -	-	×	50/6" 36-50/6"	2.4			
	0000000			- 10- -		Х	17-24-36 N=60				
2	0000	15.0 POORLY GRADED SAND WITH SILT (SP-SM), brown, dense		15-	-	X	17-22-50/6"	1.3	110		
		very dense 20.9 Boring Terminated at 20.9 Feet		- - 20-		X	40-50/5"				
prod See Elev	sedures Suppo vation	ation and Testing Procedures for a description of field and laboratory s used and additional data (If any). rting Information for explanation of symbols and abbreviations. Reference: Elevations obtained from Google Earth		roundwa	ter not	: enco	untered			Drill Rig D-50 Hammer Typ Automatic Driller	e
Not	es		Advance Hollow St Abandor Boring ba	tem Aug nment I	jer Metho	d	Cuttings and/or Be	entonite		Terracon Logged by OW Boring Start 12-19-2024 Boring Comp 12-19-2024	




ierracon

Model Layer	Graphic Log	Location: See Exploration Plan Latitude: 34.4843° Longitude: -118.1400° Depth (Ft.)	Depth (Ft.)	Water Level Observations	Sample Type	Field Test Results	Water Content (%)	Dry Unit Weight (pcf)	Atterberg Limits LL-PL-PI	Percent Fines
		SILTY SAND (SM), trace gravel, light brown very dense dense			r X	24-26-47 N=73 26-41-42	3.9	123		
	00000000000000000000000000000000000000	7.5 POORLY GRADED SAND WITH SILT AND GRAVEL (SP-SM), lig medium dense	- ght brown, _ - 10- -		X	8-11-15 N=26 6-18-21	0.9		6	
2		dense	- 15- -		X	11-15-16 N=31				
					X	14-30-42	1.8	106		
	00000000000000000000000000000000000000	very dense 30.0	25-		X	30-35-42 N=77				
proc See	edures Suppo	ation and Testing Procedures for a description of field and laboratory s used and additional data (If any). rting Information for explanation of symbols and abbreviations. Reference: Elevations obtained from Google Earth	Water Level Ob Groundwa			untered	1		Drill Rig D-50 Hammer Typ Automatic	je
Not	es		Advancement M Hollow Stem Aug Abandonment I Boring backfilled	er 1etho	d	Cuttings and/or B	entonite		Driller Terracon Logged by AT Boring Start 12-23-2024 Boring Comp 12-23-2024	



Model Layer	Graphic Log	Location: See Exploration Plan Latitude: 34.4843° Longitude: -118.1400°	Depth (Ft.)	Water Level Observations	Sample Type	Field Test Results	Water Content (%)	Dry Unit Weight (pcf)	Atterberg Limits	Percent Fines
	00000000	Depth (Ft.) POORLY GRADED SAND WITH SILT AND GRAVEL (SP-SM) , light h very dense			X	21-31-43 N=74				
2	· · · · · · · · · · · · · · · · · · ·		- 35- -		X	19-35-42 N=77				
	200000	41.5 Boring Terminated at 41.5 Feet	40-		X	21-47-50/6"				
prod See	Suppo Suppo vation I	s used and additional data (If any). orting Information for explanation of symbols and abbreviations. Reference: Elevations obtained from Google Earth	er Level Ob Groundwa	ter not	enco				Drill Rig D-50 Hammer Typ Automatic Driller Terracon	e
		Holic	ow Stem Aug	er 1etho	1	Cuttings and/or Be	ntonite		Logged by AT Boring Start 12-23-2024 Boring Comp 12-23-2024	







/er	бo	Location: See Exploration Plan	· ·	la sc	e		(%	cf)	Atterberg Limits	
Model Layer	Graphic Log	Latitude: 34.4850° Longitude: -118.1389°	Depth (Ft.)	Water Level Observations	Sample Type	Field Test Results	Water Content (%)	Dry Unit Weight (pcf)	LL-PL-PI	Percent Fines
		Depth (Ft.) POORLY GRADED SAND (SP) , trace silt and gravel, light brown, very dense		-	X	14-41-18 N=59				
			35-	-	X	15-23-29 N=52				
2			40-		X	24-50/5"				
		45.0 POORLY GRADED SAND WITH GRAVEL (SP), light brown, very der		-	Х	20-35-40 N=75				
	'·())0 0	50.8 Boring Terminated at 50.8 Feet	50-		X	29-50/4"				
proc See	edures Suppo	ation and Testing Procedures for a description of field and laboratory Wat used and additional data (If any). rting Information for explanation of symbols and abbreviations. Reference: Elevations obtained from Google Earth Particular State	er Level Ob Groundwa						Drill Rig D-50 Hammer Typ Automatic	be
Not	es	Holic	ancement N w Stem Aug ndonment I	jer					Driller Terracon Logged by OW Boring Start 12-19-2024	
						Cuttings and/or Be	entonite		Boring Comp 12-19-2024	



Model Layer	Graphic Log	Location: See Exploration Plan Latitude: 34.4854° Longitude: -118.1394° Depth (Ft.)	Depth (Ft.)	Water Level Observations	Sample Type	Field Test Results	Water Content (%)	Dry Unit Weight (pcf)	Atterberg Limits LL-PL-PI	Percent Fines
1	000000000000000000000000000000000000000	SILTY SAND WITH GRAVEL (SM), brown loose medium dense	5	-	₩3 X	3-5-4 N=9 8-10-13	3.5	119		
		dense medium dense	10-		X	7-12-24 N=36	4.2	113		32
2		20.0	15- - - - - - - - - - - - 		X	8-18-19 N=37				
		21.5 Boring Terminated at 21.5 Feet				14-30-31	1.4	113		
pro See	Suppo Suppo vation f	sused and additional data (If any). rting Information for explanation of symbols and abbreviations. Reference: Elevations obtained from Google Earth Hol	ter Level Ob Groundwa vancement N low Stem Aug andonment I ing backfilled	ter not lethoo jer Methoo	: enco 1	untered Cuttings and/or Be	entonite		Drill Rig D-50 Hammer Typ Automatic Driller Terracon Logged by OW Boring Start 12-18-2024 Boring Comp 12-18-2024	ed



ver	Бо:	Location: See Exploration Plan			ns el	/pe	š	(%	it ocf)	Atterberg Limits	
Model Layer	Graphic Log	Latitude: 34.4857° Longitude: -118.1383°		Depth (Ft.)	Water Level Observations	Sample Type	Field Test Results	Water Content (%)	Dry Unit Weight (pcf)	LL-PL-PI	Percent Fines
-	XX	Depth (Ft.) SILTY CLAYEY SAND (SC-SM), brown				T		-			-
2		very dense				X	37-50/5"	2.1	124	21-15-6	41
		medium dense		5 -		Å	4-4-6 N=10				
		7.5 SILTY SAND (SM), brown, medium dense		i - j		V	10-24-28	2.6	112		
				-		A					
1				10-		X	11-8-8 N=16				
				5							
	0	15.0 SILTY SAND WITH GRAVEL (SM), brown, medium dense		15–		W	0.10.20	2.1	104		
	Po			-		A.	8-19-26	3.1	104		
	00000000	20.0		- 20-							
	10	POORLY GRADED SAND WITH GRAVEL (SP), trace silt, brown	n, dense	20-		X	8-14-26 N=40				
2	000000000										
	00000	very dense		25		X	7-25-32				
	000000			6							
) o (30.0		30-							
See	Explor	ation and Testing Procedures for a description of field and laboratory sused and additional data (If any).	Water Le Gro				untered			Drill Rig D-50	
		rting Information for explanation of symbols and abbreviations. Reference: Elevations obtained from Google Earth								Hammer Typ Automatic	e
Not			Advance	ment M	lethor	1				Driller Terracon	
			Hollow Ste							Logged by OW	
			Abandon							Boring Start	ed
			Boring ba	ckfilled	with A	uger	Cuttings and/or B	entonite		Boring Comp 12-19-2024	oleted




Model Layer	Graphic Log	Location: See Exploration Plan Latitude: 34.4857° Longitude: -118.1383° Depth (Ft.)	Depth (Ft.)	Water Level Observations	Sample Type	Field Test Results	Water Content (%)	Dry Unit Weight (pcf)	Atterberg Limits LL-PL-PI	Percent Fines
2		POORLY GRADED SAND (SP), trace silt, light brown, very dense 35.0 POORLY GRADED SAND WITH GRAVEL (SP), trace silt, light brown an white, very dense	- - - - - - - - - - - - - - - - - - -		X	18-31-31 N=62 24-50/6" 34-44-48				
		Boring Terminated at 41.5 Feet				N=92				
proc See	edures Suppo ation F	ation and Testing Procedures for a description of field and laboratory Water L s used and additional data (If any). G rting Information for explanation of symbols and abbreviations. G Reference: Elevations obtained from Google Earth Advance Hollow S S	roundwa	ter not letho	enco	buntered			Drill Rig D-50 Hammer Typ Automatic Driller Terracon Logged by	e
		Abando Boring b	nment I ackfilled	Metho with A	d luger	Cuttings and/or Be	ntonite		OW Boring Start 12-19-2024 Boring Comp 12-19-2024	

Model Layer	Graphic Log	Location: See Exploration Plan Latitude: 34.4865° Longitude: -118.1375° Depth (Ft.)	Depth (Ft.)	Water Level Observations	Sample Type	Field Test Results	Water Content (%)	Dry Unit Weight (pcf)	Atterberg Limits LL-PL-PI	Percent Fines
2		SILTY SAND WITH GRAVEL (SM), brown dense			X	21-28-32	2.3	125		28
1		SILTY CLAYEY SAND (SC-SM), light brown, dense brown, medium dense	-			15-15-19 N=34 13-16-17	1.4	109	19-15-4	20
		10.0 POORLY GRADED SAND WITH SILT (SP-SM), trace gravel, light to brown, medium dense	brown 10-		X	8-11-14 N=25			0	10
			15-		X	17-24-32	1.1	109		
2		light brown and white, very dense	20-		X	15-41-32 N=73				
			25-		X	15-24-32 N=56				
Ser	- Expl	30.0 oration and Testing Procedures for a description of field and laboratory	ater Level Of	serva	tions				Drill Rig	
pro See	e Supp	••••••••••••••••••••••••••••••••••••••	Groundwa			untered			D-50 Hammer Tyj Automatic	pe
No	tes	Ho	dvancement I ollow Stem Aug bandonment bring backfilled	jer Metho	d	Cuttings and/or B	entonite		Driller Terracon Logged by OW Boring Start 12-18-2024 Boring Comp 12-18-2024	



er	бc	Location: See Exploration Plan		~	- 2	e	ц.	(%)	. G	Atterberg Limits	
Model Layer	Graphic Log	Latitude: 34.4865° Longitude: -118.1375°		Depth (Ft.)	Water Level Observations	Sample Type	Field Test Results	Water Content (%)	Dry Unit Weight (pcf)	LL-PL-PI	Percent Fines
		Depth (Ft.) POORLY GRADED SAND WITH SILT (SP-SM), trace gravel, br dense	rown, very			Х	21-23-35 N=58				
		35.0 SILTY SAND (SM) , trace gravel, brown, very dense		35- - -		Х	30-33-48 N=81				
2				40— - -		Х	21-26-34 N=60				
		45.0 POORLY GRADED SAND WITH SILT (SP-SM) , trace gravel, gr brown, very dense	ray and	 45 		Х	22-44-50/4"	-			
		50.0 POORLY GRADED SAND (SP), trace silt and gravel, light brown 51.5 Boring Terminated at 51.5 Feet	i, dense			X	11-19-26 N=45				
		Boring Terminated at 51.5 Feet									
proc See	edure: Suppo	ation and Testing Procedures for a description of field and laboratory s used and additional data (If any). orting Information for explanation of symbols and abbreviations. Reference: Elevations obtained from Google Earth	Water Le Gro				untered			Drill Rig D-50 Hammer Typ Automatic Driller	e
Not	es		Advancen Hollow Ste Abandoni Boring bac	em Aug ment M	er 1etho	d	Cuttings and/or Be	ntonite		Terracon Logged by OW Boring Start 12-18-2024 Boring Comp 12-18-2024	





Model Layer	Graphic Log	Location: See Exploration Plan Latitude: 34.4871° Longitude: -118.1358°	Depth (Ft.)	Water Level Observations	Sample Type	Field Test Results	Water Content (%)	Dry Unit Weight (pcf)	Atterberg Limits	Percent Fines
Mod	Grap		Dept	Wate	Sam	Fiel Re	Cont	Dr Weig	LL-PL-PI	Pe F
		Depth (Ft.) POORLY GRADED SAND WITH SILT (SP-SM) , trace gravel, light very dense	t brown,	-	X	19-29-50/4"				
2		40.0 <u>SILTY SAND (SM)</u> , brown and gray, very dense				28-34-39 N=73 18-38-48 N=86				
	6000 0000 0000	45.0 SILTY SAND WITH GRAVEL (SM), reddish brown, very dense	45		X	29-34-50/5"				
	000	50.9 Boring Terminated at 50.9 Feet	50		×	25-50/5"	-			
pro	cedure	s used and additional data (If any).	Water Level O Groundw						Drill Rig D-50	
	ation	orting Information for explanation of symbols and abbreviations. Reference: Elevations obtained from Google Earth A	Advancement Hollow Stem Au	Metho Iger	d				Hammer Type Automatic Driller Terracon Logged by OW	e
		A B	Abandonment Boring backfille	Metho d with a	d Auger	Cuttings and/or Be	entonite		Boring Starte 12-19-2024 Boring Compl	





Boring Log No. OM-1

yer	Бо,	Location: See Exploration Plan		ns Î	/be	st	(%	it Scf)	Atterberg Limits	
Model Layer	Graphic Log	Latitude: 34.4863° Longitude: -118.1385°	Depth (Ft.)	Water Level Observations	Sample Type	Field Test Results	Water Content (%)	Dry Unit Weight (pcf)	LL-PL-PI	Percent Fines
	10	Depth (Ft.) SILTY SAND WITH GRAVEL (SM), brown		-			-			-
	00000000000	medium dense	5-		X	25-25-30	7.0	124	33-16-17	50
		SILTY SAND (SM), trace gravel, loose			X	6-4-4 N=8				
1					X	5-8-8	4.2	116		
			10-		X	4-4-5 N=9				
		15.0 medium dense	15-		X	7-12-18	3.8	113	*	
2		20.0	20							
	0	POORLY GRADED SAND WITH GRAVEL (SP), trace silt, brown, c	lense 20-		M	19-19-20 N=39				
	2	21.5 Boring Terminated at 21.5 Feet		-	\square	N=39				-
See	Fxplor	ation and Testing Procedures for a description of field and laboratory	/ater Level O	bserva	tions				Drill Rig	
proc See	edures Suppo	s used and additional data (If any). rting Information for explanation of symbols and abbreviations. Reference: Elevations obtained from Google Earth	Groundwa			untered			D-50 Hammer Typ Automatic	e
Not	es		dvancement ollow Stem Au		1				Driller Terracon Logged by OW	
		A Bo	bandonment oring backfilled	Metho d with A	d luger (Cuttings and/or B	entonite		Boring Start 12-18-2024 Boring Comp 12-18-2024	



Boring Log No. OM-2

Model Layer	Graphic Log	Location: See Exploration Plan Latitude: 34.4860° Longitude: -118.1389° Depth (Ft.)	Depth (Ft.)	Water Level Observations	Sample Type	Field Test Results	Water Content (%)	Dry Unit Weight (pcf)	Atterberg Limits LL-PL-PI	Percent Fines
		CLAYEY SAND (SC), trace gravel, brown			es X	2-2-4 N=6				30
and a second		5.0 SILTY CLAYEY SAND (SC-SM), brown, loose	5	-	X	5-5-9	4.4	105		
1		10.0	10	-	X	6-7-9 N=16			21-17-4	44
		SILTY SAND (SM), brown, medium dense			X	9-10-12	2.5	110	4 4 1	
		15.0 POORLY GRADED SAND (SP), trace silt, light brown, medium d	Jense 15			3-6-10				
2				-	Å	N=16	-			
		dense 21.5	20		Ý	46-46-37	3.0	118	6	
		Boring Terminated at 21.5 Feet								
prod See	cedures Suppo	ation and Testing Procedures for a description of field and laboratory s used and additional data (If any). rting Information for explanation of symbols and abbreviations. Reference: Elevations obtained from Google Earth	Water Level (Ground			buntered			Drill Rig D-50 Hammer Typ Automatic)e
Not	es		Advancemen Hollow Stem A Abandonmen Boring backfill	uger t Metho	od	Cuttings and/or B	entonite		Driller Terracon Logged by OW Boring Start 12-18-2024 Boring Comp 12-18-2024	




	Location: See Exploration Plan		us el	/be	s t	(%)	it ocf)	Atterberg Limits	1
Graphic Log	Latitude: 34.4818° Longitude: -118.1378°	Depth (Ft.)	Water Level Observations	Sample Type	Field Test Results	Water Content (%)	Dry Unit Weight (pcf)	LL-PL-PI	Percent
	Depth (Ft.)		-0				>		
	SILTY SAND (SM), light brown							· / 1	
		_							
	medium dense			*	12 11 10				1
				A.	12-11-10	1.1	111		
		5 -				-			_
		2		Х	4-5-6 N=11	1.6	116		
				Ŧ	10-18-25				
		-		-		-			
	very dense	10-			6-23-28	-			
		5		Å	6-23-28 N=51	-			
		15-	1						
		15		X	20-50/5"	2.6	112]	
		20-	1						
		1		Х	16-36-44 N=80				
		-							
		-							
		25-		V	8-40-23				
				\wedge	N=63				
		30-							
Explo	ation and Testing Procedures for a description of field and laboratory	Water Level Ob				-		Drill Rig D-50	-
	s used and additional data (If any). orting Information for explanation of symbols and abbreviations.	Groundwa	ter not	encou	Intered			D-50 Hammer Typ)e
								Automatic	
es		Advancement N Hollow Stem Aug	lethoc	ł				Driller Terracon	
								Logged by OW	
		Abandonment I Boring backfilled	Metho	d Juger (Cuttings and/or B	entonite		Boring Start 01-08-2025	ed



5	ŋ	Location: See Exploration Plan		0	Φ			Û	Atterberg Limits	
Model Layer	Graphic Log	Latitude: 34.4818° Longitude: -118.1378°	Depth (Ft.)	Water Level Observations	Sample Type	Field Test Results	Water Content (%)	Dry Unit Weight (pcf)	Littits	Percent Fines
del	aphi		pth	ater L	mple	Resu	Wat	ight	LL-PL-PI	Fine
β	Ğ		De	Š ⁸ 0	Sa	Ē -	Ō	≫		-
-		Depth (Ft.) POORLY GRADED SAND WITH SILT (SP-SM), brown, very	/ danca	-			-			
		POCKET GRADED SAND WITH SIET (3P-3M), Drown, Very	/ dense	4.1	X	25-37-27 N=64	1.1			
				114	()					
	S.		,	-						
				-						
		35.0	35							
		SILTY SAND (SM), brown, very dense	55		M	12-34-50/4"				
				1	$\langle \rangle$,	-			
				-						
				-						
2			40	1		25-50/6"				
				-		25 50/0				
				7						
				1						
			45	-						
				4	A	28-50/6"				
				-						
			50	-		50/61				
	.4.1.1.	50.5 Boring Terminated at 50.5 Feet		-	\sim	50/6"				-
<u> </u>				-					_	-
See	Explo cedure	ration and Testing Procedures for a description of field and laboratory s used and additional data (If any).	Water Level O Groundw						Drill Rig D-50	
		rting Information for explanation of symbols and abbreviations.							Hammer Typ	be
									Automatic	
Not	es		Advancement	Metho	d				Driller Terracon	
			Hollow Stem Au						Logged by	
									ow	
			Abandonment	Metho	d				Boring Start 01-08-2025	ed
			Boring backfille	d with a	Auger	Cuttings and/or Be	entonite		Boring Com	pleted
									01-08-2025	





Ferracon


145 W Walnut St

Carson, CA



er	БĊ	Location: See Exploration Plan		<u>– s</u>	e	t.	(9)	. F	Atterberg Limits	
Model Layer	Graphic Log	Latitude: 34.4808° Longitude: -118.1379°	Depth (Ft.)	Water Level Observations	Sample Type	Field Test Results	Water Content (%)	Dry Unit Weight (pcf)	LL-PL-PI	Percent Fines
2	U	Depth (Ft.)		>0	0)			5		
		POORLY GRADED SAND WITH SILT (SP-SM), medium brown, d	lense –		X	16-19-22 N=41				
			- 35- -		X	8-20-26 N=46				
			- - 40-							
2			-		X	8-14-19 N=33				10
			- 45- -		X	14-18-19 N=37				
		medium dense	- - 50- -		X	13-14-13 N=27	_			
		Boring Terminated at 51.5 Feet								
See	Exploi cedure:	ration and Testing Procedures for a description of field and laboratory s used and additional data (If any).	Water Level Ob Groundwa			untered	-		Drill Rig D-50	
See		н	Advancement N Hollow Stem Aug	ler					Hammer Typ Automatic Driller Terracon Logged by JB Boring Start	
		A B	Abandonment I Boring backfilled	Metho with A	d luger (Cuttings and/or B	entonite		Boring Start 01-20-2025 Boring Comp 01-20-2025	










Model Layer	Graphic Log	Location: See Exploration Plan Latitude: 34.4838° Longitude: -118.1348°		Depth (Ft.)	Water Level Observations	Sample Type	Field Test Results	Water Content (%)	Dry Unit Weight (pcf)	Atterberg Limits	Percent Fines
Moc	Gra	Depth (Ft.)		Dep	Obs	Sar	ΞĔ	Con	Vei D	LL-PL-PI	
		SILTY SAND (SM), medium brown, very dense (continued)		-		X	16-22-24 N=46				
				- 35-		X	20-28-28 N=56				
2				- - 40-		V	16-21-21 N=42				
-				4 -			N=42				
				45		X	24-50/6"				
		51.5 Boring Terminated at 51.5 Feet		50- -		X	31-42-40 N=82				
		ation and Testing Procedures for a description of field and laboratory sused and additional data (If any). rting Information for explanation of symbols and abbreviations.	Water Le Gro				untered			Drill Rig D-50 Hammer Typ Automatic	e
Not	es		Advancer Hollow Ste Abandoni Boring bac	em Aug ment M	er 4etho	d	Cuttings and/or B	entonite		Driller Terracon Logged by JB Boring Start 01-20-2025 Boring Comp 01-20-2025	





erracon

145 W Walnut St

Carson, CA




yer	60-	Location: See Exploration Plan		us us	/pe	st	(%	it ocf)	Atterberg Limits	
Model Layer	Graphic Log	Latitude: 34.4802° Longitude: -118.1336°	Depth (Ft.)	Water Level Observations	Sample Type	Field Test Results	Water Content (%)	Dry Unit Weight (pcf)		Percent Fines
Mod	Graj		Dep	Wate Obse	Sam	Fie	Cont	Veig	LL-PL-PI	A.
Annual V	eem	Depth (Ft.) POORLY GRADED SAND WITH SILT (SP-SM), light brown, mea	dium				-			
		dense			X	13-13-15 N=28				
			-		X	14-19-21 N=40				6
2		very dense	40		X	17-38-40 N=78				
			- 45- - -		X	16-27-29 N=56				
		51.5 Boring Terminated at 51.5 Feet			X	17-25-28 N=53				
	Suppo	ation and Testing Procedures for a description of field and laboratory s used and additional data (If any). rrting Information for explanation of symbols and abbreviations.	Water Level Ob Groundwa	ter not	enco	untered			Drill Rig D-50 Hammer Typ Automatic Driller Terracon	e
			Hollow Stem Aug Abandonment I Boring backfilled	1etho	i uger (Cuttings and/or Be	entonite		Logged by JB Boring Start 01-20-2025 Boring Comp 01-20-2025	



becation: See Exploration Plan is an intermediate statute 34.4832° Longitude: -118.1323° is an intermediate statute statu
Depth (Ft.) SILTY SAND (SM), brown loose
SILTY SAND (SM), brown loose medium dense 5 4-5-6 NP 10 3-10-14 3-10-14 3-9 11 10 8-7-11 NP 13
Image: 15.0 POORLY GRADED SAND (SP), trace silt, light brown, medium dense
1 1 2-2-5 4.8 102 medium dense 5 4-5-6 N=11 10 3-10-14 3.9 111 10 8-7-11 N=18 10 8-7-11 N=18 10 15-1 15-1
1 1 2-2-5 4.8 102 medium dense 5 4-5-6 N=11 10 3-10-14 3.9 111 10 8-7-11 N=18 10 8-7-11 N=18 10 15-1 15-1
1 1 1 1 1 10 1 3-10-14 3.10-14 3.9 10 8-7-11 N=18 10 15
1 1 1 1 1 1 1 1 1 1 1 1 1 1
1 1 1 1 1 1 1 1 1 1 1 1 1 1
1 10 10 10 10 10 15 15 15 15 15 15 15 15 15 15
10 10 10 10 10 10 10 15 15 15 15 10 111 111
10 10 10 15.0 POORLY GRADED SAND (SP), trace silt, light brown, medium dense 15
15.0 POORLY GRADED SAND (SP), trace silt, light brown, medium dense
15.0 POORLY GRADED SAND (SP), trace silt, light brown, medium dense
15.0 POORLY GRADED SAND (SP), trace silt, light brown, medium dense
POORLY GRADED SAND (SP), trace silt, light brown, medium dense
POORLY GRADED SAND (SP), trace silt, light brown, medium dense
POORLY GRADED SAND (SP), trace silt, light brown, medium dense
POORLY GRADED SAND (SP), trace silt, light brown, medium dense
very dense 20- 39-37-21
N=58
25.0 POORLY GRADED SAND WITH SILT (SP-SM), brown, medium dense 25 8-9-9
N=18
30-
See Exploration and Testing Procedures for a description of field and laboratory procedures used and additional data (If any). Water Level Observations Drill Rig
See Supporting Information for explanation of symbols and abbreviations. Hammer Type Automatic
Driller
Notes Advancement Method Terracon Hollow Stem Auger
Logged by JB
Abandonment Method Boring backfilled with Auger Cuttings and/or Bentonite
Boring backfilled with Adger Cuttings and/or Bentonite Boring Complete 01-21-2025





Terracon

145 W Walnut St

Carson, CA




L.	ŋ	Location: See Exploration Plan		~		e			Û	Atterberg Limits	
Model Layer	Graphic Log	Latitude: 34.4819° Longitude: -118.1290°		Depth (Ft.)	Water Level Observations	Sample Type	Field Test Results	Water Content (%)	Dry Unit Weight (pcf)	LL-PL-PI	Percent Fines
Σ	G	Depth (Ft.)		Δ	≤ō	S S		Ŭ	3		
		SILTY SAND (SM), brown				000					
		A		-		m				NP	
4				-							
		medium dense				M	4-6-6 N=12			1111	
				- 4		\wedge	N=12	-			
				5 –				-	-		
						X	8-13-16	2.2	117		
						-		-	-		
							E 7 7	-			-
				- 6		М	5-7-7 N=14				23
					1				-		
1				10-	1	V	6-8-12	4.1	118	÷.	
				- 7		A.	0-0-12	4.1	110	2	
				Ē						1.00	
				- 5							
				4							
				15-			_				
				- 1		XI	4-8-8 N=16				
				1		r f					
				- B							
1		20.0		20	1						
		POORLY GRADED SAND WITH SILT (SP-SM), medium brown dense	n, medium	20–	1	V	10-20-20	4.1	124	1	
		dense		ā		A.	10-20-20	4.1	124	-	
				- 7							
				-							
				-							
2		dense		25–							
				-		XI	6-16-21 N=37				
4						ſ		-			
				-							
				30-							
See	Explo	1 ration and Testing Procedures for a description of field and laboratory	Water Lev	_	1 serva	tions		-		Drill Rig	
prod	cedure	s used and additional data (If any).	Grou	undwat	ter no	t enco	untered			Drill Rig D-50	
566	Suppo									Hammer Typ Automatic	be
					lat's					Driller Terracon	
Not	es		Advancem Hollow Ster							Logged by	
										JB	
			Abandonn Boring bacl	nent N kfilled	1etho with 4	d Auaer	Cuttings and/or B	entonite		Boring Start 01-21-2025	ed
										Boring Comp 01-21-2025	pleted



L	ŋ	Location: See Exploration Plan			e			Ð	Atterberg Limits	
Model Layer	Graphic Log	Latitude: 34.4819° Longitude: -118.1290°	Depth (Ft.)	Water Level Observations	Sample Type	Field Test Results	Water Content (%)	Dry Unit Weight (pcf)	LITIICS	Percent Fines
Σ	G	Depth (Ft.)		>ō	S		Ŭ	3		
		dense (continued)	medium – –		X	16-21-27 N=48				
					Х	21-21-27 N=48				
2		very dense	- 40- -		X	26-50/6"	-			
		45.0 SILTY SAND (SM), brown, very dense	- - 45- -		X	16-22-29 N=51				28
		51.5	- - 50-		X	14-22-32 N=54				
		Boring Terminated at 51.5 Feet								
See	Explor	ration and Testing Procedures for a description of field and laboratory s used and additional data (If any).	Water Level Ob Groundwa			untered			Drill Rig D-50	
	Suppo	orting Information for explanation of symbols and abbreviations.	Advancement M Hollow Stem Aug	lethoo					Hammer Typ Automatic Driller Terracon Logged by JB	
			Abandonment I Boring backfilled			Cuttings and/or Be	entonite		Boring Start 01-21-2025 Boring Comp 01-21-2025	





ierracon


145 W Walnut St

Carson, CA



Model Layer	Graphic Log	Location: See Exploration Plan Latitude: 34.4846° Longitude: -118.1332° Depth (Ft.)	Depth (Ft.)	Water Level Observations	Sample Type	Field Test Results	Water Content (%)	Dry Unit Weight (pcf)	Atterberg Limits LL-PL-PI	Percent Fines
1		<u>SILTY SAND (SM)</u> , medium brown, dense		-	X	13-16-18 N=34				
		^{35.0} POORLY GRADED SAND WITH SILT (SP-SM), light brown, o	dense 35		X	16-23-23 N=46				
2		40.0 SILTY CLAY (SM), brown, very dense	40		X	13-28-29 N=57				
		dense	45		X	13-27-19 N=46				
		very dense 51.5 Boring Terminated at 51.5 Feet	50		X	18-28-29 N=57				
prod	cedure	ration and Testing Procedures for a description of field and laboratory s used and additional data (If any). arting Information for explanation of symbols and abbreviations.	Water Level O Groundw			untered			Drill Rig D-50 Hammer Typ Automatic Driller	e
Not	es		Advancement Hollow Stem Au Abandonment Boring backfille	ger Metho	d	Cuttings and/or B	entonite		Terracon Logged by JB Boring Start 01-21-2025 Boring Comp 01-21-2025	







Liquid Limit

	Boring ID	Depth (Ft)	ш	PL	PI	Fines	USCS	Description
•	BESS-1	10 - 11.5	20	17	3	25.2	SM	SILTY SAND
	BESS-4	0 - 2.5	18	15	3	18.2	SM	SILTY SAND
	BESS-4	15 - 16.5	NP	NP	NP	11.2	SM	SILTY SAND
*	BESS-6	20 - 21.5	NP	NP	NP	15.6	SM	SILTY SAND
•	BESS-7	0 - 5	27	15	12	30.5	SC	CLAYEY SAND
•	BESS-8	2.5 - 4	19	16	3	25.6	SM	SILTY SAND
0	BESS-10	7.5 - 9	NP	NP	NP	26.4	SM	SILTY SAND
Δ	BESS-11	0 - 5	16	16	NP	18.6	SM	SILTY SAND with GRAVE
8	BESS-13	10 - 11.5	NP	NP	NP	12.1	SM	SILTY SAND with GRAVELL
Ð	BESS-15	0 - 5	21	15	6	41.0	SC-SM	SILTY, CLAYEY SAND
	P-1	0 - 1.5	21	18	3	27.3	SC-SM	Silty Clayey Sand
0	P-4	0 - 2.5	NP	NP	NP	9.1	SP	Poorly Graded Sand
•	SUB-1	5 - 6.5	19	15	4	19.9	SC-SM	SILTY, CLAYEY SAND
*	OM-1	0 - 5	33	16	17	49.9	SC	CLAYEY SAND
ន	OM-2	7.5 - 9	21	17	4	44.2	SC-SM	SILTY, CLAYEY SAND
	TL-2	2.5 - 4	NP	NP	NP		SM	SILTY SAND
•	TL-3	5 - 6.5	20	19	1		SM	SILTY SAND
0	TL-3	20 - 21.5	NP	NP	NP	6.2	SP-SM	POORLY GRADED SAND with SILT
×	TL-4	0 - 2	NP	NP	NP		SM	SILTY SAND
	TL-5	0 - 5	NP	NP	NP	12.9	SM	SILTY SAND

Facilities | Environmental | Geotechnical | Materials











Grain Size Distribution



Boring ID	Depth (Ft)	D ₁₀₀	D ₆₀	D ₃₀	D ₁₀	%Cobbles	%Gravel	%Sand	%Fines	%Silt	%Clay
BESS-7	0 - 5	25	0.477			0.0	7.0	62.5	30.5		
BESS-11	0 - 5	50	1.163	0.241			15.4	61.4	18.6		
SUB-2	2.5 - 4	19	0.867	0.164		0.0	10.5	69.1	20.4		




Moisture-Density Relationship



Boring ID		Depth	(Ft)		Description of Materials		
BESS-1		0 -	5			SILTY SAND	
Fines (%)	Fraction > mm size	u	PL	PI	Test Method	Maximum Dry Density (pcf)	Optimum Water Content (%)
32					ASTM D1557-Method A	136.0	8.3




Moisture-Density Relationship



Boring ID		Depth ((Ft)		Description of Materials		
BESS-3		0 - 5	5			SILTY SAND	
Fines (%)	Fraction > mm size	u	PL	PI	Test Method	Maximum Dry Density (pcf)	Optimum Water Content (%)
					ASTM D1557-Method A	135.3	8.1




Moisture-Density Relationship



Boring ID		Depth	(Ft)		Description of Materials		
BESS-5		0 -	5			SILTY SAND	
Fines (%)	Fraction > mm size	ш	PL	PI	Test Method	Maximum Dry Density (pcf)	Optimum Water Content (%)
17					ASTM D1557-Method A	136.3	7.8



Moisture-Density Relationship




Boring ID		Depth	(Ft)		Description of Materials		
BESS-13		0 - 5	5			SILTY SAND	
Fines (%)	Fraction > mm size	ш	PL	PI	Test Method	Maximum Dry Density (pcf)	Optimum Water Content (%)
41					ASTM D1557-Method A	135.8	8.2



Moisture-Density Relationship


ASTM D1557-Method A



Вог	ring ID	Depth	(Ft)		Description of Materials					
S	UB-1	0 - 5	5		SILTY SAND with GRAVEL					
Fines (%)	Fraction > mm size	ц	PL	PI	Test Method	Maximum Dry Density (pcf)	Optimum Water Content (%)			
28					ASTM D1557-Method A	133.3	8.4			




Boring ID	Depth (ft)	Description		USCS	γ _d (pcf)	W(%)
BESS-4	5	Silty Sand		SM	121	2.5
		Ultimate Shear	Peak		Ultimate	
Normal Stress (psf)	Peak Shear Stress (psf)	Stress (psf)	φ°	C (psf)	φ°	C (psf)
1000	708	564			33.0	10
2000	1476	1416	32.0	130		
4000	2640	2532				






Boring ID	Depth (ft)	Description		USCS	γ _d (pcf)	W(%)
BESS-8	10	Silty Sand		SM	116	2.7
Normal Stress	Peak Shear Stress	Ultimate Shear	Peak		Ultimate	
(psf)	(psf)	Stress (psf)	φ°	C (psf)	φ°	C (psf)
1000	1068	816				470
2000	1704	1644	27.0	600	26.0	
4000	2640	2328				






Boring ID	Depth (ft)	Description		USCS	γ _d (pcf)	W(%)
BESS-14	5	Silty Sand with Gravel		SM	119	3.5
Normal Stress	Peak Shear Stress	Ultimate Shear	Peak		Ultimate	
(psf)	(psf)	Stress (psf)	φ°	C (psf)	φ°	C (psf)
1000	732	708				250
2000	1356	1332	27.0	260	27.0	
4000	2304	2244				






Boring ID	Depth (ft)	Description		USCS	γ _d (pcf)	W(%)
TL-2	10	Silty Sand		SM		1.4
Normal Stress	Peak Shear Stress	Ultimate Shear	Peak		Ultimate	
(psf)	(psf)	Stress (psf)	φ°	C (psf)	φ°	C (psf)
1000	1044	696				0
2000	1560	816	42.0	0	31.0	
4000	3648	2388				






Boring ID	Depth (ft)	Description		USCS	γ _d (pcf)	W(%)
TL-3	2.5	Silty Sand		SM	116	6.3
Normal Stress	Peak Shear Stress	Ultimate Shear	Peak		Ultimate	
(psf)	(psf)	Stress (psf)	φ°	C (psf)	φ°	C (psf)
1000	924	756				90
2000	1284	996	27.0	350	29.0	
4000	2424	2328				






Boring I D	Depth (ft)	Descripti	on	USCS	γ _d (pcf)	W(%)	
TL-5	7.5	Silty Sand		SM	111	3.9	
		Ultimate Shear		ak	Ultimate		
Normal Stress (psf)	Peak Shear Stress (psf)	Stress (psf)	φ°	C (psf)	φ°	C (psf)	
1000	840	840		220	34.0	190	
2000	1704	1572	35.0				
4000	2952	2880					






Boring I D	Depth (ft)	Descripti	on	USCS	γ _d (pcf)	W(%)	
TL-6	5	Silty Sand		SM	117	2.2	
		Ultimate Shear	Pe	ak	Ultimate		
Normal Stress (psf)	Peak Shear Stress (psf)	Stress (psf)	¢٥	C (psf)	φ°	C (psf)	
1000	840	768		240	31.0	220	
2000	1776	1488	35.0				
4000	2976	2592					





One-Dimensional Swell or Collapse





g ID	Depth (Ft)	Description	USCS	γ _d (pcf)	WC (%)
OM-2	5 - 6.5	CLAYEY SAND	SC	105	4.4
	-				OM-2 5 - 6.5 CLAYEY SAND SC 105

Axial Strain (%)



TRANSMITTAL LETTER

DATE: January 31, 2025

ATTENTION: Janna Valdez

TO: Terracon - Carson 145 W Walnut Street Carson, CA 90248

SUBJECT: Laboratory Test Data Prairie Song Reliability Project Keegan Labs #25-0016 Terracon - Carson #LA245085

COMMENTS: Enclosed are the results for the subject project.

Dr. James T. Keegan President and Founder



Table 1 - Laboratory Tests on Soil Samples

Terracon - Carson Prairie Song Reliability Project Keegan Labs #25-0016, Your #LA245085 31-Jan-25

Sample ID			BESS-2 @ 0-2'	BESS-8 @ 0-2.5'	BESS-14 @ 0-2.5'	SUB-2 @ 0-2.5'	TL-1 @ 0-5'
Resistivity		Units					
saturated		ohm-cm	10,250	8,140	5,230	6,840	18,100
рH			7.1	7.4	7.7	7.3	7.7
Electrical							
Conductivity		mS/cm	0.02	0.05	0.05	0.04	0.03
Chemical Analy	yses (Total Sa	lts)				
Cations							
sodium	Na^{1+}	mg/kg	6.1	4.4	5.7	6.0	6.0
ammonium	$\mathrm{NH_4}^{1+}$	mg/kg	0.3	1.0	0.5	0.4	0.4
potassium	K^{1+}	mg/kg	1.7	26	17	5.4	5.4
magnesium	Mg^{2+}	mg/kg	1.5	2.3	3.9	0.7	0.9
calcium	Ca ²⁺	mg/kg	9.4	19	18	20	5.8
Anions							
carbonate	CO_{3}^{2-}		ND	ND	ND	ND	ND
bicarbonate	e HCO ₃ 1	_mg/kg	12	49	61	43	6.1
fluoride	${f F}^{1-}$	mg/kg	4.5	5.1	4.8	4.7	4.4
chloride	Cl^{1-}	mg/kg	5.8	7.7	6.2	6.6	6.5
nitrate	NO_3^{1-}	mg/kg	6.3	7.8	7.1	7.4	6.3
phosphate	PO4 ³⁻	mg/kg	8.0	9.3	7.1	7.7	5.7
sulfate	SO_4^{2-}	mg/kg	1.6	9.7	6.5	4.1	9.2
Other Tests							
sulfide	S^{2-}	mg/kg	ND	ND	ND	ND	ND
Redox		mV	278	290	282	291	288
% Moisture	H ₂ O	90	na	na	na	na	na

For test methods refer to Laboratory Test Methods attachment

Conductivity in millisiemens/cm and chemical analyses were made on a 1:5 soil-to-water extract. mg/kg = milligrams per kilogram (parts per million) of dry soil.

ND = not detected

na = not analyzed



Table 1 - Laboratory Tests on Soil Samples

Terracon - Carson Prairie Song Reliability Project Keegan Labs #25-0016, Your #LA245085 31-Jan-25

Sample ID			TL-3 @ 0-5'	TL-6 @ 0-5'	
		TT. 11			
Resistivity		Units	12 070	01 110	
saturated		ohm-cm	-	21,110	
Hq			7.1	7.0	
Electrical		<i>a</i> (
Conductivity		mS/cm	0.02	0.02	
Chemical Analy	rses ('	Total Sa	lts)		
Cations	1+	_			
sodium	Na ¹⁺	mg/kg	3.8	4.2	
ammonium	${\rm NH_4}^{1+}$	mg/kg	0.3		
potassium	K ¹⁺	mg/kg	9.6		
magnesium	Mg^{2+}	mg/kg	1.5		
calcium	Ca ²⁺	mg/kg	2.7	4.4	
Anions	aa ²⁻	(1	170	175	
carbonate	CO_3^{2-}	mg/kg	ND	ND	
bicarbonate	0		12	6.1	
fluoride	F^{1-}	mg/kg	4.5		
chloride	Cl ¹⁻	mg/kg	6.5		
nitrate	NO_{3}^{1-}		6.5		
phosphate	PO4 ³⁻		8.0	6.4	
sulfate	SO_4^-	mg/kg	2.4	0.2	
Other Tests	0				
sulfide	S^{2-}	mg/kg	ND	ND	
Redox		mV	288	293	
% Moisture	H ₂ O	010	na	na	

For test methods refer to Laboratory Test Methods attachment

Conductivity in millisiemens/cm and chemical analyses were made on a 1:5 soil-to-water extract. mg/kg = milligrams per kilogram (parts per million) of dry soil.

ND = not detected

na = not analyzed



LABORATORY TEST METHODS

DATE: January 1, 2024

LABORATORY TESTS	METHODS	RELEVANT ALTERNATE METHODS
Electrical Resistivity of Soil	ASTM G-187	ASTM G-57, AASHTO T288
Minimum Electrical Resistivity	CTM 643	AASHTO T-288
pH of Soil	ASTM G-51	CTM 643, SMWW-H*, ASSHTO T289
Anions in Water*	ASTM D4327	EPA 300, EPA 353.2, EPA 325.1, ASTM D516, SMWW 4500B
Cations in Water*	ASTM D6919	EPA 300
Chloride and Sulfate in Soil	CTM 422 & 417	ASSHTO T290 & T291
Alkalinity of Water*	ASTM D1067	SMWW 2320, EPA 305.1
Total Acidity/Alkalinity*	NIST RP539	
Sulfide (qualitative)	AWWA C-105	
Sulfide (quantitative)	ASTM D4658	EPA 376.2
Thermal Conductivity of Soil	ASTM D5334	
Oxidation/Reduction (Redox)	ASTM G200	
Linear Polarization	ASTM-G59	
MIC Bacteria in Soil	MICkit 5**	

*Adapted for soil

**Propietary testing kit manufactured by BTI-Products



21239 FM529 Rd., Bldg F Cypress, TX 77433 Office: 291-985-9344 <u>info@geothermusa.com</u> http://www.geothermusa.com

REV01: Change project name from March 5, 2025

BESS to Prairie Song Reliability Project

Terracon 145 W. Walnut Street Carson, CA 90248 Attn: Janna Valdez

<u>Thermal Resistivity Report</u> Prairie Song Reliability Project – Acton, CA (Project No. LA245085)

The following is the report of thermal dryout characterization tests conducted on four (4) bulk samples of native soil from the referenced project sent to our laboratory.

Thermal Resistivity Tests: The samples were tested at the 'optimum' moisture content and at 90% of the modified Proctor dry density *provided by Terracon*. The tests were conducted in accordance with the **IEEE standard 442-2017**. The results are tabulated below and the thermal dry out curves are presented in **Figures 1 to 4**.

Sample ID, Description, Thermal Resistivity, Moisture Content and Density

Sample ID	Depth Effort	Description	Thermal Resistivity (°C-cm/W)		Moisture Content	Dry Density	
	(ft)	(%)	(Terracon)	Wet	Dry	(%)	(lb/ft ³)
BESS-01	0 - 5	90	Silty Sand	69	148	8	121
BESS-05	0 - 5	90	Silty Sand	65	136	8	123
BESS-13	0 - 5	90	Silty Sand	67	151	8	121
SUB-01	0 - 5	90	Silty Sand with Gravel	68	144	8	120

<u>Comments</u>: The thermal characteristic depicted in the dryout curves apply for the soils at their respective test dry density.


Please contact us if you have any questions or if we can be of further assistance.

Geotherm USA, LLC Nimesh Patel

COOL SOLUTIONS FOR UNDERGROUND POWER CABLES THERMAL SURVEYS, CORRECTIVE BACKFILLS & INSTRUMENTATION

Serving the electric power industry since 1978






Terracon (Project No. LA245085)

Prairie Song Reliability Project - Acton, CA

Thermal Resistivity Report






Terracon (Project No. LA245085)

Prairie Song Reliability Project - Acton, CA

Thermal Resistivity Report






Terracon (Project No. LA245085)

Prairie Song Reliability Project - Acton, CA

Thermal Resistivity Report





Terracon (Project No. LA245085)

Prairie Song Reliability Project - Acton, CA

Thermal Resistivity Report

AP Engineering and Testing, Inc.

DBE|MBE|SBE 2607 Pomona Boulevard | Pomona, CA 91768 t. 909.869.6316 | f. 909.869.6318 | www.aplaboratory.com

CALIFORNIA BEARING RATIO (CBR) OF LABORATORY-COMPACTED SOIL ASTM D 1883

Project Name:	Prairie Song Reliability Project
Project No. :	LA245085
Boring No.:	BESS-3
Sample No.:	-
Depth (ft.) :	0-5
Soil Description :	Silty, Clayey Sand

 Tested By :
 SM

 Input By:
 JP

 Checked By:
 AP

 Date
 01/23/25

 Date
 01/27/25

 Date
 05/05/25

SAMPLE DESCRIPTION BEFORE SOAKING

Mold Number	D	
Blows Per Layer	8	
Wt of Wet Soil & Mold (gm)	12065.5	
Weight of Mold (gm)	7823	
Weight of Wet Soil (gm)	4243	
Mold Volume (cu.ft)	0.0750	
Container No.		
Wet Wt. Soil + Container (gm)	666.49	
Dry Wt. Soil + Container (gm)	649.74	
Wt. Container (gm)	451.71	
Moisture Content (%)	8.46	
Wet Density (pcf)	124.7	
Dry Density (pcf)	115.0	

DEFORMATION DURING SOAKING PERIOD Sample Length (inch)

4.584

DATE	TIME	Mold No.:	D
		Dial Rdgs	Swell (in)
02/06/25	16:40	0.0760	
02/07/25	08:10	0.0790	
02/10/25	08:10	0.0800	0.0040
Percent Swell/Collapse (+/-)			0.09

AFTER SOAKING

Mold Number	D	
Wt. of Wet Soil + Mold (gm)	12322	
Weight of Mold (gm)	7823	
Weight of Wet Soil (gm)	4499	
Final Sample Volume (cu.ft)	0.0751	
Container No.		-
Wet Wt. Soil + Container (gm)	699.01	
Dry Wt. Soil + Container (gm)	671.98	
Wt. Container (gm)	493.58	
Mosture Content (%)	15.2	
Wet Density (pcf)	132.1	-
After Test Dry Density (pcf)	114.7	

SAMPLE PREPARATION

Wt of Hammer (Lbs)	10
No. of Layers	5
No. of Blows/Layer	8
Drop Height (inches)	18
Surcharge Weight (Lbs)	10
Max. Dry Density (pcf)*	135.2
Molded Relative Comp (%)	85.0
Req'd % Moisture	8.0
No. of Trials	1

% Retained 3/4" Sieve

0.00%

*Note: Max. dry density provided by Terracon TEST LOAD DATA

Piston Diameter	(inches):	1.954
Penetration	Mold No.:	D
(inch)	LOAD (lb)	Stress (psi)
0.000	0	0.00
0.025	54	18.01
0.050	80	26.68
0.075	94	31.35
0.100	104	34.68
0.125	119	39.68
0.150	135	45.02
0.175	152	50.69
0.200	166	55.36
0.225	179	59.69
0.250	190	63.36
0.275	202	67.36
0.300	212	70.70
0.325	222	74.03
0.350	232	77.37
0.375	242	80.70
0.400	252	84.04
0.425	263	87.70
0.450	274	91.37
0.475	285	95.04
0.500	296	98.71

TEST RESULTS CBR @ .1":

CBR @ .2":

3

AP Engineering and Testing, Inc.

DBE MBE SBE 2607 Pomona Boulevard | Pomona, CA 91768 t. 909,869,6316 | f. 909,869,6318 | www.aplaboratory.com

CALIFORNIA BEARING RATIO (CBR) OF LABORATORY-COMPACTED SOIL ASTM D 1883

Project Name: Prairie Song Reliability Project Project No. : LA245085 Boring No.: BESS-3 Sample No.: -Depth (ft.) : 0-5 Soil Description : Silty, Clayey Sand

Tested By : SM Input By: JP Checked By: AP

Date 01/23/25 01/27/25 Date Date 05/05/25

SAMPLE DESCRIPTION BEFORE SOAKING

Mold Number	E	
Blows Per Layer	10	
Wt of Wet Soil & Mold (gm)	12298	
Weight of Mold (gm)	7812.5	
Weight of Wet Soil (gm)	4486	
Mold Volume (cu.ft)	0.0750	
Container No.		
Wet Wt. Soil + Container (gm)	666.49	
Dry Wt. Soil + Container (gm)	649.74	
Wt. Container (gm)	451.71	
Moisture Content (%)	8.46	
Wet Density (pcf)	131.8	
Dry Density (pcf)	121.6	

DEFORMATION DURING SOAKING PERIOD Sample Length (inch)

4.584

DATE	TIME	Mold No.:	E
		Dial Rdgs	Swell (in)
02/06/25	16:40	0.0820	
02/07/25	08:10	0.0850	
02/10/25	08:10	0.0850	0.0030
		E	1
Percent Swell/Collapse (+/-)			0.07

AFTER SOAKING

Mold Number	E	
Wt. of Wet Soil + Mold (gm)	12456	
Weight of Mold (gm)	7813	
Weight of Wet Soil (gm)	4644	
Final Sample Volume (cu.ft)	0.0750	
Container No.		
Wet Wt. Soil + Container (gm)	641.39	
Dry Wt. Soil + Container (gm)	591.39	
Wt. Container (gm)	143.91	
Mosture Content (%)	11.2	
Wet Density (pcf)	136.4	-
After Test Dry Density (pcf)	122.7	

SAMPLE PREPARATION

Wt of Hammer (Lbs)	10
No. of Layers	5
No. of Blows/Layer	10
Drop Height (inches)	18
Surcharge Weight (Lbs)	10
Max. Dry Density (pcf)*	135.2
Molded Relative Comp (%)	89.9
Req'd % Moisture	8.0
No. of Trials	1
% Retained 3/4" Sieve	0.00%

*Note: Max. dry density provided by Terracon **TEST LOAD DATA**

Piston Diamete Penetration	1	E
(inch)	LOAD (lb)	Stress (psi)
0.000	0	0.00
0.025	82	27.34
0.050	129	43.02
0.075	154	51.35
0.100	172	57.36
0.125	185	61.69
0.150	195	65.03
0.175	207	69.03
0.200	218	72.70
0.225	230	76.70
0.250	241	80.37
0.275	251	83.70
0.300	260	86.70
0.325	271	90.37
0.350	280	93.37
0.375	290	96.71
0.400	300	100.04
0.425	313	104.38
0.450	323	107.71
0.475	334	111.38
0.500	346	115.38

TEST RESULTS CBR @ .1": CBR @ .2":

6 5 AP Engineering and Testing, Inc.

DBE MBE SBE 2607 Pomona Boulevard | Pomona, CA 91768 t. 909.869.6316 | f. 909.869.6318 | www.aplaboratory.com

CALIFORNIA BEARING RATIO (CBR) OF LABORATORY-COMPACTED SOIL ASTM D 1883

Prairie Song Reliability Project Project Name: Project No. : LA245085 Boring No.: BESS-3 Sample No.: -Depth (ft.) : 0-5 Soil Description : Silty, Clayey Sand

Tested By :	SM	
Input By:	JP	
Checked By:	AP	

Date 01/23/25 01/27/25 Date Date 05/05/25

SAMPLE DESCRIPTION BEFORE SOAKING

Mold Number	F	
Blows Per Layer	25	
Wt of Wet Soil & Mold (gm)	12527	
Weight of Mold (gm)	7786	
Weight of Wet Soil (gm)	4741	
Mold Volume (cu.ft)	0.0750	
Container No.		
Wet Wt. Soil + Container (gm)	666.49	
Dry Wt. Soil + Container (gm)	649.74	
Wt. Container (gm)	451.71	
Moisture Content (%)	8.46	
Wet Density (pcf)	139.4	
Dry Density (pcf)	128.5	

DEFORMATION DURING SOAKING PERIOD Sample Length (inch)

4.584

DATE	TIME	Mold No.:	F
		Dial Rdgs	Swell (in)
02/06/25	16:40	0.1090	1
02/07/25	08:10	0.1040	h
02/10/25	08:10	0.1100	0.0010
A Design of the second se			10
Percent Swell/Collapse (+/-)		1	0.02

AFTER SOAKING

Mold Number	F	
Wt. of Wet Soil + Mold (gm)	12593	
Weight of Mold (gm)	7786	
Weight of Wet Soil (gm)	4807	
Final Sample Volume (cu.ft)	0.0750	
Container No.		
Wet Wt. Soil + Container (gm)	683.73	
Dry Wt. Soil + Container (gm)	640.42	
Wt. Container (gm)	151.00	
Mosture Content (%)	8.8	
Wet Density (pcf)	141.3	
After Test Dry Density (pcf)	129.8	

SAMPLE PREPARATION

Wt of Hammer (Lbs)	10
No. of Layers	5
No. of Blows/Layer	25
Drop Height (inches)	18
Surcharge Weight (Lbs)	10
Max. Dry Density (pcf)*	135.2
Molded Relative Comp (%)	95.0
Req'd % Moisture	8.0
No. of Trials	1

% Retained 3/4" Sieve

0.00%

*Note: Max. dry density provided by Terracon TEST LOAD DATA

Piston Diameter		1.954
Penetration	Mold No.:	F
(inch)	LOAD (lb)	Stress (psi)
0.000	0	0.00
0.025	47	15.67
0.050	103	34.35
0.075	163	54.36
0.100	235	78.37
0.125	312	104.04
0.150	385	128.39
0.175	448	149.40
0.200	501	167.07
0.225	536	178.74
0.250	551	183.74
0.275	560	186.75
0.300	576	192.08
0.325	605	201.75
0.350	640	213.42
0.375	674	224.76
0.400	714	238.10
0.425	759	253.11
0.450	807	269.11
0.475	860	286.79
0.500	913	304.46


TEST RESULTS CBR @ .1": CBR @ .2":


10 12



AP Engineering and Testing, Inc. DBE|MBE|SBE 2607 Pomona Boulevard | Pomona, CA 91768 t. 909.869.6316 | f. 909.869.6318 | www.aplaboratory.com

CALIFORNIA BEARING RATIO (CBR) OF LABORATORY-COMPACTED SOIL ASTM D 1883








AP Engineering and Testing, Inc. DBE|MBE|SBE 2607 Pomona Boulevard | Pomona, CA 91768 t. 909.869.6316 | f. 909.869.6318 | www.aplaboratory.com

CALIFORNIA BEARING RATIO (CBR) OF LABORATORY-COMPACTED SOIL ASTM D 1883

Project Name:	Prairie Song Reliability Project	Tested By :	SM	Date:	01/23/25
Project No. :	LA245085	Data Input By:	JP	Date:	01/27/25
Boring No.:	BESS-3	Checked By:	AP	Date:	05/05/25
Sample No.:					
Depth (ft.) :	0-5				
Soil Description :	Silty, Clayey Sand				

	TEST RESULTS				
Dry Density (pcf)	Maximum Dry Density by ASTM D 1557 (pcf)	Relative Compaction (%)	Blow Per Layer	CBR @0.1"	CBR @0.2"
115.0	135.2	85.0	8	3	4
121.6	135.2	89.9	10	6	5
128.5	135.2	95.0	25	10	12




~

AP Engineering and Testing, Inc. DBE|MBE|SBE 2607 Pomona Boulevard | Pomona, CA 91768 t. 909.869.6316 | f. 909.869.6318 | www.aplaboratory.com


CALIFORNIA BEARING RATIO (CBR) OF LABORATORY-COMPACTED SOIL ASTM D 1883

Prairie Song Reliability Project	Tested By :	SM	Date:	01/23/25
LA245085	Data Input By:	JP	Date:	01/27/25
BESS-3	Checked By:	AP	Date:	05/05/25
7				
0-5				
Silty, Clayey Sand				
	LA245085 BESS-3 - 0-5	LA245085Data Input By:BESS-3Checked By:-0-5	LA245085Data Input By:JPBESS-3Checked By:AP-0-5-	LA245085Data Input By:JPDate:BESS-3Checked By:APDate:-0-5

	TEST RESULTS				
Dry Density (pcf)	Maximum Dry Density by ASTM D 1557 (pcf)	Relative Compaction (%)	Blow Per Layer	CBR @0.1"	CBR @0.2"
115.0	135.2	85.0	8	3	4
121.6	135.2	89.9	10	6	5
128.5	135.2	95.0	25	10	12








$$\rho = \frac{4\pi aR}{1 + \frac{2a}{\sqrt{a^2 + 4b^2}} - \frac{a}{\sqrt{a^2 + b^2}}}$$

(feet)(centimeters)(inches)(centimeters)Resistance RResistivity p Resistance RResistance R2612512849470147(147)41222325193802512861832511131901212	pparent sistivity p
2612512849470147412223251938025618325111319012	
412223251938025618325111319012	Ω-cm)
6 183 2 5 11 13190 12	56960
	19010
8 244 2 5 8.9 13650 8.0	14070
	12270
12 366 2 5 5.7 13220 6.9	15990
20 610 2 5 4.3 16380 4.6	17760
30 914 3 8 3.3 19230 2.7	15570
50 1524 3 8 1.9 18610 1.9	18470
70 2134 3 8 1.1 15030 1.5	20480
100 3048 6 15 0.59 11310 0.82	15660
150 4572 6 15 0.47 13490 0.27	7680
300 9144 6 15 0.24	13550







ER-2 (34.4834, -118.1426)				
MiniSting	Weather	Sunny		
SZ107129	Ground Cond.	Loose Soild		
August 28, 2025	Tested By	AL/OW		
December 11, 2024	Method	Wenner 4-pin (ASTM G57-06 (2012); IEEE 81-2012)		
Site Limitation on the N-S Array due to highway				
	SZ107129 August 28, 2025 December 11, 2024	MiniStingWeatherSZ107129Ground Cond.August 28, 2025Tested ByDecember 11, 2024Method		

$$\rho = \frac{4\pi aR}{1 + \frac{2a}{\sqrt{a^2 + 4b^2}} - \frac{a}{\sqrt{a^2 + b^2}}}$$

Electrode	lectrode Spacing a		de Depth b	N-S	Test	E-W	Test
(feet)	(centimeters)	(inches)	(centimeters)	Measured Resistance <i>R</i>	Apparent Resistivity p	Measured Resistance <i>R</i>	Apparent Resistivity p
				Ω	(Ω-cm)	Ω	(Ω-cm)
2	61	2	5	100	38710	75	28990
4	122	2	5	27	20570	35	26890
6	183	2	5	16	18640	15	17220
8	244	2	5	14	21220	12	18870
12	366	2	5	7.5	17140	6.6	15290
20	610	2	5	2.8	10590	2.0	7840
30	914	3	8	1.6	9240	1.6	9460
50	1524	3	8	0.92	8810	0.92	8790
70	2134	3	8	0.68	9130	0.76	10150
100	3048	6	15	0.59	11240	0.67	12770
150	4572	6	15	0.48	13830	0.47	13450
300	9144	6	15			0.25	14090








ρ

$$=\frac{4\pi aR}{1+\frac{2a}{\sqrt{a^2+4b^2}}-\frac{a}{\sqrt{a^2+b^2}}}$$

Electrod	e Spacing a	Electro	de Depth b	de Depth <i>b</i> N-S Test		E-W	Test
(feet)	(centimeters)	(inches)	(centimeters)	Measured Resistance <i>R</i>	Apparent Resistivity p	Measured Resistance <i>R</i>	Apparent Resistivity p
				Ω	(Ω-cm)	Ω	(Ω-cm)
2	61	2	5	61	23530	43	16500
4	122	2	3	18	13790	20	15330
6	183	2	5	16	17970	13	14910
8	244	2	5	12	17780	12	18440
12	366	2	5	8.9	20410	8.4	19310
20	610	2	5	5.8	22340	5.2	20030
30	914	3	8	3.3	18980	3.2	18310
50	1524	3	8	1.8	16880	1.4	13400
70	2134	3	8	1.2	15670	0.94	12640
100	3048	6	15	0.54	10330	0.57	10840
150	4572	6	15	0.38	10800	0.38	10990
300	9144	6	15			0.21	12250






Array Loc.	ER-4 (34.4867, -118.1370)								
Instrument	MiniSting	Weather	Sunny						
Serial #	SZ107129	Ground Cond.	Loose Soild						
Cal. Check	August 28, 2025	Tested By	AL/OW						
Test Date	December 11, 2024	Method	Wenner 4-pin (ASTM G57-06 (2012); IEEE 81-2012)						
Notes & Conflicts	Site Limitation on the both arr	avs due to a sloped terra	ain on the south side and thick vegetation on east side						

ρ

$$=\frac{4\pi aR}{1+\frac{2a}{\sqrt{a^2+4b^2}}-\frac{a}{\sqrt{a^2+b^2}}}$$

Electrod	e Spacing a	Electro	de Depth b	N-S	Test	E-W Test	
(feet)	(centimeters)	(inches)	(centimeters)	Measured Resistance <i>R</i>	Apparent Resistivity p	Measured Resistance <i>R</i>	Apparent Resistivity p
				Ω	(Ω-cm)	Ω	(Ω-cm)
2	61	2	5	39	15170	40	15640
4	122	2	5	19	14670	23	18010
6	183	2	5	16	18860	17	19160
8	244	2	5	14	21710	18	27450
12	366	2	5	12	26570	12	27210
20	610	2	5	7.3	27920	8.5	32490
30	914	3	8	4.4	25050	5.2	29940
50	1524	3	8	2.1	19900	2.5	24110
70	2134	3	8	0.82	11030	1.34	17990
100	3048	6	15	0.67	12800	0.69	13200
150	4572	6	15	0.49	14090	0.50	14410
300	9144	6	15				






Weather Ground Cond.	Sunny Burrowed Ground
	Burrowed Ground
Tested By	AL/OW
Method	Wenner 4-pin (ASTM G57-06 (2012); IEEE 81-2012)
N-S Array due to road	in the north and wash in the south
	Method

ρ

$$=\frac{4\pi aR}{1+\frac{2a}{\sqrt{a^2+4b^2}}-\frac{a}{\sqrt{a^2+b^2}}}$$

Electrode	e Spacing a	Electro	ode Depth b	N-S	Test	E-W Test	
(feet)	(centimeters)	(inches)	(centimeters)	Measured Resistance <i>R</i>	Apparent Resistivity p	Measured Resistance <i>R</i>	Apparent Resistivity p
				Ω	(Ω-cm)	Ω	(Ω-cm)
2	61	2	5	111	43120	136	52580
4	122	2	5	31	23790	24	18750
6	183	2	5	17	19090	17	19050
8	244	2	5	14	20870	11	16920
12	366	2	5	8.4	19310	8.9	20580
20	610	2	5	4.7	17990	4.9	18930
30	914	3	8	3.5	20250	2.9	16490
50	1524	3	8	2.0	18810	2.0	19120
70	2134	3	8	1.3	17080	1.3	17280
100	3048	6	15			0.60	11510
150	4572	6	15			0.21	5930






Array Loc.	ER-6 (34.4802, -118.1332)								
Instrument	MiniSting	Weather	Sunny						
Serial #	SZ107129	Ground Cond.	Semi-Compacted Soil						
Cal. Check	August 28, 2025	Tested By	AL/OW						
Test Date	December 13, 2024	Method	Wenner 4-pin (ASTM G57-06 (2012); IEEE 81-2012)						
Notes &									
Conflicts	Site Limitation on th	e N-S Array due to road	in the north and descending slope in the south						

$$\rho = \frac{4\pi aR}{1 + \frac{2a}{\sqrt{a^2 + 4b^2}} - \frac{a}{\sqrt{a^2 + b^2}}}$$

trode Spacing <i>a</i> Electrode		de Depth b	N-S Test		E-W Test	
centimeters)	(inches)	(centimeters)	Measured Resistance <i>R</i>	Apparent Resistivity p	Measured Resistance <i>R</i>	Apparent Resistivity p
			Ω	(Ω-cm)	Ω	(Ω-cm)
61	2	5	83	32320	101	39120
122	2	3	33	25240	43	32640
183	2	5	23	26140	22	24870
244	2	5	15	22980	15	22650
366	2	5	11	25650	10	22950
610	2	5	6.1	23520	7.6	29170
914	3	8	4.3	24580	5.0	28640
1524	3	8	2.4	22960	2.5	23470
2134	3	8			2.2	29260
3048	6	15			0.86	16480
4572	6	15			0.51	14750
(61 122 183 244 366 610 914 1524 2134 3048	61 2 122 2 183 2 244 2 366 2 610 2 914 3 1524 3 2134 3 3048 6	61 2 5 122 2 3 183 2 5 244 2 5 366 2 5 610 2 5 914 3 8 1524 3 8 2134 3 8 3048 6 15	(inches) (centimeters) Resistance R 61 2 5 R 61 2 5 R 122 2 3 33 183 2 5 23 244 2 5 15 366 2 5 11 610 2 5 6.1 914 3 8 4.3 1524 3 8 2.4 2134 3 8 2.4 3048 6 15 6	centimeters)(inches)(centimeters)Resistance R Resistivity p 0 Ω $(\Omega$ -cm) 61 258332320 122 233325240 183 252326140 244 251522980 366 251125650 610 256.123520 914 384.324580 1524 382.422960 2134 38 3048 615	centimeters(inches)(centimeters)Resistance R Resistivity p Resistance R Ω Ω Ω Ω Ω 61 25 83 32320 101 122 2 3 333 25240 43 183 25 23 26140 22 244 2 5 15 22980 15 366 2 5 11 25650 10 610 2 5 6.1 23520 7.6 914 3 8 4.3 24580 5.0 1524 3 8 2.4 22960 2.5 2134 3 8 2.4 22960 2.2 3048 6 15 6.1 2000 2.2



Supporting Information

Contents:

Liquefaction Analyses Shaft Analyses General Notes Unified Soil Classification System

Note: All attachments are one page unless noted above.

***** ***** LIQUEFACTION ANALYSIS SUMMARY Copyright by CivilTech Software www.civiltechsoftware.com * * * * * * * * * * * * * * * * * Font: Courier New, Regular, Size 8 is recommended for this report. 2/26/2025 Licensed to , 3:51:32 PM Input File Name: C:\Users\sdhital\OneDrive - Terracon Consultants Inc\Desktop\New folder\LA245085 Prairie Song Reliability - TL-2.lig Title: LA245085 Subtitle: Prairie Song Reliability Project Surface Elev. = 3011 Hole No. =TL-2 Depth of Hole= 51.50 ft Water Table during Earthquake= 100.00 ft Water Table during In-Situ Testing= 100.00 ft Max. Acceleration= 0.87 g Earthquake Magnitude= 7.76 Input Data: Surface Elev. = 3011 Hole No. =TL-2 Depth of Hole=51.50 ft Water Table during Earthquake= 100.00 ft Water Table during In-Situ Testing= 100.00 ft Max. Acceleration=0.87 g Earthquake Magni tude=7.76 No-Liquefiable Soils: Based on Analysis 1. SPT or BPT Calculation. 2. Settlement Analysis Method: Ishihara / Yoshimine 3. Fines Correction for Liquefaction: Idriss/Seed 4. Fine Correction for Settlement: During Liquefaction* 5. Settlement Calculation in: All zones* 6. Hammer Energy Ratio, Ce = 1.427. Borehole Diameter, Cb= 1.15 8. Sampling Method, Cs= 1.2 9. User request factor of safety (apply to CSR) , User= 1.3 Plot two CSR (fs1=1, fs2=User) 10. Use Curve Smoothing: Yes* * Recommended Options

ln-Situ Depth ft	Test Da SPT	ta: gamma pcf	Fines %
2.50 5.00 7.50 10.00 15.00 20.00 25.00	8.00 12.00 11.00 15.00 20.00 40.00 28.00	120.00 120.00 120.00 115.00 110.00 110.00 120.00	24.00 24.00 10.00 10.00 10.00 10.00 10.00
30. 00 35. 00 40. 00 45. 00 50. 00	41. 00 46. 00 33. 00 37. 00 27. 00	120.00 120.00 120.00 120.00 120.00 120.00	10.00 10.00 10.00 10.00 10.00 10.00

Output Results:

Settlement of Saturated Sands=0.00 in. Settlement of Unsaturated Sands=1.31 in. Total Settlement of Saturated and Unsaturated Sands=1.31 in. Differential Settlement=0.655 to 0.865 in.


Depth ft	CRRm	CSRfs	F. S.	S_sat. in.	S_dry in.	S_all in.
2.50	0. 28	0.56	5.00	0.00	1.31	1.31
3.00	0.33	0.56	5.00	0.00	1.30	1.30
3.50	1.83	0.56	5.00	0.00	1.29	1.29
4.00	1.83	0.56	5.00	0.00	1.26	1.26
4.50	1.83	0.56	5.00	0.00	1.25	1.25
5.00	1.83	0.56	5.00	0.00	1.24	1.24
5.50	1.83	0.56	5.00	0.00	1.24	1.24
6.00	1.83	0.56	5.00	0.00	1.23	1.23
6.50	1.83	0.56	5.00	0.00	1.22	1.22
7.00	0.34	0.56	5.00	0.00	1.18	1.18
7.50	0.28	0.56	5.00	0.00	1.10	1.10
8.00	0.30	0.56	5.00	0.00	1.01	1.01
8.50	1.83	0.56	5.00	0.00	0.93	0. 93
9.00	1.83	0.56	5.00	0.00	0.86	0.86
9.50	1.83	0.55	5.00	0.00	0.80	0.80
10.00	1.83	0.55	5.00	0.00	0. 78	0. 78
10.50	1.83	0.55	5.00	0.00	0.77	0.77
11.00	1.83	0.55	5.00	0.00	0.76	0. 76
11.50	1.83	0.55	5.00	0.00	0.75	0.75
12.00	1.83	0.55	5.00	0.00	0.74	0.74
12.50	1.83	0.55	5.00	0.00	0.73	0.73
13.00	1.83	0.55	5.00	0.00	0.71	0. 71
13.50	1.83	0.55	5.00	0.00	0.70	0.70

$\begin{array}{c} 14.\ 00\\ 14.\ 50\\ 15.\ 00\\ 15.\ 50\\ 16.\ 00\\ 15.\ 50\\ 16.\ 00\\ 17.\ 00\\ 17.\ 50\\ 18.\ 00\\ 19.\ 50\\ 20.\ 00\\ 20.\ 50\\ 21.\ 00\\ 21.\ 50\\ 22.\ 50\\ 23.\ 50\\ 24.\ 00\\ 25.\ 50\\ 25.\ 50\\ 25.\ 50\\ 26.\ 00\\ 25.\ 50\\ 26.\ 00\\ 25.\ 50\\ 26.\ 00\\ 27.\ 50\\ 28.\ 00\\ 28.\ 50\\ 29.\ 00\\ 29.\ 50\\ 30.\ 00\\ 30.\ 50\\ 31.\ 00\\ 31.\ 50\\ 32.\ 00\\ 31.\ 50\\ 32.\ 00\\ 31.\ 50\\ 33.\ 50\\ 34.\ 00\\ 35.\ 50\\ 35.\ 50\\ 35.\ 50\\ 36.\ 00\\ 35.\ 50\\ 36.\ 00\\ 35.\ 50\\ 36.\ 00\\ 35.\ 50\\ 36.\ 00\\ 36.\ 50\\ 36.\ 00\\ 36.\ 50\\ 36.\ 00\\ 36.\ 50\\ 36.\ 50\\ 36.\ 00\\ 36.\ 50\\ 36.\ 00\\ 36.\ 50\\ 36.\ 00\\ 36.\ 50\\ 36.\ 00\\ 36.\ 50\\ 36.\ 00\\ 36.\ 50\\ 36.\ 00\\ 36.\ 50\\ 36.\ 00\\ 36.\ 50\\ 36.\ 00\\ 36.\ 50\\ 36.\ 00\\ 36.\ 50\\ 36.\ 00\\ 36.\ 50\\ 36.\ $	$\begin{array}{c} 1.\ 83\\$	$\begin{array}{c} 0.\ 55\\ 0.\ 55\\ 0.\ 55\\ 0.\ 55\\ 0.\ 55\\ 0.\ 55\\ 0.\ 55\\ 0.\ 55\\ 0.\ 55\\ 0.\ 55\\ 0.\ 55\\ 0.\ 55\\ 0.\ 55\\ 0.\ 54\\ 0.\ 54\\ 0.\ 54\\ 0.\ 54\\ 0.\ 54\\ 0.\ 54\\ 0.\ 54\\ 0.\ 54\\ 0.\ 54\\ 0.\ 54\\ 0.\ 54\\ 0.\ 54\\ 0.\ 54\\ 0.\ 54\\ 0.\ 53\\ 0.\ 55\ 0.\ 55\\ 0.\ 55\$	5.00 5.00	0.00 0.00	0.69 0.67 0.66 0.65 0.64 0.63 0.62 0.61 0.59 0.58 0.57 0.56 0.55 0.54 0.53 0.52 0.51 0.51 0.51 0.51 0.48 0.48 0.48 0.44 0.44 0.42 0.44 0.42 0.42 0.42 0.42 0.42 0.33 0.35 0.32 0.31	$\begin{array}{c} 0.\ 69\\ 0.\ 67\\ 0.\ 66\\ 0.\ 65\\ 0.\ 64\\ 0.\ 63\\ 0.\ 62\\ 0.\ 61\\ 0.\ 63\\ 0.\ 52\\ 0.\ 56\\ 0.\ 58\\ 0.\ 57\\ 0.\ 56\\ 0.\ 55\\ 0.\ 54\\ 0.\ 53\\ 0.\ 52\\ 0.\ 51\\ 0.\ 51\\ 0.\ 51\\ 0.\ 51\\ 0.\ 51\\ 0.\ 51\\ 0.\ 48\\ 0.\ 47\\ 0.\ 46\\ 0.\ 43\\ 0.\ 42\\ 0.\ 44\\ 0.\ 43\\ 0.\ 42\\ 0.\ 41\\ 0.\ 40\\ 0.\ 39\\ 0.\ 38\\ 0.\ 37\\ 0.\ 36\\ 0.\ 35\\$
35.00	1. 77	0. 50	5.00	0. 00	0. 34	0.34
35.50	1. 77	0. 50	5.00	0. 00	0. 33	0.33

39.00	1.73	0.49	5.00	0.00	0.26	0. 26	
39.00 39.50	1.73	0.49	5.00	0.00	0.20	0.25	
40.00	1.72	0.48	5.00	0.00	0.23	0.23	
40.50	1.72	0.48	5.00	0.00	0.22	0. 22	
41.00	1.72	0.48	5.00	0.00	0.21	0. 21	
41.50	1.71	0.47	5.00	0.00	0.19	0.19	
42.00	1.71	0.47	5.00	0.00	0.18	0. 18	
42.50	1.70	0.47	5.00	0.00	0.17	0.17	
43.00	1.70	0.47	5.00	0.00	0.17	0. 17	
43.50	1.69	0.47	5.00	0.00	0.16	0. 16	
44.00	1.69	0.46	5.00	0.00	0.15	0. 15	
44.50	1.68	0.46	5.00	0.00	0.15	0. 15	
45.00	1.68	0.46	5.00	0.00	0.14	0.14	
45.50	1.68	0.46	5.00	0.00	0.13	0. 13	
46.00	1.67	0.45	5.00	0.00	0.12	0. 12	
46.50	1.67	0.45	5.00	0.00	0.12	0. 12	
47.00	1.66	0.45	5.00	0.00	0.11	0. 11	
47.50	1.66	0.45	5.00	0.00	0.10	0. 10	
48.00	1.65	0.44	5.00	0.00	0.09	0.09	
48.50	1.65	0.44	5.00	0.00	0.08	0.08	
49.00	1.65	0.44	5.00	0.00	0.07	0.07	
49.50	1.64	0.44	5.00	0.00	0.06	0.06	
50.00	1.64	0.44	5.00	0.00	0.05	0.05	
50.50	1.63	0.43	5.00	0.00	0.03	0.03	
51.00	1.63	0.43	5.00	0.00	0.02	0.02	
51.50	1.63	0.43	5.00	0.00	0.00	0.00	
			<u> </u>				
		efaction					
(F.S. i	s limit	ed to 5,	CRRIS	limited	το 2,	CSR is limite	ed to 2)


Units: Unit: qc, fs, Stress or Pressure = atm (1.0581tsf); Unit Weight = pcf; Depth = ft; Settlement = in.

	1 atm (atmosphere) = 1 tsf (ton/ft2)						
	CRRm	Cyclic resistance ratio from soils					
	CSRsf	Cyclic stress ratio induced by a given earthquake (with user					
request	factor of safet	y)					
	F. S.	Factor of Safety against liquefaction, F.S.=CRRm/CSRsf					
	S_sat	Settlement from saturated sands					
	S_dry	Settlement from Unsaturated Sands					
	S_al I	Total Settlement from Saturated and Unsaturated Sands					
	NoLiq	No-Liquefy Soils					




Allowable Downward Capacity Total Resistance/F.S. (tons)

Depth (ft)



GENERAL NOTES

DESCRIPTION OF SYMBOLS AND ABBREVIATIONS



DESCRIPTIVE SOIL CLASSIFICATION

Soil classification is based on the Unified Soil Classification System. Coarse Grained Solls have more than 50% of their dry weight retained on a #200 sieve; their principal descriptors are: boulders, cobbles, gravel or sand. Fine Grained Soils have less than 50% of their dry weight retained on a #200 sieve; they are principally described as clays if they are plastic, and silts if they are slightly plastic or non-plastic. Major constituents may be added as modifiers and minor constituents may be added according to the relative proportions based on grain size. In addition to gradation, coarse-grained soils are defined on the basis of their in-place relative density and fine-grained soils on the basis of their consistency.

LOCATION AND ELEVATION NOTES

Unless otherwise noted, Latitude and Longitude are approximately determined using a hand-held GPS device. The accuracy of such devices is variable. Surface elevation data annotated with +/- indicates that no actual topographical survey was conducted to confirm the surface elevation. Instead, the surface elevation was approximately determined from topographic maps of the area.

STRENGTH TERMS	RELATIVE DENSITY OF COARSE-GRAINED SOILS (More than 50% retained on No. 200 sieve.) Density determined by Standard Penetration Resistance Includes gravels, sands and silts.			CONSISTENCY OF FINE-GRAINED SOILS (50% or more passing the No. 200 sieve.) Consistency determined by laboratory shear strength testing, field visual-manual procedures or standard penetration resistance			
	Descriptive Term (Density)	Standard Penetration or N-Value Blows/Ft.	Ring Sampler Blows/Ft.	Descriptive Term (Consistency)	Unconfined Compressive Strength, Qu, psf	Standard Penetration or N-Value Blows/Ft.	Ring Sampler Blows/Ft.
	Very Loose	0 - 3	0 - 6	Very Soft	less than 500	0 - 1	< 3
	Loose	4 - 9	7 - 18	Soft	500 to 1,000	2 - 4	3-4
	Medium Dense	10 - 29	19 - 58	Medium-Stiff	1,000 to 2,000	4 - 8	5 - 9
	Dense	30 - 50	59 - 98	Stiff	2,000 to 4,000	8 - 15	10 - 18
	Very Dense	> 50	≥ 99	Very Stiff	4,000 to 8,000	15 - 30	19 - 42
				Hard	> 8,000	> 30	> 42

RELATIVE PROPORTIONS OF SAND AND GRAVEL

Descriptive	Term(s)
of other con	stituents
Trace	
With	
Modifier	

Percent of **Dry Weight** < 15 15 - 29 > 30

RELATIVE PROPORTIONS OF FINES

Descriptive Term(s) of other constituents	Percent of Dry Weight
Trace	< 5
With	5-12
Modifier	> 12

GRAIN SIZE TERMINOLOGY

Major Component of Sample Boulders Cobbles Gravel Sand Silt or Clay

Over 12 in. (300 mm) 12 in. to 3 in. (300mm to 75mm) 3 in. to #4 sieve (75mm to 4.75 mm) #4 to #200 sieve (4.75mm to 0.075mm Passing #200 sieve (0.075mm)

Particle Size

erraco

PLASTICITY DESCRIPTION

Term Non-plastic Low Medium High

Plasticity Index 0 1 - 10 11 - 30

> 30



Unified Soil Classification System

^A Based on the material passing the 3-inch (75-mm) sieve

D₁₀ x D₆₀

cobbles or boulders, or both" to group name.

 $E Cu = D_{60}/D_{10}$ $Cc = (D_{30})^2$

If field sample contained cobbles or boulders, or both, add "with

^c Gravels with 5 to 12% fines require dual symbols: GW-GM well-

^D Sands with 5 to 12% fines require dual symbols: SW-SM well-

^F If soil contains ≥ 15% sand, add "with sand" to group name. ^G If fines classify as CL-ML, use dual symbol GC-GM, or SC-SM.

graded sand with silt, SW-SC well-graded sand with clay, SP-SM

poorly graded sand with silt, SP-SC poorly graded sand with clay.

graded gravel with silt, GW-GC well-graded gravel with clay, GP-GM

poorly graded gravel with silt, GP-GC poorly graded gravel with clay.

в

Criteria for Assigning Group Symbols and Group Names Using				Soil Classification	
Laboratory Tests ^A					Group Name ^B
	Gravels: More than 50% of	Clean Gravels: Less than 5% fines ^c	Cu≥4 and 1≤Cc≤3 ^E	GW	Well-graded gravel F
			Cu<4 and/or [Cc<1 or Cc>3.0] E	GP	Poorly graded gravel F
	coarse fraction retained on No. 4	Gravels with Fines: More than 12% fines ^c	Fines classify as ML or MH	GM	Silty gravel ^{F, G, H}
Coarse-Grained Soils:	sieve		Fines classify as CL or CH	GC	Clayey gravel ^{F, G, H}
More than 50% retained on No. 200 sieve	Sands: 50% or more of coarse fraction passes No. 4 sieve	Clean Sands: Less than 5% fines ^D	Cu≥6 and 1≤Cc≤3 ^E	SW	Well-graded sand ¹
			Cu<6 and/or [Cc<1 or Cc>3.0] E	SP	Poorly graded sand ^I
		Sands with Fines: More than 12% fines ^D	Fines classify as ML or MH	SM	Silty sand ^{G, H, I}
			Fines classify as CL or CH	SC	Clayey sand ^{G, H, I}
			$PI~>~7$ and plots above "A" line $^{\lrcorner}$	CL	Lean clay ^{K, L, M}
	Silts and Clays: Liquid limit less than 50	Inorganic:	PI < 4 or plots below "A" line ^J	ML	Silt ^{K, L, M}
		Organic:	LL oven dried	OL	Organic clay ^{K, L, M, N}
Fine-Grained Soils:			LL oven dried LL not dried < 0.75		Organic silt ^{K, L, M, O}
50% or more passes the No. 200 sieve	e	Inorganic:	PI plots on or above "A" line	СН	Fat clay ^{K, L, M}
	Silts and Clays:		PI plots below "A" line	MH	Elastic silt ^{K, L, M}
	Liquid limit 50 or more		LL oven dried LL not dried < 0.75	ОН	Organic clay ^{K, L, M, P}
		Organic:			Organic silt ^{K, L, M, Q}
Highly organic soils:	soils: Primarily organic matter, dark in color, and organic odor			PT	Peat

^H If fines are organic, add "with organic fines" to group name.

- If soil contains \geq 15% gravel, add "with gravel" to group name.
- J If Atterberg limits plot in shaded area, soil is a CL-ML, silty clay.
- $^{\rm K}$ If soil contains 15 to 29% plus No. 200, add "with sand" or

"with gravel," whichever is predominant

- ^L If soil contains ≥ 30% plus No. 200 predominantly sand, add "sandy" to group name.
- ^M If soil contains ≥ 30% plus No. 200, predominantly gravel, add "gravelly" to group name.
- ^N PI ≥ 4 and plots on or above "A" line.
- $^{\circ}$ PI < 4 or plots below "A" line.
- P PI plots on or above "A" line.
- $^{\rm O}$ PI plots below "A" line.
- 60 For classification of fine-grained soils and fine-grained fraction JU Line of coarse-grained soils 50 à Equation of "A" - line PLASTICITY INDEX (PI) Horizontal at PI=4 to LL=25.5. CH OT OH then PI=0.73 (LL-20) 40 Equation of "U" - line Vertical at LL=16 to PI=7 then PI=0.9 (LL-8) 30 CL OT OL 20 MH or OH 10 7 CL - MI ML or OL 4 0 110 0 10 16 20 30 40 60 70 80 90 100 50 LIQUID LIMIT (LL)