

DOCKETED

Docket Number:	26-SPPE-01
Project Title:	RB Inyokern Data Center (RBIDC)
TN #:	271673
Document Title:	Appendix N Supplement - Section N2 Revision 2
Description:	N/A
Filer:	Kyle Mohr
Organization:	R&L Capital Inc
Submitter Role:	Applicant Representative
Submission Date:	7/28/2026 10:41:57 AM
Docketed Date:	7/28/2026


RB INYOKERN DATA CENTER


Application for Small Power Plant Exemption (SPPE)

Inyokern, Kern County, California

Docket Number – 26-SPPE-01


Appendix N Supplement - Section N.2 Revision 2









SHEET INDEX	
<u>SHEET</u>	<u>DESCRIPTION</u>
SP-1.0	SITE MAP OVERVIEW
SP-1.1	SITE EASEMENTS
SP-1.2	SITE ENLARGED VIEW
SP-1.3	GENERATOR YARD ENLARGED VIEWS



SCALE: 1" = 200'



GRAPHIC SCALE


200' 100' 0' 100' 200'

(IN FEET)

1 inch = 200 ft.

[illegible]

CORNERSTONE
ENGINEERS • ADVISORS
Bringing Solutions and Light



DEVELOPMENT BY:
R & L CAPITAL, INC.
P.O. BOX 907
TRONA, CA 93592

**INYOKERN DATA CENTER
CUP X, ZONE MAP 47
INYOKERN, CALIFORNIA
SITE MAP OVERVIEW**

DESIGNER:	JEM
CHECKED BY:	CAW
DATE:	6/24/2026
DRAFTER	WS
SCALE:	AS SHOWN
COMP. NO:11600100_SITE_PLAN	
JOB NO.:	1160-01-00
SP-1.0	SHEET 1 OF 4



PROJECT DESCRIPTION:
THE PROPOSED RB INYOKERN DATA CENTER IS A 99 MW POWER GENERATING FACILITY, WITHIN AN APPROXIMATELY 238,000-SQUARE-FOOT, SINGLE-STORY DATA CENTER CAMPUS. SITUATED ON APPROXIMATELY 50-ACRES.


LEGAL DESCRIPTION:
PORTIONS OF PARCELS 2, 3 AND 4 OF PARCEL MAP NO. 4949, AS PER MAP RECORDED APRIL 19, 1979 IN BOOK 22 OF PARCEL MAPS AT PAGE 142 SITUATED IN THE NORTHWEST QUARTER OF SECTION 29, T.26S., R.39E., M.D.M. IN THE UNINCORPORATED AREA OF THE COUNTY OF KERN, STATE OF CALIFORNIA.

STATISTICAL INFORMATION:
EXISTING ZONING: M-2 PD
EXISTING LAND USE DESIGNATION: 4.1 7.2/2.5
EXISTING USE: VACANT
PROPOSED USE: DATA CENTER
ACREAGE: 50± ACRES
PROPOSED BUILDING:
HEIGHT: SINGLE STORY MAX 30' HEIGHT
DATA CENTER: 238,000 S.F. PERMANENTLY OCCUPIED
OFFICES: 17,325 S.F.
BUILDING COVERAGE: 16.0%
LANDSCAPE AREA: SHALL BE XERISCAPE, DROUGHT-TOLERANT, AND WILL FOLLOW KERN COUNTY, AND INYOKERN SPECIFIC PLAN REQUIREMENTS
PARKING SPACES PROVIDED: 155
-124 STANDARD
-5 STANDARD ADA
-1 VAN ADA
-16 EV ONLY
-2 ADA EV ONLY
-7 FUTURE EV CHARGING
ACCESSIBLE SIGNAGE AND STRIPING SHALL BE PER CBC 11B-502

- LEGEND:**
- PROPERTY BOUNDARY
 - BESS SETBACK
 - BESS BATTERY ENERGY STORAGE SETBACK
 - PAVED ROAD
 - XERISCAPE AND DROUGHT TOLERANT PLANTS

- NOTES:**
- OFFSITE GEN-TIE EASEMENT AND POINT OF INTERCONNECT ARE SHOWN ON SHEET 1.
 - THE SCE SUBTRANSMISSION LINE ALIGNMENTS AND INYOKERN SUBSTATION EXPANSION TO BE PROVIDED BY SEPARATE PLANS. SOME COMPONENTS NOT YET CONFIRMED. FINAL ENGINEERING PENDING.
 - NO PROJECT NATURAL GAS SUPPLY LINES ARE PROPOSED FOR IT-CRITICAL OR ENERGY GENERATION PURPOSES. ANY POTENTIAL INCIDENTAL BUILDING UTILITY GAS CONNECTION WILL BE DETERMINED DURING FINAL ENGINEERING.

- EASEMENTS:**
- EASEMENT FOR PUBLIC HIGH WAY PURPOSES, COUNTY ROAD NO. 440, ALSO KNOWN AS INYOKERN ROAD, AND IS LOCATED WITHIN THE NORTHERLY 30' OF SAID LIND, IN FAVOR OF COUNTY OF KERN AS ESTABLISHED BY ORDER OF THE BOARD OF SUPER VISORS OF KERN COUNTY ENTERED IN VOLUME 21 AT PAGE 130 OF MINUTE BOOKS.
 - EASEMENT FOR PUBLIC HIGH WAY PURPOSES, COUNTY ROAD NO. 697, ALSO KNOWN AS STATE HIGHWAY ROUTE 178, IN FAVOR OF COUNTY OF KERN AS ESTABLISHED BY ORDER OF THE BOARD OF SUPERVISORS OF KERN COUNTY ENTERED IN VOLUME 27 AT PAGE 232 OF MINUTE BOOKS.
 - EASEMENT FOR ROAD PURPOSES IN FAVOR OF COUNTY OF KERN PER BOOK 1131, PAGE 155 OF OFFICIAL RECORDS
 - EASEMENT FOR ELECTRIC LINES AND TELEPHONE LINES PURPOSES IN FAVOR OF SOUTHERN CALIFORNIA EDISON COMPANY, FORMERLY CALIFORNIA ELECTRIC POWER COMPANY AND INTERSTATE. TELEGRAPH COMPANY PER BOOK 1182, PAGE 162 OF OFFICIAL RECORDS. (CENTERLINE SHOWN - NO WIDTH GIVEN)
 - EASEMENT FOR TELEPHONE AND TELEPHONE LINES PURPOSES IN FAVOR OF CALIFORNIA INTERSTATE COMPANY, FORMERLY INTERSTATE. TELEGRAPH COMPANY PER BOOK 1237, PAGE 160 OF OFFICIAL RECORDS. (CENTERLINE SHOWN - NO WIDTH GIVEN)
 - EASEMENT FOR PUBLIC INGRESS, EGRESS, ROAD AND UTILITY PURPOSES IN FAVOR OF CLARENCE F. IVES, GLADYS IVES AND JACOB L. ORETSKY PER BOOK 4661, PAGE 446 OF OFFICIAL RECORDS.
 - EASEMENT FOR INGRESS, EGRESS, AND ROAD PURPOSES IN FAVOR OF THE PUBLIC IN GENERAL PER BOOK 5164, PAGE 593 AND RE-RECORDED PER BOOK 5186, PAGE 2331; BOTH OF OFFICIAL RECORDS.



BY:

REVISION:

NO. DATE:

CORNERSTONE

ENGINEERS•ADVISORS

Bringing Solutions and Light

5509 YOUNG STREET, BAKERSFIELD CA 93311
TEL: (661) 325-9474 FAX: (661) 322-0129
www.cornerstoneeng.com

DESIGNER: JEM

CHECKED BY: CAW

DATE: 6/24/2026

DRAFTER: WS

SCALE: AS SHOWN

COMP. NO:11600100_SITE_PLAN

JOB NO.: 1160-01-00

SHEET 2 OF 4


DEVELOPMENT BY:

R & L CAPITAL, INC.

P.O. BOX 907
TRONA, CA 93592

INYOKERN DATA CENTER
CUP X, ZONE MAP 47
INYOKERN, CALIFORNIA
SITE EASEMENTS

SP-1.1



PROPOSED DRAINAGE BASIN
TOP OF BASIN: 125'x520'
2:1 SIDE SLOPES
18" DEEP
DESIGN RUNOFF VOLUME: 2.2 AC-FT

APN 084-010-45
(PTN.)

APN 084-010-59


APN 084-010-43, -44 & -45
(PTN.)

EASEMENTS:

- EASEMENT FOR PUBLIC HIGH WAY PURPOSES, COUNTY ROAD NO. 440, ALSO KNOWN AS INYOKERN ROAD, AND IS LOCATED WITHIN THE NORTHERLY 30' OF SAID LIND, IN FAVOR OF COUNTY OF KERN AS ESTABLISHED BY ORDER OF THE BOARD OF SUPERVISORS OF KERN COUNTY ENTERED IN VOLUME 21 AT PAGE 130 OF MINUTE BOOKS.
- EASEMENT FOR PUBLIC HIGH WAY PURPOSES, COUNTY ROAD NO. 697, ALSO KNOWN AS STATE HIGHWAY ROUTE 178, IN FAVOR OF COUNTY OF KERN AS ESTABLISHED BY ORDER OF THE BOARD OF SUPERVISORS OF KERN COUNTY ENTERED IN VOLUME 27 AT PAGE 232 OF MINUTE BOOKS.
- EASEMENT FOR ROAD PURPOSES IN FAVOR OF COUNTY OF KERN PER BOOK 1131, PAGE 155 OF OFFICIAL RECORDS
- EASEMENT FOR ELECTRIC LINES AND TELEPHONE LINES PURPOSES IN FAVOR OF SOUTHERN CALIFORNIA EDISON COMPANY, FORMERLY CALIFORNIA ELECTRIC POWER COMPANY AND INTERSTATE TELEGRAPH COMPANY PER BOOK 1182, PAGE 162 OF OFFICIAL RECORDS. (CENTERLINE SHOWN - NO WIDTH GIVEN)
- EASEMENT FOR TELEPHONE AND TELEPHONE LINES PURPOSES IN FAVOR OF CALIFORNIA INTERSTATE COMPANY, FORMERLY INTERSTATE TELEGRAPH COMPANY PER BOOK 1237, PAGE 160 OF OFFICIAL RECORDS. (CENTERLINE SHOWN - NO WIDTH GIVEN)
- EASEMENT FOR PUBLIC INGRESS, EGRESS, ROAD AND UTILITY PURPOSES IN FAVOR OF CLARENCE F. IVES, GLADYS IVES AND JACOB L. ORETSKY PER BOOK 4661, PAGE 446 OF OFFICIAL RECORDS.
- EASEMENT FOR INGRESS, EGRESS, AND ROAD PURPOSES IN FAVOR OF THE PUBLIC IN GENERAL PER BOOK 5164, PAGE 593 AND RE-RECORDED PER BOOK 5186, PAGE 2331; BOTH OF OFFICIAL RECORDS.

LEGEND:


- PROPERTY BOUNDARY
- BESS SETBACK
- BESS BATTERY ENERGY STORAGE SETBACK
- PAVED ROAD
- XERISCAPE AND DROUGHT TOLERANT PLANTS



CORNERSTONE ENGINEERS-ADVISORS <i>Bringing Solutions and Light</i> 5509 YOUNG STREET, BAKERSFIELD CA 93311 TEL: (661) 325-9474 FAX: (661) 322-0129 www.cornerstoneeng.com	NO. _____ DATE: _____ REVISION: _____	BY: _____ NO. _____ DATE: _____ REVISION: _____
	DEVELOPMENT BY: R & L CAPITAL, INC. P.O. BOX 907 TRONA, CA 93592	
	INYOKERN DATA CENTER CUP X, ZONE MAP 47 INYOKERN, CALIFORNIA SITE ENLARGED VIEW	


DESIGNER:	JEM
CHECKED BY:	CAW
DATE:	6/24/2026
DRAFTER:	WS
SCALE:	AS SHOWN
COMP. NO:	11600100_SITE_PLAN
JOB NO.:	1160-01-00
SHEET	3
SP-1.2	OF 4

FIGURE 1-1 — REGIONAL LOCATION MAP
RB Inyokern Data Center · SPPE Docket No. 26-SPPE-01



Project Boundary

FIGURE 1-2 — VICINITY MAP
RB Inyokern Data Center · SPPE Docket No. 26-SPPE-01




0 1,000 2,000 ft

APNs 084-010-43, -44, -45, -48. See Figure 1-3 for parcel detail.

Project Boundary

FIGURE EXEC SUMM-3 — VICINITY LAND USE MAP
RB Inyokern Data Center · SPPE Docket No. 26-SPPE-01



6/30/2026

Elizabeth Huber
Project Manager
California Energy Commission
1516 Ninth Street
Sacramento, California 95814

**Re: Statement of Intended EKAPCD Permit Conditions — Emergency Backup Generators
— RB Inyokern Data Center (Docket No. 26-SPPE-01)**

Dear Ms. Huber:

On behalf of R&L Capital, Inc., the Applicant for the RB Inyokern Data Center (RBIDC or Project) (Docket No. 26-SPPE-01), this letter is submitted to the CEC docket as a supplement to the Main Application (TN 269893) in response to CEC Data Requests Set 1, DR AQ-9 and DR AQ-10. The proposed project daily and annual emissions limits requested in DR AQ-11 are provided in the Applicant's response to DR AQ-11 submitted herewith and are further documented in the updated Air Quality Impact and GHG Analysis (AQIA, Appendix F Supplement — Section F.1 Revision 1) submitted concurrently as part of this Data Request Set 1 response package.

The Project proposes forty (40) Caterpillar 3516E diesel-fired emergency standby generators, each rated at 3 MW (3,000 kW / 3,750 kVA), equipped with Johnson Matthey CompactSCRT aftertreatment (SCR + DPF + DEF) achieving Tier 4 Final-equivalent emission levels at stack, consistent with Best Available Control Technology (BACT) as evaluated in the AQIA (Appendix F.1, TN 269606). The generators are EPA Tier 2-certified base engines subject to 40 C.F.R. Part 60 Subpart IIII and are exempt from Subpart ZZZZ pursuant to 40 C.F.R. §63.6590(c)(1). The Applicant intends to submit a formal Authority to Construct (ATC) application to EKAPCD prior to engine installation consistent with Mitigation Measure MM 4.6-10 of the Main Application (TN 269893).

The Applicant will formally request that the EKAPCD Authority to Construct (ATC) and Permit to Operate (PTO) for the Project's emergency backup generators reflect the testing parameters

assumed in the AQIA (Appendix F.1, TN 269606) pursuant to EKAPCD Regulation II, Rule 210.1 (New and Modified Stationary Source Review), as follows:

With Respect to DR AQ-9 — Concurrent Testing Limitation and SCR Warm-Up Period

The Applicant will formally request EKAPCD to include an enforceable permit condition in the project's Authority to Construct and Permit to Operate limiting concurrent testing of emergency standby engines so that only a single engine operates for maintenance and readiness testing at any given time, with a limit on the number of engines tested per day consistent with the daily emissions calculations in the AQIA (Appendix F.1, TN 269606). This condition is consistent with the sequential single-engine testing protocol established in Section 4.3 (TN 269893) and Section 4.6.5.5 (TN 269893) of the Main Application, and as modeled in the AQIA (Appendix F.1, TN 269606).

With respect to the SCR warm-up period, the Applicant confirms that the daily emission calculations in the AQIA (Appendix F.1, TN 269606) account for the SCR warm-up period in the total daily emissions figure. As established in the Johnson Matthey CompactSCRT General Arrangement Drawing (Drawing No. 202-C0039989, Revision B, Appendix A.3, TN 269593), reagent injection and emissions treatment will not occur at system temperatures below 500°F, and the urea injection permissive threshold is 575°F. During the warm-up period prior to reaching this threshold, engines were assumed to emit emissions equal to the uncontrolled engine emission ratings without SCR and DPF equipped, as described in Section 4.3 (TN 269893) and the AQIA (Appendix F.1, TN 269606). Warm-up periods ranging from 7 minutes to 21 minutes depending on load point are incorporated into the AQIA modeling as referenced in Section 4.3 (TN 269893). The Applicant will formally request EKAPCD to incorporate the warm-up period assumption into the enforceable daily emissions limit condition in the Authority to Construct and Permit to Operate, ensuring that the permit condition is consistent with the modeled daily emissions basis in the AQIA (Appendix F.1, TN 269606) and the updated AQIA (Appendix F Supplement — Section F.1 Revision 1).

With Respect to DR AQ-10 — Testing Hours Restriction

The Applicant will formally request EKAPCD to include an enforceable permit condition in the project's Authority to Construct and Permit to Operate restricting all standby engine testing to the hours of 7:00 AM to 5:00 PM daily. This condition is consistent with the testing window established in Section 4.3 (TN 269893) of the Main Application and as modeled in the AQIA (Appendix F.1, TN 269606), applied as a conservative modeling assumption to ensure that emissions during testing are evaluated during the hours most likely to produce meaningful ground-level concentrations at nearby sensitive receptors. No testing or maintenance operation shall occur outside these hours except during genuine utility outages requiring emergency backup power.

The Applicant notes that as disclosed in Section 4.3 (TN 269893) of the Main Application, the Applicant is not proposing a fixed test schedule specifying hours versus load points, and that testing will be conducted based upon the Applicant's judgment considering manufacturers' recommendations, staff availability, and necessity. The testing hours restriction requested above reflects the AQIA modeling assumption and does not otherwise constrain the Applicant's operational testing program beyond the parameters modeled in the AQIA.

This letter is submitted to the CEC docket as a supplement to the Main Application (TN 269893) with a new Transmittal Number assigned at time of submission. The Applicant remains available to discuss any questions regarding the permit conditions described in this letter.

Respectfully submitted,

Kyle Mohr
Company Representative
On behalf of R&L Capital, Inc.
P.O. Box 907
Trona, California 93592

084 090 10 00 8
APIF CALIFORNIA LLC
950 TOWER LN STE 750
FOSTER CITY CA 94404-2191

084 140 02 00 9
FARRIS FREDERICK P & SUSAN
E ET AL
140 W RIDGECREST BL
RIDGECREST CA 93555

084 090 13 00 7
HUGAIS SALMAN A
P O BOX 1718
INYOKERN CA 93527

084 152 05 00 5
MARSHALL BILL H &
BARBARA L
P O BOX 38
INYOKERN CA 93527

084 010 43 00 0
R & L CAPITAL INC
P O BOX 907
TRONA CA 93592

084 040 03 00 3
SARKOVICH TESS VICTORIA
4240 JOHNSTON
RIDGECREST CA 93555

352 085 07 00 6
U S A
*
*

084 010 22 00 9
VILLACARLOS DOLORES A
2 COLINA LN
ROLLING HLS EST CA 90274-
1529

084 010 59 00 7
DILLON ENTERPRISES INC
178 VALLEY VIEW DR
EXETER CA 93221

084 140 09 00 0
FARRIS FREDERICK PAUL &
SUSAN E
140 W RIDGECREST BL
RIDGECREST CA 93555

084 152 02 00 6
JACOBS TIMOTHY D 2018 TR
219 STATION AV
RIDGECREST CA 93555-3839

084 021 01 00 8
MONTOKA SANDRA & HENRY
GEOVANI
1300 W IOWA AV
RIDGECREST CA 93555

084 010 58 00 4
RIZZARDINI HERBERT M &
VICKI JT LIV TR
830 W HOWELL AV
RIDGECREST CA 93555-3359

084 010 10 00 4
STATE OF CALIFORNIA
P O BOX 847
BISHOP CA 93514

084 021 18 00 8
UNION PACIFIC R/R CO
1400 DOUGLAS ST # 1640
OMAHA NE 68179-1610

084 040 29 00 9
WHEELER TRUST
142 ELMCREST DR
BIG PINE CA 93513-2004

084 010 21 00 6
ESCARCEGA RAFAEL
PO BOX 1532
BREA CA 92822

084 070 17 00 3
FRIEDMAN SHARON &
ELLIOTT
6203 VARIEL AV U 121
WOODLAND HILLS CA 91367-

084 010 17 00 5
LINDGREN JANIS MARIE
1009 W UPJOHN AV
RIDGECREST CA 93555

084 010 33 00 1
PEARL THOMAS FAMILY
TRUST 2024
8712 N MAGNOLIA AV # 104
SANTÉE CA 92071-4545

084 010 46 00 9
RIZZARDINI HERBERT M &
VICKI LIV TRUST
830 W HOWELL AV
RIDGECREST CA 93555-3359

084 010 42 00 7
TIMBISHA SHOSHONE TRIBE
2800 COTTAGE WAY RM W
2820
SACRAMENTO CA 95825

352 085 09 00 2
UNION PACIFIC R/R CO
1400 DOUGLAS ST # 1610
OMAHA NE 68179-1610

ATN	Owner's Name	Address 1	Address 2
084 090 10 00 8	APIF CALIFORNIA LLC	950 TOWER LN STE 750	FOSTER CITY CA 94404-2191
084 010 59 00 7	DILLON ENTERPRISES INC	178 VALLEY VIEW DR	EXETER CA 93221
084 010 21 00 6	ESCARCEGA RAFAEL	PO BOX 1532	BREA CA 92822
084 140 02 00 9	FARRIS FREDERICK P & SUSAN E ET AL	140 W RIDGECREST BL	RIDGECREST CA 93555
084 140 09 00 0	FARRIS FREDERICK PAUL & SUSAN E	140 W RIDGECREST BL	RIDGECREST CA 93555
084 070 17 00 3	FRIEDMAN SHARON & ELLIOTT	6203 VARIEL AV U 121	WOODLAND HILLS CA 91367-2472
084 090 13 00 7	HUGAIS SALMAN A	P O BOX 1718	INYOKERN CA 93527
084 152 02 00 6	JACOBS TIMOTHY D 2018 TR	219 STATION AV	RIDGECREST CA 93555-3839
084 010 17 00 5	LINDGREN JANIS MARIE	1009 W UPJOHN AV	RIDGECREST CA 93555
084 010 18 00 8	LINDGREN JANIS MARIE	1009 W UPJOHN AV	RIDGECREST CA 93555
084 152 05 00 5	MARSHALL BILL H & BARBARA L	P O BOX 38	INYOKERN CA 93527
084 021 01 00 8	MONTOYA SANDRA & HENRY GEOVANI	1300 W IOWA AV	RIDGECREST CA 93555
084 010 33 00 1	PEARL THOMAS FAMILY TRUST 2024	8712 N MAGNOLIA AV # 104	SANTEE CA 92071-4545
084 010 43 00 0	R & L CAPITAL INC	P O BOX 907	TRONA CA 93592
084 010 44 00 3	R & L CAPITAL INC	P O BOX 907	TRONA CA 93592
084 010 45 00 6	R & L CAPITAL INC	P O BOX 907	TRONA CA 93592
084 010 47 00 2	R & L CAPITAL INC	P O BOX 907	TRONA CA 93592
084 010 48 00 5	R & L CAPITAL INC	P O BOX 907	TRONA CA 93592
084 010 58 00 4	RIZZARDINI HERBERT M & VICKI JT LIV TR	830 W HOWELL AV	RIDGECREST CA 93555-3359
084 010 46 00 9	RIZZARDINI HERBERT M & VICKI LIV TRUST	830 W HOWELL AV	RIDGECREST CA 93555-3359
084 040 03 00 3	SARKOVICH TESS VICTORIA	4240 JOHNSTON	RIDGECREST CA 93555
084 010 10 00 4	STATE OF CALIFORNIA	P O BOX 847	BISHOP CA 93514
084 010 35 00 7	STATE OF CALIFORNIA	P O BOX 847	BISHOP CA 93514
084 010 42 00 7	TIMBISHA SHOSHONE TRIBE	2800 COTTAGE WAY RM W 2820	SACRAMENTO CA 95825
352 085 07 00 6	U S A	*	*
352 501 11 00 0	U S A	*	*
084 021 18 00 8	UNION PACIFIC R/R CO	1400 DOUGLAS ST # 1640	OMAHA NE 68179-1610
352 085 09 00 2	UNION PACIFIC R/R CO	1400 DOUGLAS ST # 1610	OMAHA NE 68179-1610
084 010 22 00 9	VILLACARLOS DOLORES A	2 COLINA LN	ROLLING HLS EST CA 90274-1529
084 040 29 00 9	WHEELER TRUST	142 ELMCREST DR	BIG PINE CA 93513-2004

084 211 12 01 4
ADAMS FLOYD ALAN
P O BOX 668
ANAHOLA HI 96703

084 040 32 00 7
AMS BSNS GROUP LLC
151 E TRUXTUN AV
BAKERSFIELD CA 93305

084 140 07 00 4
BARNETT WILBURN CHARLES
JR
6950 ATHEL
INYOKERN CA 93527

084 212 12 00 2
BERRI SONNEY A & BARNES
ROBERT A
132 S FIRE OPAL ST
RIDGECREST CA 93555

084 212 24 00 7
BRADY EDGAR A
P O BOX 1703
INYOKERN CA 93527

084 140 06 00 1
CALIF INTERSTATE TEL CO
*
*

084 222 17 00 0
CARROLL TIM & INGRID
PO BOX 1655
INYOKERN CA 93527

084 040 06 00 2
CISNEROS CARLOS &
AGUILAR MARIA LUCIA
38017 13TH ST E
PALMDALE CA 93550

084 212 10 00 6
DELGADO JAMES S & MARY C
S
1060 N LOGAN ST
OLATHE KS 66061-6320

084 010 59 00 7
DILLON ENTERPRISES INC
178 VALLEY VIEW DR
EXETER CA 93221

084 191 04 00 7
ADAMS JAMES D & SHERYL L
PO BOX 28
INYOKERN CA 93527

084 090 10 00 8
APIF CALIFORNIA LLC
950 TOWER LN STE 750
FOSTER CITY CA 94404-2191

084 191 27 00 4
BASINET MICHAEL J
P O BOX 1043
BONSALL CA 92003

084 151 13 00 1
BERRY BS LIVING TRUST 2024
1432 2ND ST
INYOKERN CA 93527

084 152 06 00 8
BRYANT GERALD N &
IMAGENE
17534 SNOWCAP LOOP
WARSAW MO 65355

084 100 01 00 4
CALVIN IRA L & ROSSIE
LIVING TRUST
PO BOX 1106
INYOKERN CA 93527-1106

084 130 04 00 2
CHAVEZ GEORGE
1321 W 186TH ST
GARDENA CA 90248-4118

084 151 22 00 7
CLINE ROGER H & GAYLE A
P O BOX 868
INYOKERN CA 93527

084 151 16 00 0
DELU VENTURES LLC
P O BOX 431371
LOS ANGELES CA 90043

084 191 13 00 3
DSHLD
P O BOX 10506
BAKERSFIELD CA 93389

084 191 15 00 9
ALTUNA ESTEBAN ALBERT &
F KARINA
4018 TEMESCAL AV
NORCO CA 92860

084 212 11 00 9
BAKER RICHARD D &
JENNIFER
PO BOX 432
INYOKERN CA 93527

084 140 08 00 7
BEACHBOARD JOSEPH
309 S LINCOLN ST
RIDGECREST CA 93555

084 160 08 00 3
BOW DEBRA
P O BOX 644
INYOKERN CA 93527

084 151 14 00 4
BS BERRY LIVING TRUST 2024
1432 2ND ST
INYOKERN CA 93527

084 100 10 00 0
CANNED KERN LLC
736 SHERRI ST
RIDGECREST CA 93555

084 100 03 00 0
CHIN HEI KYUNG
P O BOX 825
AZUSA CA 91702

084 040 10 00 3
COUNTY OF KERN
*
*

084 191 10 00 4
DIETZEL JAMES & LINDA FAM
TRUST
3477 JEFFERY ST
LAKE ISABELLA CA 93240

084 070 15 00 7
ERNST WALTER T
P O BOX 186
INYOKERN CA 93527

084 010 21 00 6
ESCARCEGA RAFAEL
PO BOX 1532
BREA CA 92822

084 140 09 00 0
FARRIS FREDERICK PAUL &
SUSAN E
140 W RIDGECREST BL
RIDGECREST CA 93555

084 191 09 00 2
FISCHER MICHAEL
6457 VALLEY AV
INYOKERN CA 93527

084 191 12 00 0
GARCIA ANGEL ANTONIO
MARTINEZ
PO BOX 1362
INYOKERN CA 93527-1362

084 160 17 00 9
GOMEZ FELIX SERNA
PO BOX 283
INYOKERN CA 93527-0283

084 211 15 00 4
HAHN IRMA
321 W PERDEW AV
RIDGECREST CA 93555

084 191 11 00 7
HILL DAVID L
6449 VALLEY AV
INYOKERN CA 93527

084 070 11 00 5
HUGAIS ABDULAZIZ &
TAWHEEL ENTIKHAB AL
1130 MARBELLA DR
RIDGECREST CA 93555

084 090 13 00 7
HUGAIS SALMAN A
P O BOX 1718
INYOKERN CA 93527

084 151 21 00 4
INDIAN WLS COMM
METHODIST CHR
P O BOX 936
INYOKERN CA 93527

084 140 05 00 8
FARRIS FREDERICK P & SUSAN
E
140 W RIDGECREST BL
RIDGECREST CA 93555

084 212 01 00 0
FARRIS RONALD C
6525 SIERRA AV
INYOKERN CA 93527

084 070 17 00 3
FRIEDMAN SHARON &
ELLIOTT
6203 VARIEL AV U 121
WOODLAND HILLS CA 91367-

084 160 06 00 7
GILLESPIE SHEILA
PO BOX 445
INYOKERN CA 93527

084 070 41 00 2
GRAHAM CHARLES F &
LSESLIE L
6556 SUNSET AV
INYOKERN CA 93527

084 211 11 01 1
HAHN STEVEN EDWIN &
BONNI A
PO BOX 236
INYOKERN CA 93527-0236

084 021 03 00 4
HOPE MACK A & ALICE J
P O BOX 519
INYOKERN CA 93527

084 130 15 00 4
HUGAIS ABDULAZIZ A
1130 MARBELLA DR
RIDGECREST CA 93555

084 191 20 00 3
IBRAHIM WAEL S TRUST
2601 MAIN ST STE 1000
IRVINE CA 92614-4233

084 151 06 00 1
INYOKERN CHAMBER OF
COMMERCE
P O BOX 232
INYOKERN CA 93527

084 140 02 00 9
FARRIS FREDERICK P & SUSAN
E ET AL
140 W RIDGECREST BL
RIDGECREST CA 93555

084 212 09 00 4
FILLMORE SHANNON
1201 BROWN RD
INYOKERN CA 93527

084 040 28 00 6
GALLIER HOLLY EVE
P O BOX 415
INYOKERN CA 93537-0415

084 151 23 00 0
GOMEZ FELIX S & MA DE LA
LUZ
P O BOX 283
INYOKERN CA 93527

084 211 05 00 5
HAHN IRMA
321 PERDEW AV
RIDGECREST CA 93555-2514

084 130 01 00 3
HARTMAN AB TR
325 LARKSPUR ST
RIDGECREST CA 93555-4429

084 100 04 00 3
HOWL N COYOTE INC
P O BOX 100
INYOKERN CA 93527

084 090 12 00 4
HUGAIS SALMAN A
PO BOX 1718
INYOKERN CA 93527-1718

352 085 14 00 6
INDIAN WELLS VALLEY
AIRPORT DS
110 MAHAN ST
RIDGECREST CA 93555

084 151 20 00 1
INYOKERN COMM UNITED
METH CH
P O BOX 936
INYOKERN CA 93527

084 221 02 00 9
INYOKERN COMMUNITY SERV
DIST
P O BOX 1418
INYOKERN CA 93527

084 152 02 00 6
JACOBS TIMOTHY D 2018 TR
219 STATION AV
RIDGECREST CA 93555-3839

084 130 02 00 6
JORNALES ROBERT A & HANH
T
628 W WASP AV
RIDGECREST CA 93555-5237

084 070 21 00 4
KINCHELOE CHRISTOPHER
MARK
1312 BROADWAY ST
INYOKERN CA 93527

084 010 50 00 0
LINDGREN JANICE MARIE
1009 W UPJOHN AV
RIDGECREST CA 93555

084 160 09 00 6
LLAMAS EVARISTO PUGA &
QUEZADA MARIA M
6600 ASH AV
INYOKERN CA 93527

084 070 37 00 1
MAHAN ERICK WILLIAM &
CYNTHIA LEE
PO BOX 2624
AVALON CA 90704-2624

084 070 39 00 7
MARTINEZ BARRIENTOS JOSE
ISRAEL & JENNIFER S
PO BOX 271
INYOKERN CA 93527

084 151 07 00 4
MARTY VERNA B
PO BOX 1813
RIDGECREST CA 93556-1813

084 212 25 00 0
MC MURTRIE SJ TRUST
PO BOX 2199
RIDGECREST CA 93556

084 151 08 00 7
INYOKERN COMMUNITY
SERVICES DIST
1429 N BROADWAY
INYOKERN CA 93527

084 130 16 00 7
JENNINGS ROBERT W &
GUADALUPE L
PO BOX 1584
INYOKERN CA 93527-1584

084 100 15 00 5
JOSEPH LINDA LOU
380 N CYPRESS ST
WOODLAKE CA 93286-1204

084 191 16 00 2
LEGACY CARING PARTNERS
CO
1721 RUSSELL RUTLIN WY
BAKERSFIELD CA 93311

084 010 17 00 5
LINDGREN JANIS MARIE
1009 W UPJOHN AV
RIDGECREST CA 93555

084 212 04 00 9
LUBIN ROSALINE W
26590 WARD ST
HIGHLAND CA 92346-5673

084 211 02 00 6
MANGRUM DIANE E
PO BOX 1472
INYOKERN CA 93527-1472

084 100 16 00 8
MARTINEZ CELIA DEL
CARMEN DIAZ
6047 BROWN RD
INYOKERN CA 93527-2112

084 010 36 00 0
MAVRAKIS CHRISTOS G
17794 WREN DR
CANYON COUNTRY CA 91387-
3827

084 021 01 00 8
MONTOKA SANDRA & HENRY
GEOVANI
1300 W IOWA AV
RIDGECREST CA 93555

084 070 42 00 5
IVES CLARENCE F & GLADYS
L
1115 TRUXTUN AV
BAKERSFIELD CA 93301

084 212 26 00 3
JOHNSON CHRISTIAN V
1200 BROADWAY ST
INYOKERN CA 93527

084 070 16 00 0
KELLOGG WARREN K
23 HIGHLAND CREEK DR
HENDERSON NV 89052-6612

084 010 55 00 5
LINDGREN BARBARA J
10554 MT LINCOLN DR
PEYTON CO 80831-3815

084 010 38 00 6
LINDREN RODNEY A
1009 W UPJOHN AV
RIDGECREST CA 93555

084 211 08 00 4
LYMAN LINDA
PO BOX 1750
RIDGECREST CA 93556-1750

084 152 05 00 5
MARSHALL BILL H &
BARBARA L
P O BOX 38
INYOKERN CA 93527

084 070 04 00 5
MARTINEZ JOSE DE SANTIAGO
6553 LOCUST AV
INYOKERN CA 93527

084 191 06 00 3
MC FARLAND JOSEPH A
6501 VALLEY AV
INYOKERN CA 93527-0017

084 211 17 00 0
MORROW MATTHEW JOSEPH
6508 SIERRA AV BOX 744
INYOKERN CA 93527

084 151 09 00 0
MUNOZ RICARDO
1255 S GATEWAY BL
RIDGECREST CA 93555

084 130 14 00 1
OVERLOCK VELMA R
7330 HAZELTINE AV
VAN NUYS CA 91405

084 010 33 00 1
PEARL THOMAS FAMILY
TRUST 2024
8712 N MAGNOLIA AV # 104
SANTEE CA 92071-4545

084 040 31 00 4
PHAM JOHN LUAN
9392 RUSSELL AV
GARDEN GROVE CA 92844

084 010 43 00 0
R & L CAPITAL INC
P O BOX 907
TRONA CA 93592

084 010 46 00 9
RIZZARDINI HERBERT M &
VICKI LIV TRUST
830 W HOWELL AV
RIDGECREST CA 93555-3359

084 212 15 00 1
ROSALES MARIA E T
PO BOX 704
INYOKERN CA 93527

084 191 18 00 8
SMITH MICHAEL D & KANDI L
625 GLEN CT
RIDGECREST CA 93555

084 211 04 00 2
SODEN LINDA
P O BOX 273
INYOKERN CA 93527

084 010 10 00 4
STATE OF CALIFORNIA
P O BOX 847
BISHOP CA 93514

084 021 02 00 1
MURPHY PATRICK D
P O BOX 822
INYOKERN CA 93527-0822

084 100 14 00 2
PATETE MARIE KRISTI
PO BOX 179
INYOKERN CA 93527

084 191 08 00 9
PEREZ DORINDA L
6461 VALLEY AV
INYOKERN CA 93527

084 191 02 00 1
PINTO RALPH JR
P O BOX 1975
RIDGECREST CA 93555

352 085 05 00 0
RENEWAL LLC
2200 POST OAK BL STE 1525
HOUSTON TX 77056

084 191 17 00 5
RODRIGUEZ NATANIEL
831 N CHINA LAKE BL
RIDGECREST CA 93555

084 040 03 00 3
SARKOVICH TESS VICTORIA
4240 JOHNSTON
RIDGECREST CA 93555

084 212 13 00 5
SMITH SARAH G LIVING
TRUST
PO BOX 896
INYOKERN CA 93527

084 010 11 00 7
SOUTHERN CALIF EDISON CO
2244 WALNUT GROVE AV
ROSEMEAD CA 91770-3714

084 100 02 00 7
SUNRISE AT FIVE PEAKS LLC
1700 W 39TH PL
LOS ANGELES CA 90062

084 211 01 00 3
MURRAY KATHLEEN TRUST
2023
6525 SUNSET AV
INYOKERN CA 93527-2903

084 211 07 00 1
PATTERSON JIMMY J
PO BOX 1208
INYOKERN CA 93527

084 212 08 01 0
PETTERSEN ROSA VICTORIA
3500 W OLD LINDEN RD
SHOW LOW AZ 85901-3319

084 191 03 00 4
PINTO RALPH JR
PO BOX 1975
RIDGECREST CA 93556-1975

084 010 58 00 4
RIZZARDINI HERBERT M &
VICKI JT LIV TR
830 W HOWELL AV
RIDGECREST CA 93555-3359

084 040 15 00 8
ROGERS PAULA
P O BOX 472
INYOKERN CA 93527

084 211 03 00 9
SEMBACH BETTYE RIVERA
P O BOX 1956
RIDGECREST CA 93555

084 130 03 00 9
SMITH STEPHEN WAYNE
P O BOX 134
INYOKERN CA 93527

084 151 19 00 9
SPECK ASHLEY
6553 ORCHARD AV
INYOKERN CA 93527

084 211 14 00 1
TAMAYO ARTHUR
319 NORTH ST
TAFT CA 93268

084 191 07 00 6
TAYLOR KAYE TR
PO BOX 1073
INYOKERN CA 93527

084 010 42 00 7
TIMBISHA SHOSHONE TRIBE
2800 COTTAGE WAY RM W
2820
SACRAMENTO CA 95825

352 085 08 00 9
U S A
650 CAPITOL MALL
SACRAMENTO CA 95814-4708

084 222 22 00 4
VAN VALKENBURGH GERALD
E ET AL
5365 TOSCANA WY APT 431
SAN DIEGO CA 92122-5313

084 140 01 00 6
WANG JIANPING
1903 RALPH AV
STOCKTON CA 95206

084 151 15 00 7
WESLEY JANNELL
P O BOX 566
INYOKERN CA 93527

084 212 23 00 4
WINTERS TIMOTHY
5983 LOFTY OAK RD
MEMPHIS TN 38115

084 191 05 00 0
THOMPSON ANDREW L
PO BOX 255
INYOKERN CA 93527-0255

084 040 09 00 1
TNT WESTN HOMES INC
3644 W GRAAF AV
RIDGECREST CA 93555-7931

084 021 18 00 8
UNION PACIFIC R/R CO
1400 DOUGLAS ST # 1640
OMAHA NE 68179-1610

084 040 02 00 0
VHT REVOCABLE TRUST
3104 O ST 292
SACRAMENTO CA 95816

084 040 17 00 4
WEBB PAUL
PO BOX 32
INYOKERN CA 93527-0032

084 040 29 00 9
WHEELER TRUST
142 ELMCREST DR
BIG PINE CA 93513-2004

084 021 04 00 7
WRIGHT DEWAYNE
9845 LEV AV
ARLETA CA 91331

084 070 29 00 8
THOMPSON ROBERT HOSKINS
TRUST
328 W ANTONIO DR
CLOVIS CA 93612-5022

352 085 07 00 6
U S A
*
*

352 085 09 00 2
UNION PACIFIC R/R CO
1400 DOUGLAS ST # 1610
OMAHA NE 68179-1610

084 010 22 00 9
VILLACARLOS DOLORES A
2 COLINA LN
ROLLING HLS EST CA 90274-
1529

084 152 04 00 2
WEEMS LANE MICHAEL
PO BOX 1144
INYOKERN CA 93527-1144

084 160 07 00 0
WILSON LIANNE K
PO BOX 1214
INYOKERN CA 93527-1214

084 070 03 00 2
ZENDEJAS JOE
1129 E TERRACE AV
FRESNO CA 93704-5841

ATN	Owner's Name	Address 1	Address 2
084 211 12 01 4	ADAMS FLOYD ALAN	P O BOX 668	ANAHOLA HI 96703
084 191 04 00 7	ADAMS JAMES D & SHERYL L	PO BOX 28	INYOKERN CA 93527
084 191 15 00 9	ALTUNA ESTEBAN ALBERT & F KARINA	4018 TEMESCAL AV	NORCO CA 92860
084 040 32 00 7	AMS BSNS GROUP LLC	151 E TRUXTUN AV	BAKERSFIELD CA 93305
084 090 10 00 8	APIF CALIFORNIA LLC	950 TOWER LN STE 750	FOSTER CITY CA 94404-2191
084 212 11 00 9	BAKER RICHARD D & JENNIFER	PO BOX 432	INYOKERN CA 93527
084 140 07 00 4	BARNETT WILBURN CHARLES JR	6950 ATHEL	INYOKERN CA 93527
084 191 27 00 4	BASINET MICHAEL J	P O BOX 1043	BONSALL CA 92003
084 140 08 00 7	BEACHBOARD JOSEPH	309 S LINCOLN ST	RIDGECREST CA 93555
084 212 12 00 2	BERRI SONNEY A & BARNES ROBERT A	132 S FIRE OPAL ST	RIDGECREST CA 93555
084 151 13 00 1	BERRY BS LIVING TRUST 2024	1432 2ND ST	INYOKERN CA 93527
084 160 08 00 3	BOW DEBRA	P O BOX 644	INYOKERN CA 93527
084 212 24 00 7	BRADY EDGAR A	P O BOX 1703	INYOKERN CA 93527
084 152 06 00 8	BRYANT GERALD N & IMAGE NE	17534 SNOWCAP LOOP	WARSAW MO 65355
084 151 14 00 4	BS BERRY LIVING TRUST 2024	1432 2ND ST	INYOKERN CA 93527
084 140 06 00 1	CALIF INTERSTATE TEL CO	*	*
084 100 01 00 4	CALVIN IRA L & ROSSIE LIVING TRUST	PO BOX 1106	INYOKERN CA 93527-1106
084 100 10 00 0	CANNED KERN LLC	736 SHERRI ST	RIDGECREST CA 93555
084 100 11 00 3	CANNED KERN LLC	736 SHERRI ST	RIDGECREST CA 93555
084 100 12 00 6	CANNED KERN LLC	736 SHERRI ST	RIDGECREST CA 93555
084 222 17 00 0	CARROLL TIM & INGRID	PO BOX 1655	INYOKERN CA 93527
084 130 04 00 2	CHAVEZ GEORGE	1321 W 186TH ST	GARDENA CA 90248-4118
084 100 03 00 0	CHIN HEI KYUNG	P O BOX 825	AZUSA CA 91702
084 040 06 00 2	CISNEROS CARLOS & AGUILAR MARIA LUCIA	38017 13TH ST E	PALMDALE CA 93550
084 151 22 00 7	CLINE ROGER H & GAYLE A	P O BOX 868	INYOKERN CA 93527
084 040 10 00 3	COUNTY OF KERN	*	*
084 221 01 00 6	COUNTY OF KERN	*	*
084 212 10 00 6	DELGADO JAMES S & MARY C S	1060 N LOGAN ST	OLATHE KS 66061-6320
084 151 16 00 0	DELU VENTURES LLC	P O BOX 431371	LOS ANGELES CA 90043
084 191 10 00 4	DIETZEL JAMES & LINDA FAM TRUST	3477 JEFFERY ST	LAKE ISABELLA CA 93240
084 010 59 00 7	DILLON ENTERPRISES INC	178 VALLEY VIEW DR	EXETER CA 93221
084 191 13 00 3	DSHLD	P O BOX 10506	BAKERSFIELD CA 93389

084 191 14 00 6	DSHLD	P O BOX 10506	BAKERSFIELD CA 93389
084 070 15 00 7	ERNST WALTER T	P O BOX 186	INYOKERN CA 93527
084 010 21 00 6	ESCARCEGA RAFAEL	PO BOX 1532	BREA CA 92822
084 140 05 00 8	FARRIS FREDERICK P & SUSAN E	140 W RIDGECREST BL	RIDGECREST CA 93555
084 140 02 00 9	FARRIS FREDERICK P & SUSAN E ET AL	140 W RIDGECREST BL	RIDGECREST CA 93555
084 140 09 00 0	FARRIS FREDERICK PAUL & SUSAN E	140 W RIDGECREST BL	RIDGECREST CA 93555
084 212 01 00 0	FARRIS RONALD C	6525 SIERRA AV	INYOKERN CA 93527
084 212 09 00 4	FILLMORE SHANNON	1201 BROWN RD	INYOKERN CA 93527
084 191 09 00 2	FISCHER MICHAEL	6457 VALLEY AV	INYOKERN CA 93527
084 070 17 00 3	FRIEDMAN SHARON & ELLIOTT	6203 VARIEL AV U 121	WOODLAND HILLS CA 91367-2472
084 040 28 00 6	GALLIER HOLLY EVE	P O BOX 415	INYOKERN CA 93537-0415
084 191 12 00 0	GARCIA ANGEL ANTONIO MARTINEZ	PO BOX 1362	INYOKERN CA 93527-1362
084 160 06 00 7	GILLESPIE SHEILA	PO BOX 445	INYOKERN CA 93527
084 151 23 00 0	GOMEZ FELIX S & MA DE LA LUZ	P O BOX 283	INYOKERN CA 93527
084 160 17 00 9	GOMEZ FELIX SERNA	PO BOX 283	INYOKERN CA 93527-0283
084 070 41 00 2	GRAHAM CHARLES F & LSESLIE L	6556 SUNSET AV	INYOKERN CA 93527
084 211 05 00 5	HAHN IRMA	321 PERDEW AV	RIDGECREST CA 93555-2514
084 211 15 00 4	HAHN IRMA	321 W PERDEW AV	RIDGECREST CA 93555
084 211 11 01 1	HAHN STEVEN EDWIN & BONNI A	PO BOX 236	INYOKERN CA 93527-0236
084 211 16 00 7	HAHN STEVEN EDWIN & BONNI A	PO BOX 236	INYOKERN CA 93527-0236
084 212 02 00 3	HAHN STEVEN EDWIN & BONNI A	PO BOX 236	INYOKERN CA 93527-0236
084 212 22 00 1	HAHN STEVEN EDWIN & BONNI A	PO BOX 236	INYOKERN CA 93527-0236
084 130 01 00 3	HARTMAN AB TR	325 LARKSPUR ST	RIDGECREST CA 93555-4429
084 191 11 00 7	HILL DAVID L	6449 VALLEY AV	INYOKERN CA 93527
084 021 03 00 4	HOPE MACK A & ALICE J	P O BOX 519	INYOKERN CA 93527
084 100 04 00 3	HOWLN COYOTE INC	P O BOX 100	INYOKERN CA 93527
084 100 05 00 6	HOWLN COYOTE INC	P O BOX 100	INYOKERN CA 93527
084 100 06 00 9	HOWLN COYOTE INC	P O BOX 100	INYOKERN CA 93527
084 070 11 00 5	HUGAIS ABDULAZIZ & Taweel Entikhab Al	1130 MARBELLA DR	RIDGECREST CA 93555
084 070 14 00 4	HUGAIS ABDULAZIZ & Taweel Entikhab Al	1130 MARBELLA DR	RIDGECREST CA 93555
084 070 25 00 6	HUGAIS ABDULAZIZ & Taweel Entikhab Al	1130 MARBELLA DR	RIDGECREST CA 93555
084 130 15 00 4	HUGAIS ABDULAZIZ A	1130 MARBELLA DR	RIDGECREST CA 93555
084 090 12 00 4	HUGAIS SALMAN A	PO BOX 1718	INYOKERN CA 93527-1718

084 090 13 00 7	HUGAIS SALMAN A	P O BOX 1718	INYOKERN CA 93527
084 191 20 00 3	IBRAHIM WAEL S TRUST	2601 MAIN ST STE 1000	IRVINE CA 92614-4233
352 085 14 00 6	INDIAN WELLS VALLEY AIRPORT DS	110 MAHAN ST	RIDGECREST CA 93555
084 151 21 00 4	INDIAN WLS COMM METHODIST CHR	P O BOX 936	INYOKERN CA 93527
084 151 06 00 1	INYOKERN CHAMBER OF COMMERCE	P O BX 232	INYOKERN CA 93527
084 151 20 00 1	INYOKERN COMM UNITED METH CH	P O BOX 936	INYOKERN CA 93527
084 221 02 00 9	INYOKERN COMMUNITY SERV DIST	P O BOX 1418	INYOKERN CA 93527
084 151 08 00 7	INYOKERN COMMUNITY SERVICES DIST	1429 N BROADWAY	INYOKERN CA 93527
084 070 42 00 5	IVES CLARENCE F & GLADYS L	1115 TRUXTUN AV	BAKERSFIELD CA 93301
084 070 43 00 8	IVES CLARENCE F & GLADYS L	1115 TRUXTUN AV	BAKERSFIELD CA 93301
084 152 02 00 6	JACOBS TIMOTHY D 2018 TR	219 STATION AV	RIDGECREST CA 93555-3839
084 130 16 00 7	JENNINGS ROBERT W & GUADALUPE L	PO BOX 1584	INYOKERN CA 93527-1584
084 212 26 00 3	JOHNSON CHRISTIAN V	1200 BROADWAY ST	INYOKERN CA 93527
084 130 02 00 6	JORNALES ROBERT A & HANH T	628 W WASP AV	RIDGECREST CA 93555-5237
084 130 12 00 5	JORNALES ROBERT A & HANH T	628 W WASP AV	RIDGECREST CA 93555-5237
084 130 13 00 8	JORNALES ROBERT A & HANH T	628 W WASP AV	RIDGECREST CA 93555-5237
084 100 15 00 5	JOSEPH LINDA LOU	380 N CYPRESS ST	WOODLAKE CA 93286-1204
084 070 16 00 0	KELLOGG WARREN K	23 HIGHLAND CREEK DR	HENDERSON NV 89052-6612
084 070 21 00 4	KINCHELOE CHRISTOPHER MARK	1312 BROADWAY ST	INYOKERN CA 93527
084 070 36 00 8	KINCHELOE CHRISTOPHER MARK	1312 BROADWAY ST	INYOKERN CA 93527
084 191 16 00 2	LEGACY CARING PARTNERS CO	1721 RUSSELL RUTLIN WY	BAKERSFIELD CA 93311
084 010 55 00 5	LINDGREN BARBARA J	10554 MT LINCOLN DR	PEYTON CO 80831-3815
084 010 56 00 8	LINDGREN BARBARA J	10554 MT LINCOLN DR	PEYTON CO 80831-3815
084 010 57 00 1	LINDGREN BARBARA J	10554 MT LINCOLN DR	PEYTON CO 80831-3815
084 010 50 00 0	LINDGREN JANICE MARIE	1009 W UPJOHN AV	RIDGECREST CA 93555
084 010 51 00 3	LINDGREN JANICE MARIE	1009 W UPJOHN AV	RIDGECREST CA 93555
084 010 52 00 6	LINDGREN JANICE MARIE	1009 W UPJOHN AV	RIDGECREST CA 93555
084 010 17 00 5	LINDGREN JANIS MARIE	1009 W UPJOHN AV	RIDGECREST CA 93555
084 010 18 00 8	LINDGREN JANIS MARIE	1009 W UPJOHN AV	RIDGECREST CA 93555
084 010 19 00 1	LINDGREN JANIS MARIE	1009 W UPJOHN AV	RIDGECREST CA 93555
084 010 20 00 3	LINDGREN JANIS MARIE	1009 W UPJOHN AV	RIDGECREST CA 93555
084 010 38 00 6	LINDREN RODNEY A	1009 W UPJOHN AV	RIDGECREST CA 93555
084 010 39 00 9	LINDREN RODNEY A	1009 W UPJOHN AV	RIDGECREST CA 93555

084 160 09 00 6	LLAMAS EVARISTO PUGA & QUEZADA MARIA M	6600 ASH AV	INYOKERN CA 93527
084 212 04 00 9	LUBIN ROSALINE W	26590 WARD ST	HIGHLAND CA 92346-5673
084 212 05 00 2	LUBIN ROSALINE W	26590 WARD ST	HIGHLAND CA 92346-5673
084 211 08 00 4	LYMAN LINDA	PO BOX 1750	RIDGECREST CA 93556-1750
084 070 37 00 1	MAHAN ERICK WILLIAM & CYNTHIA LEE	PO BOX 2624	AVALON CA 90704-2624
084 070 38 00 4	MAHAN ERICK WILLIAM & CYNTHIA LEE	PO BOX 2624	AVALON CA 90704-2624
084 070 40 00 9	MAHAN ERICK WILLIAM & CYNTHIA LEE	PO BOX 2624	AVALON CA 90704-2624
084 211 02 00 6	MANGRUM DIANE E	PO BOX 1472	INYOKERN CA 93527-1472
084 152 05 00 5	MARSHALL BILL H & BARBARA L	P O BOX 38	INYOKERN CA 93527
084 070 39 00 7	MARTINEZ BARRIENTOS JOSE ISRAEL & JENNIFER S	PO BOX 271	INYOKERN CA 93527
084 100 16 00 8	MARTINEZ CELIA DEL CARMEN DIAZ	6047 BROWN RD	INYOKERN CA 93527-2112
084 100 17 00 1	MARTINEZ CELIA DEL CARMEN DIAZ	6047 BROWN RD	INYOKERN CA 93527-2112
084 070 04 00 5	MARTINEZ JOSE DE SANTIAGO	6553 LOCUST AV	INYOKERN CA 93527
084 151 07 00 4	MARTY VERNA B	PO BOX 1813	RIDGECREST CA 93556-1813
084 010 36 00 0	MAVRAKIS CHRISTOS G	17794 WREN DR	CANYON COUNTRY CA 91387-3827
084 191 06 00 3	MC FARLAND JOSEPH A	6501 VALLEY AV	INYOKERN CA 93527-0017
084 212 25 00 0	MC MURTRIE SJ TRUST	PO BOX 2199	RIDGECREST CA 93556
084 021 01 00 8	MONTOYA SANDRA & HENRY GEOVANI	1300 W IOWA AV	RIDGECREST CA 93555
084 211 17 00 0	MORROW MATTHEW JOSEPH	6508 SIERRA AV BOX 744	INYOKERN CA 93527
084 151 09 00 0	MUNOZ RICARDO	1255 S GATEWAY BL	RIDGECREST CA 93555
084 151 10 00 2	MUNOZ RICARDO	1255 S GATEWAY BL	RIDGECREST CA 93555
084 021 02 00 1	MURPHY PATRICK D	P O BOX 822	INYOKERN CA 93527-0822
084 211 01 00 3	MURRAY KATHLEEN TRUST 2023	6525 SUNSET AV	INYOKERN CA 93527-2903
084 130 14 00 1	OVERLOCK VELMA R	7330 HAZELTINE AV	VAN NUYS CA 91405
084 100 14 00 2	PATETE MARIE KRISTI	PO BOX 179	INYOKERN CA 93527
084 211 07 00 1	PATTERSON JIMMY J	PO BOX 1208	INYOKERN CA 93527
084 010 33 00 1	PEARL THOMAS FAMILY TRUST 2024	8712 N MAGNOLIA AV # 104	SANTEE CA 92071-4545
084 010 34 00 4	PEARL THOMAS FAMILY TRUST 2024	8712 N MAGNOLIA AV # 104	SANTEE CA 92071-4545
084 191 08 00 9	PEREZ DORINDA L	6461 VALLEY AV	INYOKERN CA 93527
084 212 08 01 0	PETTERSEN ROSA VICTORIA	3500 W OLD LINDEN RD	SHOW LOW AZ 85901-3319
084 040 31 00 4	PHAM JOHN LUAN	9392 RUSSELL AV	GARDEN GROVE CA 92844
084 191 02 00 1	PINTO RALPH JR	P O BOX 1975	RIDGECREST CA 93555
084 191 03 00 4	PINTO RALPH JR	PO BOX 1975	RIDGECREST CA 93556-1975

084 010 43 00 0	R & L CAPITAL INC	P O BOX 907	TRONA CA 93592
084 010 44 00 3	R & L CAPITAL INC	P O BOX 907	TRONA CA 93592
084 010 45 00 6	R & L CAPITAL INC	P O BOX 907	TRONA CA 93592
084 010 47 00 2	R & L CAPITAL INC	P O BOX 907	TRONA CA 93592
084 010 48 00 5	R & L CAPITAL INC	P O BOX 907	TRONA CA 93592
352 085 05 00 0	RENEWA I LLC	2200 POST OAK BL STE 1525	HOUSTON TX 77056
352 085 06 00 3	RENEWA I LLC	2200 POST OAK BL STE 1525	HOUSTON TX 77056
352 501 09 00 5	RENEWA I LLC	2200 POST OAK BL STE 1525	HOUSTON TX 77056
352 501 10 00 7	RENEWA I LLC	2200 POST OAK BL STE 1525	HOUSTON TX 77056
084 010 58 00 4	RIZZARDINI HERBERT M & VICKI JT LIV TR	830 W HOWELL AV	RIDGECREST CA 93555-3359
084 010 46 00 9	RIZZARDINI HERBERT M & VICKI LIV TRUST	830 W HOWELL AV	RIDGECREST CA 93555-3359
084 191 17 00 5	RODRIGUEZ NATANIEL	831 N CHINA LAKE BL	RIDGECREST CA 93555
084 040 15 00 8	ROGERS PAULA	P O BOX 472	INYOKERN CA 93527
084 212 15 00 1	ROSALES MARIA E T	PO BOX 704	INYOKERN CA 93527
084 212 16 00 4	ROSALES MARIA E T	PO BOX 704	INYOKERN CA 93527
084 212 17 00 7	ROSALES MARIA E T	PO BOX 704	INYOKERN CA 93527
084 040 03 00 3	SARKOVICH TESS VICTORIA	4240 JOHNSTON	RIDGECREST CA 93555
084 211 03 00 9	SEMBACH BETTYE RIVERA	P O BOX 1956	RIDGECREST CA 93555
084 191 18 00 8	SMITH MICHAEL D & KANDI L	625 GLEN CT	RIDGECREST CA 93555
084 191 19 00 1	SMITH MICHAEL D & KANDI L	625 GLEN CT	RIDGECREST CA 93555
084 212 13 00 5	SMITH SARAH G LIVING TRUST	PO BOX 896	INYOKERN CA 93527
084 212 14 00 8	SMITH SARAH G LIVING TRUST	PO BOX 896	INYOKERN CA 93527
084 130 03 00 9	SMITH STEPHEN WAYNE	P O BOX 134	INYOKERN CA 93527
084 211 04 00 2	SODEN LINDA	P O BOX 273	INYOKERN CA 93527
084 010 11 00 7	SOUTHERN CALIF EDISON CO	2244 WALNUT GROVE AV	ROSEMEAD CA 91770-3714
084 151 19 00 9	SPECK ASHLEY	6553 ORCHARD AV	INYOKERN CA 93527
084 010 10 00 4	STATE OF CALIFORNIA	P O BOX 847	BISHOP CA 93514
084 010 35 00 7	STATE OF CALIFORNIA	P O BOX 847	BISHOP CA 93514
084 100 02 00 7	SUNRISE AT FIVE PEAKS LLC	1700 W 39TH PL	LOS ANGELES CA 90062
084 100 13 00 9	SUNRISE AT FIVE PEAKS LLC	1700 W 39TH PL	LOS ANGELES CA 90062
084 211 14 00 1	TAMAYO ARTHUR	319 NORTH ST	TAFT CA 93268
084 191 07 00 6	TAYLOR KAYE TR	PO BOX 1073	INYOKERN CA 93527
084 191 05 00 0	THOMPSON ANDREW L	PO BOX 255	INYOKERN CA 93527-0255

084 070 29 00 8	THOMPSON ROBERT HOSKINS TRUST	328 W ANTONIO DR	CLOVIS CA 93612-5022
084 010 42 00 7	TIMBISHA SHOSHONE TRIBE	2800 COTTAGE WAY RM W 2820	SACRAMENTO CA 95825
084 040 09 00 1	TNT WESTN HOMES INC	3644 W GRAAF AV	RIDGECREST CA 93555-7931
352 085 07 00 6	U S A	*	*
352 085 08 00 9	U S A	650 CAPITOL MALL	SACRAMENTO CA 95814-4708
352 501 11 00 0	U S A	*	*
084 021 18 00 8	UNION PACIFIC R/R CO	1400 DOUGLAS ST # 1640	OMAHA NE 68179-1610
352 085 09 00 2	UNION PACIFIC R/R CO	1400 DOUGLAS ST # 1610	OMAHA NE 68179-1610
352 085 10 00 4	UNION PACIFIC R/R CO	1400 DOUGLAS ST # 1610	OMAHA NE 68179-1610
084 222 22 00 4	VAN VALKENBURGH GERALD E ET AL	5365 TOSCANA WY APT 431	SAN DIEGO CA 92122-5313
084 040 02 00 0	VHT REVOCABLE TRUST	3104 O ST 292	SACRAMENTO CA 95816
084 010 22 00 9	VILLACARLOS DOLORES A	2 COLINA LN	ROLLING HLS EST CA 90274-1529
084 140 01 00 6	WANG JIANPING	1903 RALPH AV	STOCKTON CA 95206
084 040 17 00 4	WEBB PAUL	PO BOX 32	INYOKERN CA 93527-0032
084 152 04 00 2	WEEMS LANE MICHAEL	PO BOX 1144	INYOKERN CA 93527-1144
084 151 15 00 7	WESLEY JANNELL	P O BOX 566	INYOKERN CA 93527
084 040 29 00 9	WHEELER TRUST	142 ELMCREST DR	BIG PINE CA 93513-2004
084 160 07 00 0	WILSON LIANNE K	PO BOX 1214	INYOKERN CA 93527-1214
084 212 23 00 4	WINTERS TIMOTHY	5983 LOFTY OAK RD	MEMPHIS TN 38115
084 021 04 00 7	WRIGHT DEWAYNE	9845 LEV AV	ARLETA CA 91331
084 070 03 00 2	ZENDEJAS JOE	1129 E TERRACE AV	FRESNO CA 93704-5841

Patricia Newquist

From: Patricia Newquist
Sent: Friday, June 19, 2026 3:45 PM
To: 'stemperd@kerncounty.com'
Subject: Request - Service Standards and Response Time - Kern County EMS - Inyokern

Hello, Danielle.

We are processing an application for Small Power Plant Exemption permit with the California Energy Commission (CEC), **REF #26-SPPE-01**. The project is also referred to as RB Inyokern Data Center, located on the north side of SR 178 between Brown Road and I-395, Inyokern.

The CEC has requested the following information per Public Services comment (DR PS-1) : A written statement of current service standards and response times of the affected emergency medical services (EMS) agency.

We understand this type of request is handled by email or phone. Consider this a formal request, following a phone message with my contact information (see below) left this afternoon. Please expedite this request if possible. Kindly let me know if you have any questions.

We thank you in advance for your attention to this matter.

Respectfully,

Patricia Newquist

Senior Planner / Project Manager



**Cornerstone Engineering,
Inc.**

5509 Young Street, Bakersfield, CA
93311

Office: 661.325.9474

Cell: 661-333-7969

www.cornerstoneeng.com

From: [Jeff Fariss](#)
To: [Patricia Newquist](#)
Cc: [George Baker](#); [Danielle Stemper](#)
Subject: Requested Response Times
Date: Monday, June 22, 2026 10:44:16 AM

Caution: External (farissj@kerncounty.com)

First-Time Sender [Details](#)

[Safe](#) [Spam](#) [Phish](#) [More...](#) [FAQ](#) [Protection by INKY](#)

Patricia,

The area located at Brown Rd, Hwy 178 and 395 is currently classified as a Suburban response zone. Response times for that zone are as follows:

Priority 1 and 2 - 25 minutes - 90%

Priority C3A, C3B, and 3 - 30 minutes - 90%

Responses for this area should be coming from Ridgecrest.

Please let me know if you need anything else.

Jeff Fariss
EMS Program Manager
Kern County Public Health
farissj@kerncounty.com
Office - 661-868-5216
Cell – 661-301-9465



HIPAA NOTICE: The documents accompanying this electronic transmission, or this transmission itself, may contain Protected Health Information. This information belongs to the sender and is legally privileged. The information is intended only for the use of the individual or entity named above. If you are not the intended recipient, you are hereby notified that you may not disclose, copy, distribute or take action on the information in these documents. All such activities are strictly prohibited. If you have received this e-mail in error, please delete the e-mail immediately and empty your deleted items folder or take any steps necessary to ensure permanent deletion.

Patricia Newquist

From: Patricia Newquist
Sent: Friday, June 19, 2026 3:00 PM
To: 'Firerecords@kerncountyfire.org'
Subject: Request - Service Standards and Response Time - Kern County Fire Dept. Station 83 - Inyokern

Greetings,

We are processing an application for Small Power Plant Exemption permit with the California Energy Commission (CEC), **REF #26-SPPE-01**. The project is also referred to as RB Inyokern Data Center, located on the north side of SR 178 between Brown Road and I-395, Inyokern.

The CEC has requested the following information per Public Services comment (DR PS-1) : A written statement of current service standards and response times of the affected fire protection services.

We understand this type of request is handled through a Fire Record Request and that the expected turnaround time is 10-days. Please expedite this request if possible. Kindly let me know if you have any questions.

We thank you in advance for your attention to this matter.

Respectfully,

Patricia Newquist

Senior Planner / Project Manager



**Cornerstone Engineering,
Inc.**

5509 Young Street, Bakersfield, CA
93311

Office: 661.325.9474

Cell: 661-333-7969

www.cornerstoneeng.com

From: [Fire Records](#)
To: [Patricia Newquist](#)
Subject: RE: Request - Service Standards and Response Time - Kern County Fire Dept. Station 83 - Inyokern
Date: Monday, July 6, 2026 2:45:52 PM
Attachments: [image002.png](#)
[County.pdf](#)

External (firerecords@kerncountyfire.org)

[Graymail](#) [Spam](#) [Phish](#) [More...](#) [FAQ](#) [Protection by INKY](#)

Good afternoon Patricia,

Attached is the response I received regarding your request: "The first in fire station is 2.7 miles away, 6 minutes' drive time. I have also attached the ISO report for the area."

Best,



Addy Quintanilla
Office Services Technician
Kern County Fire Department
Investigation Unit

Notice: This e-mail message is for the sole use of the intended recipient(s) and may contain confidential and privileged information. Any unauthorized review, use, disclosure and distribution is prohibited. If you are not the intended recipient, please contact the sender by replying to e-mail and destroy all copies of the original message.

To contact our e-mail administrator directly, send an e-mail to: kcfdadmin@kerncountyfire.org.

From: Patricia Newquist <pmn@cornerstoneeng.com>
Sent: Tuesday, June 30, 2026 2:48 PM
To: Fire Records <firerecords@kerncountyfire.org>
Subject: RE: Request - Service Standards and Response Time - Kern County Fire Dept. Station 83 - Inyokern

CAUTION: This email originated from outside of the organization. Do not click links, open attachments, or provide information unless you recognize the sender and know the content is safe.

Hello, Addy.

Thank you for your email. How much of an extension do you need to provide us with a response? We plan on responding to CEC this week and can certainly follow up with your reply.

We do however look forward to hearing from you at your earliest opportunity.

Patricia Newquist
Senior Planner / Project Manager

Cornerstone Engineering, Inc.



5509 Young Street, Bakersfield, CA 93311
Office: 661.325.9474
Cell: 661-333-7969
www.cornerstoneeng.com

From: Fire Records <firerecords@kerncountyfire.org>
Sent: Tuesday, June 30, 2026 2:30 PM
To: Patricia Newquist <pmn@cornerstoneeng.com>
Subject: RE: Request - Service Standards and Response Time - Kern County Fire Dept. Station 83 - Inyokern

Good afternoon,

I apologies for the delay I am working with our team on your request. We ask for an extension to best provide the information you are looking for.

Best,



Addy Quintanilla
Office Services Technician
Kern County Fire Department
Investigation Unit

Notice: This e-mail message is for the sole use of the intended recipient(s) and may contain confidential and privileged information. Any unauthorized review, use, disclosure and distribution is prohibited. If you are not the intended recipient, please contact the sender by replying to e-mail and destroy all copies of the original message.

To contact our e-mail administrator directly, send an e-mail to: kcfadmin@kerncountyfire.org.

From: Patricia Newquist <pmn@cornerstoneeng.com>
Sent: Friday, June 19, 2026 3:00 PM
To: Fire Records <firerecords@kerncountyfire.org>
Subject: Request - Service Standards and Response Time - Kern County Fire Dept. Station 83 - Inyokern

CAUTION: This email originated from outside of the organization. Do not click links, open attachments, or provide information unless you recognize the sender and know the content is safe.

Greetings,

We are processing an application for Small Power Plant Exemption permit with the California Energy Commission (CEC), **REF #26-SPPE-01**. The project is also referred to as RB Inyokern Data Center, located on the north side of SR 178 between Brown Road and I-395, Inyokern.

The CEC has requested the following information per Public Services comment (DR PS-1) : A written statement of current service standards and response times of the affected fire protection services.

We understand this type of request is handled through a Fire Record Request and that the expected turnaround time is 10-days. Please expedite this request if possible. Kindly let me know if you have any questions.

We thank you in advance for your attention to this matter.

Respectfully,

Patricia Newquist

Senior Planner / Project Manager



Cornerstone Engineering, Inc.

5509 Young Street, Bakersfield, CA 93311

Office: 661.325.9474

Cell: 661-333-7969

www.cornerstoneeng.com

From: [JustFOIA Notification](#)
To: [Patricia Newquist](#)
Subject: Kern County Sheriff's Office Records Request RR-2026-990 Completed
Date: Thursday, July 16, 2026 3:58:36 PM

External (kerncountysheriffca@request.justfoia.com)

[Graymail](#) [Spam](#) [Phish](#) [More...](#) [FAQ](#) [Protection by INKY](#)



SHERIFF'S OFFICE - COUNTY OF KERN
DONNY YOUNGBLOOD
Sheriff-Coroner Public Administrator
1350 Norris Road
Bakersfield, CA 93308-2231

Dear Requestor,

The request [Request Number: RR-2026-990](#) has been completed. Please click on the request link to download the response documentation.

For retrieving these records in the future, your request number is RR-2026-990, and your security key is 2B909752.

Thank you,

Kern County Sheriff's Office - Support Services
34970 McMurtrey Avenue, 2nd Floor
Bakersfield, CA 93308
(661) 391-1601

Public Protection Classification (PPC®) Summary Report

Kern CO FD 5

California (S)

Prepared by

**Insurance Services Office, Inc.
1000 Bishops Gate Blvd., Ste. 300
P.O. Box 5404
Mt. Laurel, New Jersey 08054-5404
1-800-444-4554**

**Report Created March 2023
Effective July 1, 2023**

Background Information

Introduction

ISO collects and evaluates information from communities in the United States on their structure fire suppression capabilities. The data is analyzed using our Fire Suppression Rating Schedule (FSRS) and then a Public Protection Classification (PPC®) grade is assigned to the community. The surveys are conducted whenever it appears that there is a possibility of a PPC change. As such, the PPC program provides important, up-to-date information about fire protection services throughout the country.

The FSRS recognizes fire protection features only as they relate to suppression of first alarm structure fires. In many communities, fire suppression may be only a small part of the fire department's overall responsibility. ISO recognizes the dynamic and comprehensive duties of a community's fire service, and understands the complex decisions a community must make in planning and delivering emergency services. However, in developing a community's PPC grade, only features related to reducing property losses from structural fires are evaluated. Multiple alarms, simultaneous incidents and life safety are not considered in this evaluation. The PPC program evaluates the fire protection for small to average size buildings. Specific properties with a Needed Fire Flow in excess of 3,500 gpm are evaluated separately and assigned an individual PPC grade.

A community's investment in fire mitigation is a proven and reliable predictor of future fire losses. Statistical data on insurance losses bears out the relationship between excellent fire protection – as measured by the PPC program – and low fire losses. So, insurance companies use PPC information for marketing, underwriting, and to help establish fair premiums for homeowners and commercial fire insurance. In general, the price of fire insurance in a community with a good PPC grade is substantially lower than in a community with a poor PPC grade, assuming all other factors are equal.

ISO is an independent company that serves insurance companies, communities, fire departments, insurance regulators, and others by providing information about risk. ISO's expert staff collects information about municipal fire suppression efforts in communities throughout the United States. In each of those communities, ISO analyzes the relevant data and assigns a PPC grade – a number from 1 to 10. Class 1 represents an exemplary fire suppression program, and Class 10 indicates that the area's fire suppression program does not meet ISO's minimum criteria.

ISO's PPC program evaluates communities according to a uniform set of criteria, incorporating nationally recognized standards developed by the National Fire Protection Association and the American Water Works Association. A community's PPC grade depends on:

- **Needed Fire Flows**, which are representative building locations used to determine the theoretical amount of water necessary for fire suppression purposes.
- **Emergency Communications**, including emergency reporting, telecommunicators, and dispatching systems.
- **Fire Department**, including equipment, staffing, training, geographic distribution of fire companies, operational considerations, and community risk reduction.
- **Water Supply**, including inspection and flow testing of hydrants, alternative water supply operations, and a careful evaluation of the amount of available water compared with the amount needed to suppress fires up to 3,500 gpm.

Data Collection and Analysis

ISO has evaluated and classified over 39,000 fire protection areas across the United States using its FSRs. A combination of meetings between trained ISO field representatives and the dispatch center coordinator, community fire official, and water superintendent is used in conjunction with a comprehensive questionnaire to collect the data necessary to determine the PPC grade. In order for a community to obtain a grade better than a Class 9, three elements of fire suppression features are reviewed. These three elements are Emergency Communications, Fire Department, and Water Supply.

A review of the **Emergency Communications** accounts for 10% of the total classification. This section is weighted at **10 points**, as follows:

- Emergency Reporting 3 points
- Telecommunicators 4 points
- Dispatch Circuits 3 points

A review of the **Fire Department** accounts for 50% of the total classification. ISO focuses on a fire department's first alarm response and initial attack to minimize potential loss. The fire department section is weighted at **50 points**, as follows:

- Engine Companies 6 points
- Reserve Pumpers 0.5 points
- Pump Capacity 3 points
- Ladder/Service Companies 4 points
- Reserve Ladder/Service Trucks 0.5 points
- Deployment Analysis 10 points
- Company Personnel 15 points
- Training 9 points
- Operational considerations 2 points
- Community Risk Reduction 5.5 points (in addition to the 50 points above)

A review of the **Water Supply** system accounts for 40% of the total classification. ISO reviews the water supply a community uses to determine the adequacy for fire suppression purposes. The water supply system is weighted at **40 points**, as follows:

- Credit for Supply System 30 points
- Hydrant Size, Type & Installation 3 points
- Inspection & Flow Testing of Hydrants 7 points

There is one additional factor considered in calculating the final score – **Divergence**.

Even the best fire department will be less than fully effective if it has an inadequate water supply. Similarly, even a superior water supply will be less than fully effective if the fire department lacks the equipment or personnel to use the water. The FSRS score is subject to modification by a divergence factor, which recognizes disparity between the effectiveness of the fire department and the water supply.

The Divergence factor mathematically reduces the score based upon the relative difference between the fire department and water supply scores. The factor is introduced in the final equation.

PPC Grade

The PPC grade assigned to the community will depend on the community's score on a 100-point scale:

PPC	Points
1	90.00 or more
2	80.00 to 89.99
3	70.00 to 79.99
4	60.00 to 69.99
5	50.00 to 59.99
6	40.00 to 49.99
7	30.00 to 39.99
8	20.00 to 29.99
9	10.00 to 19.99
10	0.00 to 9.99

The classification numbers are interpreted as follows:

- Class 1 through (and including) Class 8 represents a fire suppression system that includes an FSRS creditable dispatch center, fire department, and water supply.
- Class 8B is a special classification that recognizes a superior level of fire protection in otherwise Class 9 areas. It is designed to represent a fire protection delivery system that is superior except for a lack of a water supply system capable of the minimum FSRS fire flow criteria of 250 gpm for 2 hours.
- Class 9 is a fire suppression system that includes a creditable dispatch center, fire department but no FSRS creditable water supply.
- Class 10 does not meet minimum FSRS criteria for recognition, including areas that are beyond five road miles of a recognized fire station.

New PPC program changes effective July 1, 2014

We have revised the PPC program to capture the effects of enhanced fire protection capabilities that reduce fire loss and fire severity in Split Class 9 and Split Class 8B areas (as outlined below). This new structure benefits the fire service, community, and property owner.

New classifications

Through ongoing research and loss experience analysis, we identified additional differentiation in fire loss experience within our PPC program, which resulted in the revised classifications. We based the differing fire loss experience on the fire suppression capabilities of each community. The new PPC classes will improve the predictive value for insurers while benefiting both commercial and residential property owners. Here are the new classifications and what they mean.

Split classifications

When we develop a split classification for a community — for example 5/9 — the first number is the class that applies to properties within 5 road miles of the responding fire station and 1,000 feet of a creditable water supply, such as a fire hydrant, suction point, or dry hydrant. The second number is the class that applies to properties within 5 road miles of a fire station but beyond 1,000 feet of a creditable water supply. We have revised the classification to reflect more precisely the risk of loss in a community, replacing Class 9 and 8B in the second part of a split classification with revised designations.

What's changed with the new classifications?

We've published the new classifications as "X" and "Y" — formerly the "9" and "8B" portion of the split classification, respectively. For example:

- A community currently displayed as a split 6/9 classification will now be a split 6/6X classification; with the "6X" denoting what was formerly classified as "9".
- Similarly, a community currently graded as a split 6/8B classification will now be a split 6/6Y classification, the "6Y" denoting what was formerly classified as "8B".
- Communities graded with single "9" or "8B" classifications will remain intact.

Prior Classification	New Classification
1/9	1/1X
2/9	2/2X
3/9	3/3X
4/9	4/4X
5/9	5/5X
6/9	6/6X
7/9	7/7X
8/9	8/8X
9	9

Prior Classification	New Classification
1/8B	1/1Y
2/8B	2/2Y
3/8B	3/3Y
4/8B	4/4Y
5/8B	5/5Y
6/8B	6/6Y
7/8B	7/7Y
8/8B	8/8Y
8B	8B

What's changed?

As you can see, we're still maintaining split classes, but it's how we represent them to insurers that's changed. The new designations reflect a reduction in fire severity and loss and have the potential to reduce property insurance premiums.

Benefits of the revised split class designations

- To the fire service, the revised designations identify enhanced fire suppression capabilities used throughout the fire protection area
- To the community, the new classes reward a community's fire suppression efforts by showing a more reflective designation
- To the individual property owner, the revisions offer the potential for decreased property insurance premiums

New water class

Our data also shows that risks located more than 5 but less than 7 road miles from a responding fire station with a creditable water source within 1,000 feet had better loss experience than those farther than 5 road miles from a responding fire station with no creditable water source. We've introduced a new classification —10W— to recognize the reduced loss potential of such properties.

What's changed with Class 10W?

Class 10W is property-specific. Not all properties in the 5-to-7-mile area around the responding fire station will qualify. The difference between Class 10 and 10W is that the 10W-graded risk or property is within 1,000 feet of a creditable water supply. Creditable water supplies include fire protection systems using hauled water in any of the split classification areas.

What's the benefit of Class 10W?

10W gives credit to risks within 5 to 7 road miles of the responding fire station and within 1,000 feet of a creditable water supply. That's reflective of the potential for reduced property insurance premiums.

What does the fire chief have to do?


Fire chiefs don't have to do anything at all. The revised classifications went in place automatically effective July 1, 2014 (July 1, 2015 for Texas).

What if I have additional questions?

Feel free to contact ISO at 800.444.4554 or email us at PPC-Cust-Serv@iso.com.

Distribution of PPC Grades

The 2020 published countrywide distribution of communities by the PPC grade is as follows:



Assistance

The PPC program offers help to communities, fire departments, and other public officials as they plan for, budget, and justify improvements. ISO is also available to assist in the understanding of the details of this evaluation.

The PPC program representatives can be reached by telephone at (800) 444-4554. The technical specialists at this telephone number have access to the details of this evaluation and can effectively speak with you about your questions regarding the PPC program. What's more, we can be reached via the internet at www.isomitigation.com/talk/.

We also have a website dedicated to our Community Hazard Mitigation Classification programs at www.isomitigation.com. Here, fire chiefs, building code officials, community leaders and other interested citizens can access a wealth of data describing the criteria used in evaluating how cities and towns are protecting residents from fire and other natural hazards. This website will allow you to learn more about the PPC program. The website provides important background information, insights about the PPC grading processes and technical documents. ISO is also pleased to offer Fire Chiefs Online — a special, secured website with information and features that can help improve your PPC grade, including a list of the Needed Fire Flows for all the commercial occupancies ISO has on file for your community. Visitors to the site can download information, see statistical results and also contact ISO for assistance.

In addition, on-line access to the FSRs and its commentaries is available to registered customers for a fee. However, fire chiefs and community chief administrative officials are given access privileges to this information without charge.

To become a registered fire chief or community chief administrative official, register at www.isomitigation.com.

PPC Review

ISO concluded its review of the fire suppression features being provided for Kern CO FD 5. The resulting community classification is **Class 03/3X**.

If the classification is a single class, the classification applies to properties with a Needed Fire Flow of 3,500 gpm or less in the community. If the classification is a split class (e.g., 6/XX):

- The first class (e.g., "6" in a 6/XX) applies to properties within 5 road miles of a recognized fire station and within 1,000 feet of a fire hydrant or alternate water supply.
- The second class (XX or XY) applies to properties beyond 1,000 feet of a fire hydrant but within 5 road miles of a recognized fire station.
- Alternative Water Supply: The first class (e.g., "6" in a 6/10) applies to properties within 5 road miles of a recognized fire station with no hydrant distance requirement.
- Class 10 applies to properties over 5 road miles of a recognized fire station.
- Class 10W applies to properties within 5 to 7 road miles of a recognized fire station with a recognized water supply within 1,000 feet.
- Specific properties with a Needed Fire Flow in excess of 3,500 gpm are evaluated separately and assigned an individual classification.

FSRS Feature	Earned Credit	Credit Available
Emergency Communications		
414. Credit for Emergency Reporting	3.00	3
422. Credit for Telecommunicators	3.41	4
432. Credit for Dispatch Circuits	1.95	3
440. Credit for Emergency Communications	8.36	10
Fire Department		
513. Credit for Engine Companies	5.96	6
523. Credit for Reserve Pumpers	0.50	0.50
532. Credit for Pump Capacity	3.00	3
549. Credit for Ladder Service	1.61	4
553. Credit for Reserve Ladder and Service Trucks	0.48	0.50
561. Credit for Deployment Analysis	5.05	10
571. Credit for Company Personnel	6.23	15
581. Credit for Training	7.87	9
730. Credit for Operational Considerations	2.00	2
590. Credit for Fire Department	32.70	50
Water Supply		
616. Credit for Supply System	23.39	30
621. Credit for Hydrants	2.96	3
631. Credit for Inspection and Flow Testing	2.12	7
640. Credit for Water Supply	28.47	40
Divergence	-1.15	--
1050. Community Risk Reduction	4.64	5.50
Total Credit	73.02	105.50

Emergency Communications

Ten percent of a community's overall score is based on how well the communications center receives and dispatches fire alarms. Our field representative evaluated:

- Communications facilities provided for the general public to report structure fires
- Enhanced 9-1-1 Telephone Service including wireless
- Computer-aided dispatch (CAD) facilities
- Alarm receipt and processing at the communication center
- Training and certification of telecommunicators
- Facilities used to dispatch fire department companies to reported structure fires

	Earned Credit	Credit Available
414. Credit Emergency Reporting	3.00	3
422. Credit for Telecommunicators	3.41	4
432. Credit for Dispatch Circuits	1.95	3
Item 440. Credit for Emergency Communications:	8.36	10

Item 414 - Credit for Emergency Reporting (3 points)

The first item reviewed is Item 414 "Credit for Emergency Reporting (CER)". This item reviews the emergency communication center facilities provided for the public to report fires including 911 systems (Basic or Enhanced), Wireless Phase I and Phase II, Voice over Internet Protocol, Computer Aided Dispatch and Geographic Information Systems for automatic vehicle location. ISO uses National Fire Protection Association (NFPA) 1221, *Standard for the Installation, Maintenance and Use of Emergency Services Communications Systems* as the reference for this section.

Item 410. Emergency Reporting (CER)	Earned Credit	Credit Available
A./B. Basic 9-1-1, Enhanced 9-1-1 or No 9-1-1 For maximum credit, there should be an Enhanced 9-1-1 system, Basic 9-1-1 and No 9-1-1 will receive partial credit.	20.00	20
1. E9-1-1 Wireless Wireless Phase I using Static ALI (automatic location identification) Functionality (10 points); Wireless Phase II using Dynamic ALI Functionality (15 points); Both available will be 25 points	25.00	25
2. E9-1-1 Voice over Internet Protocol (VoIP) Static VoIP using Static ALI Functionality (10 points); Nomadic VoIP using Dynamic ALI Functionality (15 points); Both available will be 25 points	25.00	25
3. Computer Aided Dispatch Basic CAD (5 points); CAD with Management Information System (5 points); CAD with Interoperability (5 points)	15.00	15
4. Geographic Information System (GIS/AVL) <u>The PSAP uses</u> a fully integrated CAD/GIS management system with automatic vehicle location (AVL) integrated with a CAD system providing dispatch assignments. The individual fire departments being dispatched <u>do not</u> need GIS/AVL capability to obtain this credit.	15.00	15
Review of Emergency Reporting total:	100.00	100

Item 422- Credit for Telecommunicators (4 points)

The second item reviewed is Item 422 “Credit for Telecommunicators (TC)”. This item reviews the number of Telecommunicators on duty at the center to handle fire calls and other emergencies. All emergency calls including those calls that do not require fire department action are reviewed to determine the proper staffing to answer emergency calls and dispatch the appropriate emergency response. The 2013 Edition of NFPA 1221, *Standard for the Installation, Maintenance and Use of Emergency Services Communications Systems*, recommends that ninety-five percent of emergency calls shall be answered within 15 seconds and ninety-nine percent of emergency calls shall be answered within 40 seconds. In addition, NFPA recommends that eighty percent of emergency alarm processing shall be completed within 60 seconds and ninety-five percent of alarm processing shall be completed within 106 seconds of answering the call.

To receive full credit for operators on duty, ISO must review documentation to show that the communication center meets NFPA 1221 call answering and dispatch time performance measurement standards. This documentation may be in the form of performance statistics or other performance measurements compiled by the 9-1-1 software or other software programs that are currently in use such as Computer Aided Dispatch (CAD) or Management Information System (MIS).

Item 420. Telecommunicators (CTC)	Earned Credit	Credit Available
A1. Alarm Receipt (AR) Receipt of alarms shall meet the requirements in accordance with the criteria of NFPA 1221	16.79	20
A2. Alarm Processing (AP) Processing of alarms shall meet the requirements in accordance with the criteria of NFPA 1221	8.39	20
B. Emergency Dispatch Protocols (EDP) Telecommunicators have emergency dispatch protocols (EDP) containing questions and a decision-support process to facilitate correct call categorization and prioritization.	20.00	20
C. Telecommunicator Training and Certification (TTC) Telecommunicators meet the qualification requirements referenced in NFPA 1061, <i>Standard for Professional Qualifications for Public Safety Telecommunicator</i> , and/or the Association of Public-Safety Communications Officials - International (APCO) <i>Project 33</i> . Telecommunicators are certified in the knowledge, skills, and abilities corresponding to their job functions.	20.00	20
D. Telecommunicator Continuing Education and Quality Assurance (TQA) Telecommunicators participate in continuing education and/or in-service training and quality-assurance programs as appropriate for their positions	20.00	20
Review of Telecommunicators total:	85.18	100

Item 432 - Credit for Dispatch Circuits (3 points)

The third item reviewed is Item 432 “Credit for Dispatch Circuits (CDC)”. This item reviews the dispatch circuit facilities used to transmit alarms to fire department members. A “Dispatch Circuit” is defined in NFPA 1221 as “A circuit over which an alarm is transmitted from the communications center to an emergency response facility (ERF) or emergency response units (ERUs) to notify ERUs to respond to an emergency”. All fire departments (except single fire station departments with full-time firefighter personnel receiving alarms directly at the fire station) need adequate means of notifying all firefighter personnel of the location of reported structure fires. The dispatch circuit facilities should be in accordance with the general criteria of NFPA 1221. “Alarms” are defined in this Standard as “A signal or message from a person or device indicating the existence of an emergency or other situation that requires action by an emergency response agency”.

There are two different levels of dispatch circuit facilities provided for in the Standard – a primary dispatch circuit and a secondary dispatch circuit. In jurisdictions that receive 730 alarms or more per year (average of two alarms per 24-hour period), two separate and dedicated dispatch circuits, a primary and a secondary, are needed. In jurisdictions receiving fewer than 730 alarms per year, a second dedicated dispatch circuit is not needed. Dispatch circuit facilities installed but not used or tested (in accordance with the NFPA Standard) receive no credit.

The score for Credit for Dispatch Circuits (CDC) is influenced by monitoring for integrity of the primary dispatch circuit. There are up to 0.90 points available for this Item. Monitoring for integrity involves installing automatic systems that will detect faults and failures and send visual and audible indications to appropriate communications center (or dispatch center) personnel. ISO uses NFPA 1221 to guide the evaluation of this item. ISO's evaluation also includes a review of the communication system's emergency power supplies.

Item 432 “Credit for Dispatch Circuits (CDC)” = 1.95 points

Fire Department

Fifty percent of a community's overall score is based upon the fire department's structure fire suppression system. ISO's field representative evaluated:

- Engine and ladder/service vehicles including reserve apparatus
- Equipment carried
- Response to reported structure fires
- Deployment analysis of companies
- Available and/or responding firefighters
- Training

	Earned Credit	Credit Available
513. Credit for Engine Companies	5.96	6
523. Credit for Reserve Pumpers	0.50	0.5
532. Credit for Pumper Capacity	3.00	3
549. Credit for Ladder Service	1.61	4
553. Credit for Reserve Ladder and Service Trucks	0.48	0.5
561. Credit for Deployment Analysis	5.05	10
571. Credit for Company Personnel	6.23	15
581. Credit for Training	7.87	9
730. Credit for Operational Considerations	2.00	2
Item 590. Credit for Fire Department:	32.70	50

Basic Fire Flow

The Basic Fire Flow for the community is determined by the review of the Needed Fire Flows for selected buildings in the community. The fifth largest Needed Fire Flow is determined to be the Basic Fire Flow. The Basic Fire Flow has been determined to be 3500 gpm.

Item 513 - Credit for Engine Companies (6 points)

The first item reviewed is Item 513 "Credit for Engine Companies (CEC)". This item reviews the number of engine companies, their pump capacity, hose testing, pump testing and the equipment carried on the in-service pumpers. To be recognized, pumper apparatus must meet the general criteria of NFPA 1901, *Standard for Automotive Fire Apparatus* which include a minimum 250 gpm pump, an emergency warning system, a 300 gallon water tank, and hose. At least 1 apparatus must have a permanently mounted pump rated at 750 gpm or more at 150 psi.

The review of the number of needed pumpers considers the response distance to built-upon areas; the Basic Fire Flow; and the method of operation. Multiple alarms, simultaneous incidents, and life safety are not considered.

The greatest value of A, B, or C below is needed in the fire district to suppress fires in structures with a Needed Fire Flow of 3,500 gpm or less: **8 engine companies**

- a) **8 engine companies** to provide fire suppression services to areas to meet NFPA 1710 criteria or within 1½ miles.
- b) **3 engine companies** to support a Basic Fire Flow of 3500 gpm.
- c) **3 engine companies** based upon the fire department's method of operation to provide a minimum two engine response to all first alarm structure fires.

The FSRS recognizes that there are **8 engine companies** in service.

The FSRS also reviews Automatic Aid. Automatic Aid is considered in the review as assistance dispatched automatically by contractual agreement between two communities or fire districts. That differs from mutual aid or assistance arranged case by case. ISO will recognize an Automatic Aid plan under the following conditions:

- It must be prearranged for first alarm response according to a definite plan. It is preferable to have a written agreement, but ISO may recognize demonstrated performance.
- The aid must be dispatched to all reported structure fires on the initial alarm.
- The aid must be provided 24 hours a day, 365 days a year.

FSRS Item 512.D "Automatic Aid Engine Companies" responding on first alarm and meeting the needs of the city for basic fire flow and/or distribution of companies are factored based upon the value of the Automatic Aid plan (up to 1.00 can be used as the factor). The Automatic Aid factor is determined by a review of the Automatic Aid provider's communication facilities, how they receive alarms from the graded area, inter-department training between fire departments, and the fire ground communications capability between departments.

For each engine company, the credited Pump Capacity (PC), the Hose Carried (HC), the Equipment Carried (EC) all contribute to the calculation for the percent of credit the FSRS provides to that engine company.

Item 513 "Credit for Engine Companies (CEC)" = 5.96 points

Item 523 - Credit for Reserve Pumpers (0.50 points)

The item is Item 523 “Credit for Reserve Pumpers (CRP)”. This item reviews the number and adequacy of the pumpers and their equipment. The number of needed reserve pumpers is 1 for each 8 needed engine companies determined in Item 513, or any fraction thereof.

Item 523 “Credit for Reserve Pumpers (CRP)” = 0.50 points

Item 532 – Credit for Pumper Capacity (3 points)

The next item reviewed is Item 532 “Credit for Pumper Capacity (CPC)”. The total pump capacity available should be sufficient for the Basic Fire Flow of 3500 gpm. The maximum needed pump capacity credited is the Basic Fire Flow of the community.

Item 532 “Credit for Pumper Capacity (CPC)” = 3.00 points

Item 549 – Credit for Ladder Service (4 points)

The next item reviewed is Item 549 “Credit for Ladder Service (CLS)”. This item reviews the number of response areas within the city with 5 buildings that are 3 or more stories or 35 feet or more in height, or with 5 buildings that have a Needed Fire Flow greater than 3,500 gpm, or any combination of these criteria. The height of all buildings in the city, including those protected by automatic sprinklers, is considered when determining the number of needed ladder companies. Response areas not needing a ladder company should have a service company. Ladders, tools and equipment normally carried on ladder trucks are needed not only for ladder operations but also for forcible entry, ventilation, salvage, overhaul, lighting and utility control.

The number of ladder or service companies, the height of the aerial ladder, aerial ladder testing and the equipment carried on the in-service ladder trucks and service trucks is compared with the number of needed ladder trucks and service trucks and an FSRS equipment list. Ladder trucks must meet the general criteria of NFPA 1901, *Standard for Automotive Fire Apparatus* to be recognized.

The number of needed ladder-service trucks is dependent upon the number of buildings 3 stories or 35 feet or more in height, buildings with a Needed Fire Flow greater than 3,500 gpm, and the method of operation.

The FSRS recognizes that there are **1 ladder companies** in service. These companies are needed to provide fire suppression services to areas to meet NFPA 1710 criteria or within 2½ miles and the number of buildings with a Needed Fire Flow over 3,500 gpm or 3 stories or more in height, or the method of operation.

The FSRS recognizes that there are **6 service companies** in service.

Item 549 “Credit for Ladder Service (CLS)” = 1.61 points

Item 553 – Credit for Reserve Ladder and Service Trucks (0.50 points)

The next item reviewed is Item 553 “Credit for Reserve Ladder and Service Trucks (CRLS)”. This item considers the adequacy of ladder and service apparatus when one (or more in larger communities) of these apparatus are out of service. The number of needed reserve ladder and service trucks is 1 for each 8 needed ladder and service companies that were determined to be needed in Item 540, or any fraction thereof.

Item 553 “Credit for Reserve Ladder and Service Trucks (CRLS)” = 0.48 points

Item 561 – Deployment Analysis (10 points)

Next, Item 561 “Deployment Analysis (DA)” is reviewed. This Item examines the number and adequacy of existing engine and ladder-service companies to cover built-upon areas of the city.

To determine the Credit for Distribution, first the Existing Engine Company (EC) points and the Existing Engine Companies (EE) determined in Item 513 are considered along with Ladder Company Equipment (LCE) points, Service Company Equipment (SCE) points, Engine-Ladder Company Equipment (ELCE) points, and Engine-Service Company Equipment (ESCE) points determined in Item 549.

Secondly, as an alternative to determining the number of needed engine and ladder/service companies through the road-mile analysis, a fire protection area may use the results of a systematic performance evaluation. This type of evaluation analyzes computer-aided dispatch (CAD) history to demonstrate that, with its current deployment of companies, the fire department meets the time constraints for initial arriving engine and initial full alarm assignment in accordance with the general criteria of in NFPA 1710, *Standard for the Organization and Deployment of Fire Suppression Operations, Emergency Medical Operations, and Special Operations to the Public by Career Fire Departments*.

A determination is made of the percentage of built upon area within 1½ miles of a first-due engine company and within 2½ miles of a first-due ladder-service company.

Item 561 “Credit Deployment Analysis (DA)” = 5.05 points

Item 571 – Credit for Company Personnel (15 points)

Item 571 “Credit for Company Personnel (CCP)” reviews the average number of existing firefighters and company officers available to respond to reported first alarm structure fires in the city.

The on-duty strength is determined by the yearly average of total firefighters and company officers on-duty considering vacations, sick leave, holidays, “Kelley” days and other absences. When a fire department operates under a minimum staffing policy, this may be used in lieu of determining the yearly average of on-duty company personnel.

Firefighters on apparatus not credited under Items 513 and 549 that regularly respond to reported first alarms to aid engine, ladder, and service companies are included in this item as increasing the total company strength.

Firefighters staffing ambulances or other units serving the general public are credited if they participate in fire-fighting operations, the number depending upon the extent to which they are available and are used for response to first alarms of fire.

On-Call members are credited on the basis of the average number staffing apparatus on first alarms. Off-shift career firefighters and company officers responding on first alarms are considered on the same basis as on-call personnel. For personnel not normally at the fire station, the number of responding firefighters and company officers is divided by 3 to reflect the time needed to assemble at the fire scene and the reduced ability to act as a team due to the various arrival times at the fire location when compared to the personnel on-duty at the fire station during the receipt of an alarm.

The number of Public Safety Officers who are positioned in emergency vehicles within the jurisdiction boundaries may be credited based on availability to respond to first alarm structure fires. In recognition of this increased response capability the number of responding Public Safety Officers is divided by 2.

The average number of firefighters and company officers responding with those companies credited as Automatic Aid under Items 513 and 549 are considered for either on-duty or on-call company personnel as is appropriate. The actual number is calculated as the average number of company personnel responding multiplied by the value of AA Plan determined in Item 512.D.

The maximum creditable response of on-duty and on-call firefighters is 12, including company officers, for each existing engine and ladder company and 6 for each existing service company.

Chief Officers are not creditable except when more than one chief officer responds to alarms; then extra chief officers may be credited as firefighters if they perform company duties.

The FSRS recognizes **28.00 on-duty personnel** and an average of **0.00 on-call personnel** responding on first alarm structure fires.

Item 571 “Credit for Company Personnel (CCP)” = 6.23 points

Item 581 – Credit for Training (9 points)

Training	Earned Credit	Credit Available
A. Facilities, and Use For maximum credit, each firefighter should receive 18 hours per year in structure fire related subjects as outlined in NFPA 1001.	35.00	35
B. Company Training For maximum credit, each firefighter should receive 16 hours per month in structure fire related subjects as outlined in NFPA 1001.	25.00	25
C. Classes for Officers For maximum credit, each officer should be certified in accordance with the general criteria of NFPA 1021. Additionally, each officer should receive 12 hours of continuing education on or off site.	10.41	12
D. New Driver and Operator Training For maximum credit, each new driver and operator should receive 60 hours of driver/operator training per year in accordance with NFPA 1002 and NFPA 1451.	5.00	5
E. Existing Driver and Operator Training For maximum credit, each existing driver and operator should receive 12 hours of driver/operator training per year in accordance with NFPA 1002 and NFPA 1451.	5.00	5
F. Training on Hazardous Materials For maximum credit, each firefighter should receive 6 hours of training for incidents involving hazardous materials in accordance with NFPA 472.	1.00	1
G. Recruit Training For maximum credit, each firefighter should receive 240 hours of structure fire related training in accordance with NFPA 1001 within the first year of employment or tenure.	5.00	5
H. Pre-Fire Planning Inspections For maximum credit, pre-fire planning inspections of each commercial, industrial, institutional, and other similar type building (all buildings except 1-4 family dwellings) should be made annually by company members. Records of inspections should include up-to date notes and sketches.	1.00	12

Item 580 “Credit for Training (CT)” = 7.87 points

Item 730 – Operational Considerations (2 points)

Item 730 “Credit for Operational Considerations (COC)” evaluates fire department standard operating procedures and incident management systems for emergency operations involving structure fires.

Operational Considerations	Earned Credit	Credit Available
Standard Operating Procedures The department should have established SOPs for fire department general emergency operations	50	50
Incident Management Systems The department should use an established incident management system (IMS)	50	50
Operational Considerations total:	100	100

Item 730 “Credit for Operational Considerations (COC)” = 2.00 points

Water Supply

Forty percent of a community's overall score is based on the adequacy of the water supply system. The ISO field representative evaluated:

- the capability of the water distribution system to meet the Needed Fire Flows at selected locations up to 3,500 gpm.
- size, type and installation of fire hydrants.
- inspection and flow testing of fire hydrants.

	Earned Credit	Credit Available
616. Credit for Supply System	23.39	30
621. Credit for Hydrants	2.96	3
631. Credit for Inspection and Flow Testing	2.12	7
Item 640. Credit for Water Supply:	28.47	40

Item 616 – Credit for Supply System (30 points)

The first item reviewed is Item 616 “Credit for Supply System (CSS)”. This item reviews the rate of flow that can be credited at each of the Needed Fire Flow test locations considering the supply works capacity, the main capacity and the hydrant distribution. The lowest flow rate of these items is credited for each representative location. A water system capable of delivering 250 gpm or more for a period of two hours plus consumption at the maximum daily rate at the fire location is considered minimum in the ISO review.

Where there are 2 or more systems or services distributing water at the same location, credit is given on the basis of the joint protection provided by all systems and services available.

The supply works capacity is calculated for each representative Needed Fire Flow test location, considering a variety of water supply sources. These include public water supplies, emergency supplies (usually accessed from neighboring water systems), suction supplies (usually evidenced by dry hydrant installations near a river, lake or other body of water), and supplies developed by a fire department using large diameter hose or vehicles to shuttle water from a source of supply to a fire site. The result is expressed in gallons per minute (gpm).

The normal ability of the distribution system to deliver Needed Fire Flows at the selected building locations is reviewed. The results of a flow test at a representative test location will indicate the ability of the water mains (or fire department in the case of fire department supplies) to carry water to that location.

The hydrant distribution is reviewed within 1,000 feet of representative test locations measured as hose can be laid by apparatus.

For maximum credit, the Needed Fire Flows should be available at each location in the district. Needed Fire Flows of 2,500 gpm or less should be available for 2 hours; and Needed Fire Flows of 3,000 and 3,500 gpm should be obtainable for 3 hours.

Item 616 “Credit for Supply System (CSS)” = 23.39 points

Item 621 – Credit for Hydrants (3 points)

The second item reviewed is Item 621 “Credit for Hydrants (CH)”. This item reviews the number of fire hydrants of each type compared with the total number of hydrants.

There are a total of 5489 hydrants in the graded area.

620. Hydrants, - Size, Type and Installation	Number of Hydrants
A. With a 6 -inch or larger branch and a pumper outlet with or without 2½ -inch outlets	5345
B. With a 6 -inch or larger branch and no pumper outlet but two or more 2½ -inch outlets, or with a small foot valve, or with a small barrel	83
C./D. With only a 2½ -inch outlet or with less than a 6 -inch branch	61
E./F. Flush Type, Cistern, or Suction Point	0

Item 621 “Credit for Hydrants (CH)” = 2.96 points

Item 630 – Credit for Inspection and Flow Testing (7 points)

The third item reviewed is Item 630 “Credit for Inspection and Flow Testing (CIT)”. This item reviews the fire hydrant inspection frequency, and the completeness of the inspections. Inspection of hydrants should be in accordance with AWWA M-17, *Installation, Field Testing and Maintenance of Fire Hydrants*.

Frequency of Inspection (FI): Average interval between the 3 most recent inspections.

Frequency	Points
1 year	30
2 years	20
3 years	10
4 years	5
5 years or more	No Credit

Note: The points for inspection frequency are reduced by 10 points if the inspections are incomplete or do not include a flushing program. An additional reduction of 10 points are made if hydrants are not subjected to full system pressure during inspections. If the inspection of cisterns or suction points does not include actual drafting with a pumper, or back-flushing for dry hydrants, 20 points are deducted.

Total points for Inspections = 1.88 points

Frequency of Fire Flow Testing (FF): Average interval between the 3 most recent inspections.

Frequency	Points
5 years	40
6 years	30
7 years	20
8 years	10
9 years	5
10 years or more	No Credit

Total points for Fire Flow Testing = 0.24 points

Item 631 “Credit for Inspection and Fire Flow Testing (CIT)” = 2.12 points

Divergence = -1.15

The Divergence factor mathematically reduces the score based upon the relative difference between the fire department and water supply scores. The factor is introduced in the final equation.

Community Risk Reduction

	Earned Credit	Credit Available
1025. Credit for Fire Prevention and Code Enforcement (CPCE)	1.99	2.2
1033. Credit for Public Fire Safety Education (CFSE)	1.55	2.2
1044. Credit for Fire Investigation Programs (CIP)	1.10	1.1
Item 1050. Credit for Community Risk Reduction	4.64	5.50

Item 1025 – Credit for Fire Prevention Code Adoption and Enforcement (2.2 points)	Earned Credit	Credit Available
Fire Prevention Code Regulations (PCR) Evaluation of fire prevention code regulations in effect.	10.00	10
Fire Prevention Staffing (PS) Evaluation of staffing for fire prevention activities.	8.00	8
Fire Prevention Certification and Training (PCT) Evaluation of the certification and training of fire prevention code enforcement personnel.	3.20	6
Fire Prevention Programs (PCP) Evaluation of fire prevention programs.	15.00	16
Review of Fire Prevention Code and Enforcement (CPCE) subtotal:	36.20	40

Item 1033 – Credit for Public Fire Safety Education (2.2 points)	Earned Credit	Credit Available
Public Fire Safety Educators Qualifications and Training (FSQT) Evaluation of public fire safety education personnel training and qualification as specified by the authority having jurisdiction.	10.00	10
Public Fire Safety Education Programs (FSP) Evaluation of programs for public fire safety education.	18.25	30
Review of Public Safety Education Programs (CFSE) subtotal:	28.25	40

Item 1044 – Credit for Fire Investigation Programs (1.1 points)	Earned Credit	Credit Available
Fire Investigation Organization and Staffing (IOS) Evaluation of organization and staffing for fire investigations.	8.00	8
Fire Investigator Certification and Training (IQT) Evaluation of fire investigator certification and training.	6.00	6
Use of National Fire Incident Reporting System (IRS) Evaluation of the use of the National Fire Incident Reporting System (NFIRS) for the 3 years before the evaluation.	6.00	6
Review of Fire Investigation Programs (CIP) subtotal:	20.00	20

Summary of PPC Review
for
Kern CO FD 5

FSRS Item	Earned Credit	Credit Available
Emergency Communications		
414. Credit for Emergency Reporting	3.00	3
422. Credit for Telecommunicators	3.41	4
432. Credit for Dispatch Circuits	1.95	3
440. Credit for Emergency Communications	8.36	10
Fire Department		
513. Credit for Engine Companies	5.96	6
523. Credit for Reserve Pumpers	0.50	0.5
532. Credit for Pumper Capacity	3.00	3
549. Credit for Ladder Service	1.61	4
553. Credit for Reserve Ladder and Service Trucks	0.48	0.5
561. Credit for Deployment Analysis	5.05	10
571. Credit for Company Personnel	6.23	15
581. Credit for Training	7.87	9
730. Credit for Operational Considerations	2.00	2
590. Credit for Fire Department	32.70	50
Water Supply		
616. Credit for Supply System	23.39	30
621. Credit for Hydrants	2.96	3
631. Credit for Inspection and Flow Testing	2.12	7
640. Credit for Water Supply	28.47	40
Divergence	-1.15	--
1050. Community Risk Reduction	4.64	5.50
Total Credit	73.02	105.5

Final Community Classification = 03/3X

Patricia Newquist

From: Patricia Newquist
Sent: Friday, June 19, 2026 3:43 PM
To: 'Sheriff@kernsheriff.org'
Subject: Request - Service Standards and Response Time - Kern County Sheriff Dept Ridgecrest Substation-Inyokern

Greetings,

We are processing an application for Small Power Plant Exemption permit with the California Energy Commission (CEC), **REF #26-SPPE-01**. The project is also referred to as RB Inyokern Data Center, located on the north side of SR 178 between Brown Road and I-395, Inyokern.

The CEC has requested the following information per Public Services comment (DR PS-1) : A written statement of current service standards and response times of the affected law enforcement services.

We understand this type of request is handled by email and expect to hear back from you within a week. Kindly expedite this request if possible. Let me know if you have any questions.

We thank you in advance for your attention to this matter.

Respectfully,

Patricia Newquist

Senior Planner / Project Manager



Cornerstone Engineering, Inc.

5509 Young Street, Bakersfield, CA
93311

Office: 661.325.9474

Cell: 661-333-7969

www.cornerstoneeng.com

From: [Itzel Meza \(Kern County Sheriff, CA\)](#)
To: [Patricia Newquist](#)
Subject: RR-2026-990_Patricia Newquist Records Request
Date: Thursday, July 16, 2026 3:58:34 PM

External (kerncountysheriffca@request.justfoia.com)

[Graymail](#) [Spam](#) [Phish](#) [More...](#) [FAQ](#) [Protection by INKY](#)

Dear Patricia Newquist:

Please consider this email the Kern County Sheriff's Office's response to your request for records, specifically:

Greetings, We are processing an application for Small Power Plant Exemption permit with the California Energy Commission (CEC), REF #26-SPPE-01. The project is also referred to as RB Inyokern Data Center, located on the north side of SR 178 between Brown Road and I-395, Inyokern. The CEC has requested the following information per Public Services comment (DR PS-1) : A written statement of current service standards and response times of the affected law enforcement services. We understand this type of request is handled by email and expect to hear back from you within a week. Kindly expedite this request if possible. Let me know if you have any questions. We thank you in advance for your attention to this matter. Respectfully, Patricia Newquist

The record(s) responsive to your request are being transmitted to you via download link. You will receive the download link in a separate email. (The records have been redacted in accordance with California Government Code § 7927.705, Cal. Const. Art. I § 1, and California Penal Code § 13300, and Evidence Code § 1040.)

Additionally, the Kern County Sheriff's Office does not have a service standard in place at this time.

With the transmission of this email and the record(s), the Kern County Sheriff's Office will consider its response to your request completed and will close this matter.

Sincerely,



DONNY YOUNGBLOOD,
Sheriff – Coroner, County of Kern
Kern County Sheriff's Office - Support Services Building
34970 McMurtrey Avenue, 2nd Floor - Civil Litigation
Bakersfield, CA 93308

From: [JustFOIA Notification](#)
To: [Patricia Newquist](#)
Subject: Kern County Sheriff's Office Records Request RR-2026-990 Completed
Date: Thursday, July 16, 2026 3:58:36 PM

External (kerncountysheriffca@request.justfoia.com)

[Graymail](#) [Spam](#) [Phish](#) [More...](#) [FAQ](#) [Protection by INKY](#)



SHERIFF'S OFFICE - COUNTY OF KERN
DONNY YOUNGBLOOD
Sheriff-Coroner Public Administrator
1350 Norris Road
Bakersfield, CA 93308-2231

Dear Requestor,

The request [Request Number: RR-2026-990](#) has been completed. Please click on the request link to download the response documentation.

For retrieving these records in the future, your request number is RR-2026-990, and your security key is 2B909752.

Thank you,

Kern County Sheriff's Office - Support Services
34970 McMurtrey Avenue, 2nd Floor
Bakersfield, CA 93308
(661) 391-1601

