

## DOCKETED

<b>Docket Number:</b>	17-BSTD-01
<b>Project Title:</b>	2019 Building Energy Efficiency Standards PreRulemaking
<b>TN #:</b>	219863
<b>Document Title:</b>	Presentation - HVAC Equipment Efficiency
<b>Description:</b>	By: Mark Alatorre, PE
<b>Filer:</b>	Hilary Fiese
<b>Organization:</b>	California Energy Commission
<b>Submitter Role:</b>	Commission Staff
<b>Submission Date:</b>	6/23/2017 10:30:12 AM
<b>Docketed Date:</b>	6/23/2017



# HVAC Equipment Efficiency

Mark Alatorre, PE  
Building Standards Office  
Efficiency Division

Pre-Rulemaking Workshop  
Imbrecht Hearing Room  
June 20, 2017



# Acknowledgements

California Statewide Codes and Standards Team

CASE Authors:


Jared Landsman (Integral Group)



# Background

## Federal Law (42USC 6313(a)(6)(A))

- Triggered when ASHRAE 90.1 is amended
- DOE determination within 18 months
- States can adopt ASHRAE 90.1 before DOE determination
- Tables 110.2A through 110.2K
- Not Subject to Cost Effectiveness





# Background

Equipment subject to this requirement:

- Small, Large and Very Large Commercial Package Air Conditioning and Heating Equipment
- Single Package Vertical Air Conditioners and Heat Pumps
- Packaged Terminal Air Conditioners and Heat Pumps
- Warm-Air Furnaces
- Commercial Packaged Boilers
- Storage Water Heaters, Instantaneous Water Heaters, and Unfired Hot Water Storage Tanks



# Proposed Code Change

Equipment	Equipment Category	Proposed Change to Efficiency
Single Package Vertical Air Conditioners (SPVAC)	Both weatherized and non-weatherized space constrained	Update EER and COP for weatherized units <65,000 Btu/h
Single Package Vertical Heat Pumps (SPVHP) - cooling & heating mode	Both weatherized and non-weatherized space constrained	Update EER and COP for weatherized units <65,000 Btu/h
Cooling Towers	Propeller or axial fan closed-circuit	Update gpm/hp to efficiency levels in ASHRAE 90.1-2016
VRF air conditioners	Air cooled	Update IEER to efficiency levels in ASHRAE 90.1-2016 being adopted after 1/1/2017
VRF heat pumps- cooling mode	Air Cooled	Update IEER to efficiency levels in ASHRAE 90.1-2016 being adopted after 1/1/2017
VRF heat pumps- cooling mode	Water-Source	Update IEER to efficiency levels in ASHRAE 90.1-2016 being adopted after 1/1/2018 and insert requirements for EER and IEER for ≥ 240,000 Btu/h size category
5 VRF heat pumps- heating mode	Water-Source	Update COP to efficiency levels in ASHRAE 90.1-2016 being adopted after 1/1/2018 and insert requirements for COP for <65,000 Btu/h and ≥ 240,000 Btu/h size category



# Energy Analysis

- Changes in efficiency only affect closed circuit cooling towers and SPVAC/SPVHP
- Prototypes selected are buildings with the highest use rate for these systems

Prototype ID	Occupancy Type (Residential, Retail, Office, etc.)	Area (ft <sup>2</sup> )	Number of Stories	Statewide New Construction Area (million ft <sup>2</sup> )
Prototype 1	High-Rise Res (cooling tower)	93,632	10	0.9
Prototype 2	Small Schools (SPVAC/SPVHP)	24,413	1	3.1/7.6



# Energy Savings

Climate Zone	First-Year Electricity Savings (GWh)		First-Year Peak Electrical Demand Reduction (MW)	
	New Construction	Alterations	New Construction	Alterations
1	0.01	0.02	6.84 x 10 <sup>-3</sup>	1.94E-02
2	0.05	0.15	3.52 x 10 <sup>-2</sup>	1.12E-01
3	0.11	0.36	1.21 x 10 <sup>-1</sup>	4.07E-01
4	0.10	0.33	7.77 x 10 <sup>-2</sup>	2.51E-01
5	0.01	0.04	1.53 x 10 <sup>-2</sup>	4.95E-02
6	0.10	0.46	8.46 x 10 <sup>-2</sup>	3.77E-01
7	0.09	0.25	1.11 x 10 <sup>-1</sup>	3.04E-01
8	0.18	0.79	1.20 x 10 <sup>-1</sup>	5.15E-01
9	0.22	0.81	1.14 x 10 <sup>-1</sup>	4.27E-01
10	0.34	0.96	2.16 x 10 <sup>-1</sup>	6.04E-01
11	0.11	0.28	4.89 x 10 <sup>-2</sup>	1.31E-01
12	0.34	0.96	1.88 x 10 <sup>-1</sup>	5.26E-01
13	0.24	0.65	1.02 x 10 <sup>-1</sup>	2.81E-01
14	0.07	0.21	3.47 x 10 <sup>-2</sup>	1.00E-01
15	0.12	0.29	8.66 x 10 <sup>-2</sup>	2.10E-01
16	0.06	0.18	3.88 x 10 <sup>-2</sup>	1.13E-01
<b>TOTAL</b>	2.15	6.74	1.40	4.43
	<b>8.89 GWh</b>		<b>5.83 MW</b>	





# Proposed Code Language

Table 110.2 – A Electrically Operated Unitary Air Conditioners and Condensing Units				
Equipment Type	Size Category	Efficiency		Test Procedure
		Before 1/1/2016	After 1/1/2016	
Air conditioners, air cooled both split system and single package	≥ 65,000 Btu/h and < 135,000 Btu/h	<del>11.2 EER</del> <del>11.4 IEER</del>	11.2 EER 12.9 IEER	ANSI/AHRI 340/360
	≥135,000 Btu/h and < 240,000 Btu/h	<del>11.0 EER</del> <del>11.2 IEER</del>	11.0 EER 12.4 IEER	
	≥ 240,000 Btu/h and < 760,000 Btu/h	<del>10.0 EER</del> <del>10.1 IEER</del>	10.0 EER 11.6 IEER	
	≥ 760,000 Btu/h	<del>9.7 EER</del> <del>10.1 IEER</del>	9.7 EER 11.2 IEER	
Air conditioners, water cooled	≥ 65,000 Btu/h and < 135,000 Btu/h	<del>12.1 EER</del> <del>12.3 IEER</del>	12.1 EER 13.9 IEER	ANSI/AHRI 340/360
	≥135,000 Btu/h and < 240,000 Btu/h	<del>12.5 EER</del> <del>12.5 IEER</del>	12.5 EER 13.9 IEER	
	≥ 240,000 Btu/h and < 760,000 Btu/h	<del>12.4 EER</del> <del>12.6 IEER</del>	12.4 EER 13.6 IEER	
	≥ 760,000 Btu/h	<del>12.2 EER</del> <del>12.4 IEER</del>	12.2 EER 13.5 IEER	



# Proposed Code Language

Table 110.2 – B Unitary and Applied Heat Pumps				
Equipment Type	Size Category	Efficiency <sup>a, b</sup>		Test Procedure
		Before 1/1/2016	After 1/1/2016	
Air Cooled (Cooling Mode), both split system and single package	≥ 65,000 Btu/h and < 135,000 Btu/h	<del>11.0 EER</del> <del>11.2 IEER</del>	11.0 EER 12 .2 IEER	ANSI/AHRI 340/360
	≥ 135,000 Btu/h and < 240,000 Btu/h	<del>10.6 EER</del> <del>10.7 IEER</del>	10.6 EER 11.6 IEER	
	≥ 240,000 Btu/h	<del>9.5 EER</del> <del>9.6 IEER</del>	9.5 EER 10.6 IEER	



# Proposed Code Language

Table 110.2 – E Packaged Terminal Air Conditioners and Packaged Terminal Heat Pumps				
Equipment Type	Size Category	Rating Condition	Efficiency <sup>a, b</sup>	Test Procedure
SPVAC (cooling mode)	< 65,000 Btu/h	95°F db/ 75°F wb Outdoor Air	<del>10.0 EER</del> <u>11.0 EER</u>	ANSI/AHRI 390
SPVHP (cooling mode)	< 65,000 Btu/h	95°F db/ 75°F wb Outdoor Air	<del>10.0 EER</del> <u>11.0 EER</u>	
SPVHP (heating mode)	< 65,000 Btu/h	95°F db/ 75°F wb Outdoor Air	<del>3.0 COP</del> <u>3.3 COP</u>	



# Proposed Code Language

**Table 110.2 – G Performance Requirements for Heat Rejection Equipment**

Equipment Type	Total System Heat Rejection Capacity at Rated Conditions	Subcategory or Rating Condition	Performance Required <sup>a,b,c,d</sup>	Test Procedure <sup>e</sup>
Propeller or axial fan Open-circuit cooling towers	All	95°F entering water 85°F leaving water 75°F entering air wb	≥ 42.1 gpm/hp	CTI ATC-105 and CTI STD-201 <u>RS</u>
Centrifugal fan Open-circuit cooling towers	All	95°F entering water 85°F leaving water 75°F entering air wb	≥ 20.0 gpm/hp	
Propeller or axial fan closed-circuit cooling towers	All	102°F entering water 90°F leaving water 75°F entering air wb	<u>≥ 14.0 gpm/hp</u> <u>≥ 16.1 gpm/hp</u>	
Centrifugal fan closed-circuit cooling towers	All	102°F entering water 90°F leaving water 75°F entering air wb	≥ 7.0 gpm/hp	



# Proposed Code Language

**Table 110.2 – H Electrically Operated Variable Refrigerant Flow Air Conditioners**

Equipment Type	Size Category	Heating Section Type	Sub-Category or Rating Condition	Minimum Efficiency	Test Procedure <sup>a</sup>
VRF Air Conditioners, Air Cooled	<65,000 Btu/h	All	VRF Multi-split System	13.0 SEER	ANSI/AHRI 1230
	≥65,000 Btu/h and <135,000 Btu/h	Electric Resistance (or none)	VRF Multi-split System	11.2 EER <del>13.1 IEER<sup>b</sup></del> <del>15.5 IEER<sup>b</sup></del>	
	≥135,000 Btu/h and <240,000 Btu/h	Electric Resistance (or none)	VRF Multi-split System	11.0 EER <del>12.9 IEER<sup>b</sup></del> <del>14.9 IEER<sup>b</sup></del>	
	≥240,000 Btu/h	Electric Resistance (or none)	VRF Multi-split System	10.0 EER <del>11.6 IEER<sup>b</sup></del> <del>13.9 IEER<sup>b</sup></del>	

<sup>a</sup> Applicable test procedure and reference year are provided under the definitions.  
<sup>b</sup> IEERs are only applicable to equipment with capacity control as specified by ANSI/AHRI 1230 test procedures.



# Proposed Code Language

Table 110.2 I Electrically Operated Variable Refrigerant Flow Air to Air and Applied Heat Pumps

Equipment Type	Size Category	Heating Section Type	Sub-Category or Rating Condition	Minimum Efficiency	Test Procedure <sup>b</sup>
VRF Air Cooled, (cooling mode)	<65,000 Btu/h	All	VRF Multi-split System	13.0 SEER	AHRI 1230
	≥65,000 Btu/h and <135,000 Btu/h	Electric Resistance (or none)	VRF Multi-split System <sup>a</sup>	11.0 EER <del>12.9 IEER <sup>c</sup></del> <del>14.6 IEER <sup>c</sup></del>	
	≥135,000 Btu/h and <240,000 Btu/h	Electric Resistance (or none)	VRF Multi-split System <sup>a</sup>	10.6 EER <del>12.3 IEER <sup>c</sup></del> <del>13.9 IEER <sup>c</sup></del>	
	≥240,000 Btu/h	Electric Resistance (or none)	VRF Multi-split System <sup>a</sup>	9.5 EER <del>11.0 IEER <sup>c</sup></del> <del>12.7 IEER <sup>c</sup></del>	
VRF Water source (cooling mode)	<65,000 Btu/h	All	VRF Multi-split systems <sup>a</sup> 86°F entering water	12.0 EER <del>15.8 IEER <sup>c</sup></del>	AHRI 1230
	≥65,000 Btu/h and <135,000 Btu/h	All	VRF Multi-split System <sup>a</sup> 86°F entering water	12.0 EER <del>15.8 IEER <sup>c</sup></del>	
	≥135,000 Btu/h	All	VRF Multi-split System <sup>a</sup> 86°F entering water	10.0 EER <del>13.8 IEER <sup>c</sup></del>	
	<u>≥240,000 Btu/h</u>	<u>All</u>	<u>VRF Multi-split System <sup>a</sup></u> <u>86°F entering water</u>	<u>10.0 EER</u> <u>12.0 IEER</u>	



# Proposed Code Language

*Continued:* Table 110.2 | Electrically Operated Variable Refrigerant Flow Air to Air and Applied Heat Pumps

Equipment Type	Size Category	Heating Section Type	Sub-Category or Rating Condition	Minimum Efficiency	Test Procedure <sup>b</sup>
VRF Water source (heating mode)	<65,000 Btu/h (cooling capacity)	---	<u>VRF Multi-split System 68°F entering water</u>	<u>4.3 COP</u>	AHRI 1230
	≥65,000 Btu/h and <135,000 Btu/h (cooling capacity)	---	VRF Multi-split System 68°F entering water	<del>4.2 COP</del> <u>4.3 COP</u>	
	≥135,000 Btu/h and <240,000 Btu/h (cooling capacity)	---	VRF Multi-split System 68°F entering water	<del>3.9 COP</del> <u>4.0 COP</u>	
	≥240,000 Btu/h (cooling capacity)	---	<u>VRF Multi-split System 68°F entering water</u>	<u>3.9 COP</u>	

<sup>a</sup> Deduct 0.2 from the required EERs and IEERs for Variable Refrigerant Flow (VRF) Multi-split system units with a heating recovery section.

<sup>b</sup> Applicable test procedure and reference year are provided under the definitions.

<sup>c</sup> IEERs are only applicable to equipment with capacity control as specified by ANSI/AHRI 1230 test procedures.



# Proposed Code Language

**Table 110.2 – J Warm-Air Furnaces and Combination Warm-Air Furnaces/Air Conditioning Units, Warm-Air Duct Furnaces and Unit Heaters**

Equipment Type	Size Category (Input)	Subcategory or Rating Condition <sup>b</sup>	Minimum Efficiency <sup>d,e</sup>	Test Procedure <sup>a</sup>
Warm-Air Furnace, Gas-Fired	< 225,000 Btu/h	Maximum Capacity <sup>b</sup>	78% AFUE or 80% Et	DOE 10 CFR Part 430 or Section 2.39, Thermal Efficiency, ANSI Z21.47
	≥ 225,000 Btu/h	Maximum Capacity <sup>b</sup>	80% Et	Section 2.39, Thermal Efficiency, ANSIZ21.47
Warm-Air Furnace, oil-Fired	< 225,000 Btu/h	Maximum Capacity <sup>b</sup>	78% AFUE or 80% Et	DOE 10 CFR Part 430 or Section 42, Combustion,
	≥ 225,000 Btu/h	Maximum Capacity <sup>b</sup>	81% Et	Section 42, Combustion, UL 727
Warm-Air Duct Furnaces, Gas-Fired	All Capacities	Maximum Capacity <sup>b</sup>	80% Ec	Section 2.10, Efficiency, ANSI Z83.8
Warm-Air Unit Heaters, Gas-Fired	All Capacities	Maximum Capacity <sup>b</sup>	80% Ec	Section 2.10, Efficiency, ANSI Z83.8
Warm-Air Unit Heaters, Oil-Fired	All Capacities	Maximum Capacity <sup>b</sup>	81% Ec	Section 40, Combustion, UL 731

a Applicable test procedure and reference year are provided under the definitions.

b Compliance of multiple firing rate units shall be at maximum firing rate.

c Combustion units not covered by [NAECA the U.S. Department of Energy Code of Federal Regulations 10 CFR 430](#) (3-phase power or cooling capacity greater than or equal to 19 kW) may comply with either rating.

d Et= thermal efficiency. Units must also include an interrupted or intermittent ignition device (IID), have jacket losses not exceeding 0.75% of the input rating, and have either power venting or a flue damper. A vent damper is an acceptable alternative to a flue damper for those furnaces where combustion air is drawn from the conditioned space.

e Ec= combustion efficiency (100% less flue losses). See test procedure for detailed discussion.

f Units must also include interrupted or intermittent ignition device (IID) and have either power venting or an automatic flue damper.





# Questions?

Mark Alatorre

[mark.alatorre@energy.ca.gov](mailto:mark.alatorre@energy.ca.gov)

(916) 654-4642

Comments Due by July 7th

Docket Number 2017-BSTD-01

[docket@energy.ca.gov](mailto:docket@energy.ca.gov)