DOCKETED			
Docket Number:	13-AFC-01C		
Project Title:	Alamitos Energy Center - Compliance		
TN #:	245714		
Document Title:	PTA for Emergency ICE Generators		
Description:	N/A		
Filer:	Charlene He		
Organization:	AES Alamitos		
Submitter Role:	Applicant		
Submission Date:	8/27/2022 8:40:32 AM		
Docketed Date:	8/27/2022		

Jacobs

Petition for Post-Certification Amendment

Installation of Two Emergency Diesel-Fired Internal Combustion Engines

For the
Alamitos Energy Center
Long Beach, California
(13-AFC-01C)

Submitted to the:
California Energy Commission

Submitted by: AES Alamitos Energy, LLC

With Technical Assistance by:

Jacobs Engineering Group Inc.

Version No: Final

Document No: PPS0714221341SAC

August 25, 2022



Petition for Post-Certification Amendment

Client Name: Alamitos Energy Center

Project Name: Installation of Two Emergency Diesel-Fired Internal Combustion Engines

Project No: D3658800.A.CS.EV.01

Document No: PPS0714221341SAC **Project Manager:** Elyse Engel

Revision No: Final Prepared By: Elyse Engel & Jerry Salamy

Date: August 25, 2022 File Name: AEC_Diesel Engine_PTA_(13-AFC-

01C)_082522_Final

Document History and Status

Revision	Date	Description	Author	Checked	Reviewed	Approved

Distribution of Copies

Revision	Issue Approved	Date Issued	Issued To	Comments

Jacobs Engineering Group Inc.

 2485 Natomas Park Drive
 T +1.916.920.0300

 Suite 600
 F +1.916.920.8463

 Sacramento, CA 95833-2937
 www.jacobs.com

 United States
 www.jacobs.com

Copyright Jacobs Engineering Group Inc. @ 2022.

All rights reserved. Reproduction and redistribution without written permission is prohibited. Jacobs, the Jacobs logo, and all other Jacobs trademarks are the property of Jacobs Engineering Group Inc.

NOTICE: This document has been prepared exclusively for the use and benefit of Jacobs' client. Jacobs accepts no liability or responsibility for any use or reliance upon this document by any third party.

Executive Summary

AES Alamitos Energy, LLC (AES or the Project Owner) is submitting this petition to the California Energy Commission (CEC) for post-Certification license modification for the Alamitos Energy Center (AEC) (13-AFC-01C). The AEC consists of a combined cycle gas turbine (CCGT) power block and a simple cycle gas turbine (SCGT) power block. The CCGT power block includes two natural gas fired turbines, two unfired heat recovery steam generators (HRSG), a condensing steam turbine (STG), an air-cooled condenser, and ancillary facilities.

This petition for post-certification license amendment (Petition to Amend or PTA) proposes to install two identical 1,112 brake-horsepower (bhp) emergency diesel-fired internal combustion engine (ICE) generators to provide emergency power supply to critical plant equipment in the CCGT power block during the gas turbine shutdown periods in the event of electrical emergency. The engines of these ICE generators will be U.S. Environmental Protection Agency (EPA) Tier 2 certified and equipped with California Air Resource Board (CARB) verified Level 3 diesel particulate filters (DPFs). No changes to the existing AEC equipment or operations are proposed.

To ensure compliance with all applicable laws, ordinances, regulations, and standards (LORS), the Project Owner has submitted a permit application under Application Numbers 636578, 636579, and 636580 to the South Coast Air Quality Management District (SCAQMD), presented in Attachment 3.1 of this PTA. A Permit to Construct (PTC)/Permit to Operate (PTO) for these two emergency ICE generators was approved by SCAQMD on August 10, 2022, with a courtesy copy submitted to the CEC on August 24, 2022. An excerpt of the applicable permit conditions is presented in Attachment 3.2 of this PTA.

To analyze potential environmental effects, an environmental impacts assessment is presented in Section 3. The assessment concludes that there will be no significant environmental impacts associated with the implementation of the actions specified in this PTA and that the project, as modified, will continue to comply with all applicable LORS.

Contents

Execu	itive S	ummary	i
Acror	ıyms a	nd Abbreviations	iv
1.	Intro	duction	1-1
	1.1	Background	1-1
	1.2	Overview of Proposed Amendments	1-1
	1.3	Necessity of Proposed Changes, an Explanation of Why it Should Be Permitted, and a Description of New Information or Change in Circumstances	1-2
	1.4	Summary of Potential Environmental Effects and Proposed Mitigation Measures	1-2
	1.5	Consistency of Changes with Applicable LORS	1-3
2.	Desci	ription of Proposed Amendments	2-1
3.	Envir	onmental Analysis of Proposed Amendments	3-1
	3.1	Air Quality and Greenhouse Gases	3-1
	3.2	Biological Resources	3-12
	3.3	Cultural Resources	3-12
	3.4	Energy and Energy Resources	3-13
	3.5	Geological and Paleontological Resources	3-14
	3.6	Hazardous Materials Management	3-14
	3.7	Land Use	3-15
	3.8	Noise and Vibration	3-15
	3.9	Public Health	3-16
	3.10	Socioeconomics	3-17
	3.11	Soil and Water Resources	3-17
	3.12	Traffic and Transportation	3-18
	3.13	Visual Resources	3-18
	3.14	Waste Management	3-19
	3.15	Wildfire	3-19
	3.16	Worker Safety and Fire Protection	3-20
4.	Poter	ntial Effects on the Public	4-1
5.	List o	f Property Owners	5-1
6.	Poter	ntial Effects on Property Owners, the Public, and Parties in the Proceeding	6-1
7.	Poter	ntially Applicable CEQA Exemptions	7-1

Attachments

- 3.1 AEC Air Permit Application3.2 ICE Generator PTC/PTO Conditions

Table

1.2-1	Informational Requirements for Post-Certification Modifications	1-2
2-1	Proposed ICE Generator Operating Schedule	2-1
3.1-1	State and Federal Air Quality Designations for Los Angeles County, California	3-1
3.1-2	Criteria Pollutant Emissions per Emergency ICE Generator	3-2
3.1-3	Criteria Pollutant Emissions for Both (2) Emergency ICE Generators	3-2
3.1-4	GHG Emissions for Emergency ICE Generators	3-3
3.1-5	Comparison to Rule 212(g) Thresholds	3-4
3.1-6	Tier 2 Emission Standards	3-6
3.1-7	Comparison to Rule 1302(r) Major Modification Thresholds	3-7
3.1-8	ATCM Emission Standards	3-10
3.1-9	Comparison to SCAQMD Significance Thresholds	3-11
3.9-1	DPM Emissions for Emergency ICE Generators	3-1 <i>6</i>

iii PPS0714221341SAC

Acronyms and Abbreviations

AEC Alamitos Energy Center

AES AES Alamitos Energy, LLC

AFC Application for Certification

AGS Alamitos Generating Station

ATCM Airborne Toxic Control Measures

BACT best available control technology

bhp brake-horsepower

CAAQS California Ambient Air Quality Standards

CARB California Air Resources Board

CCGT combined cycle gas turbine

CCR California Code of Regulations

CEC California Energy Commission

CEQA California Environmental Quality Act

CFR Code of Federal Regulations

CH₄ methane

CI compression-ignition

CO carbon monoxide

CO₂ carbon dioxide

CO₂e carbon dioxide equivalent

COC Conditions of Certification

DPF diesel particulate filter

DPM diesel particulate matter

EPA U.S. Environmental Protection Agency

FR Federal Register

g/hp-hr gram(s) per horsepower-hour

g/kWh gram(s) per kilowatt-hour

GE General Electric

GHG greenhouse gas

H₂S hydrogen sulfide

PPS0714221341SAC iv

Petition for Post-Certification Amendment

HAP hazardous air pollutants

HI hazard index

HRSG heat recovery steam generators

ICE internal combustion engine

kg/MMBtu kilogram(s) per million British thermal unit

kW kilowatt(s)
lb pound(s)

lb/hr pound(s) per hour

LORS laws, ordinances, regulations, and standards

MICR Maximum Individual Cancer Risk

MT metric ton

MW megawatt(s) N₂O nitrous oxide

N/A not applicable

NAAQS National Ambient Air Quality Standards

NESHAP National Emission Standards for Hazardous Air Pollutants

NMHC non-methane hydrocarbons

NO₂ nitrogen dioxide NO_x nitrogen oxides

NSPS New Source Performance Standards

PM_{2.5} particulate matter with an aerodynamic diameter of 2.5 microns or less

PM₁₀ particulate matter with an aerodynamic diameter of 10 microns or less

ppm part(s) per million

ppmvd part(s) per million by volume dry

PSD Prevention of Significant Deterioration

PTA Petition to Amend

PTC Permit to Construct

PTE potential to emit

PTO Permit to Operate

RECLAIM Regional Clean Air Incentives Market

RTC RECLAIM Trading Credit

Petition for Post-Certification Amendment

SCAQMD South Coast Air Quality Management District

SCGT simple cycle gas turbine

SO₂ sulfur dioxide

SO_X sulfur oxides

STG condensing steam turbine

TAC toxic air contaminants

tpy ton(s) per year

VOC volatile organic compounds

PPS0714221341SAC vi

1. Introduction

1.1 Background

The CEC approved the AEC Application for Certification (AFC) on April 12, 2017 ("Final Decision"). The AEC site is on the existing Alamitos Generating Station (AGS) property, located at 690 N. Studebaker Road in the City of Long Beach, California.

With the Final Decision, the CEC analyzed the AEC's impacts for two General Electric (GE) Model 7FA.05 combustion turbines in a combined cycle configuration and four GE Model LMS100-PB combustion turbines in a simple cycle configuration. The AEC's CCGTs began commercial operation in February 2020. Construction of the SCGTs has yet to commence and is contingent on securing a power purchase agreement.

Since issuance of the Final Decision, the following post-certification changes have also been approved by the CFC:

- Request to use a gravel area adjacent to the project site, on Southern California Edison's switchyard site, approved August 2018.
- Modification of the maximum annual operating hours of the CCGT and SCGT units and the associated air emission limits, as well as an increase of the CCGT non-cold startup nitrogen oxides (NOx) emission limits and modification of CCGT unit exhaust stack heights from 140 feet to 150 feet, approved June 2021.

In addition, the CEC is currently reviewing a PTA to remodel the entrance gate and replace the security guard shack at the AGS site.

1.2 Overview of Proposed Amendments

This PTA addresses the potential environmental impacts associated with installing two 1,112 bhp emergency diesel-fired ICE generators to provide emergency power supply to the CCGT power block. These ICE generators will:

- Be EPA Tier 2 certified and equipped with CARB-verified Level 3 DPFs for diesel particulate matter (DPM) reduction by 85 percent or greater.
- Emit NOx, sulfur oxides (SOx), carbon monoxide (CO), volatile organic compounds (VOC), particulate matter with an aerodynamic diameter of 10 microns or less (PM₁₀), particulate matter with an aerodynamic diameter of 2.5 microns or less (PM_{2.5}), DPM, and greenhouse gases (GHGs).
- Be located more than 1,000 feet from a school or other sensitive receptor.

A detailed description of the proposed modification is included in Section 2 and analyzed in Section 3.

This PTA contains all of the information that is required pursuant to the CEC's Siting Regulations (Title 20, California Code of Regulations [CCR], Section 1769, Post Certification Petition for Changes in Project Design, Operation or Performance and Amendments to the Commission Decision). The information necessary to fulfill the requirements of Section 1769 is contained in Sections 1 through 7, as summarized in Table 1.2-1.

Table 1.2-1. Informational Requirements for Post-Certification Modifications

Section 1769(a)(1) Requirements	Sections of PTA Fulfilling Requirements
(A) A complete description of the proposed change, including new language for any conditions of certification that will be affected;	Sections 1, 2, and 3
(B) A discussion of the necessity for the proposed change and an explanation of why the change should be permitted;	Sections 1.1, 1.2, 1.3, and 3
(C) A description of any new information or change in circumstances that necessitated the change;	Sections 1.1, 1.2, 1.3, and 3
(D) An analysis of the effects that the proposed change to the project may have on the environment and proposed measures to mitigate any significant environmental effects;	Sections 1.4 and 3
(E) An analysis of how the proposed change would affect the project's compliance with applicable laws, ordinances, regulations, and standards;	Sections 1.5 and 3
(F) A discussion of how the proposed change would affect the public;	Sections 1, 3, and 4
(G) A list of current assessor's parcel numbers and owners' names and addresses for all parcels within 500 feet of any affected project linears and 1,000 feet of the project site;	Section 5
(H) A discussion of the potential effect of the proposed change on nearby property owners, residents, and the public; and	Sections 3, 4, and 6
(I) A discussion of any exemptions from the California Environmental Quality Act, commencing with Section 21000 of the Public Resources Code, that the project owner believes may apply to approval of the proposed change.	Section 7

1.3 Necessity of Proposed Changes, an Explanation of Why it Should Be Permitted, and a Description of New Information or Change in Circumstances

The CEC Siting Regulations require a discussion of the necessity for the proposed revisions to the AEC Certification, an explanation of why the change should be permitted, and a description of any new information or change in circumstances that necessitated the change (Title 20, CCR, Sections 1769(a)(1)(B) and (C)). The two proposed emergency diesel-fired ICE generators will be used to provide power supply to critical plant equipment in the CCGT power block during the gas turbine shutdown periods in the event of electrical emergency. Therefore, the change to install these two generators is necessary to maintain CCGT power block operations in the event of loss of grid power. This PTA further discusses why the change should be allowed.

1.4 Summary of Potential Environmental Effects and Proposed Mitigation Measures

The CEC Siting Regulations require an analysis of the effects that the proposed change to the project may have on the environment and proposed measures to mitigate any significant environmental effect (Title 20, CCR, Section 1769(a)(1)(D)). Section 3 of this PTA includes a discussion of the potential environmental impacts associated with the modification as well as a discussion of the consistency of the modification with applicable LORS. Section 3 concludes that there will be no significant, unmitigated environmental impacts associated with implementing the actions specified in this PTA and that the project, as modified, will comply with all applicable LORS. As such, no new or additional mitigation measures are proposed as part of this PTA.

1.5 Consistency of Changes with Applicable LORS

The CEC Siting Regulations require an analysis of how the proposed change would affect the project's compliance with applicable LORS (Title 20, CCR, Section 1769(a)(1)(E)). The proposed project modification is consistent with applicable LORS, as discussed in Section 3. The proposed project change will allow the AEC to maintain CCGT power block operations in the event of loss of grid power.

2. Description of Proposed Amendments

This section includes a description of the proposed project modification, consistent with CEC Siting Regulations (Title 20, CCR, Section 1769(a)(1)(A)).

The proposed change to the AEC includes the installation of two identical 1,112 bhp emergency diesel-fired ICE generators in the CCGT power block. The emergency ICE generator engines are Model Year 2022 or newer Perkins 2806C-E18TTAG7, which is certified by the EPA as a Tier 2 engine (Family Name NCPXL18.1NYS). Each engine will be equipped with a Miratech Model LTRV24-21-10-R1 CARB-verified Level 3 Plus DPF, which reduces PM₁₀/PM_{2.5} emissions by 85 percent or greater.

The ICE generators will only be operated for backup and emergency uses, with periodic maintenance and testing runs to maintain operational readiness. Operation of the ICE generators will be limited to 50 hours per year for maintenance and testing, and up to a maximum of 200 total hours per year. The proposed operating schedule for each ICE generator is presented in Table 2-1.

Table 2-1. Proposed ICE Generator Operating Schedule

Period	Maintenance and Testing	Total Operation
Hours per Day	1	N/A
Hours per Month	4.2	N/A
Hours per Year	50	200

Source: Yorke Engineering, LLC. 2022. *Applications for Permits to Construct: Two Emergency IC Engines*. Table 2-3. April. Note:

N/A = Not applicable (i.e., not needed for emissions calculations presented in Section 3.1)

Although the proposed change will require physical installation of two new pieces of equipment, their installation will not require any significant earth-moving activities or operational changes beyond revising the existing SCAQMD operational permits. The modification will also not impact operations of the existing AEC equipment. As such, there will be no change to AEC's existing equipment and operations.

3. Environmental Analysis of Proposed Amendments

The following subsections present a discussion of the potential impacts that the proposed change may have on the environmental analysis as presented in applicable sections of the Final Decision and subsequent amendments. Each discussion includes an environmental analysis, an assessment of compliance with applicable LORS, proposed mitigation measures, and, if applicable, proposed changes to the Conditions of Certification (COCs) that are necessary as a result of the project modification.

3.1 Air Quality and Greenhouse Gases

The proposed installation of two emergency diesel-fired ICE generators at the AEC has the potential to affect air quality and GHG impacts. An air permit application reflecting the emissions associated with the two new emergency ICE generators has been submitted to the SCAQMD and is presented as Attachment 3.1. As noted above, a PTC/PTO for these two emergency ICE generators was approved by SCAQMD on August 10, 2022. The potential effects of the proposed installation are considered below.

3.1.1 Environmental Setting

The project is located in Los Angeles County, which is within the SCAQMD's jurisdiction. The SCAQMD is the EPA's delegated authority to implement state and federal air quality regulations. The SCAQMD also monitors and reports the status of the area's air quality attainment of the California and National Ambient Air Quality Standards (CAAQS and NAAQS, respectively). Table 3.1-1 presents the attainment status for Los Angeles County.

Table 3.1-1. State and Federal Air Quality Designations for Los Angeles County, California

Pollutant	State Designation	Federal Designation
Ozone	1-hour: Nonattainment 8-hour: Nonattainment	1-hour: Nonattainment (Extreme) 8-hour: Nonattainment (Extreme)
СО	1-hour: Attainment 8-hour: Attainment	1-hour: Attainment (Serious Maintenance) 8-hour: Attainment (Serious Maintenance)
NO ₂	1-hour: Attainment Annual: Attainment	1-hour: Attainment (Maintenance) Annual: Attainment (Maintenance)
SO ₂	1-hour: Attainment 24-hour: Attainment	1-hour: Attainment N/A
PM ₁₀	24-hour: Nonattainment Annual: Nonattainment	24-hour: Attainment (Serious Maintenance) N/A
PM _{2.5}	N/A Annual: Nonattainment	24-hour: Nonattainment (Serious) Annual: Nonattainment (Serious)
Lead	Attainment	Nonattainment (Partial)
H ₂ S, Sulfates, Visibility, Vinyl Chloride	Attainment/Unclassified	N/A

Sources:

California Air Resources Board (CARB). 2022. "Maps of State and Federal Area Designations." Available online at: https://ww2.arb.ca.gov/resources/documents/maps-state-and-federal-area-designations. Accessed July 27, 2022.

U.S. Environmental Protection Agency (EPA). 2022. "Nonattainment Areas for Criteria Pollutants (Green Book)." Available online at: https://www.epa.gov/green-book. Accessed July 27, 2022.

Notes:

H₂S = hydrogen sulfide

N/A = Not applicable (i.e., no standard)

NO₂ = nitrogen dioxide

 SO_2 = sulfur dioxide

3.1.2 Environmental Consequences

The proposed installation of two 1,112 bhp emergency diesel-fired ICE generators will result in increased air quality and GHG emissions at the AEC. By combusting diesel fuel, both ICE generators will emit VOC, NOx, CO, PM₁₀/PM_{2.5}, SOx, and GHGs during operations. As stated previously, the engines will be EPA Tier 2 certified with an add-on CARB-verified Level 3 DPF to achieve at least 85 percent reduction of PM₁₀/PM_{2.5} emissions. SO_X emissions will be limited through the use of low-sulfur diesel fuel. Tables 3.1-2 and 3.1-3 present the controlled criteria pollutant emissions for each emergency ICE generator and both (2) emergency ICE generators, respectively, based on the routine operating schedule presented in Table 2-1. Detailed emission calculations can be found in Appendix C of Attachment 3.1.

Table 3.1-2. Criteria Pollutant Emissions per Emergency ICE Generator

	Uncontrolled Emission	Generatora			
Pollutant	Factors (g/hp-hr)	(lb/hr)	(lb/day)	(lb/year) ^b	(tpy) ^b
NO _X	3.84	9.42	9.42	470.75	0.24
CO	0.16	0.39	0.39	19.61	0.01
VOC	0.20	0.49	0.49	24.52	0.01
PM ₁₀ /PM _{2.5}	0.02	0.007	0.007	0.368	0.0002
SO _x	0.005	0.01	0.01	0.60	0.0003

Source: Yorke Engineering, LLC. 2022. Applications for Permits to Construct: Two Emergency IC Engines. Tables 3-1 and 3-2. April.

g/hp-hr = gram(s) per horsepower-hour

lb/day = pound(s) per day

lb/hr = pound(s) per hour

lb/year = pound(s) per year

tpy = ton(s) per year

Table 3.1-3. Criteria Pollutant Emissions for Both (2) Emergency ICE Generators

	Uncontrolled Emission	Controlled Emissions for Both (2) Generators ^a			
Pollutant	Factors (g/hp-hr)	(lb/hr)	(lb/day)	(lb/year) ^b	(tpy) ^b
NO _X	3.84	18.84	18.84	941.5	0.47
CO	0.16	0.78	0.78	39.22	0.02
VOC	0.20	0.98	0.98	49.04	0.02
PM ₁₀ /PM _{2.5}	0.02	0.014	0.014	0.736	0.0004
SO _x	0.005	0.02	0.02	1.20	0.0006

Source: Yorke Engineering, LLC. 2022. *Applications for Permits to Construct: Two Emergency IC Engines*. Tables 3-1 and 3-3. April. Notes:

Table 3.1-4 presents the GHG emissions for the emergency ICE generators, based on the routine operation of only 50 hours per year for maintenance and testing at 100 percent load (54.3 gallons per hour). Detailed emission calculations can be found in Appendix C of Attachment 3.1.

^a Controlled emissions account for the engine's add-on DPF, which achieves at least an 85 percent reduction of PM₁₀/PM_{2.5}.

^b Annual emissions assume routine operation of only 50 hours per year for maintenance and testing.

^a Controlled emissions account for the engine's add-on DPF, which achieves at least an 85 percent reduction of PM₁₀/PM_{2.5}.

^b Annual emissions assume routine operation of only 50 hours per year for maintenance and testing.

Table 3.1-4. GHG Emissions for Emergency ICE Generators

	Emission Factors	Emissions per Generatora		Emissions for E Generators ^a	Both (2)
Pollutant	(kg/MMBtu)	(tpy)	(tpy CO₂e) ^b	(tpy)	(tpy CO₂e) ^b
CO ₂	73.96	30.5	30.5	61.0	61.0
CH ₄	0.003	0.0012	0.03	0.0024	0.06
N ₂ O	0.0006	0.0002	0.07	0.0004	0.14
Total			30.65		61.30

Source: Yorke Engineering, LLC. 2022. Applications for Permits to Construct: Two Emergency IC Engines. Tables 3-6 and 3-7. April.

CH₄ = methane

CO₂ = carbon dioxide

CO₂e = carbon dioxide equivalent

kg/MMBtu = kilogram(s) per million British thermal unit

 N_2O = nitrous oxide

3.1.3 Regulatory Requirements

3.1.3.1 Federal Regulations

The federal pre-construction Prevention of Significant Deterioration (PSD) program for sources subject to PSD pre-construction review permitting applies to sources located in attainment areas, which are classified as major sources. The AEC is subject to the PSD program. Therefore, PSD review applies to the proposed installation of two emergency diesel-fired ICE generators and is addressed in Section 3.1.3.2 below.

The federal operating permit program (Title V) and prohibitory rules applicable to the AEC are also addressed in Section 3.1.3.2 below.

3.1.3.2 Local Regulations

The SCAQMD has promulgated rules governing the need for sources to apply for preconstruction/operating permits and prohibitory rules. Below is an analysis of the SCAQMD rules applicable to the proposed installation of two emergency diesel-fired ICE generators at the AEC.

Rule 212 – Standards for Approving Permits and Issuing Public Notice

In accordance with Rule 212(c), public notice is required for:

- A project requesting installation of a new source or modification of an existing source, if the source is located within 1,000 feet of the outer boundary of a school, or
- A project resulting in a new or modified facility with onsite emission increases exceeding any of the daily maximums from Rule 212(q), or
- A project requesting installation of a new source or modification of an existing source, if the emission increases result in exposure to Maximum Individual Cancer Risk (MICR) greater than or equal to the applicable thresholds in Rule 212(c)(3)(A), or substances that pose a potential risk of nuisance.

^{-- =} No emission factor or emissions to be reported

^a Emissions assume routine operation of only 50 hours per year for maintenance and testing.

 $^{^{}b}$ Emissions of each GHG are converted into CO₂e using the following global warming potentials: 1 for CO₂, 25 for CH₄, and 298 for N₂O.

The nearest K-12 school, Charles F. Kettering Elementary School, is located approximately 2,170 feet northwest of the west emergency ICE generator and 2,181 feet northwest of the east emergency ICE generator, both of which are more than 1,000 feet.

As shown in Table 3.1-5, the daily emissions increases resulting from installation of the new emergency ICE generators are below the daily maximums provided in Rule 212(g).

Table 3.1-5. Comparison to Rule 212(g) Thresholds

Pollutant	Daily Maximum Threshold Project Increases (lb/day) (lb/day)		Thresholds Exceeded?
NO _X	40	18.84	N
CO	220	0.78	N
VOC	30	0.98	N
$PM_{10}/PM_{2.5}$	30	0.014	N
SO _x	60	0.02	N

Source: Yorke Engineering, LLC. 2022. Applications for Permits to Construct: Two Emergency IC Engines. Table 4-1. April.

As discussed in Section 3.9.2, the project passes a Rule 1401 Tier 2 Screening Risk Assessment, indicating that the proposed installation of two emergency diesel-fired ICE generators is not expected to result in MICR greater than or equal to the applicable thresholds.

As described above, none of the Rule 212 criteria are exceeded; therefore, Rule 212 public notice is not required for this project.

Rule 301 – Permitting and Associated Fees

The processing fees were determined using Rule 301. Attachment 3.1 documents that the Project Owner has paid the applicable processing fees to SCAQMD and has requested expedited permit processing.

Rule 401 – Visible Emissions

The subject equipment combusts low-sulfur diesel fuel and has Tier 2-certified engines equipped with DPFs. Therefore, the subject equipment is not expected to result in visible emissions. Compliance with this rule is expected.

Rule 402 - Nuisance

This project is not expected to cause injury, detriment, nuisance, or annoyance to the public, based on the subject equipment combusting low-sulfur diesel fuel and having Tier 2-certified engines equipped with DPFs. Compliance with this rule is expected.

Rule 403 – Fugitive Dust

The fugitive dust emissions requirements set forth in Rule 403 will be adhered to by the Project Owner during operation, as applicable. No significant fugitive dust emissions are expected from the facility during normal operations or due to the proposed installation of two emergency diesel-fired ICE generators. Therefore, compliance with this rule is expected.

Rule 404 - Particulate Matter - Concentration

The subject equipment combusts low-sulfur diesel fuel and has Tier 2-certified engines equipped with DPFs. Therefore, the subject equipment is not expected to result in $PM_{10}/PM_{2.5}$ emissions greater than the concentration limits established in SCAQMD Rule 404, Table 404(a). Compliance with this rule is expected.

Rule 407 - Liquid and Gaseous Air Contaminants

This rule prohibits an operator from discharging sulfur dioxide (SO₂) and CO into the atmosphere from any equipment in excess of 500 parts per million by volume dry (ppmvd) and 2,000 ppmvd, respectively. However, per SCAQMD Rule 407(b)(1), the provisions of this rule do not apply to stationary ICEs. Therefore, compliance with this rule is not required for the project's new emergency ICE generators.

Rule 409 – Combustion Contaminants

This rule prohibits an owner/operator from discharging into the atmosphere from any equipment combustion contaminants exceeding 0.1 grain per cubic foot of gas calculated to 12 percent of carbon dioxide (CO_2) at standard conditions averaged over a minimum of 15 consecutive minutes. However, the provisions of this rule do not apply to ICEs. Therefore, compliance with this rule is not required for the project's new emergency ICE generators.

Rule 431.2 – Sulfur Content of Liquid Fuels

This rule reduces SO_X emissions from diesel fuel combustion by limiting sulfur content of diesel fuel to 15 parts per million (ppm) by weight. The subject equipment combusts low-sulfur diesel fuel; therefore, compliance with this rule is expected.

Rule 474 – Fuel Burning Equipment – Oxides of Nitrogen

This rule is superseded by the requirements of the NO_x Regional Clean Air Incentives Market (RECLAIM) Program, per Rule 2001(j).

Rule 475 - Electric Power Generating Equipment

This rule limits an owner/operator from discharging combustion contaminants into the atmosphere from any electric power generating equipment with a maximum rating of more than 10 megawatts (MW). Since the electric generating potential of each emergency ICE generator is less than 10 MW, the provisions of this rule do not apply, and compliance is not required.

Regulation IX - New Source Performance Standards

The New Source Performance Standards (NSPS) establish emission standards for specific emission sources, as published in the Code of Federal Regulations (CFR) and in the Federal Register (FR) by the EPA. The following NSPS is applicable to AEC's proposed new emergency ICE generators.

40 CFR 60, Subpart IIII – Standards of Performance for Stationary Compression-Ignition Internal Combustion Engines

This rule establishes emission standards, fuel requirements, and monitoring and reporting requirements for manufacturers, owners, and operators of stationary compression-ignition (CI) ICEs. Per 40 CFR 60.4205(b), emergency stationary CI ICEs of model year 2007 and later with a displacement of less than 30 liters per cylinder that are not fire pump engines must comply with the emission standards for new non-road CI engines for the same model year and maximum engine power, as established in 40 CFR 1039, Appendix I. The Tier 2 emission standards for engines with a maximum engine power rating greater than 560 kilowatts (kW; 750 bhp) and constructed after 2006 are shown in Table 3.1-6 below.

Table 3.1-6. Tier 2 Emission Standards

Pollutant	Emission Standard (g/kWh)	Emission Standard (g/hp-hr)
NO _X	6.4	4.8
CO	3.5	2.6
PM ₁₀ /PM _{2.5}	0.2	0.15

Source: Yorke Engineering, LLC. 2022. *Applications for Permits to Construct: Two Emergency IC Engines*. Table 4-3. April. Note:

g/kWh = gram(s) per kilowatt-hour

The proposed emergency ICE generators will be Tier 2 engines; therefore, compliance with the above emission standards is expected.

Compliance with the diesel fuel requirements of 40 CFR 60.4207(b) is expected to be met through compliance with the sulfur content requirements of SCAQMD Rule 431.2.

40 CFR 60.4211(f) also limits annual operation of emergency stationary CI ICEs as follows:

- No limit on use for emergency purposes.
- A maximum of 100 hours per year for maintenance and testing, emergency demand response, and to provide power during periods of voltage or frequency deviations.
- A maximum of 50 hours per year for non-emergency purposes, which counts towards the 100-hour limit noted above.

The Project Owner intends to operate the two emergency ICE generators no more than 50 hours per year for maintenance and testing purposes. Therefore, compliance with these hour restrictions is expected.

The NSPS includes other monitoring, recordkeeping, and reporting requirements. The Project Owner will demonstrate compliance by operating and maintaining the ICE generators and their control devices in accordance with the manufacturer's recommendations.

Regulation X - National Emission Standards for Hazardous Air Pollutants

The National Emission Standards for Hazardous Air Pollutants (NESHAP) regulate the emissions of Hazardous Air Pollutants (HAP) from specific emission sources. These regulations are periodically updated to reflect actions by the EPA. The following NESHAP is applicable to AEC's proposed new emergency ICE generators.

40 CFR 63, Subpart ZZZZ – National Emission Standards for Hazardous Air Pollutants for Stationary Reciprocating Internal Combustion Engines

This rule applies to stationary reciprocating ICEs located at major or area sources of HAP emissions. A major source is defined as a facility with emissions of 10 tons per year (tpy) or more of a single HAP or 25 tpy or more of any combination of HAPs; an area source is defined as a facility that is not a major source. Because AEC is considered an area source of HAP emissions, in accordance with 40 CFR 63.6590(c)(1), the requirements of 40 CFR 63, Subpart ZZZZ will be met through expected compliance with the requirements of 40 CFR 60, Subpart IIII, as described above.

Rule 1110.2 - Emissions from Gaseous- and Liquid-Fueled Engines

This rule seeks to reduce NO_X, VOC, and CO emissions from stationary and portable engines with a maximum power rating greater than 50 bhp. This rule does not, however, apply to emergency standby engines operating no more than 200 hours per year, as evidenced by a non-resettable engine hour meter or equivalent method, per Rule 1110.2(i)(B). Because operations of each proposed emergency ICE

generator will be limited to no more than 200 hours per year per the permit conditions issued by SCAQMD, the provisions of this rule are not applicable to the proposed project.

Regulation XIII - New Source Review

The proposed installation of two emergency ICE generators results in an emission increase of nonattainment pollutants; therefore, new source review is required. However, as AEC is subject to RECLAIM for NO_X, Regulation XIII is not applicable for NO_X. Key provisions of Regulation XIII are separately addressed below.

Rule 1303 - Requirements

Rule 1303 requires use of best available control technology (BACT), emissions modeling, and emission offsets. However, per Rule 1304(a)(4), emergency equipment operating no more than 200 hours per year, as evidenced by a non-resettable engine hour meter or equivalent method, are exempt from the modeling and offset requirements of Rule 1303(b)(1) and (b)(2). Therefore, only the BACT requirements are addressed below.

Additional review under Rule 1303(b)(5), including an alternative analysis, demonstration of statewide compliance, and protection of visibility, is not required for the proposed project as the annual and daily emission increases are less than the major modification thresholds specified in Rule 1302(r), as presented in Table 3.1-7 below.

Table 3.1-7. Comparison to Rule 1302(r) Major Modification Thresholds

Pollutant	Major Modification Threshold	Project Increases	Thresholds Exceeded?
CO	50 tpy	0.02 tpy	N
VOC	1 lb/day	0.98 lb/day ^a	N
PM ₁₀ /PM _{2.5}	15 tpy	0.0004 tpy	N
SO _x	40 tpy	0.0006 tpy	N

Note:

Best Available Control Technology. In accordance with Rule 1303(a), BACT is required for new and modified equipment. Based on a review of Part B, Section I of SCAQMD's *BACT Guidelines*, ¹ BACT for a similarly-sized CI diesel-fired emergency engine is a certified Tier 2 engine with a CARB-verified DPF to reduce the maximum daily potential to emit (PTE) of PM₁₀ and PM_{2.5} to less than 1 pound per day. The proposed emergency generators meet the required emission standards; therefore, BACT is satisfied.

Rule 1325 - Federal PM_{2.5} New Source Review Program

Rule 1325 applies to any new major polluting facility, major modifications to a major polluting facility, and any modification to an existing facility that would constitute a major polluting facility in and of itself that will emit PM_{2.5} or its precursors (NO_X, SO₂, VOC, and ammonia). Rule 1325(b)(4) defines a major polluting facility as a facility located in a federal nonattainment area with a PTE greater than 70 tpy of PM_{2.5} or any of its precursors. A major modification is any change resulting in a significant emissions increase (40 tpy of NO_X, SO₂, VOC, or ammonia or 10 tpy of PM_{2.5}).

As shown in Table 3.1-3, the highest increase in criteria pollutant emissions is expected to be less than 1 tpy. As such, the proposed installation does not result in a significant emissions increase of $PM_{2.5}$ or its precursors and is not subject to $PM_{2.5}$ new source review under Rule 1325.

^a Conservatively presented as the maximum daily emissions increase.

¹ Available online at http://www.aqmd.gov/home/permits/bact/quidelines/i---scagmd-laer-bact#section!.

Rule 1401 - New Source Review for Air Toxics

Per Rule 1401(g)(1)(F), emergency ICEs that are exempted under SCAQMD Rule 1304 are not required to comply with the requirements of Rule 1401. As previously described, these emergency ICE generators will meet the exemption criteria of Rule 1304(a)(4); therefore, compliance with Rule 1401 is not required.

Rule 1470 – Requirements for Stationary Diesel-Fueled Internal Combustion and Other Compression Ignition Engines

This rule applies to any stationary CI engine with a maximum power rating of greater than 50 bhp. The rule requires the following for new emergency engines with a maximum power rating of greater than 750 bhp and located more than 500 feet from a school or sensitive receptor:

- Use CARB low-sulfur diesel fuel
- Operate no more than 50 hours per year for maintenance and testing
- Use a certified CI engine that emits:
 - DPM at a rate less than or equal to 0.20 grams per kilowatt-hour (g/kWh; 0.15 grams per horsepower-hour [g/hp-hr])
 - Non-methane hydrocarbons (NMHC) + NOX at a rate less than or equal to 6.4 g/kWh (4.8 g/hp-hr)
 - CO at a rate less than or equal to 3.5 g/kWh (2.6 g/hp-hr)

AES will use low-sulfur diesel fuel and a permit condition that limits annual operation per ICE generator to 50 hours per year for maintenance and testing purposes has been incorporated in the PTC/PTO issued by SCAQMD, as presented in Attachment 3.2. The proposed ICE generators will also comply with the applicable emission standards as Tier 2-certified engines. Therefore, compliance with this rule is expected.

Rule 1472 – Requirements for Facilities with Multiple Stationary Emergency Standby Diesel-Fueled Internal Combustion Engines

This rule strives to reduce DPM emissions from facilities with three or more stationary emergency standby diesel-fired ICEs, each with a maximum power rating greater than 50 bhp. Compliance with this rule is not required because AES does not currently operate any stationary emergency standby diesel-fired ICEs at the AEC and only two applicable emergency ICE generators will be installed for this proposed project.

Regulation XVII - Prevention of Significant Deterioration

The proposed installation of two emergency ICE generators results in an emission increase of attainment pollutants; therefore, PSD review is required for PM_{10} (24-hour NAAQS), CO, NOx, and SOx. The applicable provision of Regulation XVII is addressed below.

Rule 1703 - PSD Analysis

Rule 1703(a)(2) requires BACT for each criteria pollutant for which there is a net emission increase. As described previously, BACT for a similarly-sized CI diesel-fired emergency engine is a certified Tier 2 engine with a CARB-verified DPF. The proposed emergency ICE generators will meet the required emission standards; therefore, BACT is satisfied.

As shown in Table 3.1-3, the highest increase in criteria pollutant emissions is expected to be less than 1 tpy. As such, the increase in PTE does not constitute a significant emissions increase of attainment pollutants, as defined in Rule 1702(s).² The AEC is also not located within 10 kilometers of a Class I area. Therefore, additional evaluation under Rule 1703(a)(3) is not required.

PPS0714221341SAC 3-8

_

² The significant increase thresholds are as follows: 100 tpy for CO, 40 tpy for SO₂ and NO_x, 15 tpy for PM₁₀, and 40 tpy for VOC.

Regulation XX

Regulation XX establishes the requirements for the RECLAIM Program. AEC is a NO $_{\rm X}$ RECLAIM facility. As such, new source review for NO $_{\rm X}$ is addressed under Rule 2005, as described below, rather than under Rule 1303. The Project Owner is expected to continue complying with the NO $_{\rm X}$ monitoring, recordkeeping, and reporting requirements of Rule 2012.

Rule 2005 - New Source Review for RECLAIM

Rule 2005(c)(1)(A) requires BACT for emission increases of NOx. Rule 2005(d) defines an emission increase to occur if a source's post-project maximum hourly PTE is greater than the source's pre-project maximum hourly PTE. Because the proposed installation of two emergency ICE generators will increase the facility's maximum hourly NOx emissions, a BACT analysis is required. As described previously, BACT for a similarly-sized CI diesel-fired emergency engine is a certified Tier 2 engine with a CARB-verified DPF. The proposed emergency ICE generators will meet the required emission standards; therefore, BACT is satisfied.

Rule 2005(c)(1)(B) requires that new or modified source(s) at existing RECLAIM facilities will not exceed nitrogen dioxide (NO₂) ambient air quality standards. However, equipment used exclusively on a standby basis in case of emergency with annual operation limited to 200 hours per year, as evidenced by a non-resettable engine hour meter or equivalent method, is exempt from this requirement per Rule 2005(k)(5). Therefore, modeling is not required for the proposed project.

Rule 2005(c)(2) requires facilities to hold sufficient RECLAIM Trading Credits (RTCs) to offset the initial year of an emissions increase of NOx. The proposed installation of two emergency ICE generators will increase the facility's annual emissions, requiring RTCs to be provided at a 1-to-1 ratio. Assuming 50 hours of operation per year at maximum load (54.3 gallons per hour), the Project Owner must provide 471 pounds of NOx RTCs per generator (942 pounds of NOx RTCs total) for the first year of operation.³

Rule 2005(g) requires additional review of new major polluting facilities and major modifications at major polluting facilities. AEC is considered a major polluting facility, such that a major modification would be triggered if daily emissions of NOx or VOC increased by more than 1 pound. As shown in Table 3.1-3, the proposed installation of two emergency ICE generators will increase daily emissions by more than 1 pound; therefore, the proposed installation does constitute a major modification and additional review under Rule 2005(g) is required, as follows:

- The Project Owner's major stationary sources are in compliance with applicable federal emission limits and standards, as certified by the SCAQMD within the Statement of Basis issued for Application Numbers 636578, 636579, and 636580.
- The requirement for an alternatives analysis under Rule 2005(g)(2) is met by compliance through the California Environmental Quality Act (CEQA), as allowed under Rule 2005(g)(3). Specifically, the approval of this PTA by the CEC satisfies the requirement for an environmental review under Rule 2005(g)(3)(C).
- A protection of visibility analysis under Rule 2005(g)(4) is not required because the net emissions increase associated with the proposed installation does not exceed 40 tpy of NO_X.

Regulation XXX - Title V

As described in Rule 3000(a), the Title V Facility Permit system is the air pollution control permit system implementing the federal Operating Permit Program as required by Title V of the federal Clean Air Act, as amended in 1990, and to implement requirements for GHGs pursuant to 40 CFR 70. Regulation XXX

³ Calculated assuming an emission factor of 173.48 pounds NO_x per 1,000 gallons, as detailed in Section 4.9.3 of Attachment 3.1.

defines the Title V Facility Permit application and issuance procedures under the SCAQMD's jurisdiction, as well as compliance requirements associated with the program.

The proposed installation of two emergency ICE generators is considered a Significant Permit Revision under Rule 3000(b)(31)(I). As such, Rule 3005(f) requires the submittal of a permit revision application with contents as specified in Rule 3003. Pursuant to Rule 3003(j), prior to approval and issuance of the PTC/PTO for this proposed project, SCAQMD submitted a proposed draft permit and associated documents to EPA for a 45-day review period on June 17, 2022, and no comments were received by SCAQMD. In addition, pursuant to Rule 3006, the draft permit for this proposed project was made available by SCAQMD for at least a 30-day public comment period on or about June 21, 2022, and no comments were received from the public.

3.1.3.3 State Regulations

CARB is responsible for actions to protect public health from harmful effects of air pollution in communities in California. In support of this responsibility, CARB has promulgated Airborne Toxic Control Measures (ATCM) for several source categories that are codified in the CCR. Below is an analysis of the CARB ATCM applicable to the proposed installation of two emergency diesel-fired ICE generators at the AEC.

Airborne Toxic Control Measure for Stationary Compression-Ignition Engines

The purpose of this ATCM (Title 17, CCR, Section 93115) is to reduce DPM and criteria pollutant emissions from stationary diesel-fired CI engines with a maximum power rating greater than 50 bhp. The ATCM requires the use of CARB low-sulfur diesel fuel or other low-sulfur fuels (Title 17, CCR, Section 93115.5), as well as the following operational restrictions (Title 17, CCR, Section 93115.6(a)(2)):

"No owner or operator shall operate any new stationary emergency standby diesel-fueled CI engine (>50 bhp) in response to the notification of an impending rotating outage, unless all the following criteria are met:

- (A) The engine's permit to operate allows operation of the engine in anticipation of a rotating outage, or the [SCAQMD] has established a policy or program that authorizes operation of the engine in anticipation of a rotating outage; and
- (B) The Utility Distribution Company has ordered rotating outages in the control area where the engine is located, or has indicated It expects to issue such an order at a specified time; and
- (C) The engine is located in a specific location that is subject to the rotating outage; and
- (D) The engine is operated no more than 30 minutes prior to the time when the Utility Distribution Company officially forecasts a rotating outage in the control area; and
- (E) The engine operation is terminated immediately after the Utility Distribution Company advises that a rotating outage is no longer imminent or in effect."

The ATCM establishes the emission standards identified in Table 3.1-8, below, for new emergency standby CI engines with a maximum power rating of 750 bhp or greater. These emission standards are consistent with those required under 40 CFR 60, Subpart IIII.

Table 3.1-8. ATCM Emission Standards

Pollutant	Emission Standard (g/kWh)	Emission Standard (g/hp-hr)
NMHC + NO _X	6.4	4.8
CO	3.5	2.6
PM ₁₀ /PM _{2.5}	0.2	0.15

Source: Yorke Engineering, LLC. 2022. Applications for Permits to Construct: Two Emergency IC Engines. Table 4-4. April.

Per Title 17, CCR, Section 93115.6(a)(3)(A)(1)(c), new emergency standby CI engines with a maximum power rating greater than 50 bhp may not operate more than 50 hours per year for maintenance and testing purposes. Note that operation for emergency use is not restricted by the ATCM. To monitor hours of use, the engine must also be equipped with a non-resettable hour engine meter with a minimum display capability of 9,999 hours (Title 17, CCR, Section 93115.10(d)). Additional monthly recordkeeping provisions are specified in Title 17, CCR, Section 93115.10(f).

The proposed emergency ICE generators will be operated using CARB low-sulfur diesel fuel and equipped with EPA Tier 2-certified engines guaranteed to meet the ATCM's emission limits. The operating restrictions for emergency use and maintenance and testing, requirements for a non-resettable hour meter, and monthly recordkeeping requirements have been incorporated into the PTC/PTO issued by SCAQMD. The engine records will be maintained at the facility and available for review upon request. Therefore, compliance with this ATCM is expected.

3.1.4 Mitigation Measures

The proposed installation of two emergency ICE generators will not create a significant air quality or GHG impact and will not require additional mitigation measures beyond an increase in RECLAIM NO_X RTCs.

3.1.5 Consistency with LORS

The above analysis demonstrates that installation of two emergency ICE generators will not cause or contribute to the violation of an ambient air quality standard. Therefore, the AEC, as modified, will comply with applicable federal, state, and local air quality LORS.

Additionally, for purposes of demonstrating compliance with CEQA, comparison to the SCAQMD's criteria pollutant and GHG significance thresholds is presented in Table 3.1-9 below. As shown, the emission increases associated with the proposed project do not exceed SCAQMD's significance thresholds, thereby implying less-than-significant air quality and GHG impacts.

	•		
Pollutant	Project Increases	Significance Threshold	Threshold Exceeded?
NO _X	18.84 lb/day	55 lb/day	N
VOC	0.98 lb/day	55 lb/day	N
PM ₁₀	0.014 lb/day	150 lb/day	N
PM _{2.5}	0.014 lb/day	55 lb/day	N
SO _X	0.02 lb/day	150 lb/day	N
CO	0.78 lb/day	550 lb/day	N
CO ₂ e	54.73 MT/year	10,000 MT/year	N

Table 3.1-9. Comparison to SCAQMD Significance Thresholds

Source: South Coast Air Quality Management District (SCAQMD). 2019. South Coast AQMD Air Quality Significance Thresholds. April.

MT = metric ton(s)

Lastly, although the proposed project does constitute a major modification under SCAQMD Rule 2005(g), the requirements for an alternative analysis, demonstration of statewide compliance, and protection of visibility are not applicable, not required, or met through the CEC's CEQA-equivalent licensing process, as described in Section 3.1.3.2.

3.1.6 Conditions of Certification

The proposed installation will require new COCs related to air quality. The Project Owner expects that the permit conditions in the PTC/PTO issued by SCAQMD will be incorporated as part of the new Air Quality COCs.

3.2 Biological Resources

3.2.1 Environmental Setting

This PTA does not require changes to the biological resources setting described in the Final Decision and subsequent amendments.

3.2.2 Environmental Consequence

The proposed installation of two emergency diesel-fired ICE generators will not result in any changes to habitat or physical disturbance of special-status species, natural or cropland vegetation, soils, wetlands, vernal pools or vernal swales; interfere with wildlife or aquatic species movement; or conflict with any local policies/ordinances or any approved/adopted conservation plans.

The proposed installation will, however, increase the AEC's NO_X PTE above the licensed annual emissions of 153.08 tpy by less than 0.5 percent.⁴ This minimal increase in NO_X emissions has the potential to minimally increase the already less-than-significant nitrogen deposition impacts analyzed during licensing. During licensing, CEC staff noted that the air dispersion modeling performed to predict AEC's nitrogen deposition was likely an overprediction of the actual nitrogen deposition by as much as 10-fold and, therefore, was not expected to approach the critical nitrogen deposition levels for nearby sensitive habitats. Staff also concluded that the project area's nitrogen emissions inventory and baseline nitrogen deposition levels have decreased by more than 50 percent since the reporting of nitrogen deposition levels in $2002.^5$ Based on the conservative nature of the nitrogen deposition analysis, the proposed increase in AEC's NO_X emissions is not expected to alter or undermine the conclusions reached by the CEC staff in the Final Decision and subsequent amendments. Therefore, the modified project is expected to result in less-than-significant impacts to biological resources.

3.2.3 Mitigation Measures

The proposed installation will not create a significant biological resources impact and will not require additional mitigation measures.

3.2.4 Consistency with LORS

The modified project conforms to applicable LORS related to biological resources.

3.2.5 Conditions of Certification

The proposed installation does not require changes to the COCs for biological resources.

3.3 Cultural Resources

3.3.1 Environmental Setting

This PTA does not require changes to the cultural resources setting described in the Final Decision and subsequent amendments.

⁴ California Energy Commission (CEC). 2021. *Staff Analysis of Petition to Amend the Commission Decision*. May. Page 29, Air Quality Table 13.

⁵ California Energy Commission (CEC). 2016. *Final Staff Assessment, Part 1 for the Alamitos Energy Center (AEC)*. September. CEC-700-2016-004-FSA-PT1, Pages 4.2-34 to 4.2-37.

3.3.2 Environmental Consequences

The proposed installation will require only minor earth-moving/excavations for the foundation installation within previously disturbed soils and is not, therefore, expected to impact native soils. Additionally, the proposed installation of equipment within the CCGT power block does not materially alter the physical appearance of the project, which could potentially impact nearby historic properties. Therefore, no impacts to cultural resources are expected.

3.3.3 Mitigation Measures

No cultural resources impacts are expected from the proposed installation. Therefore, no additional mitigation measures are required.

3.3.4 Consistency with LORS

The modified project conforms to applicable LORS related to cultural resources.

3.3.5 Conditions of Certification

The proposed installation does not require changes to the COCs for cultural resources.

3.4 Energy and Energy Resources

3.4.1 Environmental Setting

This PTA proposes to secure the available energy resources in the project area by maintaining CCGT power block operations in the event of loss of grid power.

3.4.2 Environmental Consequences

The proposed installation will not result in potentially significant environmental impacts due to the wasteful, inefficient, or unnecessary consumption of energy resources. The AEC only operates when called on by the balancing authority, after preferred energy resources have been exhausted, and installation of two emergency diesel-fired ICE generators will maintain AEC's availability to operate in the event of loss of grid power. Furthermore, the potential increase in AEC's operational emissions would not conflict with or obstruct state or local planning efforts for the implementation of renewable energy or energy efficiency projects. Therefore, no impacts to energy or energy resources are expected.

3.4.3 Mitigation Measures

No energy or energy resources impacts are expected from the proposed modification. Therefore, no additional mitigation measures are required.

3.4.4 Consistency with LORS

The modified project conforms to applicable LORS related to energy and energy resources.

3.4.5 Conditions of Certification

The Final Decision and subsequent amendments did not include COCs for energy or energy resources and, as impacts are considered less than significant, none are required.

3.5 Geological and Paleontological Resources

3.5.1 Environmental Setting

This PTA does not require changes to the geological and paleontological resources setting described in the Final Decision and subsequent amendments.

3.5.2 Environmental Consequences

The proposed installation will require only minor ground disturbance/excavations for the foundation installation within previously disturbed soil and no additional geologic resources or geologic hazards have been identified in the project area. Therefore, no impacts to geological and paleontological resources are expected.

3.5.3 Mitigation Measures

No geological and paleontological resources impacts are expected from the proposed installation. Therefore, no additional mitigation measures are required.

3.5.4 Consistency with LORS

The modified project conforms to applicable LORS related to geological and paleontological resources.

3.5.5 Conditions of Certification

The proposed modification does not require changes to the COCs for geological and paleontological resources.

3.6 Hazardous Materials Management

3.6.1 Environmental Setting

This PTA does not require changes to the hazardous materials management setting described in the Final Decision and subsequent amendments.

3.6.2 Environmental Consequences

The proposed installation of two emergency diesel-fired ICE generators will require the storage of additional diesel onsite than was assumed during licensing of the AEC. As diesel fuel and other hazardous materials (petroleum products) are routinely handled, used, and stored onsite, the addition of two emergency diesel-fired ICE generators does not introduce a new or unique hazardous material to the AEC site. Therefore, the increase in volume of diesel fuel storage does not result in any greater risk to the public or environment than already established in the Final Decision and subsequent amendments. Furthermore, continued implementation of existing COCs HAZ-1, HAZ-2, HAZ-3, and HAZ-6 will reduce any impacts to less-than-significant levels. Therefore, no impacts from hazardous materials management are expected.

3.6.3 Mitigation Measures

No hazardous materials management impacts are expected from the proposed installation. Therefore, no additional mitigation measures are required.

3.6.4 Consistency with LORS

The modified project conforms to applicable LORS related to hazardous materials management.

3.6.5 Conditions of Certification

The proposed installation does not require changes to the COCs for hazardous materials management.

3.7 Land Use

3.7.1 Environmental Setting

This PTA does not require changes to the land use setting described in the Final Decision and subsequent amendments.

3.7.2 Environmental Consequences

The proposed installation does not physically divide an established community. The project change is consistent with existing land uses in the project vicinity, the policy for consistent land use designation/zoning district, and other applicable policies. Therefore, no impacts to land use are expected.

3.7.3 Mitigation Measures

No land use impacts are expected from the proposed installation. Therefore, no additional mitigation measures are required.

3.7.4 Consistency with LORS

The modified project conforms to applicable LORS related to land use.

3.7.5 Conditions of Certification

The Final Decision and subsequent amendments did not include COCs for land use and, as impacts are not expected, none are required.

3.8 Noise and Vibration

3.8.1 Environmental Setting

This PTA does not require changes to the noise and vibration setting described in the Final Decision and subsequent amendments.

3.8.2 Environmental Consequences

The proposed installation will not increase noise or vibration-producing activities at the site beyond those analyzed during licensing of the AEC. Therefore, the proposed installation will not alter the noise or vibration impacts of the project.

3.8.3 Mitigation Measures

The proposed installation will not create a significant noise and vibration impact and will not require additional mitigation measures.

3.8.4 Consistency with LORS

The modified project conforms to applicable LORS related to noise and vibration.

3.8.5 Conditions of Certification

The proposed installation does not require changes to the COCs for noise and vibration.

3.9 Public Health

3.9.1 Environmental Setting

This PTA does not require changes to the public health setting described in the Final Decision and subsequent amendments.

3.9.2 Environmental Consequences

The proposed installation of two emergency diesel-fired ICE generators will increase onsite diesel fuel consumption, which will increase DPM emissions. Table 3.9-1 presents hourly and annual emissions for the ICE generators, assuming Tier 2 engine standards with an add-on DPF to reduce emissions by at least 85 percent.

Table 3.9-1. DPM Emissions for Emergency ICE Generators

	Uncontrolled Emission Factor	DPM Emissions	
Source	(g/hp-hr)	(lb/hr)	(lb/year)
Per ICE Generator	0.02	0.007	0.37
Total (2) Generators	0.02	0.014	0.74

Source: Yorke Engineering, LLC. 2022. Applications for Permits to Construct: Two Emergency IC Engines. Table 2-3. April.

SCAQMD Rule 1401 establishes allowable limits for MICR, cancer burden, chronic hazard index (HI), and acute HI for new permit units emitting any of the toxic air contaminants (TACs) specified in Rule 1401, Table 1, including DPM. However, per SCAQMD Rule 1401(g)(1)(F), emergency ICEs that are exempted under SCAQMD Rule 1304 are not required to determine associated health risks. Because AES is permitting these ICE generators as emergency units only, a determination of health risk is not required, and public health impacts associated with their operation are expected to be less than significant.

To support this conclusion, a Rule 1401 Tier 2 Screening Risk Assessment was conducted assuming a generator operating schedule of 1 hour per day, 1 day per week, and 50 weeks per year for maintenance and testing purposes. As shown in Appendix D of Attachment 3.1, the proposed project passes the assessment, indicating that installation of the two emergency ICE generators will not result in an increase in MICR greater than or equal to 1 in 1 million or a chronic HI greater than 1 at any residential or worker receptor.

3.9.3 Mitigation Measures

The proposed installation will result in less-than-significant impacts on public health. Therefore, no additional mitigation measures are required.

3.9.4 Consistency with LORS

The modified project conforms to applicable LORS related to public health.

Additionally, as demonstrated through the Rule 1401 Tier 2 Screening Risk Assessment results presented in Appendix D of Attachment 3.1, the increase in emissions resulting from installation of the two

emergency ICE generators will not cause a MICR or chronic HI greater than the significance thresholds for purposes of complying with CEQA.

3.9.5 Conditions of Certification

The Final Decision and subsequent amendments did not include COCs for public health and, as impacts are considered less than significant, none are required.

3.10 Socioeconomics

3.10.1 Environmental Setting

This PTA does not require changes to the socioeconomic setting described in the Final Decision and subsequent amendments.

3.10.2 Environmental Consequences

The proposed installation of two emergency diesel-fired ICE generators will not alter the basis of the CEC's determination that AEC will not have a significant impact on socioeconomics. Therefore, no significant socioeconomics impacts are expected.

3.10.3 Mitigation Measures

No socioeconomics impacts are expected from the proposed installation. Therefore, no additional mitigation measures are required.

3.10.4 Consistency with LORS

The modified project conforms to applicable LORS related to socioeconomics.

3.10.5 Conditions of Certification

The proposed installation does not require changes to the COCs for socioeconomics.

3.11 Soil and Water Resources

3.11.1 Environmental Setting

This PTA does not require changes to the soil and water resources setting described in the Final Decision and subsequent amendments.

3.11.2 Environmental Consequences

The proposed installation will require only minor ground disturbance/excavations for the foundation installation within previously disturbed soil, occurs entirely within the developed project site, and will not result in an increase in water consumption or discharge. Therefore, no impacts to soil or water resources are expected.

3.11.3 Mitigation Measures

No soil and water resources impacts are expected from the proposed installation. Therefore, no additional mitigation measures are required.

3.11.4 Consistency with LORS

The modified project conforms to applicable LORS related to soil and water resources.

3.11.5 Conditions of Certification

The proposed installation does not require changes to the COCs for soil and water resources.

3.12 Traffic and Transportation

3.12.1 Environmental Setting

This PTA does not require changes to the traffic and transportation setting described in the Final Decision and subsequent amendments.

3.12.2 Environmental Consequences

The proposed installation of two emergency diesel-fired ICE generators may require 1 to 2 additional diesel deliveries per year. This increase in truck deliveries to the site does not result in a material increase in traffic in the project area. Therefore, no significant impacts to traffic or transportation are expected.

3.12.3 Mitigation Measures

The proposed installation will not create a significant traffic and transportation impact and will not require additional mitigation measures.

3.12.4 Consistency with LORS

The modified project conforms to applicable LORS related to traffic and transportation.

3.12.5 Conditions of Certification

The proposed installation does not require changes to the COCs for traffic and transportation.

3.13 Visual Resources

3.13.1 Environmental Setting

This PTA does not require changes to the visual resources setting described in the Final Decision and subsequent amendments.

3.13.2 Environmental Consequences

The proposed installation of two emergency diesel-fired ICE generators within the existing CCGT power block will not materially alter the physical appearance of the project. The operation of the ICE generators will not create a visible plume. Therefore, no impacts to visual resources are expected.

3.13.3 Mitigation Measures

No visual resources impacts are expected from the proposed installation. Therefore, no additional mitigation measures are required.

3.13.4 Consistency with LORS

The modified project conforms to applicable LORS related to visual resources.

3.13.5 Conditions of Certification

The proposed installation does not require changes to the COCs for visual resources.

3.14 Waste Management

3.14.1 Environmental Setting

This PTA does not require changes to the waste management setting described in the Final Decision and subsequent amendments.

3.14.2 Environmental Consequences

The proposed installation will not result in an increase in waste generation at the site. Therefore, no impacts to waste management are expected.

3.14.3 Mitigation Measures

No waste management impacts are expected from the proposed installation. Therefore, no additional mitigation measures are required.

3.14.4 Consistency with LORS

The modified project conforms to applicable LORS related to waste management.

3.14.5 Conditions of Certification

The proposed installation does not require changes to the COCs for waste management.

3.15 Wildfire

3.15.1 Environmental Setting

The AEC site is not located in or near a State Responsibility Area or a very high Fire Hazard Severity Zone.

3.15.2 Environmental Consequences

The proposed installation of two emergency diesel-fired ICE generators will not substantially impair an adopted emergency response/evacuation plan, expose project occupants to pollution concentrations from a wildfire, require installation or maintenance of associated infrastructure that may exacerbate fire risk, or expose people or structures to significant risks due to flooding or landslides.

3.15.3 Mitigation Measures

No wildfire impacts are expected from the proposed installation. Therefore, no additional mitigation measures are required.

3.15.4 Consistency with LORS

The modified project conforms to applicable LORS related to wildfire.

3.15.5 Conditions of Certification

The Final Decision and subsequent amendments did not include COCs for wildfire and, as no impacts are expected, none are required.

3.16 Worker Safety and Fire Protection

3.16.1 Environmental Setting

This PTA does not require changes to the worker safety and fire protection setting described in the Final Decision and subsequent amendments.

3.16.2 Environmental Consequences

The proposed installation will neither increase workers' exposure to health and safety hazards nor negatively impact the availability and adequacy of fire protection and emergency response services. Therefore, no impacts to worker safety and fire protection are expected.

3.16.3 Mitigation Measures

No worker safety and fire protection impacts are expected from the proposed installation. Therefore, no additional mitigation measures are required.

3.16.4 Consistency with LORS

The modified project conforms to applicable LORS related to worker safety and fire protection.

3.16.5 Conditions of Certification

The proposed installation does not require changes to the COCs for worker safety and fire protection.

4. Potential Effects on the Public

This section discusses the potential effects on the public that may result from the modification proposed in this PTA, in accordance with CEC Siting Regulations (Title 20, CCR, Section 1769(a)(1)(F)).

With implementation of the proposed change, the project would have no adverse effect on the public. As previously mentioned, the operation of AEC's two new emergency diesel-fired ICE generators will result in an increase in maximum potential air emissions; however, the potential impacts associated with this increase in emissions will be reduced to less-than-significant levels by surrendering additional NO_X RTCs. Amending the air quality COCs does not adversely affect the public because the facility will still adhere to the conditions in the project's Title V Facility Permit, as well as all other COCs contained in the amended CEC license. The modifications will occur entirely onsite, and air quality and public health impacts are not expected to result in unmitigated significant impacts on the public. Therefore, no significant adverse effects on the public will occur because of the project change proposed in this PTA.

5. List of Property Owners

In accordance with the CEC Siting Regulations (Title 20, CCR, Section 1769(a)(1)(G)), a list of current assessor's parcel numbers and owners' names and addresses for all parcels within 500 feet of any affected project linears and 1,000 feet of the project site will be provided under separate cover. Since the proposed change does not affect any project linears, only the list of parcel owners within 1,000 feet of the project site will be provided.

6. Potential Effects on Property Owners, the Public, and Parties in the Proceeding

This section addresses potential effects of the project change proposed in this PTA on nearby property owners, the public, and parties in the application proceeding, in accordance with CEC Siting Regulations (Title 20, CCR, Section 1769(a)(1)(H)).

As set forth in Section 3, the proposed installation of two emergency diesel-fired ICE generators will not result in any potentially significant impacts and the project will remain in compliance with all applicable LORS. The project, as modified, will not differ significantly in potential effects on adjacent land owners, compared with the project as certified. The project, therefore, would have no adverse effects on nearby property owners, the public, or other parties in the application proceeding.

7. Potentially Applicable CEQA Exemptions

This section includes a discussion of any exemptions from CEQA, commencing with Section 21000 of the Public Resources Code, that the Project Owner believes may apply to approval of the proposed change. Given the operational changes proposed, the CEQA exemption for Air Quality Permits (Title 14, CCR, Section 15281) would not apply in this case, and no other exemptions appear to be applicable.

PPS0714221341SAC 7-1

Attachment 3.1 AEC Air Permit Application

SCAQMD Permit Processing Fees Portal

Hide Tooltip

Fee Sheet

Below are the permit fees calculated based on the information entered. Click the "Print" button to print the Fee Sheet for your records.

•	
Print	Restart
Permit Unit	
IC Engine, Emergency, (> 500 HP)	\$3,859.15
IC Engine, Emergency, (> 500 HP) (1 Identical)	\$1,929.58
Expedited Processing Fee	\$2,894.37
Facility Permit Revision Fee	
Administrative Permit Revision Fee	\$2,853.99
Summary	
Permit Fees	\$5,788.73
Expedited Processing Fees	\$2,894.37
Higher Fees	\$0.00
Small Business Discount	\$0.00
Administrative Permit Revision Fee	\$2,853.99
Total:	\$11,537.09

Back

Generate Voucher

AES Alamitos, LLC

690 N Studebaker Rd Long Beach, CA 90803

SCAQMD Facility ID: 115394

April 2022

Prepared by:



www.YorkeEngr.com

Office Locations:
Los Angeles, Orange County,
Riverside, Ventura, San Diego, Fresno, Merced,
Bakersfield, Berkeley, San Francisco

Tel: (949) 248-8490 Fax: (949) 248-8499

Copyright ©2022, Yorke Engineering, LLC

Application for Permits to Construct: Two Emergency IC Engines

Prepared for:

AES Alamitos, LLC 690 N Studebaker Road Long Beach, CA 90803

SCAQMD Facility ID: 115394

April 2022

Table of Contents

1.0	INTRODUCTION	1
1.	1 Facility Contact Information	1
1.2		
1		
1.4		
2.0	PROJECT DESCRIPTION	7
2.	1 Equipment Description	7
2.2		
3.0	EMISSIONS	8
3.	1 Criteria Pollutant Emissions.	8
3.2		
3		
4.0	RULE COMPLIANCE EVALUATION	11
4.	1 Regulation II – Permits	11
	4.1.1 Rule 212, Standards for Approving Permits and Issuing Public Notice	
4.2		
	4.2.1 Rule 301, Permit Fees	12
4.	3 Regulation IV – Prohibitions	
	4.3.1 Rule 401, Visible Emissions	
	4.3.2 Rule 402, Nuisance	
	4.3.3 Rule 404, Particulate Matter Concentration	
	4.3.4 Rule 431.2, Sulfur Content of Liquid Fuels	
4.4	4 Regulation IX – Standards of Performance for New Stationary Sources	12
	4.4.1 40 CFR Part 60, Subpart IIII – Standards of Performance for Stationary	1.0
	Compression-Ignition Internal Combustion Engines	
4.:	\mathcal{E}	
	4.5.1 40 CFR Part 63, Subpart ZZZZ – National Emission Standard for Hazardous A	
4.0	Pollutants for Stationary Reciprocating Internal Combustion Engines	
4.	4.6.1 Rule 1110.2, Emissions from Gaseous and Liquid-Fueled Engines	
1	7 Regulation XIII – New Source Review; Rule 1303, Requirements	<i>13</i> 1 <i>1</i>
т.	4.7.1 Best Available Control Technology	
	4.7.2 Modeling and Offsets	
4.3	8 Regulation XIV – Toxics and Other Non-Criteria Pollutants	
•••	4.8.1 Rule 1401, New Source Review for Air Toxics	
	4.8.2 Rule 1470, Requirements for Stationary Diesel-Fueled Internal Combustion as	
	Other Compression Ignition Engines	
	4.8.3 Rule 1472, Requirements for Facilities with Multiple Stationary Emergency	,
	Standby Diesel Fueled Internal Combustion Engines	15
4.9	•	
	4.9.1 Best Available Control Technology (BACT)	15

4.9	0.2	Modeling	.15
		Offsets	
		ulation XXX – Title V Permits	
	_	porne Toxic Control Measure for Stationary Compression-Ignition Engines	

Table of Appendices

APPENDIX A – SCAQMD APPLICATION FORMS

APPENDIX B – EQUIPMENT SPECIFICATIONS

APPENDIX C – EMISSION CALCULATIONS

APPENDIX D - RULE 1401 TIER II SCREENING RISK ASSESSMENT

List of Tables

Application for Permits to Construct: Two Emergency IC Engines

1.0 INTRODUCTION

AES Alamitos, LLC (AES) is submitting this application requesting Permits to Construct (PTC) for two 1,112 brake horsepower (bhp) emergency diesel-fired internal combustion engine (ICE) generators that are proposed to be installed in the combine cycle gas turbine (CCGT) power block. These two emergency ICE generators will be used to provide emergency power supply to critical plant equipment, which is required to maintain operations during the gas turbine shutdown periods, in the event of loss of grid power to prevent forced plant outage and equipment damage. The engines of the two emergency ICE generators are Model Year 2022 Perkins 2806C-E18TTAG7, which is certified by the United States Environmental Protection Agency (U.S. EPA) as a Tier 2 engine (Family Name: NCPXL18.1NYS). Each engine will be equipped with a Miratech Model LTRV24-21-10-R1 Level 3 Plus Diesel Particulate Filter (DPF).

The emergency ICEs will emit nitrogen oxides (NO_x), sulfur oxides (SO_x), carbon monoxide (SO_x), volatile organic compounds (SO_x), respirable particulate matter (SO_x), and diesel particulate matter (SO_x) from the combustion of diesel fuel. The emergency generators will not be located within 1,000 feet of a school or other sensitive receptor and are expected to comply with all applicable rules and regulations.

This PTC application package contains the information necessary for the South Coast Air Quality Management District (SCAQMD) to process and approve the application, including facility information (Section 1.0), equipment and process descriptions (Section 2.0), emission calculations (Section 3.0), and rule applicability and compliance determinations (Section 4.0). Application forms and emission calculations are provided in the appendices. AES is requesting Expedited Permit Processing for this application.

1.1 Facility Contact Information

The applicant contact information is shown below.

Table 1-1: Facility Contact Information

Applicant's Name:	AES Alamitos, LLC	
Applicant Contact Information:	Charlene He Environmental Manager (562)493-7835 charlene.he@aes.com	
Facility ID:	115394	
Mailing Address:	690 N. Studebaker Rd. Long Beach, CA 90803	
Equipment Location:	690 N. Studebaker Rd. Long Beach, CA 90803	

1.2 Facility Location

The AES Alamitos facility is located at 690 North Studebaker Road in the City of Long Beach, California. The two emergency ICE generators are proposed to be located within the CCGT power block within the facility. An aerial view of the facility and surrounding areas is provided as Figure 1-1, and the proposed locations of the two emergency ICEs are provided in Figure 1-2. There are no schools within 1,000 feet of the proposed project location. The nearest school is Charles F Kettering Elementary School, which is located approximately 2,170 feet northwest of the west emergency ICE and 2,181 feet northwest of the east emergency ICE. The nearest commercial receptor is located 1,080 feet east of the west emergency ICE and 820 feet east of the east emergency ICE. The nearest residential receptor is located 1,257 feet west of the west emergency ICE and 1,500 feet west of the east emergency ICE. The distance between each ICE and the outer boundary of Charles F Kettering Elementary School is provided in Figures 1-3 and 1-4 to demonstrate that the engine exhaust stacks will not be within 1,000 feet of the outer boundary of the school.

1.3 Forms Included with Application

The forms included with this application are listed in Table 1-2. The forms are provided in Appendix A.

Table 1-2: SCAQMD	Forms Accompa	nying This A	Application

Form	Title	Device	
400-A	Application Form for Permit or Plan Approval	West Emergency Engine	
400-A	Application Form for Permit or Plan Approval	East Emergency Engine	
400-E-13a	Emergency Internal Combustion Engine	West Emergency Engine	
400-E-13a	Emergency Internal Combustion Engine	East Emergency Engine	
400-PS	Plot Plan and Stack Information	ation West Emergency Engine	
400-PS	Plot Plan and Stack Information	ormation East Emergency Engine	
400-A	Application Form for Permit or Plan Approval (Title V Amendment) Project		
400-CEQA	California Environmental Quality Act (CEQA) Applicability	Project	
500-A2	Title V Application Certification	Project	
500-C1	Title V Compliance Status Report	Project	
400-XPP	Expedited Permit Processing Project		

1.4 Application Preparation

This permit application was prepared by Collin Lundquist with peer review by James Adams of Yorke Engineering, LLC (Yorke). If there are technical questions regarding this application, please see the contact information in Table 1-3.

Table 1-3: Application Preparers

	Collin Lundquist	James Adams, CPP #M6901
Company:	Yorke Engineering, LLC	Yorke Engineering, LLC
Phone:	(949) 248-8490	(949) 248-8490
Cellular:	(949) 573-5122	(949) 573-7924
E-mail:	CLundquist@YorkeEngr.com	JAdams@YorkeEngr.com

Figure 1-1: Aerial View of the AES Facility and Surrounding Area



Figure 1-2: Proposed Locations of the Two Emergency ICEs



Measure the distance between two points on the ground Map Length: 2,170.41 Feet 2,170.41 Heading: 327.81 degrees ✓ Mouse Navigation Los Cerritos Channel

Figure 1-3: Distance Between the West Emergency ICE and the School Boundary

Path Polygon Circle 3D path 3D polygon leasure the distance between two points on the ground 2,181.55 Feet 2,181.55 320.21 degrees **✓** Mouse Navigation Los Cerritos Chann

Figure 1-4: Distance Between the East Emergency ICE and the School Boundary

2.0 PROJECT DESCRIPTION

2.1 Equipment Description

AES Alamitos is requesting PTCs for two emergency ICE generators to provide power to the CCGT power block in the event of an emergency resulting in a loss of grid power. The engines are Model Year 2022 Perkins 2806C-E18TTAG7 and diesel-fired, with a maximum rating of 1,112 bhp. The engines are Tier 2 U.S. EPA certified and will be equipped with an add-on Diesel Particulate Filter (DPF) to further reduce PM₁₀ emissions. The DPF is a California Air Resources Board (CARB)-verified Miratech filter, model LTRV24-21-10-R1. Equipment and DPF specifications are provided in Table 2-1, Table 2-2, and Appendix B.

Table 2-1: Engine Specifications

Parameter	Value
Manufacturer	Perkins
Model	2806C-E18TTAG7
Engine Family Name	NCPXL18.1NYS
Engine Output	1112 BHP
Tier	2

Table 2-2: DPF Specifications

Parameter	Value
Manufacturer	Miratech
Model	LTRV24-21-10-R1
Control Efficiency	85%

2.2 Operating Schedule

The AES Alamitos power plant operates 24 hours per day, 7 days per week. AES will only operate the emergency engines for backup and emergency uses. In order to maintain readiness, the emergency engines may be run periodically for maintenance and testing. In accordance with the SCAQMD requirements, operation of the engines will be limited to 50 hours per year for maintenance and testing and a maximum of 200 hours per year total operation (which includes maintenance and testing). This operating schedule is summarized in Table 2-2. Table 2-2 also shows the hours per day and hours per month that the daily and 30-day average emissions are calculated from. The hours per day and hours per month are provided for calculation purposes only.

Table 2-3: Engine Operating Schedule

Period	Maintenance and Testing	Total Operation
Hours/Day (For Calculation Purposes Only)	1	N/A
Hours/Month (For Calculation Purposes Only)	4.2	N/A
Hours/Year	50	200

3.0 EMISSIONS

3.1 Criteria Pollutant Emissions

The emergency ICEs will combust low-sulfur diesel fuel; hence, emissions of VOCs, NO_x , CO, PM, and SO_x will be generated during its operation. The "Statement of Exhaust Emissions 2022 Perkins Diesel Fueled Generator" document provided in Appendix B was used for estimating emissions (100% load rather than the weighted emissions). The Tier 2 emission rate for Non-Methane Hydrocarbons (NMHC) + NO_x is assumed to consist of 5% VOCs and 95% NO_x . So emissions are estimated based on a fuel sulfur content of 15 parts per million by weight (ppmw). Additionally, each ICE will be equipped with a DPF, reducing PM emissions by 85%. Uncontrolled emission factors for the engine operating on low-sulfur fuel are shown in Table 3-1.

Table 3-1: Uncontrolled Emission Factors

Pollutant	Emission Factor (g/Hp-hr)
VOCs	0.20
NO_x	3.84
SO_x	0.005
CO	0.16
PM	0.02

Sample calculations are shown below for NO_x emissions for the emergency generators. There are no add-on emission control devices for NO_x , and thus, the uncontrolled and controlled emissions are the same. Emission calculations for the remainder of the pollutants are similar; only the emission factor changes.

Maximum Hourly Uncontrolled (MHU)

$$MHU = 1112 \ BHP \times \frac{3.84 \ g \ NOx}{BHP - hr} \times \frac{1 \ lb}{453.5 \ g} = 9.42 \ \frac{lbs \ NOx}{hour}$$

Maximum Hourly Controlled (MHC)

$$MHC = 1112 \ BHP \times \frac{3.84 \ g \ NOx}{BHP - hr} \times \frac{1 \ lb}{453.5 \ g} = 9.42 \ \frac{lbs \ NOx}{hour}$$

Maximum Daily Uncontrolled (MDU)

$$MDU = MHU * 1 \frac{hr}{day} = 9.42 \frac{lbs NOx}{day}$$

Maximum Daily Controlled (MDC)

$$MDC = MHC * 1 \frac{hr}{day} = 9.42 \frac{lbs NOx}{day}$$

¹ Carl Moyer Program Guidance, Table D-25.

Average Annual (AA)

$$AA = 9.42 \ lbs/hr \ x \ 50 \frac{hrs}{yr} = 470.75 \ \frac{lbs \ NOx}{year}$$

30-Day Average (30DA)

$$30DA = \frac{9.42 \ lbs/hr \ x \ 4.2 \frac{hrs}{mo}}{30 \ day/mo} = 1.32 \ \frac{lbs \ NOx}{day}$$

Tables 3-2 and 3-3 summarize criteria pollutant emissions from the operation of each individual emergency engine and both engines, respectively. Detailed emission calculations are provided in Appendix C.

Table 3-2: Criteria Pollutant Emissions for Each Emergency ICE

Criteria Pollutant	AHU (lb/hr)	AHC (lb/hr)	MHU (lb/hr)	MHC (lb/hr)	MDU (lb/day)	MDC (lb/day)	AA (lb/yr)	30DA (lb/day)
VOCs	0.49	0.49	0.49	0.49	0.49	0.49	24.52	0.07
NO_x	9.42	9.42	9.42	9.42	9.42	9.42	470.75	1.32
SO_x	0.01	0.01	0.01	0.01	0.01	0.01	0.60	0.002
CO	0.39	0.39	0.39	0.39	0.39	0.39	19.61	0.05
PM_{10}	0.05	0.007	0.05	0.007	0.05	0.007	0.368	0.001

Table 3-3: Combined Criteria Pollutant Emissions for Both Emergency ICEs

Criteria Pollutant	AHU (lb/hr)	AHC (lb/hr)	MHU (lb/hr)	MHC (lb/hr)	MDU (lb/day)	MDC (lb/day)	AA (lb/yr)	30DA (lb/day)
VOCs	0.98	0.98	0.98	0.98	0.98	0.98	49.04	0.14
NO_x	18.84	18.84	18.84	18.84	18.84	18.84	941.5	2.64
SO_x	0.02	0.02	0.02	0.02	0.02	0.02	1.20	0.004
CO	0.78	.078	0.78	0.78	0.78	0.78	39.22	0.10
PM_{10}	0.10	0.014	0.10	0.014	0.10	0.014	0.736	0.002

3.2 Toxic Air Contaminant (TAC) Emissions

DPM will be emitted during the operation of the emergency engine. The DPM emission factor is based on Tier 2 engine standards with an add-on DPF to further reduce emissions. The assumed control efficiency of the DPF is 85%. Tables 3-4 and 3-5 summarizes the DPM emission factor and corresponding emissions for each individual emergency engine and the combined emissions of both engines. Emission calculations are provided in Appendix C.

Table 3-4: TAC Emission Factor and Emissions for Each Emergency ICE

Pollutant	CAS Number	Uncontrolled Emission Factor (g/Hp-hr)	MHC (lb/hr)	MAC (lb/yr)
Diesel PM	9901	0.02	0.007	0.37

Table 3-5: TAC Emission Factor and Combined Emissions for Both Emergency ICEs

Pollutant	CAS Number	Uncontrolled Emission Factor (g/Hp-hr)	MHC (lb/hr)	MAC (lb/yr)
Diesel PM	9901	0.02	0.014	0.74

3.3 Greenhouse Gas Emissions

Greenhouse gases (GHGs) are emitted during the operation of the emergency engines. GHG emissions are estimated using diesel GHG emission factors from the Code of Federal Regulations (CFR) Title 40, Section 98, Subpart C, Tables C-1 and C-2 and corresponding global warming potentials (GWPs) from 40 CFR Part 98 Subpart A, Table A-2. Emission factors are listed in kilograms per million British thermal units (kg/MMBtu).

Emissions are calculated using the higher heating value (HHV) of diesel of 19,300 Btu per pound or 0.138 MMBtu per gallon. Fuel usage is based on the engine's maximum fuel flow at 100% load of 54.3 gallons per hour, as stated in the manufacturer's specification. Annual fuel usage assumes an average usage of 50 hours per year, resulting in 2,715 gallons per year.

A sample calculation for carbon dioxide (CO₂) is shown below.

$$E_{CO_2}\left(\frac{kg}{yr}\right) = 2,715 \frac{gal}{yr} \times 0.138 \frac{MMBtu}{gal} \times \frac{73.96 \ kg \ CO_2}{MMBtu} = 27,710.59 \ kg \frac{CO_2}{yr}$$

The emissions are converted into CO₂ equivalents (CO₂e) using the GWPs for each gas. Table 3-6 summarizes the GHG emission factors, GWPs, and emissions of GHGs from each engine. Table 3-7 summarizes the GHG emission factors, GWPs, and emissions of GHGs from both engines.

Table 3-6: GHG Emissions for Each Emergency ICE

GHG	Emission Factor (kg/MMBtu)	Total Emissions (TPY)	Global Warming Potential (unitless)	Emissions of CO ₂ e (TPY)
CO ₂	73.96	30.5	1	30.5
CH ₄	0.003	0.0012	25	0.03
N ₂ O	0.0006	0.0002	298	0.07
Total	_	_	_	30.65

Table 3-7: Combined GHG Emissions for Two Emergency ICEs

GHG	Emission Factor (kg/MMBtu)	Total Emissions (TPY)	Global Warming Potential (unitless)	Emissions of CO ₂ e (TPY)
CO_2	73.96	61.0	1	61.0
CH ₄	0.003	0.0024	25	0.06
N ₂ O	0.0006	0.0004	298	0.14
Total	_	_	_	61.30

4.0 RULE COMPLIANCE EVALUATION

4.1 Regulation II – Permits

4.1.1 Rule 212, Standards for Approving Permits and Issuing Public Notice

Rule 212(c) requires public notice for:

- (c)(1). A project requesting installation of a new source or modification of an existing source, if the source is located within 1,000 feet of the outer boundary of a school; or
- (c)(2). A project resulting in a new or modified facility with on-site emission increases exceeding any of the daily maximums from Rule 212(g); or
- (c)(3). A project requesting installation of a new source or modification of an existing source, if the emission increases result in exposure to Maximum Individual Cancer Risk (MCIR) greater than or equal to the applicable thresholds in paragraph (c)(3)(A), or substances that pose a potential risk of nuisance.

As described in Section 1.2 and shown in Figures 1-3 and 1-4, the proposed project locations are not located within 1,000 feet of the outer boundary of a school. Rule 212(c)(1) does not apply.

Rule 212(g) lists daily maximum emissions increases for criteria pollutants. The project emissions changes from Table 3-3 are compared to the Rule 212(g) thresholds in Table 4-1.

Table 4-1: Rule 21	2(g) Threshold Comp	arison
	D 11 M	

Pollutant	Daily Maximum (lb/day)	Project Changes (lb/day)
NO _x	40	18.84
CO	220	0.78
VOC	30	0.98
SO_x	60	0.02
PM_{10}	30	0.014

As shown in Appendix D, the project passes a Rule 1401 Tier 2 Screening Risk Assessment. The operating schedule has been set to 1 hr/day, 1 day/wk, and 50 wk/yr to calculate 50 hrs/yr for maintenance and testing purposes. Therefore, this project would not result in an increase in MICR greater than or equal to the applicable thresholds in paragraph (c)(3)(A).

The project will not require Rule 212 public notice.

4.2 Regulation III – Fees

4.2.1 Rule 301, Permit Fees

Application fees are summarized in Table 4-2.

Table 4-2: Application Fees

Equipment/Item	Rule 301 Table IA/IB Description	Schedule	Base Fee
Emergency IC Engine	IC Engine, Emergency	B, FY 2019-20	\$3,859.15
Emergency IC Engine	IC Engine, Emergency	B, FY 2019-20	\$1,929.58
RECLAIM & Title V Permit	RECLAIM & Title V Facility Permit Amendment/Revision Fee	301(m)(4)	\$2,853.99
Expedited Permit Processing (50% of Base Permit Fee)			\$2,894.37
	\$11,537.09		

4.3 Regulation IV – Prohibitions

4.3.1 Rule 401, Visible Emissions

The emergency engines are Tier 2 engines that will be fired on low-sulfur diesel fuel. No visible emissions are expected as a result of operation of the emergency engines.

4.3.2 Rule 402, Nuisance

The emergency engines are Tier 2 engines that will be fired on low-sulfur diesel fuel. Nuisance is not expected as a result of operating the emergency engines.

4.3.3 Rule 404, Particulate Matter Concentration

The emergency engines meet Tier 2 engine standards and will be equipped with an add-on DPF. Operation of the engines is not expected to result in PM emissions greater than the applicable concentration listed in Table 404(a). Therefore, compliance with this rule is expected.

4.3.4 Rule 431.2, Sulfur Content of Liquid Fuels

The purpose of this rule is to reduce SO_x emissions from the burning of liquid fuels in stationary equipment requiring a permit to operate. Since the engines will burn low-sulfur diesel, compliance with Rule 431.2 is expected.

4.4 Regulation IX – Standards of Performance for New Stationary Sources

Regulation IX, New Source Performance Standards (NSPS), was adopted by reference to the appropriate section of the CFR. These regulations are periodically updated to reflect actions published in the Federal Register (FR) by the U.S. EPA.

4.4.1 40 CFR Part 60, Subpart IIII – Standards of Performance for Stationary Compression-Ignition Internal Combustion Engines

The provisions of this subpart are applicable to manufacturers, owners, and operators of stationary Compression-Ignition (CI) ICEs. The subpart establishes emission standards for CI ICEs constructed after 2007.

Owners and operators of 2007 model year and later emergency stationary CI ICEs with a displacement of less than 30 liters per cylinder that are not fire pump engines must comply with the emission standards for new non-road CI engines for the same model year and maximum engine power in 40 CFR Part 89.112 and 40 CFR Part 89.113 for all pollutants beginning in model year 2007. Part 89 specifies Tier 2 emission standards for engines constructed after 2006. The Tier 2 engine standards are shown in Table 4-3.

Table 4-3: Tier 2 Emission Standards

Pollutant	Emission Standard (g/kW-hr)	Emission Standard (g/hp-hr)
$NO_x + NMHC$	6.4	4.8
CO	3.5	2.6
PM	0.2	0.15

The proposed emergency engines will be Tier 2 engines; thus, compliance is expected. There are no other federal NSPS applicable to the emergency engines.

4.5 Regulation X – National Emission Standards for Hazardous Air Pollutants

Regulation X, National Emission Standards for Hazardous Air Pollutants (NESHAP), was adopted by reference to Part 61 of the CFR. These regulations are periodically updated to reflect actions published in the FR by the U.S. EPA. There are no Part 61 requirements applicable to the emergency engines.

4.5.1 40 CFR Part 63, Subpart ZZZZ – National Emission Standard for Hazardous Air Pollutants for Stationary Reciprocating Internal Combustion Engines

New stationary engines located at an area source of hazardous air pollutant (HAP) emissions comply with Subpart ZZZZ by complying with the applicable requirements of Subpart IIII or Subpart JJJJ. No further requirements apply for such engines under this part.

4.6 Regulation XI – Source-Specific Standards

4.6.1 Rule 1110.2, Emissions from Gaseous and Liquid-Fueled Engines

Rule 1110.2 applies to stationary and portable engines rated over 50 bhp and imposes requirements for NO_x, VOCs, and CO, with an exemption from the requirements for emergency engines operated no more than 200 hours per year.

"Emergency standby engines, engines used for fire-fighting and flood control, and any other emergency engines approved by the Executive Officer, which have permit conditions that limit operation to 200 hours or less per year as determined by an elapsed operating time meter, and agricultural emergency standby engines that are exempt from a District permit and operate 200 hours or less per year as determined by an elapsed operating time meter."

Therefore, the engines are exempt from Rule 1110.2.

4.7 Regulation XIII – New Source Review; Rule 1303, Requirements

The Best Available Control Technology (BACT), modeling, and offset requirements of Regulation XIII are addressed in this section.

4.7.1 Best Available Control Technology

Based on a review of SCAQMD BACT Part B Determinations, BACT for a CI diesel-fueled emergency engine is a certified Tier 2 engine with a CARB verified DPF to reduce the maximum daily potential to emit (PTE) of DPM to less than 1 lb per day. The proposed emergency engines meet the required emission standards; therefore, BACT is satisfied.

4.7.2 Modeling and Offsets

Rule 1304 exempts emergency equipment from modeling and offsets provided the source does not operate more than 200 hours per year as evidenced by a non-resettable engine hour meter or equivalent method. AES is proposing a permit condition limiting operations of each engine to no more than 200 hours per year, and each engine will be equipped with a non-resettable hour meter. Therefore, modeling and offsets are not required for this application.

4.8 Regulation XIV – Toxics and Other Non-Criteria Pollutants

4.8.1 Rule 1401, New Source Review for Air Toxics

This rule imposes limits for MICR, cancer burden, and non-cancer Acute and Chronic Hazard Indices (HIA and HIC, respectively) from new permit units, relocations, or modifications to existing permit units which emit the TACs listed in Table I of the rule. The rule establishes allowable risks for permit units requiring new permits pursuant to Rule 201 or 203.

Emergency ICEs that are exempted under Rule 1304 are also exempted from the requirements of this rule.

4.8.2 Rule 1470, Requirements for Stationary Diesel-Fueled Internal Combustion and Other Compression Ignition Engines

This rule applies to any person who owns or operates a stationary CI engine in the SCAQMD with a rated bhp greater than 50, except as provided in subdivision (h). The rule requires the following of new emergency engines that are greater than 750 bhp and are located more than 500 feet from a school or sensitive receptor:

- Use of CARB low-sulfur diesel fuel;
- New stationary emergency standby diesel-fueled engines (>50 bhp) shall not operate more than 50 hours per year for maintenance and testing;
- Use of a certified CI engine that emits DPM at a rate less than or equal to 0.15 g/bhp-hr;
- NMHC + NO_x emissions not to exceed 4.8 g/bhp-hr; and
- CO emissions not to exceed 2.6 g/bhp-hr.

AES will use CARB low-sulfur diesel fuel. AES will accept permit limits enforcing the maintenance and testing limit of 50 hours per year. The proposed engines will comply

with the applicable emission standards for Rule 1470. Therefore, compliance with this rule is expected.

4.8.3 Rule 1472, Requirements for Facilities with Multiple Stationary Emergency Standby Diesel Fueled Internal Combustion Engines

Rule 1472 applies to facilities with three or more stationary diesel emergency ICEs that are above 50 bhp, regulating specific operation and recordkeeping criteria. This rule does not apply to AES Alamitos since the facility does not currently operate any stationary emergency standby diesel-fueled ICEs, and the project only proposes installation of two engines.

4.9 Regulation XX – Regional Clean Air Incentives Market

The Regional Clean Air Incentives Market (RECLAIM) is a market-based incentive program designed to allow facilities flexibility in achieving emission reduction requirements for NO_x and SO_x under the Air Quality Management Plan using methods which include, but are not limited to, add-on controls, equipment modifications, reformulated products, operational changes, shutdowns, and the purchase of excess emission reductions.

Rule 2005 establishes the New Source Review requirements for RECLAIM facilities. Rule 2005 requires that a new or modified source meet BACT, prohibits a new or modified source from causing a violation or making significantly worse an existing violation of the State or national ambient air quality standard at any receptor location in the District for NO₂, and requires that the facility hold sufficient RECLAIM Trading Credits (RTCs) to offset the total facility emissions for the first year of operation at a 1-to-1 ratio.

4.9.1 Best Available Control Technology (BACT)

Based on a review of SCAQMD BACT Part B Determinations, BACT for a CI diesel-fueled emergency engine is a certified Tier 2 engine with a CARB verified DPF to reduce maximum daily PTE of DPM to less than 1 lb per day. The proposed emergency engine meets the required emission standards; therefore, BACT is satisfied.

4.9.2 Modeling

Rule 2005 exempts emergency equipment from modeling provided the source does not operate more than 200 hours per year as evidenced by a non-resettable engine hour meter or equivalent method. AES is proposing a permit condition limiting operations of each engine to no more than 200 hours per year, and each engine will be equipped with a non-resettable hour meter. Therefore, modeling is not required for this application.

4.9.3 *Offsets*

The proposed project will result in a net increase in NO_x emissions on a monthly and annual basis. The facility is expected to secure sufficient RTCs to offset the total facility emissions for the first year of engine operations at a 1-to-1 ratio.

AES proposes to calculate RECLAIM NO_x emissions using an emission factor of 173.48 pounds per 1,000 gallons.²

 $^{^{2}9.42\}frac{lbs}{hr}$ / $\left(54.3\frac{gal}{hr}$ / $1000\right) = 9.42\frac{lbs}{hr}$ / $0.0543\frac{gal}{hr} = 173.48$ lbs per 1000 gallons



4.10 Regulation XXX – Title V Permits

The AES Alamitos facility is a Title V major source facility. An application to modify the Title V permit is included as part of this application.

4.11 Airborne Toxic Control Measure for Stationary Compression-Ignition Engines

The purpose of this Airborne Toxic Control Measure (ATCM) is to reduce DPM and criteria pollutant emissions from stationary diesel-fueled CI engines (California Code of Regulations, Title 17, Section 93115). The ATCM requires the use of CARB low-sulfur diesel fuel or other low-sulfur fuels [Section 93115.5(a)]. The ATCM requires that a new emergency engine have the following operating restrictions [Section 93115.6(a)(2)]:

"No owner or operator shall operate any new stationary emergency standby diesel-fueled Cl engine (>50 bhp) in response to the notification of an impending rotating outage, unless all the following criteria are met:

- (A) the engine's permit to operate allows operation of the engine in anticipation of a rotating outage, or the District has established a policy or program that authorizes operation of the engine in anticipation of a rotating outage; and
- (B) the Utility Distribution Company has ordered rotating outages in the control area where the engine is located, or has indicated it expects to issue such an order at a specified time; and
- (C) the engine is located in a specific location that is subject to the rotating outage; and
- (D) the engine is operated no more than 30 minutes prior to the time when the Utility Distribution Company officially forecasts a rotating outage in the control area; and
- (F) the engine operation is terminated immediately after the Utility Distribution Company advises that a rotating outage is no longer imminent or in effect."

The ATCM establishes the emission standards identified in Table 4-4 for new CI engines with rated power output of equal to or greater than 750 hp [Section 93115.6(a)(3)].

Table 4-4: ATCM Emission Standards

Pollutant	Emission Standard (g/kW-hr)	Emission Standard (g/Hp-hr)
$NO_x + NMHC$	6.4	4.8
CO	3.5	2.6
PM	0.2	0.15

The District may allow in-use stationary emergency standby diesel-fueled CI engines (> 50 bhp) to operate up to 50 hours per year for maintenance and testing purposes if the DPM emission rate is less than or equal to 0.15 g/bhp-hr [Section 93115.6(b)(3)(A)(2)(b)].

A non-resettable hour meter with a minimum display capability of 9,999 hours shall be installed upon engine installation [Section 93115.10(d)].

The proposed emergency IC engines will be operated using CARB low-sulfur diesel fuel. The operating restrictions for emergency use and maintenance and testing will be enforceable via permit conditions. The engines are certified Tier 2 engines that are guaranteed to meet the ATCM emission limits. The requirement for an engine hour meter and compliance with the monthly recordkeeping requirements will also be enforceable through permit conditions. The engine records will be maintained at the facility and available for review upon request. Therefore, compliance with the ATCM of the two proposed emergency IC engines is expected.

APPENDIX A – SCAQMD APPLICATION FORMS

Form	Title	Device
400-A	Application Form for Permit or Plan Approval	West Emergency Engine
400-A	Application Form for Permit or Plan Approval	East Emergency Engine
400-E-13a	Emergency Internal Combustion Engine	West Emergency Engine
400-E-13a	Emergency Internal Combustion Engine	East Emergency Engine
400-PS	Plot Plan and Stack Information	West Emergency Engine
400-PS	Plot Plan and Stack Information	East Emergency Engine
400-A	Application Form for Permit or Plan Approval (Title V Amendment)	Project
400-CEQA	California Environmental Quality Act (CEQA) Applicability	Project
500-A2	Title V Application Certification	Project
500-C1	Title V Compliance Status Report	Project
400-XPP	Expedited Permit Processing	Project

Please note: each exhaust stack will have flapper cap. Flapper caps are not considered capped stacks in AERMOD. We have checked "No" for the question "Rain cap Present?" on the 400-PS forms.

South Coast Air Quality Management District

Form 400-A

Application Form for Permit or Plan Approval

List only one piece of equipment or process per form.

Mail To: SCAQMD P.O. Box 4944 Diamond Bar, CA 91765-0944

> Tel: (909) 396-3385 www.aqmd.gov

Section A - Operator Information			
1. Facility Name (Business Name of Operator to Appear on the Permit):	2. Valid AQMD Facility ID (Available On		
AES Alamitos, LLC	Permit Or Invoice Issued By AQMD):		
3. Owner's Business Name (If different from Business Name of Operator):	115394		
Section B - Equipment Location Address	Section C - Permit Mailing Address		
4. Equipment Location Is: Fixed Location Various Location (For equipment operated at various locations, provide address of initial site.)			
690 N. Studebaker Rd.	690 N. Studebaker Rd.		
Street Address	Address		
Long Beach , CA 90803	Long Beach , CA 90803		
City Zip	City State Zip		
Charlene He Environmental Manager Contact Name Title	Charlene He Environmental Manager Contact Name Title		
(562) 493-7835	(562) 493-7835		
Phone # Ext. Fax #	Phone # Ext. Fax #		
E-Mail: charlene.he@aes.com	E-Mail: charlene.he@aes.com		
Section D - Application Type			
6. The Facility Is: Not In RECLAIM or Title V In RECLAIM	☐ In Title V		
7. Reason for Submitting Application (Select only ONE):			
7a. New Equipment or Process Application: 7c. Equipment or	Process with an Existing/Previous Application or Permit:		
New Construction (Permit to Construct) Administrative	Change		
Equipment On-Site But Not Constructed or Operational Alteration/Mod	P. C. Land Co. Brown		
[12] 2.11.1.1.1.1.1.1.1.1.1.1.1.1.1.1.1.1.1.	ification without Prior Approval *		
C Compliance Plan C Change of Cor	If you checked any of the items in		
	ndition 7c., you MUST provide an existing Permit or Application Number:		
Streamlined Standard Permit Change of Loc			
C Channel of Land	ation without Prior Approval *		
Equipment On	erating with an Expired/Inactive Permit *		
Title V Application of Amendment (Refer to Title V Matrix)			
	pessing Fee and additional Annual Operating Fees (up to 3 full years) may apply (Rule 301(c)(1)(D)(i)).		
	Construction (mm/dd/yyyy): 8c. Estimated Start Date of Operation (mm/dd/yyyy): 05/01/2023		
Description of Equipment or Reason for Compliance Plan (list applicable rule):	10. For Identical equipment, how many additional		
Permit Application for Two Emergency IC Engines (first one)	applications are being submitted with this application? (Form 400-A required for each equipment / process)		
11. Are you a Small Business as per AQMD's Rule 102 definition? (10 employees or less and total gross receipts are \$500,000 or less OR a not-for-profit training center) No Yes	12. Has a Notice of Violation (NOV) or a Notice to Comply (NC) been issued for this equipment? If Yes, provide NOV/NC#: No Yes		
Section E - Facility Business Information			
13. What type of business is being conducted at this equipment location? Generation, Electric Power	14. What is your business primary NAICS Code? (North American Industrial Classification System) 221112		
15. Are there other facilities in the SCAQMD jurisdiction operated by the same operator? No Yes	16. Are there any schools (K-12) within 1000 feet of the facility property line? No Yes		
Section F - Authorization/Signature / Pereby certify that all information con	ntained herein and information submitted with this application are true and correct.		
17. Signature of Responsible Official: 18. Title of Responsib	the Official: 19. I wish to review the permit prior to issuance. (This may cause a delay in the		
20. Print Name: 21. Date:	22 Do you claim confidentiality of		
Weikko Wirta 09/	data? (If Yes, see instructions.) • No Yes		
23. Check List: Authorized Signature/Date Form 400-CEQA			
AQMD USE ONLY APPLICATION TRACKING # CHECK# AMOUNT RECEIVED \$	PAYMENT TRACKING # VALIDATION		
DATE APP DATE APP CLASS BASIC EQUIPMENT CATEGORY REJ I III CONTROL	CODE TEAM ENGINEER REASON/ACTION TAKEN		

South Coast Air Quality Management District

Form 400-A

Application Form for Permit or Plan Approval

List only one piece of equipment or process per form.

Mail To: SCAQMD P.O. Box 4944 Diamond Bar, CA 91765-0944

> Tel: (909) 396-3385 www.agmd.gov

Section A - Operator Information 1. Facility Name (Business Name of Operator to Appear on the Permit): AES Alamitos, LLC 3. Owner's Business Name (If different from Business Name of Operator): Section B - Equipment Location Address 4. Equipment Location Is: (For equipment operated at various locations, provide address of initial site.) 690 N. Studebaker Rd. Street Address Long Beach City Tape Contact Name Title Contac	IMD):		
AES Alamitos, LLC 3. Owner's Business Name (If different from Business Name of Operator): Section B - Equipment Location Address 4. Equipment Location Is: (For equipment operated at various locations, provide address of initial site.) 690 N. Studebaker Rd. Street Address Long Beach City Charlene He Environmental Manager Contact Name (562) 493-7835 Phone # Ext. Fax # E-Mail: charlene.he@aes.com Section C - Permit Mailing Address 5. Permit and Correspondence Information: (Check here if same as equipment location address 690 N. Studebaker Rd. Address Long Beach City State Zip Charlene He Contact Name (562) 493-7835 Phone # Ext. Fax # E-Mail: charlene.he@aes.com Section D - Application Type 6. The Facility Is: Not In RECLAIM or Title V In RECLAIM & Title V Programs 7. Reason for Submitting Application (Select only ONE):	IMD):		
3. Owner's Business Name (If different from Business Name of Operator): Section B - Equipment Location Address 4. Equipment Location Is:	ır_		
Section B - Equipment Location Address 4. Equipment Location Is:	ır		
4. Equipment Location Is: (For equipment operated at various locations, provide address of initial site.) 690 N. Studebaker Rd. Street Address Long Beach City Charlene He Contact Name (562) 493-7835 Phone # Ext. Fax # E-Mail: charlene.he@aes.com Section D - Application Type 6. The Facility Is: Not In RECLAIM or Title V In RECLAIM City Carlous Location (Select only ONE): 5. Permit and Correspondence Information: (Check here if same as equipment location address 690 N. Studebaker Rd. Address Long Beach City State Zip Charlene He Environmental Manager Contact Name (562) 493-7835 Phone # Ext. Fax # E-Mail: charlene.he@aes.com Section D - Application Type 6. The Facility Is: Not In RECLAIM or Title V In RECLAIM In Title V In RECLAIM & Title V Programs 7. Reason for Submitting Application (Select only ONE):	ır		
4. Equipment Location Is: (For equipment operated at various locations, provide address of initial site.) 690 N. Studebaker Rd. Street Address Long Beach City Charlene He Contact Name (562) 493-7835 Phone # Ext. Fax # E-Mail: charlene.he@aes.com Section D - Application Type 6. The Facility Is: Not In RECLAIM or Title V In RECLAIM 7. Reason for Submitting Application (Select only ONE): 5. Permit and Correspondence Information: (Check here if same as equipment location address 690 N. Studebaker Rd. Address Long Beach City State Zip Charlene He Environmental Manager Contact Name (562) 493-7835 Phone # Ext. Fax # E-Mail: charlene.he@aes.com 5. Permit and Correspondence Information: (She charles Informati	NF.		
690 N. Studebaker Rd. Street Address Long Beach City Charlene He Contact Name (562) 493-7835 Phone # Ext. Fax # E-Mail: charlene.he@aes.com Section D - Application Type 6. The Facility Is: Not In RECLAIM or Title V In RECLAIM Studebaker Rd. Address Long Beach City State Zip Charlene He Contact Name Contact Name Contact Name (562) 493-7835 Phone # Ext. Fax # E-Mail: charlene.he@aes.com Section D - Application Type 6. The Facility Is: Not In RECLAIM or Title V In RECLAIM In Title V In RECLAIM & Title V Programs	ır_		
Street Address Long Beach City Charlene He Environmental Manager Contact Name (562) 493-7835 Phone # Ext. Fax # E-Mail: charlene.he@aes.com Section D - Application Type 6. The Facility Is: Not In RECLAIM or Title V In RECLAIM Not In RECLAIM ONE): Address Long Beach City State Zip Charlene He Environmental Manager Contact Name (562) 493-7835 Phone # Ext. Fax # E-Mail: charlene.he@aes.com Section D - Application Type 6. The Facility Is: Not In RECLAIM or Title V In RECLAIM In Title V In RECLAIM & Title V Programs	ır		
Long Beach City Charlene He Environmental Manager Contact Name Title Contact Name (562) 493-7835 Phone # Ext. Fax # E-Mail: charlene.he@aes.com Section D - Application Type 6. The Facility Is: Not In RECLAIM or Title V In RECLAIM 7. Reason for Submitting Application (Select only ONE): Long Beach City State Zip Charlene He Contact Name (562) 493-7835 Phone # Ext. Fax # E-Mail: charlene.he@aes.com In Title V In RECLAIM & Title V Programs In Title V In RECLAIM & Title V Programs	er_		
City Charlene He Contact Name (562) 493-7835 Phone # Ext. Fax # E-Mail: charlene.he@aes.com Section D - Application Type 6. The Facility Is: Not In RECLAIM or Title V In RECLAIM Title Contact Name (562) 493-7835 Phone # Ext. Fax # E-Mail: charlene.he@aes.com City Charlene He Contact Name (562) 493-7835 Phone # Ext. Fax # E-Mail: charlene.he@aes.com E-Mail: charlene.he@aes.com Title Contact Name (562) 493-7835 Phone # Ext. Fax # E-Mail: charlene.he@aes.com Title Title Contact Name Title Title Title Title In Title V In RECLAIM & Title V Programs To Reason for Submitting Application (Select only ONE):	ır		
Contact Name Title (562) 493-7835 Phone # Ext. Fax # E-Mail: charlene.he@aes.com Section D - Application Type 6. The Facility Is: Not In RECLAIM or Title V In RECLAIM In Title V In RECLAIM & Title V Programs 7. Reason for Submitting Application (Select only ONE):	er		
(562) 493-7835 Phone # Ext. Fax # E-Mail: charlene.he@aes.com Section D - Application Type 6. The Facility Is: Not In RECLAIM or Title V In RECLAIM In Title V In RECLAIM & Title V Programs 7. Reason for Submitting Application (Select only ONE):			
Phone # Ext. Fax # E-Mail: charlene.he@aes.com Section D - Application Type 6. The Facility Is: Not In RECLAIM or Title V In RECLAIM In Title V In RECLAIM & Title V Programs 7. Reason for Submitting Application (Select only ONE):			
E-Mail: charlene.he@aes.com Section D - Application Type 6. The Facility Is: Not In RECLAIM or Title V In RECLAIM In Title V In RECLAIM & Title V Programs 7. Reason for Submitting Application (Select only ONE):			
Section D - Application Type 6. The Facility Is: Not In RECLAIM or Title V In RECLAIM In Title V In RECLAIM & Title V Programs 7. Reason for Submitting Application (Select only ONE):			
6. The Facility Is: Not In RECLAIM or Title V In RECLAIM In Title V In RECLAIM & Title V Programs 7. Reason for Submitting Application (Select only ONE):			
7a. New Equipment or Process Application: 7c. Equipment or Process with an Existing/Previous Application or Permit:			
New Construction (Permit to Construct) Administrative Change			
Equipment On-Site But Not Constructed or Operational Alteration/Modification Existing or Previous			
Equipment Operating Without A Permit* Alteration/Modification without Prior Approval * Permit/Application			
Compliance Plan If you checked any of the items			
7c., you MUST provide an exis			
Registration/Certification Change of Condition without Prior Approval * Permit or Application Number Streamlined Standard Permit Change of Location	(6)		
Change of Legation without Drive Assessed #			
7b. Facility Permits: Change of Location without Prior Approval *			
Title V Application or Amendment (Refer to Title V Matrix)			
RECLAIM Facility Permit Amendment * A Higher Permit Processing Fee and additional Annual Operating Fees (up to 3 full years) may apply (Rule 301(c)(1)(D)(i)).		
8a. Estimated Start Date of Construction (mm/dd/yyyy): 8b. Estimated End Date of Construction (mm/dd/yyyy): 01/01/2023 8b. Estimated End Date of Construction (mm/dd/yyyy): 8c. Estimated Start Date of Operation (mm/dd/yyyy) 05/01/2023	y):		
9. Description of Equipment or Reason for Compliance Plan (list applicable rule): 10. For Identical equipment, how many additional			
Permit Application for Two Emergency IC Engines (second one) applications are being submitted with this application? (Form 400-A required for each equipment / process) 1			
11. Are you a Small Business as per AQMD's Rule 102 definition? (10 employees or less and total gross receipts are 12. Has a Notice of Violation (NOV) or a Notice to Comply (NC) been issued for this equipment?	Yes		
(10 employees or less and total gross receipts are \$500,000 or less OR a not-for-profit training center) No Yes Comply (NC) been issued for this equipment? If Yes, provide NOV/NC#:	162		
Section E - Facility Business Information			
13. What type of business is being conducted at this equipment location? 14. What is your business primary NAICS Code?	_		
Generation, Electric Power (North American Industrial Classification System) 221112			
15. Are there other facilities in the SCAQMD jurisdiction operated by the same operator? No Sea 16. Are there any schools (K-12) within 1000 feet of the facility property line?			
Section F - Authorization/Signature I hereby certify that all information contained herein and information submitted with this application are true and correct.			
17. Signature of Responsible Official: 18. Title of Responsible Official: 19. I wish to review the permit prior to issuance. (This may cause a delay in the	No		
V.P., AES Southland Energy application process.)	Yes		
20. Print Name: Weikko Wirta 21. Date: 0 4/11 200 22. Do you claim confidentiality of data? (If Yes, see instructions.)	Yes		
23. Check List: Authorized Signature/Date Form 400-CEQA Supplemental Form(s) (ie., Form 400-E-xx) Fees Enclosed			
AOMD APPLICATION TRACKING # CHECK # AMOUNT RECEIVED PAYMENT TRACKING # VALIDATION USE ONLY S VALIDATION			
DATE APP DATE APP CLASS BASIC EQUIPMENT CATEGORY CODE TEAM ENGINEER REASON/ACTION TAKEN REJ I III GONTROL			

South Coast Air Quality Management District

FORM 400-E-13a

Emergency Internal Combustion Engine

This form must be accompanied by a completed Application for a Permit to Construct/Operate -Form 400A

Mail Application To: SCAQMD P.O. Box 4944 Diamond Bar, CA 91765

Tel: (909) 396-3385

www.aqmd.gov

Permit to be issued to (Business name of operator to appear on permit): AES Alamitos, LLC Street location where the equipment will be operated (for equipment which will be moved to various location in SCAQMD's jurisdiction, please list the initial location site): 690 N. Studebaker Rd., Long Beach, CA 90803 | West Engine **Section A: Equipment Information** Model No.: Manufacturer: Serial No.: Perkins 2806C-F18TTAG7 Date of Manufacture: **EPA Family No.:** Internal Combustion NCPXL18.1NYS For an ICE manufactured **Engine** (mm/dd/yyyy) after 7/18/94, please provide Manufacturer Maximum Rating: Date of Installation: manufacturer's specification. _{BHP @} 1,800 (mm/dd/yyyy) Electrical Generator O Fire Pump C Flood Control O Pump Driver O Compressor ICE Emergency **Function** O Other Water Pump How Is This Type of Equipment O Portable Within Facility Type • Fixed site Off- Site Rental Used? (Check All That Apply) O Diesel Oil O I PG O Natural Gas Other: Fuel O Two Cycle Cycle Type O Four Cycle **Combustion Type** O Lean Burn O Rich Burn 18.1 liters **Engine Size** No. of Cylinders O Four O Six O Eight O Ten O Twelve O Sixteen O Other **Aspiration Type** O Turbocharged Turbocharged/Aftercooled O Naturally Aspirated Check all that apply: Selective Catalytic Reduction (SCR)* ☐ Catalytic Converter Selective Non-catalytic Reduction (SNCR)* Air/Fuel Ratio Controller Non-selective Catalytic Reduction (NSCR) Diesel Particulate Filter (DPF) Other (specify)_ Model No. LTRV24-21-10-R1 Manufacturer: _Miratech _____ Device No. ____ If already permitted, indicate Permit No. (RECLAIM and/or Title V Permits) Air Pollution Control * Separate application is required. Additional Information for Diesel Particulate Filter (DPF) 85 Filter Efficiency: _ O Yes O No CARB Certified? If Yes, provide a copy of the CARB Verification Certificate, or provide the Verification No. See Attached

Operating Schedule	Normal:		cu ft/hr Average Load: _	gal/hr OR	cu ft/l	
Schedule		hours/day	days/week	wee	ks/year	
	Maximum:	hours/day	days/week	wee	ks/year	
	esting & 50) hours/year				
ection C: Engine	Data					
Is the engine E	PA certified?					
Yes Provid	de a copy of EPA's Engine (Certification.				
Choos	se one: O Tier I	Tier II	Tier III Tier IV (Interim)	Tier IV		
				-		
	de a copy of the Manufactu					
			vailable emissions data below. Prov			
Carbon Mono (grams/bhp	rando estrutura de 2000 e a 1900 de 2000 de 1900 de 19	Oxides of Nitrogen (grams/bhp-hr)	Hydrocarbons + Oxides of Nitro (grams/bhp-hr)	ogen Particulate Matte (grams/bhp-hr)		
<u> </u>						
ction D: Sensitiv						
			ve receptor (ie., long-term health ca -12), playgrounds, child care centers		enters,	
			,, p.a.y g. oan ac, on a concern			
Type of Facility			Name of Facility		Distance (feet)	
' '		U	niversity Park Estates	1.		
-	Residential		Third Sity I dik Latates] 1.4	257	
F	Residential			"	257 170	
F			Kettering Elementary Sc	"		
F				"		
F				"		
Elem	nentary School nt Certification Statem	Charles F	Kettering Elementary Sc	"		
Elem	nentary School nt Certification Staten ormation contained herein an	Charles F	Kettering Elementary Sc	"		
Elem	nentary School nt Certification Staten ormation contained herein an	Charles F	tion is true and correct.	"		
Elem ction E: Applicate a preby certify that all informature of PREPA	nentary School nt Certification Staten ormation contained herein an	Charles F nent d submitted with this applica	Kettering Elementary Sc	chool 2		
Elem ction E: Applicate a preby certify that all informature of PREPA	nentary School nt Certification Statem ormation contained herein an RER:	Charles F nent d submitted with this applica	tion is true and correct. TITLE OF PREPARER: Engineer	EPHONE NUMBER DAT	170	

RULE EVALUATION

The internal combustion engine may be subject to the following rules:

SCAQMD Rules and Regul	ations
Rule 212	Standards for Approving Permits and Issuing Public Notice
Rule 401	Visible Emissions
Rule 402	Nuisance
Rule 404	Particulate Matter – Concentration
Rule 431.1	Sulfur Content of Gaseous Fuels
Rule 431.2	Sulfur Content of Liquid Fuels
	Liquid fuels – sulfur content of 500 ppm by weight or less.
	Diesel fuel – sulfur content of 0.015% by weight or less.
Reg XIII	New Source Review
Rule 1401	New Source Review of Toxic Air Contaminants
Rule 1401.1	Requirements for New and Relocated Facilities Near Schools
Rule 1470	Requirements for Stationary Diesel-Fueled Internal Combustion and Other Compression Ignition Engines
Rule 1472	Requirements for Facilities with Multiple Stationary Emergency Standby Diesel-Fueled Internal Combustion Engines
Rule 1714	Prevention of Significant Deterioration for Greenhouse Gases
Code of Federal Regulation	s
40 CFR 60 Subpart III	Standards of Performance for Stationary Compression Ignition Internal Combustion Engines
40 CFR 60 Subpart JJJJ	Standards of Performance for New Stationary Sources
40 CFR 63 Subpart ZZZZ	National Emission Standards for Hazardous Air Pollutants for Stationary Reciprocating Internal Combustion Engines (RICE)

SAMPLE CONDITIONS FOR EMERGENCY INTERNAL COMBUSTION ENGINES (GENERATORS)

- 1. OPERATION OF THIS EQUIPMENT SHALL BE CONDUCTED IN COMPLIANCE WITH ALL DATA AND SPECIFICATIONS SUBMITTED WITH THE APPLICATION UNDER WHICH THIS PERMIT IS ISSUED.
- 2. THIS EQUIPMENT SHALL BE PROPERLY MAINTAINED AND KEPT IN GOOD OPERATING CONDITIONS AT ALL TIMES.
- 3. THE OPERATOR SHALL COMPLY WITH ALL APPLICABLE REQUIREMENTS OF SCAQMD RULE 431.2, SCAQMD RULE 1470, 40CFR PART 60 SUBPART IIII AND 40 CFR PART 63 SUBPART ZZZZ, OR THE OPERATOR SHALL NOT USE ANY DIESEL FUEL UNLESS THE FUEL IS LOW SULFUR DIESEL FOR WHICH THE SULFUR CONTENT SHALL NOT EXCEED 15 PPM BY WEIGHT AS SUPPLIED BY THE SUPPLIER.
- 4. THIS ENGINE SHALL NOT OPERATE MORE THAN 200 HOURS IN ANY ONE YEAR, WHICH INCLUDES NO MORE THAN 50 HOURS IN ANY ONE YEAR FOR MAINTENANCE AND TESTING.
- 5. THE OPERATION OF ENGINE BEYOND 50 HOURS PER YEAR ALLOTTED FOR ENGINE MAINTENANCE AND TESTING SHALL BE ALLOWED ONLY IN THE EVENT OF A LOSS OF GRID POWER OR UP TO 30 MINUTES PRIOR TO A ROTATING OUTAGE, PROVIDED THAT THE ELECTRICAL GRID OPERATOR OR ELECTRIC UTILITY HAS ORDERED ROTATING OUTAGES IN THE CONTROL AREA WHERE THE ENGINE IS LOCATED OR HAS INDICATED THAT IT EXPECTS TO ISSUE SUCH AN ORDER AT A CERTAIN TIME, AND THE ENGINE IS LOCATED IN A UTILITY SERVICE BLOCK THAT IS SUBJECT TO THE ROTATING OUTAGE. ENGINE OPERATION SHALL BE TERMINATED IMMEDIATELY AFTER THE UTILITY DISTRIBUTION COMPANY ADVISES THAT A ROTATING OUTAGE IS NO LONGER IMMINENT OR IN EFFECT.
- 6. AN OPERATIONAL NON-RESETTABLE TOTALIZING TIME METER SHALL BE INSTALLED AND MAINTAINED TO INDICATE THE ENGINE ELAPSED OPERATING TIME.
- 7. ON OR BEFORE JANUARY 15^{TH} OF EACH YEAR THE OPERATOR SHALL RECORD IN THE ENGINE OPERATING LOG:
 - A. THE TOTAL HOURS OF ENGINE OPERATION FOR THE PREVIOUS CALENDAR YEAR, AND
 - B. THE TOTAL HOURS OF ENGINE OPERATION FOR MAINTENANCE AND TESTING FOR THE PREVIOUS CALENDAR YEAR.

ENGINE OPERATION LOG(S) SHALL BE RETAINED ON SITE FOR A MINIMUM OF FIVE CALENDAR YEARS AND SHALL BE MADE AVAILABLE TO THE EXECUTIVE OFFICER OR REPRESENTATIVE UPON REQUEST.

- 8. THE OPERATOR SHALL KEEP A LOG OF ENGINE OPERATIONS DOCUMENTING THE TOTAL TIME THE ENGINE IS OPERATED EACH MONTH AND THE SPECIFIC REASON FOR OPERATION AS:
 - A. EMERGENCY USE
 - A. MAINTENANCE AND TESTING
 - C. OTHER (BE SPECIFIC)

IN ADDITION, FOR EACH TIME THE ENGINE ISMANUALLY STARTED, THE LOG SHALL INCLUDE: THE DATE OF ENGINE OPERATION, THE START AND STOP TIME OF THE ENGINE, THE SPECIFIC REASON FOR OPERATION, AND THE TOTALIZING HOUR METER READING (IN HOURS AND TENTHS OF HOURS) AT THE BEGINNING AND THE END OF THE OPERATION.

9. THIS ENGINE SHALL NOT BE USED AS PART OF A DEMAND RESPONSE PROGRAM USING INTERRUPTIBLE SERVICE CONTRACT IN WHICH A FACILITY RECEIVES A PAYMENT OR REDUCED RATES IN RETURN FOR REDUCING ITS ELECTRIC LOAD ON THE GRID WHEN REQUESTED TO DO SO BY THE UTILITY OR THE GRID OPERATOR.

10. THIS ENGINE SHALL NOT BE OPERATED MORE THAN 200 HOURS IN ANY ONE YEAR, WHICH INCLUDES NO MORE THAN 50 HOURS IN ANY ONE YEAR FOR MAINTENANCE AND TESTING TO COMPLY WITH REQUIREMENTS OF THE NATIONAL FIRE PROTECTION ASSOCIATION (NFPA). ANYTHING IN EXCESS OF 50 HOURS SHALL BE ALLOWED ONLY IN THE EVENT OF AN EMERGENCY FIRE FIGHTING OPERATION.

For Fire pumps:

11. THIS ENGINE SHALL NOT BE OPERATED MORE THAN 200 HOURS IN ANY ONE YEAR, WHICH INCLUDES NO MORE THAN 50 HOURS IN ANY ONE YEAR FOR MAINTENANCE AND TESTING TO COMPLY WITH REQUIREMENTS OF THE NATIONAL FIRE PROTECTION ASSOCIATION (NFPA). ANYTHING IN EXCESS OF 50 HOURS SHALL BE ALLOWED ONLY IN THE EVENT OF AN EMERGENCY FIRE FIGHTING OPERATION.

For Various Locations Equipment:

- 12. UPON THE FIFTH DAY AFTER PLACEMENT OF THIS EQUIPMENT INTO OPERATION AT A NEW SITE, THE DISTRICT SHALL BE NOTIFIED VIA TELEPHONE AT 877-810-6995 OF THE EXACT NATURE OF THE PROJECT AS FOLLOWS:
 - A. THE PERMIT NUMBER OF THE PORTABLE EQUIPMENT.
 - B. THE NAME AND TELEPHONE NUMBER OF A CONTACT PERSON.
 - C. THE LOCATION WHERE THE PORTABLE EQUIPMENT WILL BE OPERATED.
 - D. THE ESTIMATED TIME THE PORTABLE EQUIPMENT WILL BE LOCATED AT THE SITE.
 - E. DESCRIPTION OF THE PROJECT.
 - F. IF LESS THAN 1/4 MILE, THE DISTANCE TO THE NEAREST SENSITIVE RECEPTOR. SENSITIVE RECEPTORS ARE DEFINED AS LONG-TERM HEALTH CARE FACILITIES, REHABILITATION CENTERS, CONVALESCENT CENTERS, RETIREMENT HOMES, RESIDENCES, SCHOOLS, PLAYGROUNDS, CHILD CARE CENTERS, AND ATHLETIC FACILITIES.
- 13. THIS ENGINE AND ITS REPLACEMENT UNIT INTENDED TO PERFORM THE SAME OR SIMILAR FUNCTION, SHALL NOT RESIDE AT ANY ONE LOCATION FOR MORE THAN 12 CONSECUTIVE MONTHS. THE PERIOD DURING WHICH THE ENGINE AND ITS REPLACEMENT IS MAINTAINED AT A STORAGE FACILITY SHALL BE EXCLUDED FROM RESIDENCY TIME DETERMINATION.
- 14. THIS ENGINE SHALL NOT BE REMOVED FROM ONE LOCATION FOR A PERIOD OF TIME, AND THEN IT OR ITS EQUIVALENT ENGINE RETURNED TO THE SAME LOCATION, IN ORDER TO CIRCUMVENT THE PORTABLE ENGINE RESIDENCE TIME REQUIREMENTS.
- 15. IN ADDITION TO MAINTENANCE AND TESTING OF THIS ENGINE, THIS ENGINE SHALL ONLY BE USED FOR EITHER PROVIDING ELECTRICAL POWER TO PORTABLE OPERATIONS OR EMERGENCY POWER TO STATIONARY SOURCES. PORTABLE OPERATIONS ARE THOSE WHERE IT CAN BE DEMONSTRATED THAT BECAUSE OF THE NATURE OF THE OPERATION, IT IS NECESSARY TO PERIODICALLY MOVE THE EQUIPMENT FROM ONE LOCATION TO ANOTHER. EMERGENCIES AT STATIONARY SOURCES ARE THOSE THAT RESULT IN AN INTERRUPTION OF SERVICE OF THE PRIMARY POWER SUPPLY OR DURING STAGE II OR III ELECTRICAL EMERGENCIES DECLARED BY THE CALIFORNIA INDEPENDENT SYSTEM OPERATOR.

South Coast Air Quality Management District

FORM 400-E-13a

Emergency Internal Combustion Engine

This form must be accompanied by a completed Application for a Permit to Construct/Operate -Form 400A

Mail Application To: SCAQMD P.O. Box 4944 Diamond Bar, CA 91765

Tel: (909) 396-3385

www.aqmd.gov

Permit to be issued to (Business name of operator to appear on permit):				
AES Alamitos, LLC Street location where the equipment will be operated (for equipment which will be moved to various location in SCAQMD's jurisdiction,				
please list the initial lo			d to various location in SCAQ	MD's jurisdiction,
Section A: Equipm	nent Information			
	Manufacturer:	Model No.	:	Serial No.:
	Perkins	2806C-l	E18TTAG7	
Internal Combustion	EPA Family No.:		Date of Manufacture:	
Engine	NCPXL18.1NYS		(mm/dd	/yyyy) For an ICE manufactured
	Manufacturer Maximum Rating:		Date of Installation:	after 7/18/94, please provide manufacturer's specification.
	<u>1,112 _{BHP @} 1,800 _{RPM}</u>		(mm/dd	/уууу)
105.5	© Electrical Generator) Flood Cor	trol Pump Driver	O Compressor
ICE Emergency Function	O Water Pump O Other			
Туре	Fixed site Portable How Is This Type Used? (Check Al	That Apply	() Within Facil	ity Off- Site Rental
Fuel	O Diesel Oil O LPG Natural	Gas	Other:	
Cycle Type	O Two Cycle O Four Cycle			
Combustion Type	O Lean Burn O Rich Burn			
Engine Size	18.1 <u>liters</u>			
No. of Cylinders	O Four O Six O Eight O Tel	1 O	Twelve O Sixteen	Other
Aspiration Type	O Naturally Aspirated O Turbocharg	ed	O Turbocharged/Aft	tercooled
Air Pollution Control	Check all that apply: Selective Catalytic Reduction (SCR)* Selective Non-catalytic Reduction (SNCR)* Non-selective Catalytic Reduction (NSCR) Diesel Particulate Filter (DPF) Manufacturer: Miratech If already permitted, indicate Permit No. * Separate application is required. Additional Information for Filter Efficiency: 85 % CARB Certified? Yes No	Air/ No Oth Model N Diesel Pa	rticulate Filter (DPF)	(RECLAIM and/or Title V Permits)
	Installing a backpressure relief system? O Yes	O No		

el Consumption	Maximum Load:	54.3	gal/hr OR	cu ft/hr	Average Load:	gal/hr	ORcu f
	Normal:		hours/day		days/week		weeks/year
Operating Maximum:			hours/day		days/week		weeks/year
	Testing & Maintenance:	50	hours/year				
ection C: Engir	ie Data		el relia		10 B		
Is the engine	EPA certified?						
O Yes Pro	vide a copy of EPA	's Engine Ce	ertification.				
	_			~	6	A	
Ch	oose one: O	Tier I	Tier II	C Tier III	Tier IV (Interim)	O Tier IV	
O No Pro	vide a copy of the	Manufacture	r's Emissions Data	l .			
16	anufacturor'e omic	einne data ie	not available, pro	vide available emi	ssions data below. Provid	le supporting docu	uments.
11 11	andiacturer 5 cinis	sions data is					
Carbon Me		rocarbons	Oxides of Nit	rogen Hydroc	arbons + Oxides of Nitroge	en Particulat	e Matter
	onoxide Hyd				arbons + Oxides of Nitroge (grams/bhp-hr)	en Particulat (grams/t	3 450 mm and 450 200 mm
Carbon Me	onoxide Hyd	rocarbons	Oxides of Nit				3 450 mm and 450 200 mm
Carbon Me	onoxide Hyd	rocarbons	Oxides of Nit				3 450 mm and 450 200 mm
Carbon M (grams/b	onoxide Hyd hp-hr) (gran	rocarbons	Oxides of Nit				3 450 mm and 450 200 mm
Carbon Mo (grams/b	pnoxide Hydrophydd (graf hp-hr) (graf tive Receptors	rocarbons ns/bhp-hr)	Oxides of Niti (grams/bhp	-hr)	(grams/bhp-hr)	(grams/k	ohp-hr)
Carbon Mo (grams/b	onoxide Hydihp-hr) (gran	rocarbons ns/bhp-hr)	Oxides of Nit (grams/bhp	sensitive receptor		(grams/k	tation centers,
Carbon Mo (grams/b	onoxide Hydihp-hr) (gran	rocarbons ns/bhp-hr)	Oxides of Nit (grams/bhp	sensitive receptor	(grams/bhp-hr)	(grams/k	tation centers,
Carbon Mo (grams/b	onoxide Hydihp-hr) (gran	rocarbons ns/bhp-hr)	Oxides of Nit (grams/bhp	sensitive receptor	(grams/bhp-hr)	(grams/k	tation centers,
Carbon Mo (grams/b	tive Receptors from engine stack cent centers, retire	rocarbons ns/bhp-hr)	Oxides of Nit (grams/bhp	sensitive receptor rools (K-12), playgro	(grams/bhp-hr) (ie., long-term health care bunds, child care centers, a	(grams/k	tation centers,
Carbon Mo (grams/b	tive Receptors from engine stack cent centers, retire Type of Facility Residential	rocarbons ns/bhp-hr)	Oxides of Nite (grams/bhp	sensitive receptor rols (K-12), playgro Name	(grams/bhp-hr) (ie., long-term health care bunds, child care centers, a of Facility Park Estates	facilities, rehabilit	tation centers, ies):
Carbon Mo (grams/b	tive Receptors from engine stack cent centers, retire	rocarbons ns/bhp-hr)	Oxides of Nite (grams/bhp	sensitive receptor rols (K-12), playgro Name	(grams/bhp-hr) (ie., long-term health care bunds, child care centers, a of Facility	facilities, rehabilit	tation centers, ies): Distance (feet) 1500
Carbon Mo (grams/b	tive Receptors from engine stack cent centers, retire Type of Facility Residential	rocarbons ns/bhp-hr)	Oxides of Nite (grams/bhp	sensitive receptor rols (K-12), playgro Name	(grams/bhp-hr) (ie., long-term health care bunds, child care centers, a of Facility Park Estates	facilities, rehabilit	tation centers, ies): Distance (feet) 1500
Carbon Mo (grams/b	tive Receptors from engine stack cent centers, retire Type of Facility Residential	rocarbons ns/bhp-hr)	Oxides of Nite (grams/bhp	sensitive receptor rols (K-12), playgro Name	(grams/bhp-hr) (ie., long-term health care bunds, child care centers, a of Facility Park Estates	facilities, rehabilit	tation centers, ies): Distance (feet) 1500
Carbon Mo (grams/b	tive Receptors from engine stack cent centers, retire Type of Facility Residential ementary Sch	to the fencelinement homes	Oxides of Niti (grams/bhp	sensitive receptor rols (K-12), playgro Name	(grams/bhp-hr) (ie., long-term health care bunds, child care centers, a of Facility Park Estates	facilities, rehabilit	tation centers, ies): Distance (feet) 1500
Carbon Mo (grams/b	tive Receptors from engine stack cent centers, retire Type of Facility Residential ementary Sch	to the fenceliment homes	Oxides of Niti (grams/bhp	sensitive receptor rols (K-12), playgro Name University les F Ketterir	(grams/bhp-hr) (ie., long-term health care bunds, child care centers, a of Facility Park Estates ag Elementary School	facilities, rehabilit	tation centers, ies): Distance (feet) 1500
Carbon Mo (grams/b) ection D: Sensi A. Distance convales Ele ection E: Applie	tive Receptors from engine stack cent centers, retire Type of Facility Residential ementary Sch	to the fenceliment homes	Oxides of Niti (grams/bhp	sensitive receptor rols (K-12), playgro Name University les F Ketterir	(grams/bhp-hr) (ie., long-term health care bunds, child care centers, a of Facility Park Estates ag Elementary School	facilities, rehabilit	tation centers, ies): Distance (feet) 1500
Carbon Mo (grams/b) ection D: Sensi A. Distance convales Ele ection E: Applice ereby certify that all GNATURE OF PRE	tive Receptors from engine stack cent centers, retire Type of Facility Residential ementary Sch	to the fenceliement homes	Oxides of Nite (grams/bhp) ine of the nearest parts of the nearest part	sensitive receptor rols (K-12), playgro Name University les F Ketterir application is true a	(grams/bhp-hr) (ie., long-term health care bunds, child care centers, a of Facility Park Estates ag Elementary School correct. LE OF PREPARER: gineer	facilities, rehabilit	tation centers, ies): Distance (feet) 1500 2181
Carbon Mo (grams/b) ection D: Sensi A. Distance convales Election E: Application Application Convalues ENATURE OF PRE ENTACT PERSON I	tive Receptors from engine stack cent centers, retire Type of Facility Residential ementary Sch	to the fenceliement homes	Oxides of Nite (grams/bhp) ine of the nearest parts of the nearest part	sensitive receptor rols (K-12), playgro Name University les F Ketterir application is true a TIT En	(grams/bhp-hr) (ie., long-term health care bunds, child care centers, a of Facility Park Estates ag Elementary School correct LE OF PREPARER: gineer NTACT PERSON'S TELEP	facilities, rehabilit	Distance (feet) 1500 2181 DATE SIGNED:
Carbon Mo (grams/b) ection D: Sensi A. Distance convales Ele ection E: Applice ereby certify that all GNATURE OF PRE	tive Receptors from engine stack cent centers, retire Type of Facility Residential ementary Sch	to the fenceliement homes	Oxides of Nite (grams/bhp) ine of the nearest; , residences, school Char cht submitted with this	sensitive receptor rols (K-12), playgro Name University les F Ketterir application is true a TIT En	(grams/bhp-hr) (ie., long-term health care bunds, child care centers, a of Facility Park Estates ag Elementary School correct LE OF PREPARER: gineer NTACT PERSON'S TELEP (2) 493-7835	facilities, rehabilit	tation centers, ies): Distance (feet) 1500 2181

RULE EVALUATION

The internal combustion engine may be subject to the following rules:

SCAQMD Rules and Regul	ations
Rule 212	Standards for Approving Permits and Issuing Public Notice
Rule 401	Visible Emissions
Rule 402	Nuisance
Rule 404	Particulate Matter – Concentration
Rule 431.1	Sulfur Content of Gaseous Fuels
Rule 431.2	Sulfur Content of Liquid Fuels
	Liquid fuels – sulfur content of 500 ppm by weight or less.
	Diesel fuel – sulfur content of 0.015% by weight or less.
Reg XIII	New Source Review
Rule 1401	New Source Review of Toxic Air Contaminants
Rule 1401.1	Requirements for New and Relocated Facilities Near Schools
Rule 1470	Requirements for Stationary Diesel-Fueled Internal Combustion and Other Compression Ignition Engines
Rule 1472	Requirements for Facilities with Multiple Stationary Emergency Standby Diesel-Fueled Internal Combustion Engines
Rule 1714	Prevention of Significant Deterioration for Greenhouse Gases
Code of Federal Regulation	s
40 CFR 60 Subpart III	Standards of Performance for Stationary Compression Ignition Internal Combustion Engines
40 CFR 60 Subpart JJJJ	Standards of Performance for New Stationary Sources
40 CFR 63 Subpart ZZZZ	National Emission Standards for Hazardous Air Pollutants for Stationary Reciprocating Internal Combustion Engines (RICE)

SAMPLE CONDITIONS FOR EMERGENCY INTERNAL COMBUSTION ENGINES (GENERATORS)

- 1. OPERATION OF THIS EQUIPMENT SHALL BE CONDUCTED IN COMPLIANCE WITH ALL DATA AND SPECIFICATIONS SUBMITTED WITH THE APPLICATION UNDER WHICH THIS PERMIT IS ISSUED.
- 2. THIS EQUIPMENT SHALL BE PROPERLY MAINTAINED AND KEPT IN GOOD OPERATING CONDITIONS AT ALL TIMES.
- 3. THE OPERATOR SHALL COMPLY WITH ALL APPLICABLE REQUIREMENTS OF SCAQMD RULE 431.2, SCAQMD RULE 1470, 40CFR PART 60 SUBPART IIII AND 40 CFR PART 63 SUBPART ZZZZ, OR THE OPERATOR SHALL NOT USE ANY DIESEL FUEL UNLESS THE FUEL IS LOW SULFUR DIESEL FOR WHICH THE SULFUR CONTENT SHALL NOT EXCEED 15 PPM BY WEIGHT AS SUPPLIED BY THE SUPPLIER.
- 4. THIS ENGINE SHALL NOT OPERATE MORE THAN 200 HOURS IN ANY ONE YEAR, WHICH INCLUDES NO MORE THAN 50 HOURS IN ANY ONE YEAR FOR MAINTENANCE AND TESTING.
- 5. THE OPERATION OF ENGINE BEYOND 50 HOURS PER YEAR ALLOTTED FOR ENGINE MAINTENANCE AND TESTING SHALL BE ALLOWED ONLY IN THE EVENT OF A LOSS OF GRID POWER OR UP TO 30 MINUTES PRIOR TO A ROTATING OUTAGE, PROVIDED THAT THE ELECTRICAL GRID OPERATOR OR ELECTRIC UTILITY HAS ORDERED ROTATING OUTAGES IN THE CONTROL AREA WHERE THE ENGINE IS LOCATED OR HAS INDICATED THAT IT EXPECTS TO ISSUE SUCH AN ORDER AT A CERTAIN TIME, AND THE ENGINE IS LOCATED IN A UTILITY SERVICE BLOCK THAT IS SUBJECT TO THE ROTATING OUTAGE. ENGINE OPERATION SHALL BE TERMINATED IMMEDIATELY AFTER THE UTILITY DISTRIBUTION COMPANY ADVISES THAT A ROTATING OUTAGE IS NO LONGER IMMINENT OR IN EFFECT.
- 6. AN OPERATIONAL NON-RESETTABLE TOTALIZING TIME METER SHALL BE INSTALLED AND MAINTAINED TO INDICATE THE ENGINE ELAPSED OPERATING TIME.
- 7. ON OR BEFORE JANUARY 15^{TH} OF EACH YEAR THE OPERATOR SHALL RECORD IN THE ENGINE OPERATING LOG:
 - A. THE TOTAL HOURS OF ENGINE OPERATION FOR THE PREVIOUS CALENDAR YEAR, AND
 - B. THE TOTAL HOURS OF ENGINE OPERATION FOR MAINTENANCE AND TESTING FOR THE PREVIOUS CALENDAR YEAR.

ENGINE OPERATION LOG(S) SHALL BE RETAINED ON SITE FOR A MINIMUM OF FIVE CALENDAR YEARS AND SHALL BE MADE AVAILABLE TO THE EXECUTIVE OFFICER OR REPRESENTATIVE UPON REQUEST.

- 8. THE OPERATOR SHALL KEEP A LOG OF ENGINE OPERATIONS DOCUMENTING THE TOTAL TIME THE ENGINE IS OPERATED EACH MONTH AND THE SPECIFIC REASON FOR OPERATION AS:
 - A. EMERGENCY USE
 - A. MAINTENANCE AND TESTING
 - C. OTHER (BE SPECIFIC)

IN ADDITION, FOR EACH TIME THE ENGINE ISMANUALLY STARTED, THE LOG SHALL INCLUDE: THE DATE OF ENGINE OPERATION, THE START AND STOP TIME OF THE ENGINE, THE SPECIFIC REASON FOR OPERATION, AND THE TOTALIZING HOUR METER READING (IN HOURS AND TENTHS OF HOURS) AT THE BEGINNING AND THE END OF THE OPERATION.

9. THIS ENGINE SHALL NOT BE USED AS PART OF A DEMAND RESPONSE PROGRAM USING INTERRUPTIBLE SERVICE CONTRACT IN WHICH A FACILITY RECEIVES A PAYMENT OR REDUCED RATES IN RETURN FOR REDUCING ITS ELECTRIC LOAD ON THE GRID WHEN REQUESTED TO DO SO BY THE UTILITY OR THE GRID OPERATOR.

10. THIS ENGINE SHALL NOT BE OPERATED MORE THAN 200 HOURS IN ANY ONE YEAR, WHICH INCLUDES NO MORE THAN 50 HOURS IN ANY ONE YEAR FOR MAINTENANCE AND TESTING TO COMPLY WITH REQUIREMENTS OF THE NATIONAL FIRE PROTECTION ASSOCIATION (NFPA). ANYTHING IN EXCESS OF 50 HOURS SHALL BE ALLOWED ONLY IN THE EVENT OF AN EMERGENCY FIRE FIGHTING OPERATION.

For Fire pumps:

11. THIS ENGINE SHALL NOT BE OPERATED MORE THAN 200 HOURS IN ANY ONE YEAR, WHICH INCLUDES NO MORE THAN 50 HOURS IN ANY ONE YEAR FOR MAINTENANCE AND TESTING TO COMPLY WITH REQUIREMENTS OF THE NATIONAL FIRE PROTECTION ASSOCIATION (NFPA). ANYTHING IN EXCESS OF 50 HOURS SHALL BE ALLOWED ONLY IN THE EVENT OF AN EMERGENCY FIRE FIGHTING OPERATION.

For Various Locations Equipment:

- 12. UPON THE FIFTH DAY AFTER PLACEMENT OF THIS EQUIPMENT INTO OPERATION AT A NEW SITE, THE DISTRICT SHALL BE NOTIFIED VIA TELEPHONE AT 877-810-6995 OF THE EXACT NATURE OF THE PROJECT AS FOLLOWS:
 - A. THE PERMIT NUMBER OF THE PORTABLE EQUIPMENT.
 - B. THE NAME AND TELEPHONE NUMBER OF A CONTACT PERSON.
 - C. THE LOCATION WHERE THE PORTABLE EQUIPMENT WILL BE OPERATED.
 - D. THE ESTIMATED TIME THE PORTABLE EQUIPMENT WILL BE LOCATED AT THE SITE.
 - E. DESCRIPTION OF THE PROJECT.
 - F. IF LESS THAN 1/4 MILE, THE DISTANCE TO THE NEAREST SENSITIVE RECEPTOR. SENSITIVE RECEPTORS ARE DEFINED AS LONG-TERM HEALTH CARE FACILITIES, REHABILITATION CENTERS, CONVALESCENT CENTERS, RETIREMENT HOMES, RESIDENCES, SCHOOLS, PLAYGROUNDS, CHILD CARE CENTERS, AND ATHLETIC FACILITIES.
- 13. THIS ENGINE AND ITS REPLACEMENT UNIT INTENDED TO PERFORM THE SAME OR SIMILAR FUNCTION, SHALL NOT RESIDE AT ANY ONE LOCATION FOR MORE THAN 12 CONSECUTIVE MONTHS. THE PERIOD DURING WHICH THE ENGINE AND ITS REPLACEMENT IS MAINTAINED AT A STORAGE FACILITY SHALL BE EXCLUDED FROM RESIDENCY TIME DETERMINATION.
- 14. THIS ENGINE SHALL NOT BE REMOVED FROM ONE LOCATION FOR A PERIOD OF TIME, AND THEN IT OR ITS EQUIVALENT ENGINE RETURNED TO THE SAME LOCATION, IN ORDER TO CIRCUMVENT THE PORTABLE ENGINE RESIDENCE TIME REQUIREMENTS.
- 15. IN ADDITION TO MAINTENANCE AND TESTING OF THIS ENGINE, THIS ENGINE SHALL ONLY BE USED FOR EITHER PROVIDING ELECTRICAL POWER TO PORTABLE OPERATIONS OR EMERGENCY POWER TO STATIONARY SOURCES. PORTABLE OPERATIONS ARE THOSE WHERE IT CAN BE DEMONSTRATED THAT BECAUSE OF THE NATURE OF THE OPERATION, IT IS NECESSARY TO PERIODICALLY MOVE THE EQUIPMENT FROM ONE LOCATION TO ANOTHER. EMERGENCIES AT STATIONARY SOURCES ARE THOSE THAT RESULT IN AN INTERRUPTION OF SERVICE OF THE PRIMARY POWER SUPPLY OR DURING STAGE II OR III ELECTRICAL EMERGENCIES DECLARED BY THE CALIFORNIA INDEPENDENT SYSTEM OPERATOR.

Mail To: SCAQMD P.O. Box 4944 Diamond Bar, CA 91765-0944

> Tel: (909) 396-3385 www.aqmd.gov

Section A - Operator Info	rmation			
•	e of Operator To Appears On The Permit):	Valid AQMD Facility ID (Available On Permit Or Invoice Issued By AQMD):		
AES Alamitos, LLC		115394		
	at will be operated (for equipment which will be moved to various lo	cation in AQMD's jurisdiction, please list the initial location site):		
690 N. Studebaker	Rd., Long Beach, CA 90803 West Engine	Fixed Location		
Section B - Location Data	a			
Plot Plan	Please attach a site map for the project with distances and scales. Thomas Brothers page, a web-based map, or a sketch that shows	Identify and locate the proposed equipment on the map. A copy of the appropriate the major streets and location of the equipment is acceptable.		
	Is the facility located within a 1/4 mile radius (1,320 feet) of the lf yes, please provide name(s) of school(s) below: School Name: Charles F Kettering	·		
	School Address: 550 Silvera Ave.			
Location of Schools Nearby	Long Beach, CA 90803			
	Distance from stack or equipment vent to the outer boundary of the school: 2,170	Distance from stack or equipment vent feet to the outer boundary of the school: feet		
	CA Health & Safety Code 42301.9: "School" means any public or	private school used for purposes of the education of more than 12 children in de any private school in which education is primarily conducted in private homes.		
Population Density	Urban	nted for by urban land use categories, i.e., multi-family dwelling or industrial.)		
7 . 01 .5	Mixed Use Residential Commercial Zone (M-U)	Service and Professional Zone (C-S) Medium Commercial (C-3)		
Zoning Classification	Heavy Commercial (C-4)	Commercial Manufacturing (C-M)		
Section C - Emission Rel	lease Parameters - Stacks, Vents			
	Stack Height: 15.33 feet (above ground level)	What is the height of the closest building nearest the stack?feet		
	Stack Inside Diameter: 10.75 inches	Stack Flow: 6,397 acfm Stack Temperature: 918 °F		
	Rain Cap Present: O Yes O No	Stack Orientation: Vertical Orientation:		
Stack Data	If the stack height is less than 2.5 times the closest building heigh (attach additional sheet if necessary):	t (H), please provide information on any building within 5xH distance from the stack		
	Building #/Name:	Building #/Name:		
	Building Height:feet (above ground level)	Building Height:feet (above ground level)		
	Building Width:feet	Building Width:feet		
	Building Length:feet	Building Length:feet		
Receptor Distance From Equipment Stack or Roof	Distance to nearest residence or sensitive receptor*:	1,257 feet		
Vents/Openings	Distance to nearest business:	1,080 feet		
	Are the emissions released from vents and/or openings from If yes, please provide:	a building? Yes • No		
Building Information	Building #/Name:	Building Width:feet		
	Ruilding Height: feet (shove ground level)	Ruilding Length: feet		

^{*}AQMD Rule 1470 defines SENSITIVE RECEPTOR as meaning any residence including private homes, condominiums, apartments, and living quarters, schools as defined under paragraph (b)(57), preschools, daycare centers and health facilities such as hospitals or retirement and nursing homes. A sensitive receptor includes long term care hospitals, hospices, prisons, and dormitories or similar live-in housing.

South Coast Air Quality Management District

Form 400-PS

Plot Plan And Stack Information Form

This form must be accompanied by a completed Application for a Permit to Construct/Operate - Form 400A and Form 400-CEQA.

Section D - Authorization/Signa	ature	and the state		Property of the Control of the Contr
I hereby certify that all information of	contained herein and informatio	n submittfgfed with th	nis application is true and correct.	
Signature of Preparer:	Title of Preparer:		Preparer's Phone #: (949) 573-5122	
Engineer,		Preparer's Pnone #: (Volume of the control of the c		
Contact Person: Charlene He Contact's Email: charlene.he@aes.com		Contact's Phone#: (562) 493-7835 Contact's Fax#:		Date Signed:
				4/20/2022
	empt from disclosure because it qui ime of submittal to the District.	nd any supplemental do ualifies as a trade secre	ot, as defined in the District's Guideline	ay be disclosed to a third party. If you wish to as for Implementing the California Public Records

Mail To: SCAQMD P.O. Box 4944 Diamond Bar, CA 91765-0944

> Tel: (909) 396-3385 www.aqmd.gov

Section A - Operator Info	rmation			
Tacility Name (Business Name of Operator To Appears On The Permit): Valid AQMD Facility ID (Available On Permit Or Invoice Issued By AQMD):				
AES Alamitos, LLC 115394				
Address where the equipmen	t will be operated (for equipment which will be moved to various l	location in AQMD's jurisdiction, please list the initial location site):		
690 N. Studebaker	Rd., Long Beach, CA 90803 East Engine	Fixed Location		
Section B - Location Data	a			
Plot Plan	Please attach a site map for the project with distances and scales Thomas Brothers page, a web-based map, or a sketch that show	s. Identify and locate the proposed equipment on the map. A copy of the appropriate s the major streets and location of the equipment is acceptable.		
	Is the facility located within a 1/4 mile radius (1,320 feet) of the lf yes, please provide name(s) of school(s) below: School Name: Charles F Kettering			
	School Address: 550 Silvera Ave.	School Address:		
Location of Schools Nearby	Long Beach, CA 90803			
	Distance from stack or equipment vent to the outer boundary of the school: 2,181	Distance from stack or equipment vent feet to the outer boundary of the school: feet		
		or private school used for purposes of the education of more than 12 children in ude any private school in which education is primarily conducted in private homes.		
Population Density	Urban	unted for by urban land use categories, i.e., multi-family dwelling or industrial.)		
	Mixed Use Residential Commercial Zone (M-U)	○ Service and Professional Zone (C-S)		
Zoning Classification	Heavy Commercial (C-4)	Commercial Manufacturing (C-M)		
ection C - Emission Release Parameters - Stacks, Vents				
	Stack Height: 15.33 feet (above ground level)	What is the height of the closest building nearest the stack?		
	Stack Inside Diameter: 10.75 inches	Stack Flow: 6,397 acfm Stack Temperature: 918 €		
	Rain Cap Present: Yes • No	Stack Orientation: Vertical Horizontal		
Stack Data	If the stack height is less than 2.5 times the closest building heig (attach additional sheet if necessary):	ht (H), please provide information on any building within 5xH distance from the stack		
	Building #/Name:	Building #/Name:		
	Building Height:feet (above ground level)	Building Height:feet (above ground level)		
	Building Width:feet	Building Width:feet		
	Building Length:feet	Building Length:feet		
Receptor Distance From Equipment Stack or Roof	Distance to nearest residence or sensitive receptor*:	1,500 feet		
Vents/Openings	Distance to nearest business:	820 feet		
	Are the emissions released from vents and/or openings from If yes, please provide:	n a building? Yes • No		
Building Information	Building #/Name:	Building Width:feet		

Building Length: _

Building Height: _____feet (above ground level)

^{*}AQMD Rule 1470 defines SENSITIVE RECEPTOR as meaning any residence including private homes, condominiums, apartments, and living quarters, schools as defined under paragraph (b)(57), preschools, daycare centers and health facilities such as hospitals or retirement and nursing homes. A sensitive receptor includes long term care hospitals, hospices, prisons, and dormitories or similar live-in housing.

South Coast Air Quality Management District

Form 400-PS

Plot Plan And Stack Information Form

This form must be accompanied by a completed Application for a Permit to Construct/Operate - Form 400A and Form 400-CEQA.

Section D - Authorization/Signa	ature	70.000		Property of the Control of the Contr
I hereby certify that all information of	contained herein and informatio	n submittfgfed with th	nis application is true and correct.	
Signature of Preparer:	Title of Preparer:		Preparer's Phone #: (949) 573-5122	
Engineer,		Preparer's Pnone #: (Volume of the control of the c		
Contact Person: Charlene He Contact's Email: charlene.he@aes.com		Contact's Phone#: (562) 493-7835 Contact's Fax#:		Date Signed:
				4/20/2022
	empt from disclosure because it qui ime of submittal to the District.	nd any supplemental do ualifies as a trade secre	ot, as defined in the District's Guideline	ay be disclosed to a third party. If you wish to as for Implementing the California Public Records

South Coast Air Quality Management District

Form 400-A

Application Form for Permit or Plan Approval List only one piece of equipment or process per form.

Mail To: SCAQMD P.O. Box 4944 Diamond Bar, CA 91765-0944

> Tel: (909) 396-3385 www.aqmd.gov

Section A - Operator Information				
1. Facility Name (Business Name of Operator to Appear on the Permit):	2. Valid AQMD Facility ID (Available On			
AES Alamitos, LLC	Permit Or Invoice Issued By AQMD):			
3. Owner's Business Name (If different from Business Name of Operator):	115394			
Section B - Equipment Location Address	Section C - Permit Mailing Address			
4. Equipment Location Is: Fixed Location Various Locatio				
(For equipment operated at various locations, provide address of initial site.)				
690 N. Studebaker Rd.	690 N. Studebaker Rd.			
Street Address	Address			
Long Beach , CA 90803	Long Beach , CA 90803			
City Zip	City State Zip			
Charlene He Environmental Manager Contact Name Title	Charlene He Environmental Manager Contact Name Title			
(562) 493-7835	(562) 493-7835			
Phone # Ext. Fax #	Phone # Ext. Fax #			
E-Mail: charlene.he@aes.com	E-Mail: charlene.he@aes.com			
Section D - Application Type				
6. The Facility Is: Not In RECLAIM or Title V In RECLAIM	☐ In Title V			
7. Reason for Submitting Application (Select only ONE):				
7a. New Equipment or Process Application: 7c. Equipment of	r Process with an Existing/Previous Application or Permit:			
New Construction (Permit to Construct) Administrativ	e Change			
Equipment On-Site But Not Constructed or Operational Alteration/Mo	Fulation of Basilians			
.(BEC) 그렇게 모임.() : [1] [1] [1] [1] [1] [1] [1] [1	odification without Prior Approval *			
Compliance Plan Change of C	If you checked any of the items in			
	dition without Prior Approval * 7c., you MUST provide an existing Permit or Application Number:			
Streamlined Standard Permit Change of Li				
Change of L	ocation without Prior Approval *			
Faultoment C	perating with an Expired/Inactive Permit *			
Title V Application or Amendment (Refer to Title V Matrix)	peraing with an Expired/mactive Fermit			
The second of th	rocessing Fee and additional Annual Operating Fees (up to 3 full years) may apply (Rule 301(c)(1)(D)(i)).			
	f Construction (mm/dd/yyyy): 8c. Estimated Start Date of Operation (mm/dd/yyyy): 30/2023 05/01/2023			
9. Description of Equipment or Reason for Compliance Plan (list applicable rule):	10. For Identical equipment, how many additional			
Title V and RECLAIM facility permit amendment for two emergency generators.	applications are being submitted with this application? (Form 400-A required for each equipment / process)			
11. Are you a Small Business as per AQMD's Rule 102 definition?	12. Has a Notice of Violation (NOV) or a Notice to			
(10 employees or less and total gross receipts are \$500,000 or less OR a not-for-profit training center) No Yes	Comply (NC) been issued for this equipment? If Yes, provide NOV/NC#:			
Section E - Facility Business Information				
13. What type of business is being conducted at this equipment location? Generation, Electric Power	14. What is your business primary NAICS Code? (North American Industrial Classification System) 221112			
15. Are there other facilities in the SCAQMD jurisdiction operated by the same operator?	16. Are there any schools (K-12) within 1000 feet of the facility property line? No Yes			
	ontained herein and information submitted with this application are true and correct.			
17. Signature of Responsible Official: 18. Title of Respons	ible Official: 19. I wish to review the permit prior to issuance. This may cause a delay in the			
V.P, AES So	outhland Energy application process.) Yes			
20. Print Name: 21. Date: 04/1	22. Do you claim confidentiality of data? (If Yes, see instructions.) • No Yes			
23. Check List: Authorized Signature/Date Form 400-CEQA	■ Supplemental Form(s) (ie., Form 400-E-xx) ■ Fees Enclosed			
AOMD USE ONLY APPLICATION TRACKING # CHECK # AMOUNT RECEIVED \$	PAYMENT TRACKING # VALIDATION			
DATE APP DATE APP CLASS BASIC EQUIPMENT CATEGOR	RY CODE TEAM ENGINEER REASON/ACTION TAKEN			



South Coast Air Quality Management District Form 400-CEQA California Environmental Quality Act (CEQA) Applicability

Mail To: SCAQMD P.O. Box 4944 Diamond Bar, CA 91765-0944

> Tel: (909) 396-3385 www.aqmd.gov

The SCAQMD is required by state law, the California Environmental Quality Act (CEQA), to review discretionary permit project applications for potential air quality and other environmental impacts. This form is a screening tool to assist the SCAQMD in clarifying whether or not the project ¹ has the potential to generate significant adverse environmental impacts that might require preparation of a CEQA document [CEQA Guidelines § 15060(a)]. Form 400-CEQA and the instructions for guidance on completing this form are available at http://www.aqmd.gov/home/permits/permit-application-forms. For each Form 400-A application, also complete and submit one Form 400-CEQA. If submitting multiple Form 400-A applications for the same project at the same time, only one Form 400-CEQA is necessary for the entire project. If you need assistance completing this form, contact Permit Services at (909) 396-3385.

Secti	ion A -	Facil	ity Information		
1. Fac	cility Na	ame (l	Business Name of Operator to Appear on the Permit):	2. SCAQMD Facility ID:	
A	ES Ala	amito	s, LLC	115394	
	wo Er		tion: ency IC Engines		
Secti	ion B -	Revi	ew For Exemption From Further CEQA Action		
Chec comp	k "Yes olete S	" or " ection	No" as applicable. If "Yes" is checked for any question in D - Signatures.	n Section B, skip Section C and proceed to page 2 and	
	Yes	No	Is this application for:		
1.	0	0	A request for a change of operator only (without equipment	nt or process change modifications)?	
2.	0	0	A functionally identical permit unit replacement with no in	crease in equipment unit rating or emissions?	
3.	0	0	A change of daily VOC permit limit to a monthly VOC perm	it limit?	
4.	0	0	Equipment damaged as a result of a disaster during state of	f emergency?	
5.	0	0	A Title V (e.g., SCAQMD Regulation XXX) permit renewal w	ithout equipment or process change modifications?	
6.	0	0	A Title V administrative permit revision?		
7.	0	0	The conversion of an existing permit into an initial Title V p	permit?	
Secti	on C -	Revie	ew of Impacts Which May Trigger Further CEQA Review	V	
Chec sheet	k "Yes t and a	or "	No" as applicable. To avoid delays in processing your apit to this form.	oplication(s), explain all "Yes" responses on a separate	
	Yes	No			
1.	0	0	Is this project specifically evaluated in a previously certified If "Yes" is checked, attach a copy of the signed Notice of Determination		
2.	0	0	Is this project specifically exempted from CEQA by another If "Yes" is checked, attach a copy of the signed Notice of Exemption		
3.	0	0	Is this project part of a larger project? If "Yes" is checked, atta	ach a separate sheet to briefly describe the larger project.	
4.	0	0	Will the project increase the QUANTITY of hazardous materials stored aboveground onsite or transported by mobile vehicle to or from the site by greater than or equal to the amounts associated with each compound listed on Form 40 CEQA, Table 1 - Regulated Substances List and Threshold Quantities for Accidental Release Prevention [http://www.aqmd.gov/home/regulations/ceqa/ceqa-permit-forms]? If "Yes" is checked, attach a separate sheet to identify each hazardous material and corresponding quantity to be transported, stored, or used.		
5.	0	0		, Table 2 - Other Air Toxics and Their Screening Levels [http:// 'Yes" is checked, attach a separate sheet to identify each air toxic and	
6.	0	0	Will the project require any demolition, excavation, and/or exceeding 20,000 square feet?	grading construction activities that encompass an area	

¹ A "project" means the whole of an action which has a potential for resulting in physical change to the environment, including construction activities, clearing or grading of land, improvements to existing structures, and activities or equipment involving the issuance of a permit. For example, a project might include installation of a new, or modification of an existing internal combustion engine, dry cleaning facility, boiler, gas turbine, spray coating booth, solvent cleaning tank, etc.

existing internal combustion engine, dry cleaning facility, boiler, gas turbine, spray coating booth, solvent cleaning tank, etc.

Form 400-CEQA, Table 2 – Other Air Toxics and Their Screening Levels, contains a list of air toxics that either do not have a cancer potency (CP) or reference exposure level (REL) approved by the Office of Environmental Health Hazards Assessment (OEHHA) or have a combination of OEHHA-approved and non-approved CPs or RELs.

Secti	ion C -	- Revi	ew of Impacts Which May Trigger Further CEQA	A (concluded)		
	Yes	No				
7.	0	0	liquefied petroleum gas (LPG), or landfill gas)? If " fuel use via on the Greenhouse Gas (GHG) online estimate	ombustion equipment that uses fuel (e.g., gasoline, diesel, natural gas, "Yes" is checked, then the applicant will need to calculate the amount of GHGs from tor [http://www.aqmd.gov/home/regulations/cega/cega-permit-forms], and s and providing the documentation. Refer to the Instructions for Form 400-CEQA for		
8.	0	0	chemicals listed on Form 400-CEQA, Table 3 - Gree	not addressed in Question 7 that require the use of, or will generate, any enhouse Gases [http://www.aqmd.gov/home/regulations/ceqa/ceqa-permit-lentify each equipment unit, the chemical name(s), and the quantity of each		
9.	0	0	Will the project include the open outdoor storage if "Yes" is checked, include a plot plan with the application	of dry bulk solid materials that could generate dust? on package.		
10.	0	0	permit requirements? For example, landfills, materials	e off-site odors from activities that may not be subject to SCAQMD is recovery/recycling facilities (MRF), and compost materials or other types of we the potential to generate odor complaints subject to SCAQMD Rule 402 –		
11.	0	0	Will the project cause an increase of emissions from	om marine vessels, trains and/or airplanes?		
12.	0	0	The following examples identify some, but not all, types generates steam; 2) a project that uses water as part of or the production process; 4) a project that requires a new, lines, sewage hook-ups etc.; 5) a project where the water for the project; 6) a project that requires new or the expenses.	roject increase demand for potable water at the facility by more than 262,820 gallons per day? It is examples identify some, but not all, types of projects that may result in a "Yes" answer to this question: 1) a project that sam; 2) a project that uses water as part of operating air pollution control equipment; 3) a project that requires water as part of in process; 4) a project that requires a new, or the expansion of an existing, sewage treatment facility, new water lines, sewage hook-ups etc.; 5) a project where the water demand exceeds the capacity of the local water purveyor to supply sufficient water ct; 6) a project that requires new or the expansion of existing, water supply and conveyance facilities; and, 7) a project that it to hydrotest pipelines, storage tanks etc. for structural integrity.		
13.	0	0		/ill the project create an increase in the mass inflow of effluents to a public wastewater treatment facility that would equire a new, or revision to an existing, National Pollutant Discharge Elimination System (NPDES) or other related pern		
14.	0	0	Will the project result in the need for more than 35	50 new employees?		
15.	0	0	Will the project result in an increase in heavy-duty truck round-trips per day?	y transport truck traffic to and/or from the facility by more than 350		
16.	0	0	Will the project result in an increase in customer tr	raffic by more than 700 visits per day?		
17.	0	0	Will the project result in temporary or permanent noise ordinance?	noise or vibration in excess of what is allowed by the applicable local		
18.	0	0	Will the project create a permanent need for new of Check "No" if the projected potential amount of solid wast	or additional solid waste disposal? ste to be generated by the project is less than five tons per day.		
19.	0	0	Will the project create a permanent need for new of Check "No" if the projected potential amount of hazardous equivalent in pounds).	or additional hazardous waste disposal? us wastes to be generated by the project is less than 42 cubic yards per day (or		
20.	0	0	Will the project include equipment that after instal surroundings or block views?	allation or modification will change the visual character of the site and its		
21.	0	0	Will the project have equipment that will create a	new source of external lighting that will be visible at the property line?		
Section	on D –	SIGN	IATURES			
UNDERS	BY CERTIF STAND T ABILITY.	Y THAT HAT TH	ALL INFORMATION CONTAINED HEREIN AND INFORMATION SUBMIS FORM IS A SCREENING TOOL AND THAT THE SCAQMD RESE	MITTED WITH THIS APPLICATION IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE. I RVES THE RIGHT TO CONSIDER OTHER PERTINENT INFORMATION IN DETERMINING CEQA		
		lesponsi	ible Official of Firm	2. Title of Responsible Official of Firm: Vice President, AES Southland Energy		
3. Print	Name of	Respon	nsible Official of Firm: Weikko Wirta	4. Date Signed: 04/18/2022		
(71	14) 374	4-1421		7. Email of Responsible Official of Firm: Weikko.wirta@aes.com		
8. Signa	ture of P	reparer,	r, (If prepared by person other than responsible official of firm):	9. Title of Preparer:		
10. Prin	nt Name o	of Prepa	rer: O. His I and the last	Engineer 11. Date Signed: L/ / 2 / 2 2 2		
12. Pho	ne # of P	renarer	Collin Lundquist	11. Date Signed: 4/25/2022		
	2. Phone # of Preparer: 13. Fax # of Preparer: (949) 573-5122			clundquist@yorkeengr.com		



Mail To: SCAQMD P.O. Box 4944 Diamond Bar, CA 91765-0944

> Tel: (909) 396-3385 www.aqmd.gov

Section I - Operator Information			
1. Facility Name (Business Name of Operator)	That Appears On Permit):	2. Valid AQMD Facility	ID (Available On Permit Or Invoice
AES Alamitos, LLC		Issued By AQMD):	115394
3. This Certification is a. Ti	tle V Application (Initial, Revision or	Renewal)	
out mitted with a /o	upplement/Correction to a Title V Ap		
	ACT Part 1	P. 100 P.	
J	NOT I CIT I		
4. Is Form 500-C2 included with this Certif	Section 2 O Ver O Ne		
Section II - Responsible Official Certificat			
Read each statement carefully and check each		Ba or 3b.	
1. For Initial, Permit Renewal, and Admini			
a. O The facility, including equipment		per Rule 219, is currently operati	ing and will continue to operate in
	ments that do not specifically pertai		and that have been identified as
 ii. <u>except</u> for those devices operating in compliance v 	or equipment that have been ident with the specified applicable requirer	ified on the completed and attac ment(s).	hed Form 500-C2 that will not be
 The facility, including equipment requirements with future effective 	t that are exempt from written per dates.	rmit per Rule 219, will meet in	a timely manner, all applicable
2. For Permit Revision Application Certific	cations:		
 The equipment or devices to w identified in Section II and Section 	hich this permit revision applies, on III of Form 500-C1.	will in a timely manner comply	with all applicable requirements
3. For MACT Hammer Certifications:			
 The facility is subject to Section following information is submitted 	112(j) of the Clean Air Act (Subpart with a Title V application to comply	B of 40 CFR part 63), also know with the Part 1 requirements of S	wn as the MACT "hammer." The ection 112(j).
b. The facility is not subject to Section	on 112(j) of the Clean Air Act (Subpa	art B of 40 CFR part 63).	
Section III - Authorization/Signature			
I certify under penalty of law that I am the responsible	e official for this facility as defined in AQM	ID Regulation XXX and that based on i	nformation and belief formed after
reasonable inquiry, the statement and information in 1. Signature of Responsible Official:			, accurate, and complete.
1. Signature of Responsible Official.		of Responsible Official: President, AES Southland	Energy
3. Print Name:	4. Date:	2 1 1 -	
Weikko Wirta		09/18/2	022
5. Phone #: (714) 374-1421	6. Fax #		
7. Address of Responsible Official:			
690 N. Studebaker Rd.		Long Beach CA	90803
Street #	Gity	State	Zip

Acid Rain facilities must certify their compliance status of the devices subject to applicable requirements under Title IV by an individual who meets the definition of Designated (or Alternate) Representative in 40 CFR Part 72.

Section IV - Designated Representative Certification Statemer	t		
For Acid Rain Facilities Only: I am authorized to make this sub- affected units for which the submission is made. I certify unde statements and information submitted in this document and all responsibility for obtaining the information, I certify that the state accurate, and complete. I am aware that there are significant po- required statements and information, including the possibility	r penalty of law that I have persor its attachments. Based on my in atements and information are to tl enalties for submitting false stater	nally examined, quiry of those in he best of my kn	and am familiar with, the ndividuals with primary nowledge and belief true.
Signature of Designated Representative or Alternate.	Title of Designated Representat Vice President, AES S		rgy
Print Name of Designated Representative or Alternate: Weikko Wirta	4. Date: 04/1	P/202	2
5. Phone #:	6. Fax #:		
(714) 374-1421			
7. Address of Designated Representative or Alternate:			
690 N. Studebaker Rd.	Long Beach	CA	90803
Street#	City	State Zip	

South Coast Air Quality Management District

Form 500-C1

Title V Compliance Status Report

To provide the compliance status of your facility with applicable federally enforceable requirements and identify other local-only requirements, complete this form and attach it to a completed compliance certification Form 500-A2. As appropriate, all submittals of Form 500-C2 as appropriate should also be attached to this form.

Mail To: SCAQMD P.O. Box 4944 Diamond Bar, CA 91765-0944

> Tel: (909) 396-3385 www.aqmd.gov

Section I - Operator Information

1. Facility Name (Business Name of Operator That Appears On Permit):

AES Alamitos, LLC

 Valid AQMD Facility ID (Available On Permit Or Invoice Issued By AQMD):

115394

PROCEDURES FOR DETERMINING COMPLIANCE STATUS

- Equipment verification: Review the list of pending applications, and either the preliminary Title V facility permit or the list of current permits to operate that the AQMD provided you, to
 determine if they completely and accurately describe all equipment operating at the facility. Attach a statement to describe any discrepancies.
- Identify applicable requirements*: Use the checklist in Section II to identify all applicable and federally-enforceable local, state, and federal rules and regulations, test methods, and monitoring, recordkeeping and reporting (MRR) requirements that apply to any equipment or process (including equipment exempt from a permit by Rule 219) at your facility.
 The potential applicable requirements, test methods and MRR requirements are identified and listed adjacent to each given equipment/process description. Check off each box adjacent to the corresponding requirement as it applies to your particular equipment/process.
 - Note: Even if there is only one piece of equipment that is subject to a particular requirement, the appropriate box should be checked.
- Identify additional applicable requirements*: Use Section III to identify any additional requirements not found in Section II. Section II is not a complete list of all applicable requirements. It does not include recently adopted NESHAP regulations by EPA or recent amendments to AQMD rules. Do not add rules listed in Section V here.
- 4. Identify any requirements that do not apply to a specific piece of equipment or process: Also use Section III to identify any requirements that are listed in Section II but that do not apply to a specific piece of equipment or process. Fill out Section III of this form and attach a separate sheet to explain the reason(s) why the identified rules do not apply. Note: Listing any requirement that does not apply to a specific piece of equipment will not provide the facility with a permit shield unless one is specifically requested by completing Form 500-D and is approved by AQMD.
- 5. Identify SIP-approved rules that are not current AQMD rules: Use Section IV to identify older versions of current AQMD rules that are the EPA-approved versions in the State Implementation Plan (SIP), and that are still applicable requirements as defined by EPA. The facility is <u>not</u> required to certify compliance with the items checked in Section IV provided that the non-SIP approved rule in Section II is at least as stringent as the older SIP-approved version in Section IV.
- 6. Identify Local-Only Enforceable Regulatory Requirements: Use Section V to identify AQMD rules that are not SIP-approved and are not federally enforceable.
- Determine compliance: Determine if all equipment and processes are complying with all requirements identified in Sections II and III. If each piece of equipment complies with all applicable requirements, complete and attach Form 500-A2 to certify the compliance status of the facility. If any piece of equipment is not in compliance with any of the applicable requirements, complete and attach Form 500-C2 in addition to Form 500-A2.
- * The following AQMD rules and regulations are not required to be included in Section II and do not have to be added to Section III: Regulation I, List and Criteria in Regulation II, Rule 201, Rule 201, Rule 201, Rule 202, Rule 203, Rule 205, Rule 206, Rule 207, Rule 208, Rule 209, Rule 210, Rule 212, Rule 214, Rule 215, Rule 216, Rule 217, Rule 219, Rule 220, Rule 221, Regulation III, Regulation VIII, Regulation XVI, Regulation XVI, Regulation XVI, Regulation XXI, Regulation XXII, and Regulation XXX.
- ** Emission units adversely affected by the gap between current and SIP-approved versions of rules may initially be placed in a non-Title V portion of the permit

Section II - Applicable Requirements, Tes	st Methods, & MRR Requirements		
Equipment/Process	Applicable Requirement	Test Method	MRR Requirement
All Air Pollution Control Equipment Using Combustion (RECLAIM & non-RECLAIM sources)	Rule 480 (10/07/77)	N/A	N/A
All Coating Operations (12/15/00)	Rule 442	Rule 442(f)	Rule 442(g)
All Combustion Equipment, ≥ 555 Mmbtu/Hr (except for NOx RECLAIM sources)	Rule 474 (12/04/81)	AQMD TM 7.1 or 100.1	
All Combustion Equipment Except Internal	Rule 407 (04/02/82)	✓ AQMD TM 100.1 or 10.1, 307-91	
Combustion Engines (RECLAIM & non-RECLAIM sources)	Rule 409 (08/07/81)	✓AQMD TM 5.1, 5.2, or 5.3	
All Combustion Equipment Using Gaseous Fuel (except SOx RECLAIM sources)	Rule 431.1 (06/12/98)	Rule 431.1(f)	Rule 431.1(d) & (e)
All Combustion Equipment Using Liquid Fuel (except SOx RECLAIM sources)	Rule 431.2 (09/15/00)	Rule 431.2(g)	Rule 431.2(f)
All Combustion Equipment Using Fossil Fuel (except SOx RECLAIM sources)	Rule 431.3 (05/07/76)		
All Equipment	Rule 401 (11/09/01)	California Air Resources Board Visible Emission Evaluation	
	Rule 405 (02/07/86)	✓ AQMD TM 5.1, 5.2, or 5.3	
	Rule 408 (05/07/76)	N/A	√ Rule 430(b)
	Rule 430 (07/12/96)	N/A	▼ Kule 430(b)
	Rule 701 (06/13/97)		
	New Source Review, BACT		
	✓ Rule 1703 (10/07/88)		
	40 CFR68 - Accidental Release Prevention	See Applicable Subpart	See Applicable Subpart
All Equipment Processing Solid Materials	Rule 403 (06/03/05)	Rule 403(d)(3)	Rule 403(f)
All Equipment With Exhaust Stack (except cement kilns subject to Rule 1112.1)	Rule 404 (02/07/86)	AQMD TM 5.1, 5.2, or 5.3	
All Facilities Using Solvents to Clean Various	Rule 109 (05/02/03)	√ Rule 109(g)	√ Rule 109(c)
Items or Equipment	√ Rule 1171 (05/01/09)	√ Rule 1171(e)	√ Rule 1171(c)(6)
	40 CFR63 SUBPART T	See Applicable Subpart	See Applicable Subpart
All RECLAIM Equipment (NOx & SOx)	Reg. XX - RECLAIM	Rule 2011, App. A (05/06/05) Rule 2012, App. A (05/06/05)	Rule 2011, App. A (05/06/05) Rule 2012, App. A (05/06/05)
Abrasive Blasting	Rule 1140 (08/02/85)	Rule 1140(d) & (e), AQMD Visible Emission Method	

KEY ABBREVIATIONS: Reg. = AQMD Regulation App. = Appendix Rule = AQMD Rule AQMD TM = AQMD T	CFR = Code of Federal Regulations Method CCR = California Code of Regulations
---	---

Equipment/Process	Applicable Requirement	Test Method	MRR Requirement
Aggregate and Related Operations	Rule 1157 (09/08/06)	Rule 1157(f)	Rule 1157(e)
Appliances Containing Ozone Depleting Substances (except Motor Vehicle Air Conditioners): Manufacturing, Repair, Maintenance, Service, & Disposal	40 CFR82 SUBPART F	See Applicable Subpart	See Applicable Subpart
Asphalt	See Manufacturing, Asphalt Processing & Aspl	nalt Roofing	
Asphalt Concrete/Batch Plants	40 CFR60 SUBPART I	See Applicable Subpart	See Applicable Subpart
Benzene Emissions, Maleic Anhydride Plants, Ethylbenzene/Styrene Plants, Benzene Storage Vessels, Benzene Equipment Leaks, & Coke By-Product Recovery Plants	Rule 1173 (02/06/09) Rule 1176 (09/13/96) 40 CFR61 SUBPART L 40 CFR63 SUBPART R 40 CFR63 SUBPART C	Rule 1173(j) Rule 1176(h) See Applicable Subpart See Applicable Subpart See Applicable Subpart See Applicable Subpart	Rule 1173(i) Rule 1176(f) & (g) See Applicable Subpart See Applicable Subpart See Applicable Subpart See Applicable Subpart
Benzene Transfer Operations	Rule 1142 (07/19/91) 40 CFR61 SUBPART BB 40 CFR63 SUBPART Y	Rule 1142(e) See Applicable Subpart See Applicable Subpart	Rule 1142(h) See Applicable Subpart See Applicable Subpart
Benzene Waste Operations	Rule 1176 (09/13/96) 40 CFR61 SUBPART FF 40 CFR63 SUBPART CC	Rule 1176(h) See Applicable Subpart See Applicable Subpart	Rule 1176(f) & (g) See Applicable Subpart See Applicable Subpart
Beryllium Emissions	40 CFR61 SUBPART C	See Applicable Subpart	See Applicable Subpart
Beryllium Emissions, Rocket Motor Firing	40 CFR61 SUBPART D	See Applicable Subpart	See Applicable Subpart
Boiler, < 5 Mmbtu/Hr (non-RECLAIM sources)	Rule 1146.1 (09/05/08) Rule 1146.2 (05/05/06) 40 CFR63 SUBPART DDDDD	Rule 1146.1(d) N/A See Applicable Subpart	Rule 1146.1(c)(2) & (c)(3) N/A See Applicable Subpart
Boiler, < 5 Mmbtu/Hr (RECLAIM sources)	Rule 1146.1 (09/05/08) - excluding NOx requirements 40 CFR63 SUBPART DDDDD	Rule 1146.1(d) See Applicable Subpart	Rule 1146.1(c)(2) & (c)(3) See Applicable Subpart

Section II - Applicable Requirements, Test Methods, & MRR Requirements			
Equipment/Process	Applicable Requirement	Test Method	MRR Requirement
Boiler, ≥ 5 Mmbtu/Hr (non-RECLAIM sources)	Rule 218 (05/14/99) Rule 429 (12/21/90) Rule 475 (08/07/78)	AQMD TM 100.1 N/A AQMD TM 5.1, 5.2, or 5.3 AQMD TM 7.1, 100.1, 5.1, 5.2, or 5.3	Rule 218(e) & (f) Rule 429(d)
	Rule 476 (10/08/76) Rule 1146 (09/05/08) 40 CFR60 SUBPART D 40 CFR60 SUBPART Dc 40 CFR63 SUBPART DDDDD	Rule 1146(d) See Applicable Subpart See Applicable Subpart See Applicable Subpart See Applicable Subpart	Rule 1146(c)(6) & (c)(7) See Applicable Subpart See Applicable Subpart See Applicable Subpart See Applicable Subpart
Boiler, ≥ 5 Mmbtu/Hr (RECLAIM sources)	Rule 475 (08/07/78) Rule 476 (10/08/76) - excluding NOx requirements Rule 1146 (09/05/08) - excluding NOx requirements Rule 2011 (05/06/05) Or Rule 2012 (05/06/05) 40 CFR60 SUBPART D 40 CFR60 SUBPART Dc 40 CFR63 SUBPART DDDDD	AQMD TM 5.1, 5.2, or 5.3 AQMD TM 7.1, 100.1, 5.1, 5.2, or 5.3 Rule 1146(d) Rule 2011, App. A (05/06/05) Rule 2012, App. A (05/06/05) See Applicable Subpart See Applicable Subpart See Applicable Subpart See Applicable Subpart	Rule 1146(c)(6) & (c)(7) Rule 2011, App. A (05/06/05) Rule 2012, App. A (05/06/05) See Applicable Subpart See Applicable Subpart See Applicable Subpart See Applicable Subpart
Boiler, Petroleum Refining (non-RECLAIM sources)	Rule 218 (05/14/99) Rule 429 (12/21/90) Rule 431.1 (06/12/98) Rule 475 (08/07/78) Rule 1146 (09/05/08) 40 CFR60 SUBBPART J 40 CFR63 SUBPART DDDDD	AQMD TM 100.1 N/A Rule 431.1(f) AQMD TM 5.1, 5.2, or 5.3 Rule 1146(d) See Applicable Subpart See Applicable Subpart	Rule 218(e) & (f) Rule 429(d) Rule 431.1(d) & (e) Rule 1146(c)(6) & (c)(7) See Applicable Subpart See Applicable Subpart

KEY ABBREVIATIONS: Reg. = AQMD Regulation App. = Appendix Rule = AQMD Rule AQMD TM = AQMD Te	CFR = Code of Federal Regulations Method CCR = California Code of Regulations
--	---

Section II - Applicable Requirements, Test Methods, & MRR Requirements			
Equipment/Process	Applicable Requirement	Test Method	MRR Requirement
Boiler, Petroleum Refining (RECLAIM sources)	Rule 1146 (09/05/08) - excluding NOx requirements Rule 2011 (05/06/05) Or Rule 2012 (05/06/05) 40 CFR60 SUBPART J 40 CFR63 SUBPART DDDDD	Rule 1146(d) Rule 2011, App. A (05/06/05) Or Rule 2012, App. A (05/06/05) See Applicable Subpart See Applicable Subpart	Rule 1146(c)(6) & (c)(7) Rule 2011, App. A (05/06/05) Or Rule 2012, App. A (05/06/05) See Applicable Subpart See Applicable Subpart
Boilers, Electric Utility (non-RECLAIM sources)	Rule 218 (05/14/99) Rule 429 (12/21/90) Rule 1135 (07/19/91) 40 CFR60 SUBPART Db 40 CFR63 SUBPART DDDDD	AQMD TM 100.1 N/A Rule 1135(e) See Applicable Subpart See Applicable Subpart	Rule 218(e) & (f) Rule 429(d) Rule 1135(e) See Applicable Subpart See Applicable Subpart
Boilers, Electric Utility (RECLAIM sources)	Rule 2012 (05/06/05) 40 CFR60 SUBPART Db 40 CFR63 SUBPART DDDDD	Rule 2012, App. A (05/06/05) See Applicable Subpart See Applicable Subpart	Rule 2012, App. A (05/06/05) See Applicable Subpart See Applicable Subpart
Bulk Loading Of Organic Liquids	Rule 462 (05/14/99) 40 CFR60 SUBPART XX 40 CFR63 SUBPART R 40 CFR63 SUBPART BBBBBB 40 CFR63 SUBPART EEEE	Rule 462(f) See Applicable Subpart See Applicable Subpart See Applicable Subpart See Applicable Subpart	Rule 462(g) See Applicable Subpart See Applicable Subpart See Applicable Subpart See Applicable Subpart
Cadmium Electroplating Operation	Rule 1426 (05/02/03)		Rule 1426(e)
Calciner, Mineral Industries Calciner, Petroleum Coke	40 CFR60 SUBPART UUU Rule 477 (04/03/81) Rule 1119 (03/02/79) 40 CFR63 SUBPART L	See Applicable Subpart AQMD Visible Emissions, AQMD TM 5.1, 5.2, or 5.3 AQMD TM 6.1 or 100.1 See Applicable Subpart	See Applicable Subpart See Applicable Subpart
Charbroilers	Rule 1174 (10/05/90) Rule 1138 (11/14/97)	AQMD Test Protocol Rule 1138(g)	Rule 1138(d)
Chrome Plating & Chromic Acid Anodizing Operation	Rule 1426 (05/02/03) Rule 1469 (12/05/08)	Rule 1469(e)	Rule 1426(e) Rule 1469(g), (j) & (k)

KEY ABBREVIATIONS: Reg. = AQMD Regulation App. = Appendix AQMD TM = AQMD Test Methods	CFR = Code of Federal Regulations CCR = California Code of Regulations
---	--

Section II - Applicable Requirements, Test Methods, & MRR Requirements			
Equipment/Process	Applicable Requirement	Test Method	MRR Requirement
Coating Operation, Adhesive Application	Rule 109 (05/02/03)	Rule 109(g)	Rule 109(c)
Operation	Rule 481 (01/11/02)	Rule 481(d)	
	Rule 1132 (05/05/06)	Rule 1132(f)	Rule 1132(g)
	Rule 1168 (01/07/05)	Rule 1168(f) & (e)	Rule 1168(d)
	Rule 1171 (05/01/09)	Rule 1171(e)	Rule 1171(c)(6)
	40 CFR60 SUBPART RR	See Applicable Subpart	See Applicable Subpart
Coating Operation, Aerospace Assembly &	Rule 109 (05/02/03)	Rule 109(g)	Rule 109(c)
Component Manufacturing	Rule 481 (01/11/02)	Rule 481(d)	
	Rule 1124 (09/21/01)	Rule 1124(e) & (f)	Rule 1124(j) & (d)
	Rule 1132 (05/05/06)	Rule 1132(f)	Rule 1132(g)
	Rule 1171 (05/01/09)	Rule 1171(e)	Rule 1171(c)(6)
	40 CFR63 SUBPART GG	See Applicable Subpart	See Applicable Subpart
Coating Operation, Graphic Arts (Gravure,	Rule 109 (05/02/03)	Rule 109(g)	Rule 109(c)
Letter Press, Flexographic & Lithographic Printing Process, Etc.)	Rule 481 (01/11/02)	Rule 481(d)	
Tillung Frocess, Etc.)	Rule 1130 (10/08/99)	Rule 1130(h)	Rule 1130(e)
	Rule 1132 (05/05/06)	Rule 1132(f)	Rule 1132(g)
	Rule 1171 (05/01/09)	Rule 1171(e)	Rule 1171(c)(6)
	40 CFR60 SUBPART QQ	See Applicable Subpart	See Applicable Subpart
	40 CFR60 SUBPART RR	See Applicable Subpart	See Applicable Subpart
	40 CFR60 SUBPART FFF	See Applicable Subpart	See Applicable Subpart
	40 CFR60 SUBPART VVV	See Applicable Subpart	See Applicable Subpart
	40 CFR63 SUBPART KK	See Applicable Subpart	See Applicable Subpart
	40 CFR63 SUBPART JJJJ	See Applicable Subpart	See Applicable Subpart
Coating Operation, Magnet Wire Coating	Rule 109 (05/02/03)	Rule 109(g)	Rule 109(c)
	Rule 481 (01/11/02)	Rule 481(d)	<u> </u>
	Rule 1126 (01/13/95)	Rule 1126(d)	Rule 1126(c)(4)
	Rule 1132 (05/05/06)	Rule 1132(f)	Rule 1132(g)
	Rule 1171 (05/01/09)	Rule 1171(e)	☐ Rule 1171(c)(6)

KEY ABBREVIATIONS: Reg. = AQMD Regulation App. = Appendix Rule = AQMD Rule AQMD TM = AQMD Test Method	CFR = Code of Federal Regulations CCR = California Code of Regulations
---	--

Section II - Applicable Requirements, Test Methods, & MRR Requirements			
Equipment/Process	Applicable Requirement	Test Method	MRR Requirement
Coating Operation, Marine Coating (Except for	Rule 109 (05/02/03)	Rule 109(g)	Rule 109(c)
recreational equipment)	Rule 481 (01/11/02)	Rule 481(d)	
	Rule 1106 (01/13/95)	Rule 1106(e)	Rule 1106(c)(5)
	Rule 1132 (05/05/06)	Rule 1132(f)	☐Rule 1132(g)
	Rule 1171 (05/01/09)	Rule 1171(e)	Rule 1171(c)(6)
	40 CFR63 SUBPART II	See Applicable Subpart	See Applicable Subpart
Coating Operation, Metal Coating	Rule 109 (05/02/03)	Rule 109(g)	Rule 109(c)
	Rule 481 (01/11/02)	Rule 481(d)	
	Rule 1107 (01/06/06)	Rule 1107(e)	Rule 1107(j)
	Rule 1132 (05/05/06)	Rule 1132(f)	Rule 1132(g)
	Rule 1171 (05/01/09)	Rule 1171(e)	Rule 1171(c)(6)
	40 CFR60 SUBPART EE	See Applicable Subpart	See Applicable Subpart
	40 CFR60 SUBPART SS	See Applicable Subpart	See Applicable Subpart
	40 CFR63 SUBPART NNNN	See Applicable Subpart	See Applicable Subpart
	40 CFR63 SUBPART MMMM	See Applicable Subpart	See Applicable Subpart
	40 CFR63 SUBPART RRRR	See Applicable Subpart	See Applicable Subpart
Coating Operation, Metal Containers, Closure,	Rule 109 (05/02/03)	Rule 109(g)	Rule 109(c)
& Coil Coating Operations	Rule 481 (01/11/02)	Rule 481(d)	
	Rule 1125 (03/07/08)	Rule 1125(e)	☐Rule 1125(c)(6)
	Rule 1132 (05/05/06)	Rule 1132(f)	Rule 1132(g)
	Rule 1171 (05/01/09)	Rule 1171(e)	Rule 1171(c)(6)
	40 CFR60 SUBPART TT	See Applicable Subpart	See Applicable Subpart
	40 CFR60 SUBPART WW	See Applicable Subpart	See Applicable Subpart
	40 CFR63 SUBPART KKKK	See Applicable Subpart	See Applicable Subpart
	40 CFR63 SUBPART SSSS	See Applicable Subpart	See Applicable Subpart
Coating Operation, Motor Vehicle & Mobile	Rule 109 (05/02/03)	Rule 109(g)	Rule 109©
Equipment Non-Assembly Line Coating Operation	Rule 481 (01/11/02)	Rule 481(d)	□
- Operation	Rule 1132 (05/05/06)	Rule 1132(f)	☐Rule 1132(g)
	Rule 1151 (12/02/05)	Rule 1151(h)	Rule 1151(f)
	Rule 1171 (05/01/09)	Rule 1171(e)	Rule 1171(c)(6)

KEY ABBREVIATIONS:Reg. = AQMD Regulation
Rule = AQMD RuleApp. = Appendix
AQMD TM = AQMD Test MethodCFR = Code of Federal Regulations
CCR = California Code of Regulations

Section II - Applicable Requirements, Test Methods, & MRR Requirements			
Equipment/Process	Applicable Requirement	Test Method	MRR Requirement
Coating Operation, Motor Vehicle Assembly	Rule 109 (05/02/03)	Rule 109(g)	Rule 109(c)
Line	Rule 481 (01/11/02)	Rule 481(d)	
	Rule 1115 (05/12/95)	Rule 1115(e)	Rule 1115(g)
	Rule 1132 (05/05/06)	Rule 1132(f)	
	Rule 1171 (05/01/09)	Rule 1171(e)	Rule 1171(c)(6) See Applicable Subpart
	40 CFR60 SUBPART MM	See Applicable Subpart	
	40 CFR63 SUBPART IIII	See Applicable Subpart	See Applicable Subpart
Coating Operation, Paper, Fabric, & Film	Rule 109 (05/02/03)	Rule 109(g)	☐ Rule 109(c)
Coating Operations	Rule 481 (01/11/02)	Rule 481(d)	
	Rule 1128 (03/08/96)	Rule 1128(f)	Rule 1128(e)
	Rule 1132 (05/05/06)	Rule 1132(f)	Rule 1132(g)
	Rule 1171 (05/01/09)	Rule 1171(e)	Rule 1171(c)(6)
	40 CFR60 SUBPART VVV	See Applicable Subpart	See Applicable Subpart
	40 CFR63 SUBPART OOOO	See Applicable Subpart	See Applicable Subpart
Coating Operation, Plastic, Rubber, & Glass	Rule 109 (05/02/03)	Rule 109(g)	Rule 109(c)
	Rule 481 (01/11/02)	Rule 481(d)	
	Rule 1145 (12/04/09)	Rule 1145(e)	Rule 1145(d)
	Rule 1132 (05/05/06)	Rule 1132(f)	Rule 1132(g)
	Rule 1171 (05/01/09)	Rule 1171(e)	Rule 1171(c)(6) See Applicable Subpart
	40 CFR60 SUBPART TTT	See Applicable Subpart	
	40 CFR63 SUBPART NNNN	See Applicable Subpart	See Applicable Subpart
	40 CFR63 SUBPART PPPP	See Applicable Subpart	See Applicable Subpart
Coating Operation, Pleasure Craft	Rule 109 (05/02/03)	Rule 109(g)	Rule 109(c)
	Rule 481 (01/11/02)	Rule 481(d)	
	Rule 1106.1 (02/12/99)	Rule 1106.1(e)	Rule 1106.1(d)
	Rule 1132 (05/05/06)	Rule 1132(f)	Rule 1132(g)
	Rule 1171 (05/01/09)	Rule 1171(e)	Rule 1171(c)(6)
	40 CFR63 SUBPART II	See Applicable Subpart	See Applicable Subpart

KEY ABBREVIATIONS: Reg. = AQMD Regulation App. = Appendix Rule = AQMD Rule AQMD TM = AQMD Test Method	CFR = Code of Federal Regulations CCR = California Code of Regulations
---	--

Section II - Applicable Requirements, Test Methods, & MRR Requirements			
Equipment/Process	Applicable Requirement	Test Method	MRR Requirement
Coating Operation, Screen Printing	Rule 109 (05/02/03)	Rule 109(g)	Rule 109(c)
	Rule 1130.1 (12/13/96)	Rule 1130.1(g)	Rule 1130.1(c)(5)
	Rule 1132 (05/05/06)	Rule 1132(f)	Rule 1132(g)
	Rule 1171 (05/01/09)	Rule 1171(e)	Rule 1171(c)(6)
	40 CFR63 SUBPART KK	See Applicable Subpart	See Applicable Subpart
Coating Operation, Use Of Architectural	Rule 109 (05/02/03)	√ Rule 109(g)	√ Rule 109(c)
Coating (Stationary Structures)	Rule 481 (01/11/02)	√ Rule 481(d)	
	✓ Rule 1113 (07/13/07)	✓ Rule 1113(e)	
	Rule 1132 (05/05/06)	Rule 1132(f)	☐Rule 1132(g)
	✓ Rule 1171 (05/01/09)	Rule 1171(e)	Rule 1171(c)(6)
Coating Operation, Wood Flat Stock	Rule 109 (05/02/03)	Rule 109(g)	Rule 109(c)
	Rule 481 (01/11/02)	Rule 481(d)	
	Rule 1104 (08/13/99)	Rule 1104(e)	Rule 1104(d)
	Rule 1132 (05/05/06)	Rule 1132(f)	Rule 1132(g)
	Rule 1171 (05/01/09)	Rule 1171(e)	Rule 1171(c)(6)
	40 CFR63 SUBPART II	See Applicable Subpart	See Applicable Subpart
Coating Operation, Wood Products	Rule 109 (05/02/03)	Rule 109(g)	Rule 109(c)
(Commercial Furniture, Cabinets, Shutters, Frames, Toys)	Rule 481 (01/11/02)	Rule 481(d)	
Traines, roys)	Rule 1132 (05/05/06)	Rule 1132(f)	Rule 1132(g)
	Rule 1136 (06/14/96)	Rule 1136(f)	Rule 1136(d) & (g)
	Rule 1171 (05/01/09)	Rule 1171(e)	Rule 1171(c)(6)
	40 CFR63 SUBPART JJ	See Applicable Subpart	See Applicable Subpart
Coater	See Coating Operations		
Columns	See Petroleum Refineries, Fugitive Emissions		
Composting Operation	Rule 1133 (01/10/03)		
	Rule 1133.1 (01/10/03)	Rule 1133.1(e)	Rule 1133.1(d)
	Rule 1133.2 (01/10/03)	Rule 1133.2(g)	Rule 1133.2(h)
Compressors	See Fugitive Emissions or Petroleum Refineries	, Fugitive Emissions	
Concrete Batch Plants	See Nonmetallic Mineral Processing Plants		
Consumer Product Manufacturing	See Manufacturing, Consumer Product		
Cooling Tower, Hexavalent Chromium	40 CFR63 SUBPART Q	See Applicable Subpart	See Applicable Subpart
KEY ABBREVIATIONS: Reg. = AQMD Regulation Rule = AQMD Rule		= Code of Federal Regulations = California Code of Regulations	

Equipment/Process	Applicable Requirement	Test Method	MRR Requirement
Copper Electroplating Operation	Rule 1426 (05/02/03)		Rule 1426(e)
Crude Oil Production	See Oil Well Operations	·	
Crusher	See Nonmetallic Mineral Processing Plan	ts	
Dairy Farms and Related Operations	Rule 1127 (08/06/04)	Rule 1127(h)	Rule 1127(g)
Degreasers	Rule 109 (05/02/03) Rule 1122 (05/01/09) Rule 1171 (05/01/09) 40 CFR63 SUBPART T	Rule 109(g) Rule 1122(h) Rule 1171(e) See Applicable Subpart	Rule 109(c) Rule 1122(i) Rule 1171(c)(6) See Applicable Subpart
Dry Cleaning, Perchloroethlyene	Rule 1421 (12/06/02)	Rule 1421(e) & (i)	Rule 1421(g) & (h)
Dry Cleaning, Petroleum Solvent	Rule 109 (05/02/03) Rule 1102 (11/17/00) 40 CFR60 SUBPART JJJ	Rule 109(g) Rule 1102(g) See Applicable Subpart	Rule 109(c) Rule 1102(f) See Applicable Subpart
Dryers, Mineral Industries	40 CFR60 SUBPART UUU	See Applicable Subpart	See Applicable Subpart
Ethylene Oxide Sterilizer	See Sterilizer, Ethylene Oxide		•
Flanges	See Fugitive Emissions or Petroleum Refi	neries, Fugitive Emissions	
Fluid Catalytic Cracking Unit	Rule 218 (05/14/99) Rule 1105 (09/01/84) Rule 1105.1 (11/07/03)	AQMD TM 100.1 Rule 1105(c)(1) Rule 1105.1(f)	Rule 218(e) & (f) Rule 1105(c)(2) Rule 1105.1(e)
Foundries, Iron and Steel	40 CFR63 SUBPART EEEEE	See Applicable Subpart	See Applicable Subpart
Friction Materials Manufacturing	See Manufacturing, Friction Materials		<u>'</u>
Fugitive Emissions, Benzene	Rule 1173 (12/06/02) 40 CFR61 SUBPART L 40 CFR61 SUBPART V 40 CFR63 SUBPART R 40 CFR63 SUBPART CC	Rule 1173(j) See Applicable Subpart See Applicable Subpart See Applicable Subpart See Applicable Subpart	Rule 1173(i) See Applicable Subpart See Applicable Subpart See Applicable Subpart See Applicable Subpart

Section II - Applicable Requirements, Te Equipment/Process	Applicable Requirement	Test Method	MRR Requirement
Fugitive Emissions, Chemical Plant	Rule 466 (10/07/83)	Rule 466(f)	Rule 466(e)
I ugitive Emissions, Chemican Tant	Rule 466.1 (03/16/84)	Rule 466.1(g)	Rule 466.1(h)
			\ <u>\</u>
	Rule 467 (03/05/82)	Rule 467(f)	Rule 467(e)
	Rule 1173 (02/06/09)	Rule 1173(j) See Applicable Subpart	Rule 1173(i) See Applicable Subpart
	40 CFR60 SUBPART VV	See Applicable Subpart	See Applicable Subpart
	40 CFR61 SUBPART V		
	40 CFR63 SUBPART F	See Applicable Subpart	See Applicable Subpart
	40 CFR63 SUBPART G	See Applicable Subpart	See Applicable Subpart
	40 CFR63 SUBPART H	See Applicable Subpart	See Applicable Subpart
	40 CFR63 SUBPART I	See Applicable Subpart	See Applicable Subpart
	40 CFR63 SUBPART R	See Applicable Subpart	See Applicable Subpart
	40 CFR63 SUBPART CC	See Applicable Subpart	See Applicable Subpart
Fugitive Emissions, Natural Gas Processing	Rule 466 (10/07/83)	Rule 466(f)	Rule 466(e)
Plant	Rule 466.1 (03/16/84)	Rule 466.1(g)	Rule 466.1(h)
	Rule 467 (03/05/82)	Rule 467(f)	Rule 467(e)
	Rule 1173 (02/06/09)	Rule 1173(j)	Rule 1173(i)
	40 CFR60 SUBPART KKK	See Applicable Subpart	See Applicable Subpart
	40 CFR61 SUBPART V	See Applicable Subpart	See Applicable Subpart
	40 CFR63 SUBPART F	See Applicable Subpart	See Applicable Subpart
	40 CFR63 SUBPART G	See Applicable Subpart	See Applicable Subpart
	40 CFR63 SUBPART H	See Applicable Subpart	See Applicable Subpart
	40 CFR63 SUBPART I	See Applicable Subpart	See Applicable Subpart
	40 CFR63 SUBPART R	See Applicable Subpart	See Applicable Subpart
	40 CFR63 SUBPART CC	See Applicable Subpart	See Applicable Subpart

KEY ABBREVIATIONS: Reg. = AQMD Regulation App. = Appendix Rule = AQMD Rule AQMD TM = AQMD Test Method	CFR = Code of Federal Regulations CCR = California Code of Regulations
---	--

Section II - Applicable Requirements, Tes	Section II - Applicable Requirements, Test Methods, & MRR Requirements			
Equipment/Process	Applicable Requirement	Test Method	MRR Requirement	
Fugitive Emissions, Oil & Gas Production	Rule 466 (10/07/83)	Rule 466(f)	Rule 466(e)	
Facility	Rule 466.1 (03/16/84)	Rule 466.1(g)	Rule 466.1(h)	
	Rule 467 (03/05/82)	Rule 467(f)	Rule 467(e)	
	Rule 1173 (02/06/09)	Rule 1173(j)	Rule 1173(i)	
	40 CFR61 SUBPART V	See Applicable Subpart	See Applicable Subpart	
	40 CFR63 SUBPART F	See Applicable Subpart	See Applicable Subpart	
	40 CFR63 SUBPART G	See Applicable Subpart	See Applicable Subpart	
	40 CFR63 SUBPART H	See Applicable Subpart	See Applicable Subpart	
	40 CFR63 SUBPART I	See Applicable Subpart	See Applicable Subpart	
	40 CFR63 SUBPART R	See Applicable Subpart	See Applicable Subpart	
	40 CFR63 SUBPART CC	See Applicable Subpart	See Applicable Subpart	
Fugitive Emissions, Pipeline Transfer Station	Rule 466 (10/07/83)	Rule 466(f)	Rule 466(e)	
	Rule 466.1 (03/16/84)	Rule 466.1(g)	Rule 466.1(h)	
	Rule 467 (03/05/82)	Rule 467(f)	Rule 467(e)	
	Rule 1173 (02/06/09)	Rule 1173(j)	Rule 1173(i)	
	40 CFR61 SUBPART V	See Applicable Subpart	See Applicable Subpart	
	40 CFR63 SUBPART F	See Applicable Subpart	See Applicable Subpart	
	40 CFR63 SUBPART G	See Applicable Subpart	See Applicable Subpart	
	40 CFR63 SUBPART H	See Applicable Subpart	See Applicable Subpart	
	40 CFR63 SUBPART I	See Applicable Subpart	See Applicable Subpart	
	40 CFR63 SUBPART R	See Applicable Subpart	See Applicable Subpart	
	40 CFR63 SUBPART CC	See Applicable Subpart	See Applicable Subpart	
Furnace, Basic Oxygen Process	40 CFR60 SUBPART Na	See Applicable Subpart	See Applicable Subpart	
Furnace, Electric Arc, For Steel Plants: Constructed After August 17, 1983	40 CFR60 SUBPART AAa	See Applicable Subpart	See Applicable Subpart	
Furnace, Electric Arc, For Steel Plants: Constructed After Oct. 21, 1974, & On Or Before Aug. 17, 1983	40 CFR60 SUBPART AA	See Applicable Subpart	See Applicable Subpart	
Furnace, Glass Melting	Rule 1117 (01/06/84)	Rule 1117(c), AQMD TM 7.1 or 100.1		
	40 CFR60 SUBPART CC	See Applicable Subpart	See Applicable Subpart	
Furnace, Lead Melting, Automotive Batteries	Rule 1101 (10/07/77)	AQMD TM 6.1		
	40 CFR63 SUBPART X	See Applicable Subpart	See Applicable Subpart	
KEY ABBREVIATIONS: Reg. = AQMD Regulation Rule = AQMD Rule		= Code of Federal Regulations = California Code of Regulations		

Section II - Applicable Requirements, Test Methods, & MRR Requirements			
Equipment/Process	Applicable Requirement	Test Method	MRR Requirement
Gasoline Transfer & Dispensing Operation	Rule 461 (06/03/05)	Rule 461(f)	Rule 461(e)(6) & (e)(7)
Glass Manufacturing	See Manufacturing, Glass		
Grain Elevators	40 CFR60 SUBPART DD	See Applicable Subpart	See Applicable Subpart
Halon-containing Equipment, Use for Technician Training, Testing, Maintenance, Service, Repair, or Disposal	40 CFR82 SUBPART H	See Applicable Subpart	See Applicable Subpart
Hazardous Waste Combustors	40 CFR63 SUBPART EEE	See Applicable Subpart	See Applicable Subpart
Heater, Asphalt Pavement	Rule 1120 (08/04/78)	AQMD Visible Emissions, AQMD TM 6.2	Rule 1120(f)
Heaters, Petroleum Refinery Process	Rule 429 (12/21/90) Rule 431.1 (06/12/98) Rule 1146 (09/05/08) 40 CFR60 SUBPART J 40 CFR63 SUBPART DDDDD	N/A Rule 431.1(f) Rule 1146(d) See Applicable Subpart See Applicable Subpart	Rule 429(d) Rule 431.1(d) & (e) Rule 1146(c)(6) & (c)(7) See Applicable Subpart See Applicable Subpart
Heaters, Process	See Boilers		
Incinerators	40 CFR60 SUBPART E 40 CFR60 SUBPART CCCC	See Applicable Subpart See Applicable Subpart	See Applicable Subpart See Applicable Subpart
Inorganic Arsenic Emissions, Arsenic Trioxide & Metallic Arsenic Production Facilities	40 CFR61 SUBPART P	See Applicable Subpart	See Applicable Subpart
Internal Combustion Engines, Reciprocating	Rule 1110.2 (07/09/10) 40 CFR60 SUBPART IIII and JJJJ 40 CFR63 SUBPART ZZZZ	Rule 1110.2(g) See Applicable Subpart See Applicable Subpart	Rule 1110.2(f) See Applicable Subpart See Applicable Subpart
Kiln, Cement Plant	Rule 1112 (06/06/86) Rule 1112.1 (12/04/09) 40 CFR60 SUBPART F	N/A N/A See Applicable Subpart	N/A N/A See Applicable Subpart

Rule = AOMD Rule	App. = Appendix AQMD TM = AQMD Test Method	CFR = Code of Federal Regulations CCR = California Code of Regulations
------------------	---	--

Section II - Applicable Requirements, Test Methods, & MRR Requirements			
Equipment/Process	Applicable Requirement	Test Method	MRR Requirement
Landfills	Rule 1150 (10/15/82)		
	Rule 1150.1 (03/17/00)	Rule 1150.1(j)	Rule 1150.1(e) & (f)
	40 CFR60 SUBPART WWW	See Applicable Subpart	See Applicable Subpart
	40 CFR63 SUBPART AAAA	See Applicable Subpart	See Applicable Subpart
Lead Acid Battery Manufacturing Plants	See Manufacturing, Lead Acid Battery		
Lead Electroplating Operation	Rule 1426 (05/02/03)		Rule 1426(e)
Manufacturing, Asphalt Processing & Asphalt	Rule 470 (05/07/76)	N/A	See Applicable Subpart
Roofing	Rule 1108 (02/01/85)	Rule 1108(b)	See Applicable Subpart
	Rule 1108.1 (11/04/83)	Rule 1108.1 (b)	
	40 CFR60 SUBPART UU	See Applicable Subpart	
	40 CFR63 SUBPART LLLLL	See Applicable Subpart	
Manufacturing, Brick & Structural Clay Products	40 CFR63 SUBPART JJJJJ	See Applicable Subpart	See Applicable Subpart
Manufacturing, Cement	Rule 1156 (03/06/09)	Rule 1156(g)	Rule 1156(f)
Manufacturing, Clay Ceramics	40 CFR63 SUBPART KKKKK	See Applicable Subpart	See Applicable Subpart
Manufacturing, Coatings & Ink	Rule 1141.1 (11/17/00)	N/A	Rule 1141.1(c)
(SIC Code 2851)	40 CFR63 SUBPART HHHHH	See Applicable Subpart	See Applicable Subpart
Manufacturing, Consumer Product	Title 17 CCR 94500		
Manufacturing, Food Product	Rule 1131 (06/06/03)	Rule 1131(e)	Rule 1131(d)
Manufacturing, Friction Materials	40 CFR63 SUBPART QQQQQ	See Applicable Subpart	See Applicable Subpart
Manufacturing, Glass	Rule 1117 (01/06/84)	Rule 1117(c), AQMD TM 7.1 or 100.1	
	40 CFR60 SUBPART CC	See Applicable Subpart	See Applicable Subpart
	40 CFR61 SUBPART N	See Applicable Subpart	See Applicable Subpart
Manufacturing, Hydrochloric Acid	40 CFR63 SUBPART NNNNN	See Applicable Subpart	See Applicable Subpart
Manufacturing, Lead-Acid Battery	40 CFR60 SUBPART KK	See Applicable Subpart	See Applicable Subpart
KEY ABBREVIATIONS: Reg. = AQMD Regulation Rule = AQMD Rule	App. = Appendix AQMD TM = AQMD Test Method	CFR = Code of Federal Regulations CCR = California Code of Regulations	

Section II - Applicable Requirements, Test Methods, & MRR Requirements			
Equipment/Process	Applicable Requirement	Test Method	MRR Requirement
Manufacturing, Lime	40 CFR63 SUBPART AAAAA	See Applicable Subpart	See Applicable Subpart
Manufacturing, Magnetic Tape Industry	40 CFR60 SUBPART SSS	See Applicable Subpart	See Applicable Subpart
	40 CFR63 SUBPART EE	See Applicable Subpart	See Applicable Subpart
Manufacturing, Miscellaneous Organic Chemical	40 CFR63 SUBPART FFFF	See Applicable Subpart	See Applicable Subpart
Manufacturing, Nitric Acid	Rule 218 (05/14/99)	AQMD TM 100.1	Rule 218(e) & (f)
_	Rule 1159 (12/06/85)	AQMD TM 7.1 or 100.1	
	40 CFR60 SUBPART G	See Applicable Subpart	See Applicable Subpart
Manufacturing, Plywood & Composite Wood	Rule 1137 (02/01/02)	N/A	Rule 1137(e)
Products	40 CFR63 SUBPART DDDD	See Applicable Subpart	See Applicable Subpart
Manufacturing, Polymer Industry	40 CFR60 SUBPART DDD	See Applicable Subpart	See Applicable Subpart
	40 CFR63 SUBPART W	See Applicable Subpart	See Applicable Subpart
	40 CFR63 SUBPART J	See Applicable Subpart	See Applicable Subpart
Manufacturing, Polymeric Cellular Foam	Rule 1175 (09/07/07)	Rule 1175(f)	Rule 1175(e)
	40 CFR63 SUBPART UUUU	See Applicable Subpart	See Applicable Subpart
Manufacturing, Products Containing Halon Blends	40 CFR82 SUBPART H	See Applicable Subpart	See Applicable Subpart
Manufacturing, Products Containing Organic Solvents	Rule 443.1 (12/05/86)	N/A	N/A
Manufacturing, Products Containing Ozone	40 CFR82 SUBPART A	See Applicable Subpart	See Applicable Subpart
Depleting Substances (ODS)	40 CFR82 SUBPART E	See Applicable Subpart	See Applicable Subpart
Manufacturing, Reinforced Plastic Composites	40 CFR63 SUBPART WWWW	See Applicable Subpart	See Applicable Subpart
Manufacturing, Refractory Products	40 CFR63 SUBPART SSSSS	See Applicable Subpart	See Applicable Subpart
Manufacturing, Resin	Rule 1141 (11/17/00)	Rule 1141(d)	Rule 1141(c)
	40 CFR63 SUBPART W	See Applicable Subpart	See Applicable Subpart
Manufacturing, Rubber Tire	40 CFR63 SUBPART XXXX	See Applicable Subpart	See Applicable Subpart
Manufacturing, Semiconductors	Rule 109 (05/02/03)	Rule 109(g)	Rule 109(c)
	Rule 1164 (01/13/95)	Rule 1164(e)	Rule 1164(c)(5)
	Rule 1171 (05/01/09)	Rule 1171(e)	Rule 1171(c)(6)
	40 CFR63 SUBPART BBBBB	See Applicable Subpart	See Applicable Subpart
Manufacturing, Solvent	Rule 443 (05/07/76)	N/A	N/A
-	· · · · · · · · · · · · · · · · · · ·	·	•
KEY ABBREVIATIONS: Reg. = AQMD Regulation Rule = AQMD Rule	App. = Appendix AQMD TM = AQMD Test Method	CFR = Code of Federal Regulations CCR = California Code of Regulations	

Equipment/Process	Applicable Requirement	Test Method	MRR Requirement
Manufacturing, Sulfuric Acid	Rule 469 (02/13/81) 40 CFR60 SUBPART H 40 CFR60 SUBPART Cd	AQMD TM 6.1 or 6.2 See Applicable Subpart See Applicable Subpart	See Applicable Subpart See Applicable Subpart
Manufacturing, Surfactant	Rule 1141.2 (01/11/02)	Rule 1141.2(e) AQMD TM 25.1	
Manufacturing, Synthetic Organic Chemical Manufacturing Industry (SOCMI) Air Oxidation Unit Processes	40 CFR60 SUBPART III 40 CFR60 SUBPART NNN	See Applicable Subpart See Applicable Subpart	See Applicable Subpart See Applicable Subpart
Manufacturing, Synthetic Organic Chemical Manufacturing Industry (SOCMI) Reactor Processes	40 CFR60 SUBPART RRR	See Applicable Subpart	See Applicable Subpart
Manufacturing, Vinyl Chloride	40 CFR61 SUBPART F	See Applicable Subpart	See Applicable Subpart
Manufacturing, Water Heaters	Rule 1121 (09/03/04)	N/A	N/A
Manufacturing, Wool Fiberglass Insulation	40 CFR60 SUBPART PPP	See Applicable Subpart	See Applicable Subpart
Manure Processing Operations	Rule 1127 (08/06/04)	Rule 1127(h)	Rule 1127(g)
Marine Tank Vessel Operations	Rule 1142 (07/19/91)	Rule 1142(e)	Rule 1142(h)
	Rule 1173 (02/06/09) 40 CFR63 SUBPART Y	Rule 1173(j) See Applicable Subpart	Rule 1173(i) See Applicable Subpart
Mercury Emissions	40 CFR61 SUBPART E 40 CFR63 SUBPART IIII	See Applicable Subpart See Applicable Subpart	See Applicable Subpart See Applicable Subpart
Motor Vehicle Air Conditioners with Ozone Depleting Substances (ODS): Repair, Service, Manufacturing, Maintenance, or Disposal	40 CFR82 SUBPART B 40 CFR82 SUBPART F	See Applicable Subpart See Applicable Subpart	See Applicable Subpart See Applicable Subpart
Municipal Waste Combustors	40 CFR60 SUBPART Cb 40 CFR60 SUBPART Ea 40 CFR60 SUBPART Eb	See Applicable Subpart See Applicable Subpart See Applicable Subpart	See Applicable Subpart See Applicable Subpart See Applicable Subpart
✓ Negative Air Machines/HEPA, Asbestos	✓ 40 CFR61 SUBPART M	See Applicable Subpart	See Applicable Subpart
Nickel Electroplating Operation	Rule 1426 (05/02/03)		Rule 1426(e)
Nonmetallic Mineral Processing Plants	Rule 404 (02/07/86) Rule 405 (02/07/86) 40 CFR60 SUBPART OOO	AQMD TM 5.1, 5.2, or 5.3 AQMD TM 5.1, 5.2, or 5.3 See Applicable Subpart	See Applicable Subpart
Off-site Waste and Recovery Operation	40 CFR63 SUBPART DD	See Applicable Subpart	See Applicable Subpart

•	pp. = Appendix	•
---	----------------	---

Section II - Applicable Requirements, Test Methods, & MRR Requirements			
Equipment/Process	Applicable Requirement	Test Method	MRR Requirement
Oil and Gas Well Operation	Rule 1148 (11/05/82)	AQMD TM 25.1	
	Rule 1148.1 (03/05/04)	Rule 1148.1 (g)	Rule 1148.1 (f)
Onshore Natural Gas Processing, SO2 Emissions	40 CFR60 SUBPART LLL	See Applicable Subpart	See Applicable Subpart
Open Fires	Rule 444 (11/07/08)		
Open Storage, Petroleum Coke	Rule 403 (06/03/05)	Rule 403(d)(4)	Rule 403(f)
	Rule 403.1 (04/02/04)		Rule 403.1(h)
	Rule 1158 (06/11/99)	Rule 1158(h)	Rule 1158(j)
Open Storage	Rule 403 (06/03/05)	Rule 403(d)(4)	Rule 403(f)
	Rule 403.1 (04/02/04)		Rule 403.1(h)
Outer Continental Shelf Platform	Rule 1183 (03/12/93)	40 CFR55	40 CFR55
	40 CFR55	See Applicable Subpart	See Applicable Subpart
Oven, Commercial Bakery	Rule 1153 (01/13/95)	Rule 1153(h)	Rule 1153(g)
Oven, Petroleum Coke	Rule 477 (04/03/81)	AQMD Visible Emissions, AQMD	
_		TM 5.1, 5.2, or 5.3	
	40 CFR63 SUBPART L	See Applicable Subpart	See Applicable Subpart
	40 CFR63 SUBPART CCCCC	See Applicable Subpart	See Applicable Subpart
Ozone Depleting Substances (ODS) or Alternative ODS, Use	40 CFR82 Subpart G	See Applicable Subpart	See Applicable Subpart

 KEY ABBREVIATIONS:
 Reg. = AQMD Regulation Rule = AQMD Rule
 App. = Appendix AQMD TM = AQMD Test Method
 CFR = Code of Federal Regulations CCR = California Code of Regulations

Section II - Applicable Requirements, T		<u> </u>	
Equipment/Process	Applicable Requirement	Test Method	MRR Requirement
Petroleum Refineries	Rule 218 (05/14/99)	AQMD TM 100.1	Rule 218(e) & (f)
	Rule 465 (08/13/99)		
	Rule 468 (10/08/76)	AQMD TM 6.1 or 6.2	
	Rule 469 (02/13/81)	AQMD TM 6.1 or 6.2	
	Rule 1118 (11/04/05)	Rule 1118(j)	Rule 1118(f), (g), (h), & (i)
	Rule 1123 (12/07/90)	N/A	Rule 1123(c)
	Rule 1189 (01/21/00)	Rule 1189(f)	Rule 1189(e) See Applicable Subpart
	40 CFR60 SUBPART J	See Applicable Subpart	See Applicable Subpart
	40 CFR63 SUBPART F	See Applicable Subpart	See Applicable Subpart
	40 CFR63 SUBPART G	See Applicable Subpart	See Applicable Subpart
	40 CFR63 SUBPART H	See Applicable Subpart	''
	40 CFR63 SUBPART I	See Applicable Subpart	See Applicable Subpart
	40 CFR63 SUBPART CC	See Applicable Subpart	See Applicable Subpart
	40 CFR63 SUBPART EEEE	See Applicable Subpart	See Applicable Subpart
	40 CFR63 SUBPART GGGGG	See Applicable Subpart	See Applicable Subpart
	Title 13 CCR 2250		
Petroleum Refineries, Fugitive Emissions	Rule 1173 (02/06/09)	Rule 1173(j)	Rule 1173(i)
	Rule 466 (10/07/83)	Rule 466(f)	Rule 466(e)
	Rule 466.1 (03/16/84)	Rule 466.1(g)	Rule 466.1(h)
	Rule 467 (03/05/82)	Rule 467(f)	Rule 467(e)
	40 CFR60 SUBPART GGG	See Applicable Subpart	See Applicable Subpart
	40 CFR61 SUBPART V	See Applicable Subpart	See Applicable Subpart
	40 CFR63 SUBPART F	See Applicable Subpart	See Applicable Subpart
	40 CFR63 SUBPART G	See Applicable Subpart	See Applicable Subpart
	40 CFR63 SUBPART H	See Applicable Subpart	See Applicable Subpart
	40 CFR63 SUBPART I	See Applicable Subpart	See Applicable Subpart
	40 CFR63 SUBPART R	See Applicable Subpart	See Applicable Subpart
	40 CFR63 SUBPART CC	See Applicable Subpart	See Applicable Subpart

KEY ABBREVIATIONS: Reg. = AQMD Regulation App. = Appendix Rule = AQMD Rule AQMD TM = AQMD Test Method	CFR = Code of Federal Regulations CCR = California Code of Regulations
---	--

Section II - Applicable Requirements, Test Methods, & MRR Requirements			
Equipment/Process	Applicable Requirement	Test Method	MRR Requirement
Petroleum Refineries, Storage Tanks	Rule 463 (05/06/05)	Rule 463(g)	Rule 463(e)(5)
	Rule 1178 (04/07/06)	Rule 1178(i)	Rule 1178(f) & (h)
	40 CFR60 SUBPART K	See Applicable Subpart	See Applicable Subpart
	40 CFR60 SUBPART Ka	See Applicable Subpart	See Applicable Subpart
	40 CFR60 SUBPART Kb	See Applicable Subpart	See Applicable Subpart
	40 CFR63 SUBPART F	See Applicable Subpart	See Applicable Subpart
	40 CFR63 SUBPART G	See Applicable Subpart	See Applicable Subpart
	40 CFR63 SUBPART H	See Applicable Subpart	See Applicable Subpart
	40 CFR63 SUBPART I	See Applicable Subpart	See Applicable Subpart
	40 CFR63 SUBPART R	See Applicable Subpart	See Applicable Subpart
	40 CFR63 SUBPART CC	See Applicable Subpart	See Applicable Subpart
	40 CFR63 SUBPART EEEE	See Applicable Subpart	See Applicable Subpart
Petroleum Refineries, Wastewater Systems	Rule 1176 (09/13/96)	Rule 1176(h)	Rule 1176(f) & (g)
	Rule 464 (12/07/90)	N/A	
	40 CFR60 SUBPART QQQ	See Applicable Subpart	See Applicable Subpart
	40 CFR63 SUBPART CC	See Applicable Subpart	See Applicable Subpart
Pharmaceuticals & Cosmetics Manufacturing	Rule 1103 (03/12/99)	Rule 1103(f)	Rule 1103(e)
	40 CFR63 SUBPART GGG	See Applicable Subpart	See Applicable Subpart
Polyester Resin Operation	Rule 109 (05/02/03)	Rule 109(g)	Rule 109(c)
	Rule 1162 (07/08/05)	Rule 1162(f)	Rule 1162(e)
	Rule 1171 (05/01/09)	Rule 1171(e)	Rule 1171(c)(6)
Primary Magnesium Refining	40 CFR63 SUBPART TTTTT	See Applicable Subpart	See Applicable Subpart
Printing Press	See Coating Operations		
Publicly Owned Treatment Works Operations	Rule 1179 (03/06/92)	Rule 1179(e)	Rule 1179(c) & (d)
	40 CFR60 SUBPART O	See Applicable Subpart	See Applicable Subpart
Pumps	See Fugitive Emissions or Petroleum Ref	ineries, Fugitive Emissions	

KEY ABBREVIATIONS: Reg. = AQMD Regulation App. = Appendix AQMD TM = AQMD Test Method	CFR = Code of Federal Regulations CCR = California Code of Regulations
--	--

Section II - Applicable Requirements, Test Methods, & MRR Requirements				
Equipment/Process	Applicable Requirement	Test Method	MRR Requirement	
Recycling & Recovery Equipment for Ozone Depleting Substances (ODS),	40 CFR82 SUBPART F	See Applicable Subpart	See Applicable Subpart	
Refrigerant Reclaimers for Ozone Depleting Substances (ODS)	☐40 CFR82 SUBPART F	See Applicable Subpart	See Applicable Subpart	
Rendering Plant	Rule 472 (05/07/76)	N/A	Rule 472(b)	
Rock Crushing	See Nonmetallic Mineral Processing Plant	ts	•	
Secondary Aluminum Production	40 CFR63 SUBPART LL	See Applicable Subpart	See Applicable Subpart	
Semiconductor Manufacturing	See Manufacturing, Semiconductors	·	·	
Sewage Treatment Plants	See Publicly Owned Treatment Works Operation			
Site Remediation	40 CFR63 SUBPART GGGGG	See Applicable Subpart	See Applicable Subpart	
Smelting, Primary Copper	40 CFR63 SUBPART QQQ	See Applicable Subpart	See Applicable Subpart	
Smelting, Secondary Lead	40 CFR60 SUBPART L 40 CFR63 SUBPART X	See Applicable Subpart See Applicable Subpart	See Applicable Subpart See Applicable Subpart	
Soil Decontamination / Excavation	Rule 1166 (05/11/01) 40 CFR63 SUBPART GGGGG	Rule 1166(e) See Applicable Subpart	Rule 1166(c)(1)(C) See Applicable Subpart	
Spray Booth	See Coating Operations	<u>'</u>		
Sterilizer, Ethylene Oxide	terilizer, Ethylene Oxide 40 CFR63 SUBPART O		See Applicable Subpart	
Storage Tank, Degassing Operation	Rule 1149 (07/14/95) 40 CFR63 SUBPART CC	See Applicable Subpart	See Applicable Subpart	

 KEY ABBREVIATIONS:
 Reg. = AQMD Regulation Rule = AQMD Rule
 App. = Appendix AQMD TM = AQMD Test Method
 CFR = Code of Federal Regulations CCR = California Code of Regulations

Section II - Applicable Requirements, Test Methods, & MRR Requirements					
Equipment/Process	Applicable Requirement	Test Method	MRR Requirement		
Storage Tank, Greater Than 19,815 Gallon Capacity	Rule 463 (05/06/05) Rule 1178 (04/07/06) 40 CFR63 SUBPART F 40 CFR63 SUBPART H 40 CFR63 SUBPART I 40 CFR60 SUBPART K 40 CFR60 SUBPART K 40 CFR60 SUBPART Ka 40 CFR60 SUBPART Kb 40 CFR63 SUBPART R 40 CFR63 SUBPART R 40 CFR63 SUBPART BBBBBB	Rule 463(g) Rule 1178(i) See Applicable Subpart	Rule 463(e)(5) Rule 1178(h) See Applicable Subpart		
Synthetic Fiber Production Facilities	40 CFR60 SUBPART HHH	See Applicable Subpart	See Applicable Subpart		
Taconite Iron Ore Processing Facilities	40 CFR63 SUBPART RRRRR	See Applicable Subpart	See Applicable Subpart		
▼Turbine, Stationary Gas-Fired	Rule 1134 (08/08/97) Rule 475 (08/07/78) 40 CFR60 SUBPART GG 40 CFR60 SUBPART KKKK 40 CFR63 SUBPART YYYY	Rule 1134(e) & (g) AQMD TM 5.1, 5.2, or 5.3 See Applicable Subpart See Applicable Subpart See Applicable Subpart	Rule 1134(d) & (f) See Applicable Subpart See Applicable Subpart See Applicable Subpart		
Turbine, Stationary Oil-Fired	40 CFR63 SUBPART YYYY	See Applicable Subpart	See Applicable Subpart		
Valves	See Fugitive Emissions or Petroleum Refineries	, Fugitive Emissions	'		
Vessel, Refinery Process	Rule 1123 (12/07/90)	N/A	Rule 1123(c)		
Vessels	See Petroleum Refineries, Fugitive Emissions				

KEY ABBREVIATIONS:	Reg. = AQMD Regulation Rule = AQMD Rule	App. = Appendix AQMD TM = AQMD Test Method	CFR = Code of Federal Regulations CCR = California Code of Regulations	

Section II - Applicable Requirements, Test Methods, & MRR Requirements				
Equipment/Process	Applicable Requirement	Test Method	MRR Requirement	
Wastewater, Chemical Plant	Rule 464 (12/07/90) Rule 1176 (09/13/96) 40 CFR63 SUBPART F 40 CFR63 SUBPART G 40 CFR63 SUBPART H 40 CFR63 SUBPART I 40 CFR63 SUBPART CC	N/A Rule 1176(h) See Applicable Subpart	Rule 1176(f) & (g) See Applicable Subpart	
Wastewater Treatment, Other	Rule 464 (12/07/90) Rule 1176 (09/13/96)	N/A Rule 1176(h)	Rule 1176(f) & (g)	
Woodworking Operations	Rule 1137 (02/01/02)	N/A	Rule 1137(e)	

 KEY ABBREVIATIONS:
 Reg. = AQMD Regulation Rule = AQMD Rule
 App. = Appendix AQMD TM = AQMD Test Method
 CFR = Code of Federal Regulations CCR = California Code of Regulations

Section III - Supplemental Identification of Specific Requirements

Complete this section only if there is a specific requirement (i.e., rule reference, test method, or MRR requirement) that is:

- 1. Listed for a specific type of equipment or process in Section II of this form & **DOES NOT** pertain to a specific device at your facility*; OR,
- 2. Is **NOT** Listed for a specific type of equipment or process in Section II of this form but it **IS** applicable to a specific device at your facility.

NOTES:

- 1. For any specific requirement, test method, or MRR requirement that is identified as "Remove," attach additional sheets to explain the reasons why the specific requirement does not pertain to the device listed.
- 2. All boxes that are checked in Section II and any additional requirements identified in this section as "Add" will be used to determine the facility's compliance status. This information will be used to verify the certification statements made on Form 500-A2.
- 3. Do not use this section to identify equipment that is exempt from specific rule requirements. Your equipment is automatically considered to be in compliance with the rule that specifically exempts the equipment from those requirements.
- 4. Listing any requirement that does not apply to a specific piece of equipment in this section will not provide the facility with a permit shield unless one is specifically requested by completing Form 500-D and approved by the AQMD.
- * If this section is completed as part of the initial Title V application & there is no device number assigned, refer to the existing permit or application number in this column.

Device No.*	Specific Requirement (Rule Number & Date)	Add (A) or Remove (R) (Check one)	Test Method	Add (A) or Remove (R) (Check one)	MRR Requirement	Add (A) or Remove (R) (Check one)
		O A O R		OAOR		OAOR
		O A O R		OAOR		OAOR
		OAOR		OAOR		OAOR
		OAOR		OAOR		OAOR
		OAOR		OAOR		OAOR
		OAOR		OAOR		OAOR
		OAOR		OAOR		OAOR
		OAOR		OAOR		OAOR
		OAOR		OAOR		OAOR
		OAOR		OAOR		OAOR
		OAOR		OAOR		OAOR
		OAOR		OAOR		OAOR
		OAOR		OAOR		OAOR
		OAOR		OAOR		OAOR
		OAOR		OAOR		OAOR
		OAOR		OAOR		OAOR
		OAOR		OAOR		OAOR
		OAOR		OAOR		OAOR
		OAOR		OAOR		OAOR
		OAOR		OAOR		OAOR
		OAOR		OAOR		OAOR
		OAOR		OAOR		OAOR

Section IV - SIP-Approved Rules That Are Not The Most Current AQMD Rules Check off each SIP-Approved Rule as it applies to the facility. Use the blanks at the end of this form to fill-in new items. Adoption/ Adoption/ Check (√) Check (√) SIP - Approved Rule Amendment SIP - Approved Rule **Amendment** If Applies If Applies **Date** Date 401 03/02/84 **√** 431.2 05/04/90 461 6/3/05 466.1 05/02/80 469 04/07/76 475 10/08/76 1112 01/06/84 1112.1 2/7/86 1113 11/08/96 1117 1/6/83 1122 07/11/97 1132 03/05/04 1140 02/01/80 1146 11/17/00 1146.1 5/13/94 1151 12/11/98 1158 6/11/99 1162 11/17/00 1166 07/14/95 1171 11/07/03

05/13/94

09/10/99

1175

1186

Section V - AQMD Rules That Are Not SIP-Approved (Continued on Following Page) Check off each AQMD Rule as it applies to the facility. Use the blanks at the end of this form to fill-in new items. Adoption/ Adoption/ Check (√) Check (√) Non SIP - Approved Rule Non SIP - Approved Rule Amendment Amendment If Applies If Applies **Date Date** 53 Los Angeles Co. N/A $\sqrt{}$ 1192 06/16/00 53 Orange Co. N/A 1193 07/09/10 53 Riverside Co. N/A 1194 10/20/00 53 San Bernardino Co. N/A 1195 05/05/06 53A San Bernardino Co. N/A 1196 06/06/08 402 05/07/76 1401 09/10/10 **√** 429 12/21/90 1401.1 11/04/05 07/12/96 1402 430 03/04/05 |√ 441 05/07/76 1403 10/05/07 473 05/07/76 1404 04/06/90 477 04/03/81 1405 01/04/91 480 10/07/77 1406 07/08/94 1109 08/05/88 1407 07/08/94 1411 1110.2 07/09/10 03/01/91 1116.1 10/20/78 1414 05/03/91 1127 08/06/04 1415 10/14/94 1143 07/09/10 1418 09/10/99 1147 12/05/08 1420 09/11/92 1148.1 03/05/04 1420.1 11/05/10 1150 10/15/82 1421 12/06/02 1155 12/04/09 1425 03/16/01 03/06/09 1426 05/02/03 1156 1157 09/08/06 1163 06/07/85 1170 05/06/88 1183 03/12/93 1186.1 01/09/09

06/16/00

1191

Section V - AQMD Rules That Are Not SIP-Approved (Continued on Following Page) Check off each AQMD Rule as it applies to the facility. Use the blanks at the end of this form to fill-in new items. Adoption/ Adoption/ Check (√) Check (√) Non SIP - Approved Rule Amendment Non SIP - Approved Rule Amendment If Applies If Applies Date **Date** 1469 12/05/08 2009.1 05/11/01 2501 1469.1 03/04/05 05/09/97 1470 2506 06/01/07 12/10/99 1472 03/07/08 2009 01/07/05



South Coast Air Quality Management District

Form 400 - XPP

Express Permit Processing RequestForm 400-A, Form 400-CEQA and one or more 400-E-xx form(s) must accompany all submittals.

Mail To: SCAQMD P.O Box 4944 Diamond Bar, CA 91765-0944

Tel: (909) 396-3385 www.aqmd.gov

Section A - Operator Information				
Facility Name (Business Name of Operator AES Alamitos, LLC	To Appear On The Permit):	2. Valid AQMD Facility AQMD):	ID (Available On Permit Or Invoice Issued By 115394	
Section B - Equipment Location Add	ess	Section C - Permit Mailing Address		
3. Fixed Location (For equipment operated at various loc 690 N. Studebaker Rd.	Various Location ations, provide address of initial site.)	Permit and Correspondence Information:		
Street Address		Address		
Long Beach	.CA 90803	Long Beach	CA 90803	
City	State Zip	City	State Zip	
Charlene He	Environmental Managr	Charlene He	Environmental Managr	
Contact Name Title (562) 493-7835 Phone # Ext. Fax # charlene.he@aes.com		Contact Name (562) 493-7835	Title	
		Phone # Ext. charlene.he@aes.com	Fax#	
E-Mail		E-Mail	· · · · · · · · · · · · · · · · · · ·	
Section D - Authorization/Signature				
I understand that the Expedit and that the application may Permit Processing neither gu Express Permit Processing is has commenced, the expedit and information submitted w	be subject to additional fee larantees action by any spe s subject to availability of q ed fees will not be refunded	es per Rule 301. I understand ecific date nor does it guarant ualified staff; and that once I d. I hereby certify that all info	I that requests for Express tee permit approval; that Express Permit Processing	
5. Signature of Responsible Official:		Note of Responsible Official: Vice President, AES Southland Energy		
7. Print Name of Responsible Official: Weikko Wirta	3	8. Date: 04/1p/ 2	922	
9. Phone #: (714) 374-1421		10. Fax #:		

AQMD USE ONLY		APPLICA:	TION TRACE	KING#		TYPE B C	EQUIPMENT CATEGORY CODE	FEE SCHEDULE:		VALIDATION
ENG. A	1	R	ENG. DATE	Á	R	CLASS	ASSIGNMENT Unit Engineer	CHECK/MONEY ORDER #	AMOUNT S	TRACKING #

APPENDIX B – EQUIPMENT SPECIFICATIONS



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY 2022 MODEL YEAR CERTIFICATE OF CONFORMITY WITH THE CLEAN AIR ACT

OFFICE OF TRANSPORTATION AND AIR QUALITY ANN ARBOR, MICHIGAN 48105

Certificate Issued To: Caterpillar Inc.

(U.S. Manufacturer or Importer)

Certificate Number: NCPXL18.1NYS-003

Effective Date: 06/01/2021

Expiration Date: 12/31/2022

4.100

06/01/2021

Revision Date:
N/A

Issue Date:

Model Year: 2022

Manufacturer Type: Original Engine Manufacturer

Engine Family: NCPXL18.1NYS

Mobile/Stationary Indicator: Stationary **Emissions Power Category:** 560<kW<=2237

Fuel Type: Diesel

After Treatment Devices: No After Treatment Devices Installed

Non-after Treatment Devices: Electronic Control, Engine Design Modification

Byron J. Bunker, Division Director

Compliance Division

Pursuant to Section 111 and Section 213 of the Clean Air Act (42 U.S.C. sections 7411 and 7547) and 40 CFR Part 60, and subject to the terms and conditions prescribed in those provisions, this certificate of conformity is hereby issued with respect to the test engines which have been found to conform to applicable requirements and which represent the following engines, by engine family, more fully described in the documentation required by 40 CFR Part 60 and produced in the stated model year.

This certificate of conformity covers only those new compression-ignition engines which conform in all material respects to the design specifications that applied to those engines described in the documentation required by 40 CFR Part 60 and which are produced during the model year stated on this certificate of the said manufacturer, as defined in 40 CFR Part 60.

It is a term of this certificate that the manufacturer shall consent to all inspections described in 40 CFR 1068 and authorized in a warrant or court order. Failure to comply with the requirements of such a warrant or court order may lead to revocation or suspension of this certificate for reasons specified in 40 CFR Part 60. It is also a term of this certificate that this certificate may be revoked or suspended or rendered void *ab initio* for other reasons specified in 40 CFR Part 60.

This certificate does not cover engines sold, offered for sale, or introduced, or delivered for introduction, into commerce in the U.S. prior to the effective date of the certificate.

Standby Power Rating 750 kW, 938 kVA, 60 Hz

Prime Power Rating* 675 kW, 844 kVA, 60 Hz





*EPA Certified Prime ratings are not available in the US or its Territories



Codes and Standards

Not all codes and standards apply to all configurations. Contact factory for details.





UL2200, UL6200, UL1236, UL489, UL142



CSA C22.2, B149





BS5514 and DIN 6271



SAE J1349



NFPA 37, 70, 99, 110



NEC700, 701, 702, 708



ISO 3046, 7637, 8528, 9001



NEMA ICS10, MG1, 250, ICS6, AB1



ANSI C62.41

Powering Ahead

For over 50 years, Generac has provided innovative design and superior manufacturing.

Generac ensures superior quality by designing and manufacturing most of its generator components, including alternators, enclosures and base tanks, control systems and communications software.

Generac gensets utilize a wide variety of options, configurations and arrangements, allowing us to meet the standby power needs of practically every application.

Generac searched globally to ensure the most reliable engines power our generators. We choose only engines that have already been proven in heavy-duty industrial applications under adverse conditions.

Generac is committed to ensuring our customers' service support continues after their generator purchase.

INDUSTRIAL DIESEL GENERATOR SET

EPA Certified Stationary Emergency

STANDARD FEATURES

ENGINE SYSTEM

- Oil Drain Extension
- Heavy Duty Air Cleaner
- Fan Guard
- Stainless Steel Flexible Exhaust Connection
- Critical Silencer (Enclosed Units Only)
- · Factory Filled Oil and Coolant
- Radiator Duct Adapter (Open Set Only)
- Oil Temperature Indication and Alarm

Fuel System

- Primary Fuel Filter
- Secondary Fuel Filter

Cooling System

- Closed Coolant Recovery System
- UV/Ozone Resistant Hoses
- · Factory-Installed Radiator
- 50/50 Ethylene Glycol Antifreeze
- Radiator Drain Extension

Electrical System

- Battery Charging Alternator
- **Battery Cables**
- **Battery Tray**
- **Rubber-Booted Engine Electrical Connections**
- Solenoid Activated Starter Motor

ALTERNATOR SYSTEM

- UL2200 GENprotect™
- 12 Leads (3-Phase, Non 600V)
- Class H Insulation Material
- Vented Rotor
- 2/3 Pitch
- Skewed Stator
- **Auxiliary Voltage Regulator Power Winding**
- **Amortisseur Winding**
- Permanent Magnet Excitation
- Sealed Bearings
- Full Load Capacity Alternator
- Protective Thermal Switch

GENERATOR SET

- Internal Genset Vibration Isolation
- Separation of Circuits High/Low Voltage
- Separation of Circuits Multiple Breakers
- Wrapped Exhaust Piping (Enclosed Units Only)
- Standard Factory Testing
- 2 Year Limited Warranty (Standby Rated Units)
- 1 Year Limited Warranty (Prime Rated Units)
- Silencer Mounted in the Discharge Hood (Enclosed Units Only)

ENCLOSURE (If Selected)

GENERAC[®]

· Rust-Proof Fasteners with Nylon Washers to Protect Finish

INDUSTRIAL

- · High Performance Sound-Absorbing Material (Sound Attenuated Enclosures)
- Gasketed Doors
- Upward Facing Discharge Hoods (Radiator and Exhaust)
- Stainless Steel Lift Off Door Hinges
- Stainless Steel Lockable Handles
- RhinoCoat™ Textured Polyester Powder Coat Paint

FUEL TANKS (If Selected)

- UL 142/ULC S601 Tank
- Double Wall
- Vents
- Sloped Top
- Sloped Bottom
- Factory Pressure Tested (2 psi)
- Rupture Basin Alarm
- Fuel Level
- · Check Valve in Supply and Return Lines
- RhinoCoat[™] Textured Polyester Powder Coat Paint

CONTROL SYSTEM



Power Zone® Pro Sync Controller

Program Functions

- NFPA 110 Level 1 Compliant
- Engine Protective Functions
- **Alternator Protective Functions**
- Digital Engine Governor Control
- Digital Voltage Regulator
- Multiple Programmable Inputs and Outputs
- Remote Display Capability
- Remote Communication via Modbus® RTU, Modbus TCP/IP, and Ethernet 10/100
- Alarm and Event Logging with Real Time Stamping
- Expandable Analog and Digital Inputs and Outputs

- Remote Wireless Software Update Capable Wi-Fi®, Bluetooth®, BMS and Remote Telemetry
- Built-In Programmable Logic Eliminates the Need for External Controllers Under Most Conditions
- **Ethernet Based Communications** Between Generators
- Programmable I/O Channel Properties
- **Built-In Diagnostics**
- On-Board Manual Storage

Protections

- Low Oil Pressure
- Low Coolant Level
- High/Low Coolant Temperature
- Sensor Failure
- Oil Temperature
- Over/Under Speed
- Over/Under Voltage
- Over/Under Frequency
- Over/Under Current
- Over Load
- High/Low Battery Voltage
- **Battery Charger Current**
- Phase to Phase and Phase to Neutral Short Circuits (I²T Algorithm)

7 Inch Color Touch Screen Display

- Resistive Color Touch Screen
- Sunlight Readable (1400 NITS)
- Easily Identifiable Icons
- Multi-Lingual
- On Screen Editable Parameters
- Key Function Monitoring
- Three Phase Voltage, Amperage, kW, kVA, and kVAr
- Selectable Line to Line or Line to **Neutral Measurements**
- Frequency
- **Engine Speed**
- **Engine Coolant Temperature**
- Engine Oil Pressure
- **Engine Oil Temperature**
- Battery Voltage
- Hourmeter
- Warning and Alarm Indication
- Diagnostics
- Maintenance Events/Information

INDUSTRIAL DIESEL GENERATOR SET

EPA Certified Stationary Emergency

CONFIGURABLE OPTIONS

ENGINE SYSTEM

- O Engine Coolant Heater
- Oil Heater
- O Critical Grade Silencers (Open Set Only)
- O Level 1 Fan and Belt Guards (Enclosed Units Only)
- O Radiator Stone Guard (Open Set Only)

ELECTRICAL SYSTEM

- 10A UL Listed Battery Charger
- O Battery Warmer

ALTERNATOR SYSTEM

- O Alternator Upsizing
- O Anti-Condensation Heater

CIRCUIT BREAKER OPTIONS

- O Main Line Circuit Breaker
- 2nd Main Line Circuit Breaker
- O Shunt Trip and Auxiliary Contact
- O Electronic Trip Breakers

GENERATOR SET

- O 8 Position Load Center
- O Extended Factory Testing

ENCLOSURE

- O Weather Protected Enclosure
- O Level 1 Sound Attenuated
- Level 2 Sound Attenuated
- O Level 2 Sound Attenuated with Motorized Dampers
- O Steel Enclosure
- O Aluminum Enclosure
- Up to 200 MPH Wind Load Rating (Contact Factory for Availability)
- O AC/DC Enclosure Lighting Kit
- O Door Open Alarm Switch
- O Enclosure Heater (with Motorized Dampers Only)

CONTROL SYSTEM

GENERAC

O NFPA 110 Compliant 21-Light Remote Annunciator

INDUSTRIAL

- O Remote Relay Panel (8 or 16)
- O Ground Fault Annunciator
- O 10A Engine Run Relay
- O 120V GFCI and 240V Outlets
- O Oil Temperature Indication and Alarm
- O Remote E-Stop (Break Glass-Type, Surface Mount)
- Remote E-Stop (Red Mushroom-Type, Surface Mount)
- O Remote E-Stop (Red Mushroom-Type, Flush Mount)
- O Remote Communication Modem
- Damper Alarm Contacts (with Motorized Dampers Only)
- O 100 dB Alarm Horn

WARRANTY (Standby Gensets Only)

- O 2 Year Extended Limited Warranty
- 5 Year Limited Warranty
- O 5 Year Extended Limited Warranty
- O 7 Year Extended Limited Warranty
- 10 Year Extended Limited Warranty

ENGINEERED OPTIONS

ENGINE SYSTEM

- O Fluid Containment Pan
- O Coolant Heater Ball Valves

ALTERNATOR SYSTEM

O 3rd Breaker Systems

GENERATOR SET

- Special Testing
- O Battery Box

FUEL TANKS

- Overfill Protection Valve
- O UL 2085 Tank
- O Stainless Steel Tank
- O Special Fuel Tanks
- O Vent Extensions
- O 5 Gallon Spill Containment Box
- O Dealer Supplied AHJ Requirements

INDUSTRIAL DIESEL GENERATOR SET

EPA Certified Stationary Emergency



APPLICATION AND ENGINEERING DATA

ENGINE SPECIFICATIONS

_		
1-10	na	rai

Make	Perkins
Cylinder #	6
Туре	In-Line
Displacement - In ³ (L)	543 (18.1)
Bore - in (mm)	5.71 (145)
Stroke - in (mm)	7.20 (183)
Compression Ratio	14.0:1
Intake Air Method	Turbocharged/Aftercooled
Number of Main Bearings	7
Cylinder Head Type	Cast Iron
Piston Type	Aluminum

Engine Governing

Oil Pump Type

Governor	Electronic
Frequency Regulation (Steady State)	±0.25%
Lubrication System	

Gear Driven

Oil Filter Type Full Flow Spin-On Cartridge Crankcase Capacity - qt (L) 71.8 (68)

Cooling System

Cooling System Type	Pressurized Closed Recovery
Fan Type	Pusher
Fan Speed - RPM	1,440
Fan Diameter - in (mm)	45 (1,143)

Fuel System

Fuel Type	Ultra Low Sulfur Diesel #2
Fuel Filtering (Microns)	10 Primary and 2 Secondary
Injector Type	EUI
Fuel Supply Line - in (mm)	84 (2,134)
Fuel Return Line - in (mm)	84 (2,134)

Engine Electrical System

System Voltage	24 VDC
Battery Charger Alternator	50 A
Battery Size	See Battery Index 0161970SBY
Battery Voltage	12 VDC
Ground Polarity	Negative

ALTERNATOR SPECIFICATIONS

Standard Model	K0820124Y22
Poles	4
Field Type	Revolving
Insulation Class - Rotor	Н
Insulation Class - Stator	Н
Total Harmonic Distortion	<5%
Telephone Interference Factor (TIF)	< 50

Standard Excitation	Permanent Magnet
Bearings	Sealed Ball
Coupling	Direct via Flexible Disc
Prototype Short Circuit Test	Yes
Voltage Regulator Type	Digital
Number of Sensed Phases	All
Regulation Accuracy (Steady State)	±0.25%

INDUSTRIAL DIESEL GENERATOR SET

EPA Certified Stationary Emergency



OPERATING DATA

POWER RATINGS - DIESEL

	Standby		
Three-Phase 120/208 VAC @0.8pf	750 kW	Amps: 2,605	
Three-Phase 120/240 VAC @0.8pf	750 kW	Amps: 2,258	
Three-Phase 277/480 VAC @0.8pf	750 kW	Amps: 1,129	
Three-Phase 346/600 VAC @0.8pf	750 kW	Amps: 903	

MOTOR STARTING CAPABILITIES (skVA)

skVA vs. Voltage Dip

		• •	
277/480 VAC	30%	208/240 VAC	30%
K0820124Y22	2,100	K0820124Y22	1,500
K0912124Y22	2,700	K0912124Y22	2,000
K1000124Y22	2.700	K1000124Y22	1.900

FUEL CONSUMPTION RATES*

Diesel - gph (Lph)

Fuel Pump Lift - ft (m)	Percent Load	Standby	
12 (3.7)	25%	14.3 (54.1)	
	50%	25.6 (97.0)	
Total Fuel Pump Flow (Combustion + Return) gph (Lph)	75%	38.0 (143.8)	
111 (420)	100%	49.7 (188.0)	

^{*} Fuel supply installation must accommodate fuel consumption rates at 100% load.

COOLING

		Standby	
Air Flow (Fan Air Flow Across Radiator) - Open Set	scfm (m ³ /min)	27,376 (775.2)	
Coolant Flow	gpm (Lpm)	128 (485)	
Coolant System Capacity	gal (L)	27.3 (103.3)	
Maximum Operating Ambient Temperature	°F (°C)	122 (50)	
Maximum Operating Ambient Temperature (Before Derate)	See Bulletin	ulletin No. 0199280SSD	
Maximum Additional Radiator Backpressure	in H ₂ O (kPa)	0.5 (0.12)	

COMBUSTION AIR REQUIREMENTS

	Standby	
Flow at Rated Power - scfm (m ³ /min)	2.507 (71)	

ENGINE			EXHAUST	
		Standby		Standby
Rated Engine Speed	RPM	1,800	Exhaust Flow (Rated Output) scfm (m³/mir	1) 6,397 (181)
Horsepower at Rated kW**	hp	1,112	Maximum Exhaust Backpressure (Post Silencer) inHg (kPa)	2.95 (9.99)
Piston Speed	ft/min (m/min)	2,160 (658)	Exhaust Temperature (Rated Output - Post Silencer) °F (°C)	918 (492)
BMEP	psi (kPa)	443 (3,053)		

^{**} Refer to "Emissions Data Sheet" for maximum bHP for EPA and SCAQMD permitting purposes.

Deration – Operational characteristics consider maximum ambient conditions. Derate factors may apply under atypical site conditions.


Please contact a Generac Power Systems Industrial Dealer for additional details. All performance ratings in accordance with ISO3046, BS5514, ISO8528, and DIN6271 standards. Standby - See Bulletin 0187500SSB

Prime - See Bulletin 0187510SSB

EPA Certified Stationary Emergency

DIMENSIONS AND WEIGHTS*









OPEN SET


Run Time - Hours	Usable Capacity - Gal (L)	L x W x H - in (mm)	Weight - lbs (kg)
No Tank	-	154.4 (3,923) x 71.0 (1,803) x 80.3 (2,040)	10,468 - 10,913 (4,748 - 4,950)
6	334 (1,264)	158.5 (4,025) x 71.0 (1,803) x 94.3 (2,396)	12,143 - 12,588 (5,508 - 5,710)
20	1,001 (3,789)	158.5 (4,025) x 71.0 (1,803) x 116.3 (2,954)	13,068 - 13,513 (5,927 - 6,129)
20	1,001 (3,789)	228.0 (5,791) x 71.0 (1,803) x 105.3 (2,675)	13,618 - 14,063 (6,177 - 6,379)
40	2,002 (7,578)	290.0 (7,366) x 71.0 (1,803) x 116.3 (2,954)	15,318 - 15,763 (6,948 - 7,150)





WEATHER PROTECTED ENCLOSURE


Run Time	Usable Capacity	L x W x H - in (mm)	0 (losure Only) s (kg)
- Hours	- Gal (L)		Steel	Aluminum
No Tank	-	207.4 (5,268) x 71.0 (1,803) x 80.0 (2,032)		
6	334 (1,264)	207.4 (5,268) x 71.0 (1,803) x 94.0 (2,388)		
20	1,001 (3,789)	207.4 (5,268) x 71.0 (1,803) x 116.0 (2,946)	2,467 (967)	1,380 (474)
20	1,001 (3,789)	228.0 (5,791) x 71.0 (1,803) x 105.0 (2,667)		
40	2,002 (7,578)	290.0 (7,366) x 71.0 (1,803) x 116.0 (2,946)		






LEVEL 1 SOUND ATTENUATED ENCLOSURE

Run Time - Hours	Usable Capacity	L x W x H - in (mm)	٠, ١	losure Only) s (kg)
- nouis	- Gal (L)		Steel	Aluminum
No Tank	-	247.5 (6,285) x 71.0 (1,803) x 80.0 (2,032)		
6	334 (1,264)	247.5 (6,285) x 71.0 (1,803) x 94.0 (2,388)		
20	1,001 (3,789)	247.5 (6,285) x 71.0 (1,803) x 116.0 (2,946)	3,472 (1,423)	1,812 (670)
20	1,001 (3,789)	247.5 (6,285) x 71.0 (1,803) x 105.0 (2,667)		
40	2,002 (7,578)	290.0 (7,366) x 71.0 (1,803) x 116.0 (2,946)		





LEVEL 2 SOUND ATTENUATED ENCLOSURE

Run Time - Hours	Usable Capacity	Weight (Encl L x W x H - in (mm) - lbs		,
- Hours	- Gal (L)		Steel	Aluminum
No Tank	-	207.4 (5,268) x 71.0 (1,803) x 114.1 (2,899)		
6	334 (1,264)	207.4 (5,268) x 71.0 (1,803) x 128.1 (3,255)		
20	1,001 (3,789)	207.4 (5,268) x 71.0 (1,803) x 150.1 (3,813)	3,809 (1,576)	1,955 (735)
20	1,001 (3,789)	228.0 (5,791) x 71.0 (1,803) x 139.1 (3,534)		
40	2.002 (7.578)	290.0 (7.366) x 71.0 (1.803) x 150.1 (3.813)		

^{*} All measurements are approximate and for estimation purposes only.

YOUR FACTORY RECOGNIZED GENERAC INDUSTRIAL DEALER			

Specification characteristics may change without notice. Dimensions and weights are for preliminary purposes only. Please contact a Generac Power Systems Industrial Dealer for detailed installation drawings.



STATEMENT OF EXHAUST EMISSIONS 2022 Perkins Diesel Fueled Generator

The measured emissions values provided here are proprietary to Generac and it's authorized dealers. This information may only be disseminated upon request to regulatory governmental bodies for emissions permitting purposes or to specifying organizations as submittal data when expressly required by project specifications, and shall remain confidential and not open to public viewing. This information is not intended for compilation or sales purposes and may not be used as such, nor may it be reproduced without the expressed written permission of Generac Power Systems, Inc.. The data provided shall not be meant to include information made public by Generac.

Generator Model: **SD/MD750 EPA Certificate Number:** NCPXL18.1NYS-003 750 **CARB Certificate Number:** kW Rating: **Not Applicable**

Engine Family: NCPXL18.1NYS SCAQMD CEP Number: 618807 2806C-E18TTAG7 **Engine Model: Emission Standard Category:** Tier 2

Rated Engine Power (BHP)*: Certification Type: Stationary Emergency CI 1,112 (40 CFR Part 60 Subpart IIII) Fuel Consumption (gal/hr)*: 54.3

Aspiration: Turbocharged/Aftercooled

1,800 Rated RPM:

EMISSIONS BASED ON ENGINE POWER OF SPECIFIC ENGINE MODEL

These Values Are Actual Composite Weighted Exhaust Emissions Results Over the EPA 5-Mode Test Cycle

CO	NOx + NMHC	PM	
0.90	5.60	0.05	Grams/kW-hr
0.67	4.18	0.07	Grams/bhp-hr

These values are 100% load data exhaust emissions results.

CO	NOx + NMHC	PM	
0.22	5.42	0.03	Grams/kW-hr
0.16	4.04	0.02	Grams/bhp-hr

- The stated values are actual exhaust emission test measurements obtained from an engine representative of the type described above.
- Values based on 5-Mode testing are official data of record as submitted to regulatory agencies for certification purposes. Testing was conducted in accordance with prevailing EPA protocol, which is typically accepted by SCAQMD and other regional authorities.
- No emissions values provided above are to be construed as quarantees of emission levels for any given Generac generator unit.
- Generac Power Systems, Inc. reserves the right to revise this information without prior notice.
- Consult state and local regulatory agencies for specific permitting requirements.
- The emission performance data supplied by the equipment manufacturer is only one element required toward completion of the permitting and installation process. State and local regulations may vary on a case-by-case basis and local agencies must be consulted by the permit application/ equipment owner prior to equipment purchase or installation. The data supplied herein by Generac Power Systems Inc. cannot be construed as a quarantee of installability of the generating set.

1 0F 1

^{*}Engine power and fuel consumption are declared by the engine manufacturer of record and the U.S EPA.





Proposal Number: RFP-22-001072

Application & Performance Warranty Data

Project Information

Site Location: California

Project Name: SD750 18.1 Liter
Application: Standby Power

Number Of Engines: 4

Operating Hours per Year: 200

Engine Specifications

Engine Manufacturer: Generac

Model Number: SD750 18.1 L

Rated Speed: 1800 RPM

Type of Fuel: Ultra-Low Sulfur Diesel (ULSD)

Type of Lube Oil: 1 wt% sulfated ash or less

Lube Oil Consumption: 0.1 % Fuel Consumption

Number of Exhaust Manifolds:

Engine Cycle Data

Load	Speed	Power	Exhaust Flow	Exhaust Temp.	Fuel Cons.	PM ₁₀	02	H ₂ O
%		bhp	acfm (cfm)	°F		g/bhp-hr	%	%
100	Rated	1,112	6,397	918		0.02	10	12.5

Emission Data (100% Load)

		Raw Engine Emissions						Target Outlet Emissions					
Emission	g/bhp- hr	tons/yr	ppmvd @ 15% O ₂	ppmvd	g/kW-hr	lb/MW- hr	g/bhp- hr	tons/yr	ppmvd @ 15% O ₂	ppmvd	g/kW-hr	lb/MW- hr	Calculated Reduction
PM ₁₀	0.02	0	7	12	0.027	0.06	0	0	1	2	0.004	0.01	85%

System Specifications

CARB Verified DOC/DPF System Specifications (LTRV24-21-10-R1)

Sound Attenuation: Critical Grade

Design Exhaust Flow Rate: 6,397 acfm (cfm)

Design Exhaust Temperature¹: 918° F
Minimum Regeneration Temperature²: 500° F

System Pressure Loss: 13.0 inH₂O (Clean)

CONFIDENTIAL Page 3 of 14 Proposal Date: 2/16/2022





Proposal Number: RFP-22-001072

MIRATECH Scope of Supply & Equipment Details

	Model Number	Quantity
DPF Housing & Catalyst	LTRV24-21-10-R1	1 / engine
DPF Housing Kit	LTRV24-10-HSG-0	1 / engine
DPF Housing	LTRV24-10-HSG	1 / engine
Material	Carbon Steel	
• Paint	Standard High Temperature Black Paint	
Door Location	Right	
Dimensions	H 32.625 in x W 44.125 in x L 85 in	
 Inlet Pipe Size & Connection 	10 in FF Flange, 150# ANSI standard bolt pattern	
 Outlet Pipe Size & Connection 	10 in FF Flange, 150# ANSI standard bolt pattern	
Weight Including Catalyst	1,328 lbs	
Weight Without Catalyst	891 lbs	
Tray Set	Tray Set-LTR24-300mm	1 / engine
Gasket	LTR Expansion Mat	11 / engine
Gasket	3010.0002	1 / engine
DPF Block	LTR-DPF-Filter-Block	21 / engine
DPF Spacer	Soot Filter Spacer	3 / engine
Oxidation Catalyst	MECR-OX-SB3113-2400-2000-291	1 / engine
Data Logger	DPF-DataLogger-Assembly	1 / engine
Nut, Bolt, and Gasket Set	NBG-LTR24	1 / engine

Customer Scope Of Supply

- Support Structure
- · Attachment to Support Structure (Bolts, Nuts, Levels, etc.)
- Expansion Joints
- Exhaust Piping
- · Inlet Pipe Bolts, Nuts, & Gasket
- · Outlet Pipe Bolts, Nuts, & Gasket
- · Insulation for Exhaust Piping
- Insulation for Housing
- Installation, Fabrication, and Installation of Mounting Frame for Particulate Filters







Proposal Number: RFP-22-001072

Special Notes & Conditions

- For housings and exhaust components that are insulated, internally or externally, please refer to Section 7.1 of the General Terms and Conditions of Sale to prevent voiding MIRATECH product warranty.
 - Carbon steel is suitable for temperatures up to 900° F / 482° C continuously, when covered with external insulation or a heat shield.
 For continuous operation above 900° F / 482° C, where the equipment is externally insulated or has a heat shield, stainless steel should be used.
- Diesel Particulate Filters depend on exhaust temperature to keep soot regenerated and the filter back pressure within acceptable levels. If the
 engine will be operated consistently at low loads/low exhaust temperatures, the customer should make provisions to add load via facility
 operations or a load bank. Refer to the included <u>Guidelines for Successful Operation of LTR™ DPF</u>.
- A packed silencer installed upstream of the MIRATECH catalyst system will void MIRATECH's limited warranty.
- Final catalyst housings are dependent on engine output and required emission reductions. Changes may be made to optimize the system
 design at the time of order.
- Any drawings included with this proposal are preliminary in nature and could change depending on final product selection.
- Any sound attenuation listed in this proposal is based on housing with catalyst elements installed.
- Any emission reductions listed in this proposal are based on housing with catalyst elements installed.
- MIRATECH will confirm shipping location upon placement of order.





	모
ļ	유
	š
	SS
	Ξ
	Date
	품
	·
	10
	-
	9
	N
	읈
	23
	10

PAINT:

SYSTEM 1)

. HIGH TEMPERATURE BLACK (MIRATECH COATING

WEIGHTS (APPROXIMATE) **EMPTY HOUSING** 891 lb ONE (1) FULL DPF CATALYST LAYER 437 lb ONE (1) OXIDATION ELEMENT 53 lb HOUSING HAS CAPACITY FOR ONE(1) FULL DPF CATALYST LAYERS HOUSING HAS CAPACITY FOR ONE(1) OXIDATION ELEMENT 84.500 47.250 18.250 19.000 (2) LIFTING LUG-42.617 DOOR 40,188 CLAMPS (2) 1/2" NPT SAMPLE PORTS (2) 1/4" NPT SAMPLE PORTS 35,438 EXHAUST INLET EXHAUST OUTLET (2) 10" FF FLANGE 150 Ib ANSI STANDARD BOLT PATTERN 2.188 ACCESS SERVICE 26.313 3.500 I.D. DOOR 18.500 34.750 TYP FRONT VIEW 6.000 TYP RIGHT VIEW 34.000 Ø16.000 Ø10.750 O.D. TYP I.D. TYP 15.781 NOTES: ONLY USE LIFTING LUGS TO LIFT HOUSING
 ALLOW MINIMUM 50" CLEARANCE FROM DOOR FOR LOADING AND MAINTENANCE
 NO FORCES OR MOMENTS MAY BE APPLIED TO THE FLANGES
 MUST BE MOUNTED HORIZONTALLY (CUSTOM HOUSING REQUIRED TO MOUNT VERTICALLY)
 CARB VERIFIED FOR STATIONARY APPLICATIONS LEFT VIEW **W** MIRALECH PROJECT NAME PROPRIETARY AND CONFIDENTIAL DIMENSIONS ARE APPROXIMATE IN INCHES PROPOSAL NUMBER THE INFORMATION CONTAINED IN LTRV24-10 MATERIAL CONSTRUCTION: UNLESS OTHERWISE SPECIFIED THIS DRAWING IS THE SOLE PROPERTY Sales Drawing . CARBON STEEL OF MIRATECH CORPORATION, ANY

REPRODUCTION IN PART OR AS A

WHOLE WITHOUT THE WRITTEN

CORPORATION IS PROHIBITED.

PERMISSION OF MIRATECH

SALES ORDER NO.

CUSTOMER P.O.

DO NOT SCALE DRAWING

ACF

CDT

DRAWING

SCALE 1:24

LTRV24-10 SD

03/31/2014

03/31/2014

REV

0

SHEET I OF I

DRAWN

REVIEWED BY

State of California AIR RESOURCES BOARD

EXECUTIVE ORDER DE-14-005-07

Pursuant to the authority vested in the California Air Resources Board (CARB) by Health and Safety Code, Division 26, Part 5, Chapter 2; and pursuant to the authority vested in the undersigned by Health and Safety Code section 39515 and 39616 and Executive Order G-14-012;

This action relates to Verification under sections 2700 through 2711 of title 13 of the California Code of Regulations:

Miratech Group, LLC (Miratech) MIRATECH® LTR™ DOC/DPF

CARB has reviewed Miratech's request for verification of the MIRATECH® LTR™ DOC/DPF. Based on an evaluation of the data provided, and pursuant to the terms and conditions specified below, the Executive Officer of CARB hereby finds that the MIRATECH® LTR™ DOC/DPF reduces emissions of diesel particulate matter (PM) consistent with a Level 3 device (greater than or equal to 85 percent reductions) (California Code of Regulations (CCR), title 13, sections 2702 (f) and (g) and section 2708) and complies with the CARB January 1, 2009, nitrogen dioxide (NO2) limit (CCR, title 13, section 2702 (f) and section 2706 (a)). Accordingly, the Executive Officer determines that the system merits verification and, subject to the terms and conditions specified below, classifies the MIRATECH® LTR™ DOC/DPF as a Level 3 Plus for use with stationary emergency standby generators using engine families listed in Attachment 1.

This verification is subject to the following terms and conditions:

- The engine must be used in a stationary application associated with emergency standby generators and rated greater than or equal to 50 horsepower (hp).
- The engine must be certified for use in California or certified by the United States Environmental Protection Agency and the engine must be in its original certified configuration.
- The engine must be certified Tier 1, Tier 2, Tier 3, Tier 4i with a rated horsepower between 50 and 75 or over 750, or Tier 4 Alt 20 percent nitrogen oxide (NOx) and PM, nonroad or stationary diesel engine meeting 0.22 grams per brake horsepower-hour (g/bhp-hr) diesel PM or less based on certification or in-use emissions testing (as tested on an appropriate steady-state certification cycle outlined in the CARB off-road regulations, similar to ISO 8178 D2).
- The engine must not employ exhaust gas recirculation (EGR).
- The engine must not have a pre-existing oxidation catalyst.
- The engine must not have a pre-existing diesel particulate filter.
- The engine must not have a pre-existing selective catalytic reduction.

- The engine must be four-stroke.
- The engine can be turbocharged or naturally-aspirated.
- Miratech must review actual operating conditions (duty cycle, baseline emissions, and engine exhaust backpressure and temperature profiles, and other pre-installation compatibility assessments as required in section 2706 (t) of title 13, of the CCR) prior to retrofitting an engine with the MIRATECH[®] LTR[™] DOC/DPF to ensure compatibility.
- The engine should be well maintained and not consume lubricating oil at a rate greater than that specified by the engine manufacturer.
- The MIRATECH® LTR™ DOC/DPF must not be operated with fuel additives, as defined in section 2701 of title 13, of the CCR, unless explicitly verified for use with fuel additive(s).
- The other terms and conditions are specified below.

Table 1: Conditions for the MIRATECH® LTR™ DOC/DPF

Parameter	Value
Application	Stationary Emergency Standby Power Generation
Size Range	Diesel engines rated greater than or equal to 50 hp
Engine Type	Diesel, with or without turbocharger, without EGR, mechanically or electronically controlled, Tier 1, Tier 2, Tier 3, Tier 4i with a rated horsepower between 50 and 75 or over 750, or Tier 4 Alt 20 percent NOx and PM, certified to 0.22 g/bhp-hr or less of PM.
Minimum Exhaust Temperature for Filter Regeneration	260° Celsius / 500° Fahrenheit. At 550° Fahrenheit, regeneration takes approximately 45 minutes.
Maximum Consecutive Minutes Operating Below Passive Regeneration Temperature	720 Minutes
Number of Cold Start and 40 Minute Idle Sessions before Regeneration Required	18
Number of Hours of Operation Before Cleaning of Filter Required	Application-Specific. 2000 Hours Typical.
Fuel	California diesel fuel with less than or equal to 15 ppm sulfur or a biodiesel blend provided that the biodiesel portion of the blend complies with ASTM D6751, the diesel portion of the blend complies with title 13 (CCR), sections 2281 and 2282, and the blend contains no more than 20 percent biodiesel by volume.
Verification Level	Level 3 Plus Verification: PM - at least 85 percent reduction NO2 - meets January 2009 limit

This Executive Order is valid provided that installation instructions for MIRATECH® LTR™ DOC/DPF do not recommend tuning the engine to specifications different from those of the engine manufacturer. The product must not be used with any other systems or engine modifications without CARB and manufacturer approval.

The MIRATECH® LTR™ DOC/DPF is a passive diesel exhaust filter system. It consists of a filter housing, DOC, DPF, and monitoring system (backpressure sensor, temperature sensor, and a display unit that provides warnings when the filter becomes clogged or damaged). Changes made to the design or operating conditions of MIRATECH® LTR™ DOC/DPF, as exempted by CARB, which adversely affect the performance of the engine's pollution control system, shall invalidate this Executive Order.

No changes are permitted to the MIRATECH® LTR™ DOC/DPF without CARB evaluation and approval. CARB must be notified in writing of any changes to any part of MIRATECH® LTR™ DOC/DPF. Failure to do so shall invalidate this Executive Order.

No person shall alter, physically disable, disconnect, bypass, or tamper with an installed CARB verified diesel emissions control strategy, as outlined in title 13 CCR section 2711(e). Should CARB become aware that a design feature of a verified device is altered, physically disabled, disconnected, bypassed, or tampered on multiple units by independent persons, Miratech will be responsible to propose a design modification and recall plan to the Executive Officer to minimize existing and potential for future tampering of the verified device.

Marketing of the MIRATECH® LTR™ DOC/DPF using identification other than that shown in the Executive Order or for an application other than that listed in the Executive Order shall be prohibited unless prior approval is obtained from CARB.

As specified in the Diesel Emissions Control Strategy Verification Procedure (CCR, title 13, section 2706 (j)), CARB assigns each Diesel Emissions Control Strategy a family name. The designated family name for the verification as outlined above is:

CA/MES/2014/PM3+/N00/ST/DPF01

This designated family name must be used in reference to this Executive Order as part of the system labeling requirement. Labels attached to the MIRATECH® LTR™ DOC/DPF and the engine must be identical.

Proper engine maintenance is critical for the proper functioning of the diesel emissions control strategy. The owner of the equipment on which the diesel emissions control strategy is installed is strongly advised to adhere to all good engine maintenance practices. Failure to document proper engine maintenance, including keeping records of the engine's oil consumption, may be grounds for denial of a warranty claim.

The terms and conditions of this Executive Order must be satisfied regardless of where the system is sold in order for the system to be considered verified. Systems sold as verified, or which carry a CARB-approved label, must satisfy all the terms and conditions of this Executive Order.

Additionally, as stated in the Diesel Emissions Control Strategy Verification Procedure, Miratech is responsible for honoring the record keeping requirements (CCR, title 13, section 2702), their warranty (CCR, title 13, section 2707), conducting in-use compliance testing (CCR, title 13, section 2709), and complying with the system labeling requirements (CCR, title 13, section 2706 (j)).

In addition, CARB reserves the right in the future to review this Executive Order and verification provided herein to assure that the verified add-on or modified part continues to meet the standards and procedures of CCR, title 13, section 2222, et seq and CCR, title 13, sections 2700 through 2711.

Systems verified under this Executive Order shall conform to all applicable California emissions regulations. This Executive Order does not release Miratech from complying with all other applicable regulations.

Violation of any of the above conditions shall be grounds for revocation of this Executive Order.

Executive Order DE-14-005-06 is hereby superseded and is of no further force and effect.

Executed at Sacramento, California, this <u>25</u> day of <u>May</u> 2021.

Richard Boyd

Assistant Division Chief

Richard By

Transportation and Toxics Division

APPENDIX C – EMISSION CALCULATIONS



Copyright © $\mathbf{2022}$, Yorke Engineering, LLC

Table C-1 Criteria Pollutant Emissions

Pollutant	Emission Factor	References	AHU	AHC	мни	мнс	MDU	MDC	AA	30DA
	(g/bhp-hr)		(lb/hr)	(lb/hr)	(lb/hr)	(lb/hr)	(lb/day)	(lb/day)	(lb/yr)	(lb/day)
VOC	0.20	[1,2]	0.49	0.49	0.49	0.49	0.49	0.49	24.52	0.07
NOx	3.84	[1,2]	9.42	9.42	9.42	9.42	9.42	9.42	470.75	1.32
SOx	0.005	[3]	0.01	0.01	0.01	0.01	0.01	0.01	0.60	0.002
CO	0.16	[1]	0.39	0.39	0.39	0.39	0.39	0.39	19.61	0.05
PM10/PM2.5 (No DPF)	0.02	[1,4]	0.05		0.05		0.05			
PM10/PM2.5 (With DPF)	0.003	[1,4]		0.007		0.007		0.007	0.368	0.001

Table C-2 Toxic Air Contaminant Emissions

Pollutant	CAS Number	Emission Factor (g/bhp- hr)	References	MHC (lb/hr)	MAC (lb/year)
Diesel PM	9901	0.02	[1,4]	0.007	0.37

Table C-3 GHG Emissions

Pollutant	Emissions (kg/yr)	Emissions (mt/yr)	Emissions (tpy)	GWP ^a	Emissions of CO ₂ e (tpy)
CO2	27,710.6	27.7	30.5	1	30.5
CH4	1.1	0.0011	0.0012	25	0.03
N2O	0.2	0.0002	0.0002	298	0.07
					30.65

Equipment and Operating Parameters

Valu	Units	
Operating schedule	50	hr/yr
Operating schedule	1	hr/day
Operating Schedule	4.2	hr/mo
Engine rating	1112	hp
Fuel use	401	lb/hr
Fuel use	54.3	gal/hr
Max Annual Fuel Use	2,715	gal/yr

Other Factors and Constants

Val	ue	References
453.5	g/lb	Constant
7000	BTU/hp-hr	[5]
137,000	BTU/gal diesel	[6]
7.05	lb/gal diesel	[6]
64	lb/lb mol SO2	Constant
32	lb/lb mol S	Constant
15	ppmw S in USLD	[7]
95%	%NOx	[2]
5%	%NMHC	[2]
4.04	g NHMC-NOx/bhp-hr	[1]
0.16	g CO/bhp-hr	[1]
0.02	g PM/bhp-hr	[1]
85%	DPF PM Filtration	[8]
05%	Efficiency	[0]
0.138	Diesel No. 2b	[b]
0.156	MMBtu/gal	[D]
73.96	CO2 EF for Diesel	[b]
75.50	kg/MMBtu	[D]
0.003	CH4 EF for Diesel	[b]
0.005	kg/MMBtu	[D]
0.0006	N2O EF for Diesel	[b]
0.0006	kg/MMBtu	נטן
1.10231	Metric tons (mt) to	[c]
1.10231	Short tons (st/mt)	[C]

References

- [1] PM, NMHC+NOX, CO per "STATEMENT OF EXHAUST EMISSIONS 2022 Perkins Diesel Fueled Generator" document.
- [2] 95% of NMHC+NOx as NOx and 5% as NMHC (VOC/ROC) per 2005 Carl Moyer Guidelines Table B-22 (NOx and MHC Fraction Default Values for All Engines except TRUs)
- [3] SOx EF based on mass balance of 15 ppmw sulfur content in diesel fuel and engine fuel consumption rate
- [4] Assume 100% diesel PM is <2.5 microns ("80%-95% of the mass of particles in DE is in the size range from 0.05-1.0" per EPA Health Assessment for Diesel Engine Exhaust May 2002)
- [5] Default Brake-Specific Fuel Capacity (BSFC) per AP-42 Table 3.3-1 (10/96)
- [6] Defaults for diesel/distillate fuel oil per AP-42 Appendix A (09/85)
- [7] CA diesel limited to 15 ppm sulfur for sale or supply (CCR §2281(a)(2) Sulfur Content of Diesel Fuel)
- [8] Miratech DPF Spec Sheet PDF, 85% PM reduction.
- (a) Source: 40 CFR 98 Subpart A, Table A-1, [78 FR 71948, Nov. 29, 2013] effective Jan. 1, 2014.
- (b) Source: 40 CFR 98 Subpart C, Tables C-1 and C-2.
- (c) Source: 40 CFR 98 Subpart A, Table A-2.

APPENDIX D - RULE 1401 TIER II SCREENING RISK ASSESSMENT

TIER 2 SCREENING RISK ASSESSMENT REPORT

(Procedure Version 8.1 & Package N, September 1, 2017) - Risk Tool V1.103

A	/N: West		Fac: AES Alamitos, LI	LC Application deer	ned complete date:	4/30/2022
1. Stack Data				2. Tier 2 Data		
				Dispersion Factors tables	Point Source	
Equipment Type	Diesel ICE	_	Engine Horse Power: 1112 BHP	For Chronic X/Q	Table 10	
			Engine Year Built: 2022 Generator Engine? YES	For Acute X/Q max	Table 10.6	
Combustion Eff	0.85		Engine Emission Factor: 0.02 g/bhp-hr	Dilution Factors		
	No T-BACT	_ [Receptor	X/Q (µg/m³)/(tons/yr)	X/Q (μg/m³)
		_		Residential	0.10	4.3
				Commercial - Worker	0.12	3.:
Operation Schedule	1	_ hrs/day _ days/week		Intake and Adjustment Factors		
	50	weeks/year			Residential	Wo
				Year of Exposure	30	
Stack Height	15.33	_ ft		Combined Exposure Factor (CEF) - Table 4	677.40	55.
				Worker Adjustment Factor (WAF) - Table 5	1	4.:
Distance to Residential	383.1	_m				
Distance to Commercial	329.2	_m				
Meteorological Station	Long Beach	Airport				

Page 1 of 11 4/19/2022

X/Qmax

 $(\mu g/m^3)/(lbs/hr)$ 4.31 3.52

> Worker 55.86 4.20

A/N:	West	Application deemed complete date:	04/30/22

3. Rule 1401 Compound Data

Compound	R1 - Uncontrolled (lbs/hr)	R2 - Controlled (lbs/hr)	CP (mg/kg-day) ⁻¹	MP MICR Resident	MP MICR Worker	MP Chronic Resident	MP Chronic Worker	REL Chronic (μg/m³)	REL 8-hr Chronic (μg/m³)	REL Acute (μg/m³)	MWA
Particulate Emissions from Diesel-Fueled En	4.90E-02	7.35E-03	1.10E+00	1.00	1.00	1.00	1.00	5.00E+00			
											-
											-
											-
											+
						+					
		-									

A/N: West Application deemed complete date: 04/30/22

4. Emission Calculations

Compound	R1 (lbs/hr)	R2 (lbs/hr)	R1 (lbs/day)	R2 (lbs/day)	R2 (lbs/yr)	R2 (tons/yr)
Particulate Emissions from Diesel-Fueled En	4.90E-02	7.35E-03	4.90E-02	7.35E-03	3.67E-01	1.84E-04
T. 4.1	4.00E-02	# 25E 02	4.00E-02	# 25E 02	2.67E-01	1.045.04
Total	4.90E-02	7.35E-03	4.90E-02	7.35E-03	3.67E-01	1.84E-04

TIER 2 RESULTS	A/N: West	Application deemed complete date: 04/30/22
----------------	-----------	--

Page 3 of 11

4/19/2022

5a. MICR

 $MICR\ Resident = CP\ (mg/(kg-day))^{-1} * Q\ (ton/yr) * (X/Q)\ Resident * CEF\ Resident * MP\ Resident * 1e-6 * MWAF$

MICR Worker = CP (mg/(kg-day))^-1 * Q (ton/yr) * (X/Q) Worker * CEF Worker* MP Worker* WAF Worker* 1e-6 * MWAF

G 1	D 11 (11	G : 1
Compound	Residential	Commercial
Particulate Emissions from Diesel-Fueled En	1.32E-08	5.61E-09
Total	1.32E-08	5.61E-09
	PASS	PASS
	r ASS	rASS

5b. Is Cancer Burden Calculation Needed (MICR >1E-6)?

NO

New X/Q at which MICR $_{70yr}$ is one-in-a-million [($\mu g/m^3$)/(tons/yr)]: New Distance, interpolated from X/Q table using New X/Q (meter): Zone Impact Area (km²): Zone of Impact Population (7000 person/km²):

Cancer Burden:

Tier 2 Report - 190410-copy-of-risktool-(v1-103)-r040919---aqmd-procedure-8-1 (19)

Page 4 of 11 4/19/2022

6. Hazard Index Summary

HIA = [Q(lb/hr) * (X/Q)max * MWAF]/Acute REL

HIC = [Q(ton/yr) * (X/Q) * MP * MWAF] / Chronic REL

HIC 8-hr= [Q(ton/yr) * (X/Q) * WAF * MWAF] / 8-hr Chronic REL

Target Organs	Acute	Chronic	8-hr Chronic	Acute Pass/Fail	Chronic Pass/Fail	8-hr Chronic Pass/Fail
Alimentary system (liver) - AL			N/A	Pass	Pass	Pass
Bones and teeth - BN			N/A	Pass	Pass	Pass
Cardiovascular system - CV			N/A	Pass	Pass	Pass
Developmental - DEV			N/A	Pass	Pass	Pass
Endocrine system - END			N/A	Pass	Pass	Pass
Eye			N/A	Pass	Pass	Pass
Hematopoietic system - HEM			N/A	Pass	Pass	Pass
Immune system - IMM			N/A	Pass	Pass	Pass
Kidney - KID			N/A	Pass	Pass	Pass
Nervous system - NS			N/A	Pass	Pass	Pass
Reproductive system - REP			N/A	Pass	Pass	Pass
Respiratory system - RESP		4.35E-06	N/A	Pass	Pass	Pass
Skin			N/A	Pass	Pass	Pass

A/N: West

Page 5 of 11 4/19/2022

Application deemed complete date: 04/30/22

A/N:	West	Application deemed complete date:	04/30/22
1 1/ 1 10	11 050	application accinca complete date.	0 1/30/22

6a. Hazard Index Acute - Resident

HIA = [Q(lb/hr) * (X/Q)max resident * MWAF] / Acute REL

	HIA - Residential									
Compound Particulate Emissions from Diesel-Fueled En	AL	CV	DEV	EYE	HEM	IMM	NS	REP	RESP	SKIN
Particulate Emissions from Diesel-Fueled En										
Total										
			l	1	l	L		l	1	

Page 6 of 11 4/19/2022

6a. Hazard Index Acute - Worker

Application deemed complete date: 04/30/22

HIA = [Q(lb/hr) * (X/Q)max Worker * MWAF] / Acute REL

		HIA - Commercial										
Compound	AL	CV	DEV	EYE	HEM	IMM	NS	REP	RESP	SKIN		
Particulate Emissions from Diesel-Fueled En												
Total												
TOTAL												

Page 7 of 11 4/19/2022

A/N:	West	Application deemed complete date:	04/30/22

6b. Hazard Index Chronic - Resident

HIC = [Q(ton/yr) * (X/Q) Resident * MP Chronic Resident * MWAF] / Chronic REL

	HIC - Residential												
Compound	AL	BN	CV	DEV	END	EYE	HEM	IMM	KID	NS	REP	RESP	SKIN
Particulate Emissions from Diesel-Fueled En												3.55E-06	
Fotal	+									1		3.55E-06	

Page 8 of 11 4/19/2022

A/N:	West	Application deemed complete date:	04/30/22

6b. Hazard Index Chronic - Worker

HIC = [Q(ton/yr) * (X/Q) * MP Chronic Worker * MWAF] / Chronic REL

	HIC - Commercial												
Compound	AL	BN	CV	DEV	END	EYE	HEM	IMM	KID	NS	REP	RESP	SKIN
Particulate Emissions from Diesel-Fueled En												4.35E-06	
Total												4.35E-06	

Page 9 of 11 4/19/2022

A/N: West

Application deemed complete date: __04/30/22__

HIC 8-hr = [Q(ton/yr) * (X/Q) Resident * WAF Resident * MWAF] / 8-hr Chronic REL

	HIC - Residential												
Compound	AL	BN	CV	DEV	END	EYE	HEM	IMM	KID	NS	REP	RESP	SKIN
Particulate Emissions from Diesel-Fueled En													
Total													L

Page 10 of 11 4/19/2022

A/N: West Application deemed complete date:04/30/2	A/N:	West	Application deemed complete date:	04/30/22
--	------	------	-----------------------------------	----------

6c. 8-hour Hazard Index Chronic - Worker

HIC 8-hr = [Q(ton/yr) * (X/Q) Worker * WAF Worker * MWAF] / 8-hr Chronic REL

Compound AL BN CV DEV END EYE HEM IMM KID NS REP RESP SKN Particulate Emissions from Dissel-Fueled En Image: Compound of the particular Emissions from Dissel-Fueled En Image: Compound of the particular Emissions from Dissel-Fueled En Image: Compound of the particular Emissions from Dissel-Fueled En Image: Compound of the particular Emissions from Dissel-Fueled En Image: Compound of the particular Emissions from Dissel-Fueled En Image: Compound of the particular Emissions from Dissel-Fueled En Image: Compound of the particular Emissions from Dissel-Fueled En Image: Compound of the particular Emissions from Dissel-Fueled En Image: Compound of the particular Emissions from Dissel-Fueled En Image: Compound of the particular Emissions from Dissel-Fueled En Image: Compound of the particular Emissions from Dissel-Fueled En Image: Compound of the particular Emissions from Dissel-Fueled En Image: Compound of the particular Emissions from Dissel-Fueled En Image: Compound of the particular Emissions from Dissel-Fueled En Image: Compound of the particular Emissions from Dissel-Fueled En Image: Compound of the particular Emissions from Dissel-Fueled En Image: Compound of the particular Emissions from Dissel-Fueled En Image: Compound of the particular Emissions from Dissel-Fueled En Image: Compound of the particular Emissions from Dissel-Fueled En Image: Compound of the particular Emissions from Dissel-Fueled En		HIC - Commercial												
Particulate Emissions from Diesel-Pucled En	Compound	AL	BN	CV	DEV	END	EYE	HEM	IMM	KID	NS	REP	RESP	SKIN
Total	Particulate Emissions from Diesel-Fueled En													
Total														
Total														
Total														
Total														
Total														
Total														
Total														
Total														
Total														
Total														
Total														
Total														
Total														
Total														
Total														
Total														
Total														
Total														
Total														
Total														
Total														
Total														
Total														
Total														
Total														
	Total													

Page 11 of 11 4/19/2022

TIER 2 SCREENING RISK ASSESSMENT REPORT

(Procedure Version 8.1 & Package N, September 1, 2017) - Risk Tool V1.103

A/N: East		Fac: AES Alamitos, LLC	Application deemed complete date:				
1. Stack Data			2. Tier 2 Data				
			Dispersion Factors tables	Point Source			
Equipment Type	Diesel ICE	Engine Horse Power: 1112 BHP	For Chronic X/Q	Table 10			
		Engine Year Built: 2022	For Acute X/Q max	Table 10.6			
Combustion Eff	0.85	Generator Engine? YES Engine Emission Factor: 0.02 g/bhp-hr	Dilution Factors				
	No T-BACT	g	Receptor	X/Q ($\mu g/m^3$)/(tons/yr)	X/Q (μg/m³)/		
			Residential	0.07	3		
			Commercial - Worker	0.20	4.3		
Operation Schedule	1 hrs/day days/week		Intake and Adjustment Factors				
	50 weeks/year			Residential	Wo		
			Year of Exposure	30			
Stack Height	15.33ft		Combined Exposure Factor (CEF) - Table 4	677.40	55.		
			Worker Adjustment Factor (WAF) - Table 5	1	4.2		
Distance to Residential	m						
Distance to Commercial	m						
Meteorological Station	Long Beach Airport						

Page 1 of 11 4/19/2022

X/Qmax $(\mu g/m^3)/(lbs/hr)$ 3.37 4.82

> Worker 55.86 4.20

A/N:_	East	Application deemed complete date:	04/30/22

3. Rule 1401 Compound Data

Compound	R1 - Uncontrolled (lbs/hr)	R2 - Controlled (lbs/hr)	CP (mg/kg-day) ⁻¹	MP MICR Resident	MP MICR Worker	MP Chronic Resident	MP Chronic Worker	REL Chronic (μg/m³)	REL 8-hr Chronic (μg/m³)	REL Acute (μg/m³)	MWAF
Particulate Emissions from Diesel-Fueled Er	4.90E-02	7.35E-03	1.10E+00	1.00	1.00	1.00	1.00	5.00E+00			
											-
											-
											-
											-
											-
											-
											+
											-
											+
											

A/N: East Application deemed complete date: 04/30/22

4. Emission Calculations

Compound	R1 (lbs/hr)	R2 (lbs/hr)	R1 (lbs/day)	R2 (lbs/day)	R2 (lbs/yr)	R2 (tons/yr)
Particulate Emissions from Diesel-Fueled En	4.90E-02	7.35E-03	4.90E-02	7.35E-03	3.67E-01	1.84E-04
T. 4.1	4.00E-02	# 25E 02	4.00E-02	# 25E 02	2.67E-01	1.045.04
Total	4.90E-02	7.35E-03	4.90E-02	7.35E-03	3.67E-01	1.84E-04

TIER 2 RESULTS	A/N: East	Application deemed complete date: 04/30/22
----------------	-----------	--

Page 3 of 11

4/19/2022

5a. MICR

MICR Resident = CP (mg/(kg-day))^-1 * Q (ton/yr) * (X/Q) Resident * CEF Resident * MP Resident * 1e-6 * MWAF

MICR Worker = CP (mg/(kg-day))^-1 * Q (ton/yr) * (X/Q) Worker * CEF Worker* MP Worker* WAF Worker* 1e-6 * MWAF

Compound Particulate Emissions from Diesel-Fueled En	Residential	Commercial
Particulate Emissions from Diesel-Fueled En	9.19E-09	9.48E-09
Total	9.19E-09	9.48E-09
	PASS	PASS

5b. Is Cancer Burden Calculation Needed (MICR >1E-6)?

NO

New X/Q at which MICR $_{70yr}$ is one-in-a-million [($\mu g/m^3$)/(tons/yr)]: New Distance, interpolated from X/Q table using New X/Q (meter): Zone Impact Area (km²): Zone of Impact Population (7000 person/km²):

Cancer Burden:

Tier 2 Report - 190410-copy-of-risktool-(v1-103)-r040919---aqmd-procedure-8-1 (19)

Page 4 of 11 4/19/2022

6. Hazard Index Summary

HIA = [Q(lb/hr) * (X/Q)max * MWAF] / Acute REL

HIC = [Q(ton/yr) * (X/Q) * MP * MWAF] / Chronic REL

HIC 8-hr= [Q(ton/yr) * (X/Q) * WAF * MWAF] / 8-hr Chronic REL

Target Organs	Acute	Chronic	8-hr Chronic	Acute Pass/Fail	Chronic Pass/Fail	8-hr Chronic Pass/Fail
Alimentary system (liver) - AL			N/A	Pass	Pass	Pass
Bones and teeth - BN			N/A	Pass	Pass	Pass
Cardiovascular system - CV			N/A	Pass	Pass	Pass
Developmental - DEV			N/A	Pass	Pass	Pass
Endocrine system - END			N/A	Pass	Pass	Pass
Eye			N/A	Pass	Pass	Pass
Hematopoietic system - HEM			N/A	Pass	Pass	Pass
Immune system - IMM			N/A	Pass	Pass	Pass
Kidney - KID			N/A	Pass	Pass	Pass
Nervous system - NS			N/A	Pass	Pass	Pass
Reproductive system - REP			N/A	Pass	Pass	Pass
Respiratory system - RESP		7.35E-06	N/A	Pass	Pass	Pass
Skin			N/A	Pass	Pass	Pass

A/N: East

Page 5 of 11 4/19/2022

Application deemed complete date: 04/30/22

A/N:	East	Application deemed complete date:	04/30/22

6a. Hazard Index Acute - Resident

HIA = [Q(lb/hr) * (X/Q)max resident * MWAF] / Acute REL

		AL CV DEV EYE HEM IMM NS REP RESP SKIN										
Compound	AL	CV	DEV	EYE	HEM	IMM	NS	REP	RESP	SKIN		
Particulate Emissions from Diesel-Fueled En												
Total												

Page 6 of 11 4/19/2022

6a. Hazard Index Acute - Worker

|--|

Application deemed complete date: 04/30/22

HIA = [Q(lb/hr) * (X/Q)max Worker * MWAF] / Acute REL

				HIA - Comme	cial					
Compound	AL	CV	DEV	EYE	HEM	IMM	NS	REP	RESP	SKIN
Particulate Emissions from Diesel-Fueled En										
Total										

Page 7 of 11

4/19/2022

A/N:	East	Application deemed complete date:	04/30/22

6b. Hazard Index Chronic - Resident

HIC = [Q(ton/yr) * (X/Q) Resident * MP Chronic Resident * MWAF] / Chronic REL

	HIC - Residential												
Compound	AL	BN	CV	DEV	END	EYE	HEM	IMM	KID	NS	REP	RESP	SKIN
Particulate Emissions from Diesel-Fueled En												2.47E-06	
m												2.455.00	
Total											1	2.47E-06	

Page 8 of 11 4/19/2022

A/N:	East	Application deemed complete date:	04/30/22

6b. Hazard Index Chronic - Worker

HIC = [Q(ton/yr) * (X/Q) * MP Chronic Worker * MWAF] / Chronic REL

	HIC - Commercial												
Compound	AL	BN	CV	DEV	END	EYE	HEM	IMM	KID	NS	REP	RESP	SKIN
Particulate Emissions from Diesel-Fueled En												7.35E-06	
Total												7.35E-06	

Page 9 of 11 4/19/2022

A/N: East

Application deemed complete date: __04/30/22__

 $HIC \ 8-hr = \left[Q(ton/yr)*(X/Q) \ Resident*WAF \ Resident*MWAF\right]/8-hr \ Chronic \ REL$

Compound AL BN CV DEV END EYE HEM MMM KID NS REP RESP SKIN Particulate Emissions from Dissel-Fueled Fix Image: Compound of the Emission of the Emissi		HIC - Residential												
Particulate Emissions from Diesel-Fueled En	Compound	AL	BN	CV	DEV	END	EYE	HEM	IMM	KID	NS	REP	RESP	SKIN
	Particulate Emissions from Diesel-Fueled En													
Total														
Fotal														
Fotal														
Fotal														
Fotal														
Fotal														
Fotal														
Fotal														
Fotal														
Fotal														
Fotal														
Fotal														
Fotal														
Total														
Total														
Total														
Total														
Total														
Total														
Total														
Total														
Total														
Total														
Total														
Total														
Total														
Total														
	Total													

Page 10 of 11 4/19/2022

A/N:	East	Application deemed complete date:	04/30/22

6c. 8-hour Hazard Index Chronic - Worker

 $HIC \ 8-hr = [Q(ton/yr) * (X/Q) \ Worker * WAF \ Worker * MWAF] / \ 8-hr \ Chronic \ REL$

	HIC - Commercial												
Compound	AL	BN	CV	DEV	END	EYE	HEM	IMM	KID	NS	REP	RESP	SKIN
Particulate Emissions from Diesel-Fueled En													
Total													
		l .	1	l .		l .		1	l	I			l .

Page 11 of 11 4/19/2022

Attachment 3.2 ICE Generator PTC/PTO Conditions

August 10, 2022

Ms. Charlene He Environmental Manager AES Alamitos 690 N. Studebaker Rd. Long Beach, CA 90803

Subject: Title V

Title V Significant Permit Revision, AES Alamitos, ID 115394, Rev. 40

Dear Ms. He:

Please find attached the revised Title Page, Table of contents, and Section D of the Title V/RELCAIM facility permit for the equipment located at 690 N. Studebaker Rd. Long Beach, CA 90803. The revised section reflects the approval of the two identical diesel emergency engines to be constructed/operated. The corresponding application numbers and their device IDs are summarized in the table below:

Appl. No.	Equipment	Section	Device ID
636578	Diesel Emergency Engine, 1112 BHP	D	D213
636579	Diesel Emergency Engine, 1112 BHP	D	D214

South Coast AQMD submitted a proposed draft permit and associated documents to EPA Region IX for a 45-day review period on June 17, 2022 and no comments were received. The draft permit was also made available for at least a 30 day public comment period on or about June 21, 2022 and no comments were received from the public.

Please review the attached sections carefully. Insert the enclosed sections into your Title V/RECLAIM Facility Permit and discard the earlier versions. If you determine there are administrative errors or if you have questions concerning changes to your permit, please contact Mr. Jaebin Ju at (909) 396-2642 or by email at iju@aqmd.gov within 30 days of the receipt of your permit.

Sincerely,

Angela Shibata

Senior Air Quality Engineering Manager

Engineering and Permitting

AIS:LC:JJ

Enclosures: Title V/RECLAIM facility permit revision

cc with enclosure

Mr. Gerardo Rios, EPA Region IX

Title V Central file

A/N 636580 (TV Significant Revision)

Title Page

Facility ID:

115394

Revision #: 40 Date: August 02, 2022

FACILITY PERMIT TO OPERATE

AES ALAMITOS, LLC 690 N STUDEBAKER RD LONG BEACH, CA 90803

NOTICE

IN ACCORDANCE WITH RULE 206, THIS PERMIT TO OPERATE OR A COPY THEREOF MUST BE KEPT AT THE LOCATION FOR WHICH IT IS ISSUED.

THIS PERMIT DOES NOT AUTHORIZE THE EMISSION OF AIR CONTAMINANTS IN EXCESS OF THOSE ALLOWED BY DIVISION 26 OF THE HEALTH AND SAFETY CODE OF THE STATE OF CALIFORNIA OR THE RULES OF THE SOUTH COAST AIR QUALITY MANAGEMENT DISTRICT. THIS PERMIT SHALL NOT BE CONSTRUED AS PERMISSION TO VIOLATE EXISTING LAWS, ORDINANCES, REGULATIONS OR STATUTES OF ANY OTHER FEDERAL, STATE OR LOCAL GOVERNMENTAL AGENCIES.

Wayne Nastri Executive Officer

Jason Aspell

Deputy Executive Officer Engineering and Permitting



Section D Facility ID: Revision #:

FACILITY PERMIT TO OPERATE AES ALAMITOS, LLC

SECTION D: FACILITY DESCRIPTION AND EQUIPMENT SPECIFIC CONDITIONS

The operator shall comply with the terms and conditions set forth below:

Equipment	ID No.	Connected To	RECLAIM Source Type/ Monitoring Unit	Emissions* And Requirements	Conditions			
Process 14: INTERNAL COMBUSTION - EMERGENCY POWER								
INTERNAL COMBUSTION ENGINE, EMERGENCY POWER, DIESEL FUEL, PERKINS, MODEL 2806C-E18TTAG7, WITH WITH A DIESEL PARTICULATE FILTER, MIRATECH, MODEL LTRV24-20-10-R1, 1112 BHP A/N: 636578	D213			CO: 2.6 GRAM/BHP-HR DIESEL (8) [40CFR 60 Subpart IIII, 6-29-2021]; CO: 2.6 GRAM/BHP-HR DIESEL (4) [RULE 1303(a)(1)-BACT, 5-10-1996; RULE 1303(a)(1) -BACT, 12-6-2002; RULE 1470, 10-1-2021]; NOX: 469 LBS/1000 GAL DIESEL (1); NOX + ROG: 4.8 GRAM/BHP-HR DIESEL (4) [RULE 1303(a)(1)-BACT, 5-10-1996; RULE 1303(a)(1) -BACT, 12-6-2002; RULE 1470, 10-1-2021]; NOX + ROG: 4.8 GRAM/BHP-HR DIESEL (8) [40CFR 60 Subpart IIII, 6-29-2021]; PM: (9); PM: 0.15 GRAM/BHP-HR DIESEL (4) [RULE 1303(a)(1)-BACT, 5-10-1996; RULE 1303(a)(1) -BACT, 12-6-2002; RULE 1470, 10-1-2021]; PM: 0.15 GRAM/BHP-HR DIESEL (8) [40CFR 60 Subpart IIII, 6-29-2021]; PM: 0.15 GRAM/BHP-HR DIESEL (8) [40CFR 60 Subpart IIII, 6-29-2021]	B61.2, C1.8, C1.9, D12.18, E74.1, E116.1 E193.17, E193.18, H23.9, K67.9			

 (1) (1A) (1B) Der 	otes RECLAIM emission factor
---------------------------------------	------------------------------

(10)

(2) (2A) (2B) Denotes RECLAIM emission rate

(3) Denotes RECLAIM concentration limit Denotes BACT emission limit

Denotes air toxic control rule limit

(8) (8A) (8B) Denotes 40 CFR limit (e.g. NSPS, NESHAPS, etc.)

^{(5) (5}A) (5B) Denotes command and control emission limit (6)

⁽⁷⁾ Denotes NSR applicability limit

See App B for Emission Limits

See section J for NESHAP/MACT requirements

Refer to section F and G of this permit to determine the monitoring, recordkeeping and reporting requirements for this device.

Page: 15 Section D Facility ID: Revision #: August 02, 2022

FACILITY PERMIT TO OPERATE AES ALAMITOS, LLC

SECTION D: FACILITY DESCRIPTION AND EQUIPMENT SPECIFIC CONDITIONS

The operator shall comply with the terms and conditions set forth below:

Equipment	ID No.	Connected To	RECLAIM Source Type/ Monitoring Unit	Emissions* And Requirements	Conditions		
Process 14:INTERNAL COMBUSTION - EMERGENCY POWER							
INTERNAL COMBUSTION ENGINE, EMERGENCY POWER, DIESEL FUEL, PERKINS, MODEL 2806C-E18TTAG7, WITH A DIESEL PARTICULATE FILTER, MIRATECH, MODEL LTRV24-20-10-RI, 1112 BHP A/N: 636579	D214			CO: 2.6 GRAM/BHP-HR DIESEL (8) [40CFR 60 Subpart IIII, 6-29-2021]; CO: 2.6 GRAM/BHP-HR DIESEL (4) [RULE 1303(a)(1)-BACT, 5-10-1996; RULE 1303(a)(1) -BACT, 12-6-2002; RULE 1470, 10-1-2021]; NOX: 469 LBS/1000 GAL DIESEL (1); NOX + ROG: 4.8 GRAM/BHP-HR DIESEL (4) [RULE 1303(a)(1)-BACT, 5-10-1996; RULE 1303(a)(1) -BACT, 12-6-2002; RULE 1470, 10-1-2021]; NOX + ROG: 4.8 GRAM/BHP-HR DIESEL (8) [40CFR 60 Subpart IIII, 6-29-2021]; PM: (9); PM: 0.15 GRAM/BHP-HR DIESEL (4); PM: 0.15 GRAM/BHP-HR DIESEL (4); PM: 0.15 GRAM/BHP-HR DIESEL (8) [RULE 1303(a)(1) -BACT, 5-10-1996; RULE 1303(a)(1) -BACT, 12-6-2002; RULE 1470, 10-1-2021; 40CFR 60 Subpart IIII, 6-29-2021]			

^{(1) (1}A) (1B) Denotes RECLAIM emission factor

^{(2) (2}A) (2B) Denotes RECLAIM emission rate

Denotes RECLAIM concentration limit

Denotes BACT emission limit

^{(5) (5}A) (5B) Denotes command and control emission limit (6)

Denotes air toxic control rule limit

⁽⁷⁾ Denotes NSR applicability limit

^{(8) (8}A) (8B) Denotes 40 CFR limit (e.g. NSPS, NESHAPS, etc.)

See App B for Emission Limits

⁽¹⁰⁾ See section J for NESHAP/MACT requirements

Refer to section F and G of this permit to determine the monitoring, recordkeeping and reporting requirements for this device.

| Section D | Page: 37 | Facility 1D: 115394 | Revision #: 17 | Date: August 02, 2022

FACILITY PERMIT TO OPERATE AES ALAMITOS, LLC

SECTION D: FACILITY DESCRIPTION AND EQUIPMENT SPECIFIC CONDITIONS

The operator shall comply with the terms and conditions set forth below:

[Devices subject to this condition: D45, D48, D51]

B61.1 The operator shall not use natural gas containing the following specified compounds:

Compound	Range	grain per 100 scf	
H2S	greater than	0.25	

This concentration limit is an annual average based on monthly samples of natural gas composition or gas supplier documentation. Gaseous fuel samples shall be tested using South Coast AQMD Method 307-91 for total sulfur calculated as H2S.

[RULE 1303(a)(1)-BACT, 5-10-1996; RULE 1303(a)(1)-BACT, 12-6-2002]

[Devices subject to this condition: D165, D173]

B61.2 The operator shall only use fuel oil containing the following specified compounds:

Compound	ppm by weight
Sulfur less than or equal to	15.0

[RULE 1470, 10-1-2021; RULE 431.2, 5-4-1990; RULE 431.2, 9-15-2000; 40CFR 60 Subpart IIII, 6-29-2021]

[Devices subject to this condition: D213, D214]

C. Throughput or Operating Parameter Limits

C1.3 The operator shall limit the number of start-ups to no more than 62 in any one calendar month.

Section D Page: 40 Facility ID: 115394 Revision #: 17 Date: August 02, 2022

FACILITY PERMIT TO OPERATE AES ALAMITOS, LLC

SECTION D: FACILITY DESCRIPTION AND EQUIPMENT SPECIFIC CONDITIONS

The operator shall comply with the terms and conditions set forth below:

The number of cold startups shall not exceed 2 in any calendar month, the number of warm startups shall not exceed 4 in any calendar month, and the number of hot starts shall not exceed 4 in any calendar month, with no more than 1 startup in any one day.

The number of cold startups shall not exceed 24 in any calendar year, the number of warm startups shall not exceed 48 in any calendar year, and the number of hot startups shall not exceed 48 in any calendar year.

For the purposes of this condition, a cold startup is defined as a startup which occurs after the auxiliary boiler has been shut down for 48 hours or more. A cold startup shall not exceed 170 minutes. The NOx emissions from a cold startup shall not exceed 4.22 lbs.

For the purposes of this condition, a warm startup is defined as a startup which occurs after the auxiliary boiler has been shut down 10 hours or more but less than 48 hours. A warm startup shall not exceed 85 minutes. The NOx emissions from a warm startup shall not exceed 2.11 lbs.

For the purposes of this condition, a hot startup is defined as a startup which occurs after the auxiliary boiler has been shut down for less than 10 hours. A hot startup shall not exceed 25 minutes. The NOx emissions from a hot startup shall not exceed 0.62 lbs.

The operator shall maintain records in a manner approved by the South Coast AQMD, to demonstrate compliance with this condition and the records shall be made available to South Coast AQMD personnel upon request.

[RULE 1303(a)(1)-BACT, 5-10-1996; RULE 1303(a)(1)-BACT, 12-6-2002; RULE 1703(a)(2) - PSD-BACT, 10-7-1988; RULE 2005, 12-4-2015]

[Devices subject to this condition: D181]

C1.8 The operator shall limit the operating time to no more than 200 hour(s) in any one year.

Section D Page: 41 Facility ID: 115394 Revision #: 17 Date: August 02, 2022

FACILITY PERMIT TO OPERATE AES ALAMITOS, LLC

SECTION D: FACILITY DESCRIPTION AND EQUIPMENT SPECIFIC CONDITIONS

The operator shall comply with the terms and conditions set forth below:

The 200 hours per year shall include no more than 50 hours in any one year for maintenance and testing purposes..

The operation of the engine beyond the 50 hr/yr allotted for engine maintenance and testing shall be allowed only in the event of a loss of grid power or up to 30 minutes prior to a rotating outage, provided that the grid operator or electric utility has ordered rotating outages in the control area where the engine is located or has indicated that it expects to issue such an order at a certain time, and the engine is located in a utility service block that is subject to the rotating outage..

Engine operation shall be terminated immediately after the utility distribution company advises that a rotating outage is no longer imminent or in effect..

[RULE 1110.2, 2-1-2008; RULE 1110.2, 11-1-2019; RULE 1304(a)-Modeling and Offset Exemption, 6-14-1996; RULE 1304(c)-Offset Exemption, 6-14-1996; RULE 1470, 10-1-2021]

[Devices subject to this condition: D213, D214]

C1.9 The operator shall limit the maintenance testing to no more than 5 hour(s) in any one month.

[RULE 1304(a)-Modeling and Offset Exemption, 6-14-1996; RULE 1304(c)-Offset Exemption, 6-14-1996]

[Devices subject to this condition: D213, D214]

C157.1 The operator shall install and maintain a pressure relief valve set at 50 psig.

[RULE 1303(a)(1)-BACT, 5-10-1996; RULE 1303(a)(1)-BACT, 12-6-2002]

Section D Page: 46
Facility ID: 115394
Revision #: 17
Date: August 02, 2022

FACILITY PERMIT TO OPERATE AES ALAMITOS, LLC

SECTION D: FACILITY DESCRIPTION AND EQUIPMENT SPECIFIC CONDITIONS

The operator shall comply with the terms and conditions set forth below:

The operator shall also install and maintain a device to continuously record the parameter being measured. Continuously record shall be defined as measuring at least once every month and shall be calculated based upon the average of the continuous monitoring for that month.

The pressure gauge shall be accurate to within plus or minus 5 percent. It shall be calibrated once every 12 months.

The pressure differential shall not exceed 2.0 inches water column.

[RULE 1303(a)(1)-BACT, 5-10-1996; RULE 1303(a)(1)-BACT, 12-6-2002; RULE 1703(a)(2) - PSD-BACT, 10-7-1988; RULE 2005, 12-4-2015]

[Devices subject to this condition: C183]

D12.18 The operator shall install and maintain a(n) non-resettable elapsed time meter to accurately indicate the elapsed operating time of the engine.

[RULE 1110.2, 2-1-2008; RULE 1110.2, 11-1-2019; RULE 1304(a)-Modeling and Offset Exemption, 6-14-1996; RULE 1304(c)-Offset Exemption, 6-14-1996; 40CFR 60 Subpart IIII, 6-29-2021]

[Devices subject to this condition: D213, D214]

D28.1 The operator shall conduct source test(s) in accordance with the following specifications:

| Section D | Page: 59 | Facility ID: 115394 | Revision #: 17 | Date: August 02, 2022

FACILITY PERMIT TO OPERATE AES ALAMITOS, LLC

SECTION D: FACILITY DESCRIPTION AND EQUIPMENT SPECIFIC CONDITIONS

The operator shall comply with the terms and conditions set forth below:

[Devices subject to this condition: C53]

E74.1 Notwithstanding the requirements of Section E conditions, this permit to construct shall expire if construction to this equipment is not complete within one year from the date of issuance of this permit, unless an extension is granted in writing by the South Coast AQMD.

[RULE 205, 1-5-1990]

[Devices subject to this condition: D213, D214]

E116.1 This engine shall not be used as part of a demand response program using interruptible service contract in which a facility receives a payment or reduced rates in return for reducing its electric load on the grid when requested to do so by the utility or the grid operator.

[RULE 1470, 10-1-2021]

[Devices subject to this condition : D213, D214]

E144.1 The operator shall vent this equipment, during filling, only to the vessel from which it is being filled.

[RULE 1303(a)(1)-BACT, 5-10-1996; RULE 1303(a)(1)-BACT, 12-6-2002]

[Devices subject to this condition: D19, D151, D152, D153, D163]

E179.3 For the purpose of the following condition number(s), continuously record shall be defined as recording at least once every hour and shall be calculated based upon the average of the continuous monitoring for that hour.

Condition Number 12-6

Section D Page: 64 Facility ID: 115394 Revision #: 17 Date: August 02, 2022

FACILITY PERMIT TO OPERATE AES ALAMITOS, LLC

SECTION D: FACILITY DESCRIPTION AND EQUIPMENT SPECIFIC CONDITIONS

The operator shall comply with the terms and conditions set forth below:

The operator shall record the total net power generated in a calendar month in megawatt-hours.

The operator shall calculate and record greenhouse gas emissions for each calendar month using the following formula:

GHG = 61.41 * FF

Where GHG is the greenhouse gas emissions in tons of CO2 and FF is the monthly fuel usage in millions standard cubic feet.

The operator shall calculate and record the CO2 emissions in pounds per net megawatt-hour based on a 12-month rolling average. The CO2 emissions from this equipment shall not exceed 861,119 tons per year per turbine on a 12-month rolling average basis. The calendar annual average CO2 emissions shall not exceed 916.01 lbs per gross megawatt-hours (inclusive of equipment degradation).

The operator shall maintain records to demonstrate compliance with this condition and shall make such records available to the Executive Officer upon request. The records shall be maintained for a minimum of 5 years in a manner approved by South Coast AQMD.

[RULE 1714, 12-10-2012; RULE 1714, 3-1-2019]

[Devices subject to this condition: D165, D173]

E193.17The operator shall operate and maintain this equipment according to the following requirements:

Section D Page: 65 Facility ID: 115394 Revision #: 17

FACILITY PERMIT TO OPERATE AES ALAMITOS, LLC

SECTION D: FACILITY DESCRIPTION AND EQUIPMENT SPECIFIC CONDITIONS

The operator shall comply with the terms and conditions set forth below:

The operator shall comply with the emission standards specified in 40 CFR 60.4205(b) by purchasing an engine certified to the emission standards in 40 CFR 60.4205(b), as applicable, for the same model year and maximum engine power. The engine must be installed and configured according to the manufacturer's emission related specifications.

The operator shall operate and maintain the engine and control device according to the manufacturer's written emission-related instructions (or procedures developed by the operator that are approved by the engine manufacturer), change only those emission-related settings that are permitted by the manufacturer, and meet the requirements of 40 CFR 1068, as they apply.

[40CFR 60 Subpart IIII, 6-29-2021]

[Devices subject to this condition: D213, D214]

E193.18 The operator shall operate and maintain this equipment according to the following requirements:

| Section D | Page: 66 | Facility ID: 115394 | Revision #: 17 | Date: August 02, 2022

FACILITY PERMIT TO OPERATE AES ALAMITOS, LLC

SECTION D: FACILITY DESCRIPTION AND EQUIPMENT SPECIFIC CONDITIONS

The operator shall comply with the terms and conditions set forth below:

This engine shall not be operated unless its exhaust is vented to the diesel exhaust after-treatment system which is in full operation and in good operating condition at all times.

The equipment shall comply with the CARB Executive Order DE-14-005-07.

Removal of the diesel particulate filter's filter media for cleaning may only occur under the following conditions:

- A. The internal combustion engine shall not be operated for maintenance and testing or any other non-emergency use while the diesel particulate filter media is removed; and
- B. The diesel particulate filter media shall be returned and re-installed within 10 working days from the date of removal; and
- C. The owner or operator shall maintain records indicating the date(s) the diesel particulate filter media was removed for cleaning and the date(s) the filter media was re-installed. Records shall be retained for a minimum period of three years.

[RULE 1470, 10-1-2021; RULE 2005, 12-4-2015; RULE 2005, 11-5-2021]

[Devices subject to this condition: D213, D214]

E448.1 The operator shall comply with the following requirements:

Section D Page: 6 Facility ID: 11539 Revision #: Date: August 02, 20

FACILITY PERMIT TO OPERATE AES ALAMITOS, LLC

SECTION D: FACILITY DESCRIPTION AND EQUIPMENT SPECIFIC CONDITIONS

The operator shall comply with the terms and conditions set forth below:

H23.7 This equipment is subject to the applicable requirements of the following rules or regulations:

Contaminant	Rule	Rule/Subpart	
CO	District Rule	1146	
NOX	District Rule	1146	
NOX	District Rule	1100	

[RULE 1100, 1-10-2020; RULE 1146, 11-1-2013; RULE 1146, 12-4-2020]

[Devices subject to this condition: D181]

H23.8 This equipment is subject to the applicable requirements of the following rules or regulations:

Contaminant	Rule	Rule/Subpart	
Refrigerants	District Rule	1415	
Refrigerants	40CFR82, SUBPART	F	

[RULE 1415, 12-3-2010; 40CFR 82 Subpart F, 12-27-2017]

[Devices subject to this condition: E212]

H23.9 This equipment is subject to the applicable requirements of the following rules or regulations:

Contaminant	Rule	Rule/Subpart	
Sulfur compounds	District Rule	431.2	
PM	District Rule	1470	

Section D Page: 69 Facility ID: 115394 Revision #: 17 Date: August 02, 2022

FACILITY PERMIT TO OPERATE AES ALAMITOS, LLC

SECTION D: FACILITY DESCRIPTION AND EQUIPMENT SPECIFIC CONDITIONS

The operator shall comply with the terms and conditions set forth below:

[RULE 1470, 10-1-2021; RULE 431.2, 5-4-1990; RULE 431.2, 9-15-2000]

[Devices subject to this condition: D213, D214]

K. Record Keeping/Reporting

K40.2 The operator shall provide to the District a source test report in accordance with the following specifications:

Emission data shall be expressed in terms of lbs/MM cubic feet.

All moisture concentration shall be expressed in terms of percent corrected to 3 percent oxygen.

Source test results shall be submitted to the District no later than 60 days after the source test was conducted.

All exhaust flow rate shall be expressed in terms of dry standard cubic feet per minute (DSCFM) and dry actual cubic feet per minute (DACFM).

Source test results shall also include fuel flow rate (CFH) and generator output (MW) under which the test was conducted.

Emission data shall be expressed in terms of concentration (ppmv), corrected to 3 percent oxygen, dry basis.

Emission data shall be expressed in terms of mass rate (lbs/hr). In addition, solid PM emissions, if required to be tested, shall also be reported in terms of grains per DSCF.

Section D Page: 73 Facility ID: 115394 Revision #: 17 Date: August 02, 2022

FACILITY PERMIT TO OPERATE AES ALAMITOS, LLC

SECTION D: FACILITY DESCRIPTION AND EQUIPMENT SPECIFIC CONDITIONS

The operator shall comply with the terms and conditions set forth below:

K67.8 The operator shall keep records, in a manner approved by the District, for the following parameter(s) or item(s):

the total hourly amount of injected ammonia(NH3)

[RULE 2012, 5-6-2005]

[Devices subject to this condition: C53]

K67.9 The operator shall keep records, in a manner approved by the District, for the following parameter(s) or item(s):

The operator shall keep records of any corrective action taken after the backpressure monitor has notified the operator that the backpressure limit of the engine is approached.

An engine operating log listing on a monthly basis the emergency use hours of operation, maintenance and testing hours of operation, and any other hours of use with a description of the reason for operation. Additionally, each time the engine is started manually, the log shall include the date of operation and the timer reading in hours at the beginning and end of operation.

The log shall be kept for a minimum of five calendar years prior to the current year and made available to District personnel upon request. The total hours of operation for the previous calendar year shall be recorded sometime during the first 15 days of January of each year.

[RULE 1110.2, 2-1-2008; RULE 1110.2, 11-1-2019; RULE 1304(a)-Modeling and Offset Exemption, 6-14-1996; RULE 1304(c)-Offset Exemption, 6-14-1996; 40CFR 60 Subpart III, 6-29-2021]

[Devices subject to this condition: D213, D214]