

**DOCKETED**

<b>Docket Number:</b>	23-IEPR-04
<b>Project Title:</b>	Accelerating Bulk Grid Connection
<b>TN #:</b>	250823
<b>Document Title:</b>	Presentation - Queued Up - Status and Drivers of Generator Interconnection Backlogs
<b>Description:</b>	Joseph Rand & Will Gorman Lawrence Berkeley National Laboratory
<b>Filer:</b>	Raquel Kravitz
<b>Organization:</b>	Lawrence Berkeley National Laboratory (LBNL)
<b>Submitter Role:</b>	Public Agency
<b>Submission Date:</b>	6/29/2023 12:51:06 PM
<b>Docketed Date:</b>	6/29/2023

# Queued Up: Status and Drivers of Generator Interconnection Backlogs

**Joseph Rand & Will Gorman**

Lawrence Berkeley National Laboratory

California Energy Commission Briefing

June, 2023

*This work was funded by the U.S. Department of Energy under Contract No. DE-AC02-05CH11231. The views and opinions of the authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof, or The Regents of the University of California.*

*Image source: Licensed from Shutterstock*




# Outline

- Current status of U.S. interconnection queues
- Evidence of a problem:
  - 1. Delays and bottlenecks
  - 2. Increasing interconnection costs
- Discussion: Reforms and possible solutions

*NOTE: Focus on transmission interconnection, not distribution/DER interconnection*

*Thanks to DOE, and especially the i2X program, for supporting this work*

# Current interconnection process was designed in 2003 for an electricity system with fewer, larger, centralized power plants (though RTOs have implemented some reforms)




- Transmission grid operators require new projects looking to connect to the grid to undergo a series of impact studies
- These studies determine the grid upgrades necessary to allow projects to connect safely and reliably, and allocate the cost of those upgrades
- Withdrawals can result in multiple re-studies: a vicious cycle of delays, backlogs & higher costs


Source: Derived from image courtesy of Lawrence Berkeley National Laboratory and used with permission. | GAO-23-105583

# Active capacity in queues (~2,040 GW) exceeds installed capacity of entire U.S. power plant fleet (~1,250 GW), as well as peak load and installed capacity in most ISO/RTOs

Entire U.S. Installed Capacity vs. Active Queues




RTO Installed Capacity & Peak Load vs. Active Queues



Comparisons of queue capacity to installed capacity or peak load should also consider generators' contributions to resource adequacy, for example their "effective load carrying capability" (ELCC). As variable resources, solar and wind contribute a smaller percentage of their nameplate capacity to resource adequacy compared to dispatchable generation like natural gas.

Decarbonizing the electric sector therefore requires higher levels of *installed* solar and wind capacity to achieve the same resource adequacy contributions. High levels of storage can offset this need to some degree. Electrification of buildings and transport will also result in load growth.

# Especially strong developer interest in solar (~947 GW) and storage (~680 GW); Hybrid plants represent a large fraction of proposed solar and storage




- **“Wind”** includes both onshore and offshore.
- **“Other”** includes
  - Hydropower
  - Geothermal
  - Biomass/biofuel
  - Landfill gas
  - Solar thermal
  - Oil/diesel
- **“Storage”** is primarily (99%) battery, but also includes pumped storage hydro, compressed air, gravity rail, and hydrogen.

See <https://emp.lbl.gov/queues> to access an interactive data visualization tool.

Notes: (1) \*Hybrid storage capacity is estimated for some projects using storage:generator ratios from projects that provide separate capacity data, and that value is only included starting in 2020. Storage duration is not provided in interconnection queue data. (2) Wind capacity includes onshore and offshore for all years, but offshore is only broken out starting in 2020. (3) Hybrid generation capacity is included in all applicable generator categories. (4) Not all of this capacity will be built.

# Active queue capacity highest in the non-ISO West (598 GW), followed by MISO (339 GW) and PJM (298 GW). Solar and storage requests are booming in most regions.




Notes: (1) \*Hybrid storage capacity is estimated for some projects using storage:generator ratios from projects that provide separate capacity data, and that value is only included starting in 2020. Storage duration is not provided in interconnection queue data. (2) Wind capacity includes onshore and offshore for all years, but offshore is only broken out starting in 2020. (3) Hybrid generation capacity is included in all applicable generator categories. (4) Not all of this capacity will be built.

## Hybrids comprise a sizable fraction of all proposed solar plants in multiple regions; wind hybrids are less common overall but still a large proportion in CAISO

Region	% of Proposed Capacity Hybridizing in Each Region			
	Solar	Wind	Gas	Storage
CAISO	97%	45%	15%	53%
ERCOT	42%	4%	3%	42%
ISO-NE	33%	0%	0%	8%
MISO	34%	12%	0%	n/a
NYISO	19%	0%	0%	n/a
PJM	24%	1%	0%	21%
SPP	18%	1%	0%	n/a
Southeast (non-ISO)	21%	0%	0%	n/a
West (non-ISO)	81%	17%	74%	n/a
<b>TOTAL</b>	<b>48%</b>	<b>8%</b>	<b>17%</b>	<b>n/a</b>

- **Solar** hybridization relative to total amount of solar in each queue is highest in CAISO (97%) and non-ISO West (81%), and is above or near 20% in all regions
- **Wind** hybridization relative to total amount of wind in each queue is highest in CAISO (45%), the non-ISO West (17%), and MISO (12%), and is less than 5% in all other regions

# Only 21% of projects that applied for interconnection prior to 2018 have been built – 72% have been withdrawn (7% are still actively trying!)




**One consequence of high withdrawal rates is the need to restudy the projects that remain in the queue, increasing uncertainty in cost outcomes and further elongating the process**


The completion rate is even lower when calculated in terms of proposed capacity [14%]

# Evidence of a Problem #1: Increasing timelines

# Study duration exceeds 3 years in most grid operating regions; ERCOT and Southeast are faster. Battery projects tend to be processed more quickly than other types




# Some delays are also evident *outside* of the interconnection process: procurement / offtake, local permitting, construction, etc.




- Limited data were available to analyze typical durations from interconnection agreement to commercial operations
- Considering 737 projects across 6 entities, the typical IA to COD duration has increased only modestly since 2007.
  - From ~17 months for projects built from 2007-2014 to ~22 months for projects built from 2015-2022.
- But, that duration has increased dramatically for CAISO projects in the last 5 years.
  - The typical solar project built in CAISO since 2018 took over 4 years to reach commercial operations *after securing an interconnection agreement*; those built in 2022 averaged over 6 years.

# The median duration from interconnection request to commercial operations date continues to rise, reaching ~5 years for projects completed in 2022; Longest in CAISO



Duration for projects reaching COD from 2018-2022




Notes: (1) In-service date was only available for 6 ISOs (CAISO, ERCOT, ISO-NE, NYISO, PJM, SPP) and 5 utilities (Duke, LADWP, PSCo, SOCO, WAPA) representing 58% of all operational projects. (2) Duration is calculated as the number of months from the queue entry date to the in-service date.

## Evidence of a Problem #2: Increasing interconnection costs

# Interconnection costs have grown over time in all studied regions, driven primarily by broader network upgrades (not local interconnection costs)

## Average Interconnection Costs

Total Interconnection Costs by Request Status




Region	“Earlier” period	“Recent” period
<b>MISO</b>	(2000-) 2018	2019-2021
<b>SPP</b>	2010-2019	2020-2022
<b>PJM</b>	2000/2017 - 2019	2020-2022
<b>NYISO</b>	2006-2016	2017-2021
<b>ISO-NE</b>	2010-2017	2018-2021

- Average interconnection costs have grown across regions and request types:
  - ▣ Often doubling for projects that have **completed** all studies
  - ▣ increasing even more for **active** projects currently moving through the queues.
  - ▣ Projects that **withdraw** have the highest interconnection costs

# A brief comment on enhancing interconnection data transparency

- Note that these issues are *not always* CAISO specific
- The publicly-accessible interconnection data lack details and are *not well standardized* across the U.S. Do not always include:
  - ▣ Data on active, completed, AND withdrawn projects
  - ▣ Key dates such as IA signed or study phase completion
  - ▣ Granular geospatial information
- Cost data are particularly *difficult and time consuming* to collect
  - ▣ Manual PDF data scraping in regions where public reports are available
  - ▣ Not available in CAISO territory, for concerns over confidentiality
- FERC 845 data reporting meant to fill some of these transparency problems, but are often not standardized and difficult to use for *consistent analysis, tracking, and comparison* across Balancing Areas

Coverage area of entities for which interconnection data was collected by LBNL



# Proposed reforms are underway at FERC and among most RTOs, but more opportunities remain

## FERC NOPR: Queue Reform

- *Cluster studies; first ready, first served*; higher *fees & readiness* criteria
- *Timeline, process, data, and reporting* requirements for transmission providers
- Improved and more coordinated process for *affected system studies*
- Revisions to *study data & assumptions* to better match real system/conditions and ensure reliability
- Consideration of *grid-enhancing technologies*

## Possibilities Beyond FERC's Interconnection NOPR

- Proactive *transmission planning* and *enhanced coordination* between transmission planning and interconnection.
- Facilitate generator *project prioritization* (e.g. via open seasons, auctions, etc)
- Enhance *data transparency* on transmission availability and possible interconnection costs to pre-screen interconnection requests
- Better harmonize interconnection study methods and requirements; goal to enhance *automation* of the interconnection study processes
- *More interconnection resources and staff* to speed the process
- Revisit *impact threshold criteria* and potentially update energy-only interconnection process
- *Revisions to interconnection cost allocation*: reform of participant funding for network upgrades
- Consider *surplus interconnection and generator replacement* business models



BERKELEY LAB

# BERKELEY LAB

LAWRENCE BERKELEY NATIONAL LABORATORY

## Contact:

Joseph Rand ([jrand@lbl.gov](mailto:jrand@lbl.gov))

Will Gorman ([wgorman@lbl.gov](mailto:wgorman@lbl.gov))

## More Information:

- Visit <https://www.energy.gov/eere/i2x> to learn about and participate in the DOE's i2X program
- Visit <https://emp.lbl.gov/queues> interconnection queue analysis and data
- Visit [https://emp.lbl.gov/interconnection\\_costs](https://emp.lbl.gov/interconnection_costs) for research on generator interconnection costs

## Acknowledgements:

This work was funded by the U.S. Department of Energy's Office of Energy Efficiency and Renewable Energy, in particular the Solar Energy Technologies Office and the Wind Energy Technologies, in part via the Interconnection Innovation eXchange (i2X). We thank Ammar Qusaibaty, Michele Boyd, Juan Botero, Cynthia Bothwell, Jian Fu, Patrick Gilman, Gage Reber, and Paul Spitsen for supporting this project.

## Disclaimer

This document was prepared as an account of work sponsored by the United States Government. While this document is believed to contain correct information, neither the United States Government nor any agency thereof, nor The Regents of the University of California, nor any of their employees, makes any warranty, express or implied, or assumes any legal responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by its trade name, trademark, manufacturer, or otherwise, does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof, or The Regents of the University of California. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof, or The Regents of the University of California.

Ernest Orlando Lawrence Berkeley National Laboratory is an equal opportunity employer.

## Copyright Notice

This manuscript has been authored by an author at Lawrence Berkeley National Laboratory under Contract No. DE-AC02-05CH11231 with the U.S. Department of Energy. The U.S. Government retains, and the publisher, by accepting the article for publication, acknowledges, that the U.S. Government retains a non-exclusive, paid-up, irrevocable, worldwide license to publish or reproduce the published form of this manuscript, or allow others to do so, for U.S. Government purposes



# Appendix



# Additional Reference Material to Consider

---

- Solution eXchange summary notes, linked in the power point file for each meeting, found: <https://www.energy.gov/eere/i2x/i2x-solution-e-xchanges>
- ESIG Webinar, AEMO's Connection Simulation Tool (March 20, 2023), <https://www.esig.energy/event/webinar-aemos-connection-simulation-tool/>
- FERC Order 845, <https://ferc.gov/sites/default/files/2020-06/Order-845.pdf>
- MISO Point of Interconnection Map, <https://giqueue.misoenergy.org/PoiAnalysis/index.html>
- ESIG August 2022 Interconnection Workshop and Summary, <https://www.esig.energy/event/joint-generator-interconnection-workshop/>
- ESIG May 2022 webinar
- ESIG GETs Webinar, May 2023
- MISO-SPP Joint Targeted Interconnection Queue Study, <https://www.misoenergy.org/stakeholder-engagement/committees/miso-spp-joint-targeted-interconnection-queue-study/>
- FERC. 2003. *Standardization of Generator Interconnection Agreements and Procedures*. Order No. 2003, 104 FERC ¶ 61,103.

## Additional Reference Material to Consider (cont.)

---

- ESIG Webinar, Multi-value Transmission Planning for a Decarbonized Future, May 2022  
<https://www.esig.energy/event/webinar-multi-value-transmission-planning-for-a-decarbonized-future/>
- ESIG Fall Technical Workshop, 2021, Closing Panel: Transmission – the Great Enabler  
<https://www.esig.energy/event/2021-fall-technical-workshop/>
- Enel's White paper, Plugging In: A Roadmap for Modernizing & Integrating Interconnection and Transmission Planning,  
<https://www.enelgreenpower.com/content/dam/enel-egp/documenti/share/working-paper.pdf>


# DOE's Interconnection Innovation e-Xchange (i2X)

**Mission:** To enable a **simpler, faster, and fairer** interconnection of clean energy resources while enhancing the **reliability, resiliency, and security** of our **distribution and bulk-power electric grids**



## Stakeholder Engagement

- Nation-wide engagement platform and collaborative exchanges
- Generate innovative solutions from discussion with utilities, grid operators, state/local governments, clean energy industry, non-profits



## Data & Analytics

- Collect and analyze interconnection data to inform solutions development
- Increase transparency of interconnection process



## Strategic Roadmap

- Create roadmap to inform interconnection process improvements
- Identify both near- and long-term opportunities and solutions




## Technical Assistance

- Leverage DOE laboratory expertise to directly support stakeholders
- Focus on requests targeting key problems identified in roadmap



# Methods and Data Sources

- Data collected from interconnection queues for 7 ISOs / RTOs and 35 utilities, which collectively represent >85% of U.S. electricity load
  - Projects that connect to the bulk power system, not behind-the-meter
  - Includes projects in queues through the end of 2022
  - The full sample includes:
    - 3,846 “operational” projects
    - 10,262 “active” projects
    - 374 “suspended” projects
    - 15,672 “withdrawn” projects
- Hybrid / co-located projects were identified and categorized
  - Storage capacity in hybrids (separate from generator capacity) was estimated based on available data for some projects
- Note that being in an interconnection queue *does not guarantee* ultimate construction




*Coverage area of entities for which data was collected  
Data source: Homeland Infrastructure Foundation-Level Data (HIFLD)  
A full list of included balancing areas can be found in the Appendix  
Note that service areas can overlap  
No data collected for Hawaii or Alaska*

# High-Level Findings


## Developer interest in solar, storage, and wind is strong

- Over 10,000 projects representing 1,350 gigawatts (GW) of generator capacity and 680 GW of storage actively seeking interconnection
- Most (~1260 GW) proposed generation is zero-carbon
- Hybrids comprise a large share of proposed projects



## Completion rates are generally low; wait times are increasing


- Only ~21% of projects (14% of capacity) requesting interconnection from 2000-2017 reached commercial operations by the end of 2022




- Completion rates are even lower for wind (20%) and solar (14%)
- The average time projects spent in queues before being built has increased markedly. The typical project built in 2022 took 5 years from the interconnection request to commercial operations<sup>1</sup>, compared to 3 years in 2015 and <2 years in 2008.

## Proposed capacity is widely distributed across the U.S.

- Substantial proposed solar capacity exists in most regions of the U.S.; 947 GW of solar active in queues
- Wind capacity is highest in NYISO, the non-ISO West, PJM, and SPP, with increasing share of offshore projects
- Storage is primarily in the West and CAISO, but also strong in ERCOT, MISO, and PJM; much in hybrid configurations
- Only 82 GW of gas capacity active in the queues, less than 10% of active solar capacity




# Active interconnection requests are growing in all regions; highest for solar (~950 GW), storage (~680 GW), and wind (~300 GW, including 113 GW offshore)




Solar and storage requests are booming in most regions; after being overwhelmed in 2021, CAISO and PJM “paused” new requests in 2022

# Interest in hybrid plants has increased over time: Hybrids comprise 52% of active storage capacity (358 GW), 48% of solar (457 GW), and 8% of wind (24 GW)




\*Hybrid storage capacity is estimated using storage:generator ratios from projects that provide separate capacity data




- **Solar Hybrids** include: Solar+Storage (431 GW), Solar+Wind (3 GW), Solar+Wind+Storage (8 GW)
- **Wind Hybrids** include: Wind+Storage (19 GW), Wind+Solar (1 GW), Wind+Solar+Storage (4 GW)
- **Storage Hybrids** may be paired with any generator type; most are paired with solar
- **Gas Hybrids** include: Gas+Solar+Storage (13 GW), Gas+Storage (0.4 GW), Gas+Solar (0.3 GW) [not shown above]

# Capacity-weighted completion rates are even lower: Only 14% of all capacity requesting interconnection from 2000-2017 is online; 16% of wind capacity, 10% of solar capacity

Percentage of capacity online by region:



Percentage of capacity online by generator type:



Notes: (1) Completion rate shown here is capacity-weighted, calculated as the capacity that is online by end of 2022 divided by the total capacity requesting interconnection each year. (2) Includes data from 7 ISO/RTOs and 26 utilities.



# The mean duration prior to withdrawing has edged higher in recent years; later-stage withdrawals are becoming more common

Duration Analyzed:

Interconnection Request (IR)

Withdrawn Date

Commercial Operations (COD)




- Some recently-withdrawn projects are waiting longer in the queues before making the determination to withdraw
- Later stage withdrawals can be costly for developers and can disrupt assumptions built into other projects' interconnection studies, necessitating re-studies in some cases and increasing study durations


# The median duration from request to withdrawn date ticked up in 2022; wind projects typically spend more time in queues than gas or solar prior to withdrawing



Median Duration from Interconnection Request to Withdrawn Date, by Region




Median Duration from Interconnection Request to Withdrawn Date, by Generator Type



Notes: (1) Withdrawn date was available for 6,323 projects from 5 ISOs and 6 utilities. (2) Duration is calculated as the number of months from the queue entry date to the date the project was withdrawn from queues.

# After falling from a 2012 peak, the typical duration from interconnection request (IR) to interconnection agreement (IA) increased sharply since 2015, reaching 35 months in 2022




Notes: (1) Sample includes 3,348 projects from 6 ISO/RTOs and 5 non-ISO utilities with executed interconnection agreements since 2005. (2) Not all data used in this analysis are publicly available.


# IR to COD timelines are longest in CAISO, NYISO, and SPP; solar and wind projects typically take longer than other types, with standalone battery projects moving fastest to completion



Median Duration from Interconnection Request to Commercial Operations, by Region




Median Duration from Interconnection Request to Commercial Operations, by Generator Type



Notes: (1) In-service date was only available for 6 ISOs and 5 utilities representing 58% of all operational projects; . (2) Duration is calculated as the number of months from the queue entry date to the in-service date.


# There is a clear step change in IR to IA duration between “small” (<20 MW) and “large” (>20 MW) generator interconnection procedures



- On average, projects with rated capacity <20 MW complete studies and execute interconnection agreements much faster than larger projects
  - Median is 11 months for projects <5 MW
  - 15 months for projects 5 - <20 MW
- The median duration for projects 20 MW or larger hovers around 30 months across the four larger project groups analyzed
- 20 MW is the threshold between the FERC “large” and “small” generator interconnection procedures (LGIP / SGIP)
  - The median LGIP duration is twice the median SGIP duration for projects in our sample

# Larger projects have longer development timelines: Typical IR to COD duration increases monotonically by project size (MW)

Duration Analyzed: Interconnection Request (IR) → Interconnection Agreement (IA) → Commercial Operations (COD)



- For the smallest projects in our sample (<5 MW), the median project came online less than 2 years (20 months) after the interconnection request
- The median 5-20 MW project, meanwhile, takes nearly 3 years (33 months) from IR to COD
- Larger projects spend even more time in the interconnection and development process, with the median 100-200 MW project taking >4 years and the median 200+ MW project taking over 4.5 years (55 months) from IR to COD

# A “wicked” problem: multifaceted drivers of interconnection backlogs

**General sentiment:** we are asking the serial queue process designed in 2003 to do too much. Reforms are needed, but also perhaps a fundamental re-thinking is required given clean energy transformation demanded.

Transmission expansion has been **limited over the last decade, focused primarily on local reliability upgrades**

Bulk grid not developing rapidly, leading to **inadequate transmission** and to high **network upgrade costs assigned** to generators in queue

Developers use queue requests for data collection given low information **transparency, low entry cost, high network upgrade costs, and uncertain costs** given serial nature and re-studies

Enormous **increase in number and capacity** of projects in queues, creating **workflow and workforce challenges** when relying on existing tools and administrative processes

Lack of **standardization, inaccurate study data & assumptions, low consideration of grid-enhancing technologies, generator technology changes, network cost assignment, and late withdrawals**

Multi-year **queue delays** leading to re-studies, **reliability concerns, high generator-pays upgrade costs**, and frustrated stakeholders (developers and transmission operators alike)

**A vicious cycle: the increasing number of requests increase delays and uncertainty, which further incentivizes developers to submit more requests**

# Balancing Areas Included In Data:

ISO/RTOs	Other (non-ISO) Transmission Operators				
PJM	Southern Company	Associated Electric Coop.	LG&E & KU Energy	Portland General Electric	Public Service Co. of NM
MISO	Tennessee Valley Authority	PSCO	Salt River Projects	Idaho Power	Avista
ERCOT	Duke/Progress	Santee Cooper	NV Energy	Florida Municipal Power Pool	El Paso Electric
SPP	WAPA	Georgia Transmission Corp.	Navajo-Crystal	Tri-State G&T	Imperial Irrigation District
NYISO	Florida Power & Light	Arizona Public Service	Dominion	Jacksonville Electric Authority	Platte River Power Authority
CAISO	Bonneville Power Admin.	LADWP	Puget Sound Energy	Tucson Electric Power	Black Hills Colorado
ISO-NE	PacifiCorp	Seminole Electric Coop.	Tampa Electric Co.	NorthWestern	Cheyenne Light Fuel & Power