

DOCKETED	
Docket Number:	21-AFC-02
Project Title:	Willow Rock Energy Storage Center
TN #:	254804
Document Title:	Willow Rock Energy Storage Center Supplemental AFC Volume II - Appendix 54A - Part I
Description:	N/A
Filer:	Amanda Cooley
Organization:	Ellison Schneider Harris & Donlan LLP
Submitter Role:	Applicant Representative
Submission Date:	3/1/2024 4:46:44 PM
Docketed Date:	3/1/2024

APPENDIX 5.4A

**Agapito Associates, Inc. (2024)
Geotechnical Characterization
Report for the Willow Rock-
Dawn Road Project Site**

GEOTECHNICAL CHARACTERIZATION REPORT FOR THE WILLOW ROCK – DAWN ROAD PROJECT SITE

Prepared for:

Hydrostor Inc.
333 Bay Street, Suite 520
Toronto, ON MSH 2V1, Canada

February 16, 2024

Prepared by:



AGAPITO ASSOCIATES, INC.

715 Horizon Drive, Suite 340
Grand Junction, CO 81506

1536 Cole Blvd. Bldg. 4, Suite 310
Lakewood, CO 80401

GEOTECHNICAL CHARACTERIZATION REPORT FOR THE WILLOW ROCK – DAWN ROAD PROJECT SITE

TABLE OF CONTENTS

	<u>Page</u>
1 Introduction.....	1-1
2 Geotechnical Setting	2-1
2.1 Records Search.....	2-1
2.2 Regional and Local Geology	2-1
3 Site Specific Geotechnical Conditions.....	3-1
3.1 Surficial Geotechnical Investigation.....	3-1
3.2 Subsurface Geotechnical Investigation.....	3-1
3.2.1 Core Hole Lithology	3-3
3.2.2 Rock Quality.....	3-9
3.2.3 Packer Testing	3-9
3.2.4 Geophysical Logging	3-9
3.2.5 Structural Defects	3-13
4 Geotechnical Characterization	4-1
4.1 Geomechanical Properties of the Intact Rock.....	4-1
4.1.1 Unit Weight	4-1
4.1.2 Uniaxial Compressive Strength	4-2
4.1.3 Elastic Properties.....	4-4
4.1.4 Slake Durability	4-4
4.2 Rock Mass Characterization.....	4-6
4.2.1 Rock Mass Rating (RMR).....	4-6
4.2.2 NGI Q-system.....	4-8
4.3 In-situ Stress Conditions	4-10
4.3.1 Regional Stress.....	4-10
4.3.2 Borehole Breakout	4-10
4.3.3 Sigma Overcore.....	4-12
4.4 Seismic Risk.....	4-13
4.5 Rock Mass Strength and Deformation Properties.....	4-14
4.5.1 Geological Strength Index (GSI)	4-14
4.5.2 Hoek-Brown Criterion	4-17
4.5.3 Mohr-Coulomb Criterion.....	4-21
4.5.4 Rock Mass Elastic Modulus	4-22
4.5.5 Joint Stiffness	4-23
4.5.6 Rock Mass Dilation.....	4-24
5 Conclusions.....	5-1
6 References.....	6-1

Appendix A	Geotechnical Logs	A-1
Appendix B	Acoustic Televiwer (ATV) Logs	B-1
Appendix C	Laboratory Testing Reports	C-1
Appendix D	Rock Mass Ratings	D-1
Appendix E	IST2D Stress Measurements.....	E-1

LIST OF TABLES

	Page
Table 3-1. Laboratory UCS Test Results from the Surface Geotechnical Investigation Program.....	3-3
Table 3-2a. Summary of Lithology in ZEV-CH-01-23	3-5
Table 3-2b. Summary of Lithology in ZEV-CH-02-23	3-5
Table 3-2c. Summary of Lithology in ZEV-CH-03-23	3-6
Table 3-4. RQD Classification System	3-9
Table 3-5. Condition of Rock Mass Discontinuities Associated with Different Hydraulic Conductivities	3-13
Table 3-6. Summary of Structure Orientation and Dip in the Cavern Target Interval.....	3-15
Table 3-7. Discontinuity Spacing Classification.....	3-16
Table 4-1. Summary of Laboratory Rock Mechanics Testing Results from the Exploration Core Holes	4-1
Table 4-2. Summary of Triaxial Test Results from the Exploration Core Holes.....	4-1
Table 4-3. Summary of IST2D Stress Testing in Core Hole ZEV-CH-03-23	4-12
Table 4-4. Hoek-Brown Parameters.....	4-21
Table 4-5. Intact Mohr-Coulomb Properties for Various Stresses.....	4-22
Table 4-6. Rock Mass Mohr-Coulomb Properties for Various Stresses	4-22
Table 4-7. Rock Mass Modulus	4-23
Table 4-8. Summary of Joint Normal Stiffness and Joint Shear Stiffness.....	4-24

LIST OF FIGURES

Figure 1-1. Location of the Willow Rock – Dawn Road Project Site	1-2
Figure 2-1. Geologic Map of the Antelope Valley in the Western Mojave Desert Showing the Location of the Project Area	2-3
Figure 2-2. 15-minute Rosamond Quadrangle Geologic Map Showing the Location of the Project Area the Mapped and Inferred Location of the Northwest-Southeast Trending Normal Fault	2-4
Figure 2-3. Satellite Image Showing the Project Area and the Surface Exposure of the Northwest-Southeast Trending Normal Fault.....	2-5
Figure 2-4. Cross-section Showing the Bedrock Geology around the Project Area	2-6
Figure 3-1. Logged and Inferred Subsurface Geotechnical Conditions at the Project Site	3-2
Figure 3-2. Location of Deep Subsurface Exploration Core Holes at the Project Site	3-4
Figure 3-3. Degree of Alteration Logged in Core Hole ZEV-CH-01-23	3-7
Figure 3-4. Degree of Alteration Logged in Core Hole ZEV-CH-02-23	3-8

Figure 3-5.	Degree of Alteration Logged in Core Hole ZEV-CH-03-23	3-8
Figure 3-6.	Rock Quality Logged in Core Hole ZEV-CH-01-23	3-10
Figure 3-7.	Rock Quality Logged in Core Hole ZEV-CH-02-23	3-10
Figure 3-8.	Rock Quality Logged in Core Hole ZEV-CH-03-23	3-11
Figure 3-9.	Flow Rate and Permeability Recorded in Core Hole ZEV-CH-01-23	3-12
Figure 3-10.	Flow Rate and Permeability Recorded in Core Hole ZEV-CH-02-23	3-12
Figure 3-11.	Flow Rate and Permeability Recorded in Core Hole ZEV-CH-03-23	3-12
Figure 3-12.	Stereonet and Rose Diagram of the Joints within the Cavern Target Horizon for ZEV-CH-01-23	3-13
Figure 3-13.	Stereonet and Rose Diagram of the Joints within the Cavern Target Horizon for ZEV-CH-02-23	3-14
Figure 3-14.	Stereonet and Rose Diagram of the Joints within the Cavern Target Horizon for ZEV-CH-03-23	3-14
Figure 3-15.	Stereonet and Rose Diagram of the Joints within the Cavern Target Horizon for all Core Holes Combined.....	3-15
Figure 3-16.	Histogram Showing the Distribution of Discontinuity Spacing for All Joint Sets in the Target Cavern Horizon.....	3-17
Figure 3-17.	Histogram Showing the Distribution of Discontinuity Spacing for Joint Set 1 in the Target Cavern Horizon.....	3-17
Figure 3-18.	Histogram Showing the Distribution of Discontinuity Spacing for Joint Set 2 in the Target Cavern Horizon.....	3-18
Figure 4-1.	Intact Rock Strength Recorded in Core Hole ZEV-CH-01-23	4-2
Figure 4-2.	Intact Rock Strength Recorded in Core Hole ZEV-CH-02-23	4-3
Figure 4-3.	Intact Rock Strength Recorded in Core Hole ZEV-CH-03-23	4-3
Figure 4-4.	Slake Durability Index Recorded in Core Hole ZEV-CH-01-23.....	4-4
Figure 4-5.	Slake Durability Index Recorded in Core Hole ZEV-CH-02-23.....	4-5
Figure 4-6.	Slake Durability Index Recorded in Core Hole ZEV-CH-03-23.....	4-5
Figure 4-7.	Rock Mass Rating for Core Hole ZEV-CH-01-23	4-6
Figure 4-8.	Rock Mass Rating for Core Hole ZEV-CH-02-23	4-7
Figure 4-9.	Rock Mass Rating for Core Hole ZEV-CH-03-23	4-7
Figure 4-10.	Q Ratings for Core Hole ZEV-CH-01-23	4-8
Figure 4-11.	Q Ratings for Core Hole ZEV-CH-02-23	4-9
Figure 4-12.	Q Ratings for Core Hole ZEV-CH-03-23	4-9
Figure 4-13.	Map Showing the Measured Orientation of the In-situ Horizontal Stresses in the Antelope Valley	4-10
Figure 4-14.	Theoretical Borehole Cross-section, Showing the Relationship between the Major Principal Horizontal Stress, the Minor Principal Horizontal Stress for Borehole Breakout and Tensile Fracture	4-11
Figure 4-15.	Acoustic Televiwer Logs Showing Borehole Breakout in the Amplitude Logs for Core Holes ZEV-CH-01-23 and ZEV-CH-02-23	4-11
Figure 4-16.	Map Showing the Chance of any Level of Damaging Earthquake Shaking in 100 years from the 2023 50-State National Seismic Hazard Model.....	4-14
Figure 4-17.	GSI Ratings for Core Hole ZEV-CH-01-23	4-16
Figure 4-18.	GSI Ratings for Core Hole ZEV-CH-02-23	4-16
Figure 4-19.	GSI Ratings for Core Hole ZEV-CH-03-23	4-17
Figure 4-20.	Linear Regression Analysis for the Input and Derivation of m_i Constant	4-19
Figure 4-21.	Guidelines for Estimating Disturbance Factor.....	4-20


DISCLAIMER: *This report contains professional opinions based on information provided by the Owner. Agapito Associates, Inc. makes no warranties, either expressed or implied, as to the accuracy or completeness of the information herein. Opinions are based on subjective interpretations of geotechnical data; other equally valid interpretations may exist. Identification and control of hazardous conditions are the responsibilities of the Owner.*

1 INTRODUCTION

The Willow Rock – Dawn Road Project site (Willow Rock) is located approximately 2 miles north of Rosamond, California in the Mojave Desert (see Figure 1-1). The site is bounded by the Antelope Valley Freeway to the west and the Sierra Highway to the east. Drilling records from the site indicate the existing ground surface is located between 2,560 and 2,570 feet above mean sea level (ft AMSL).

The site has been selected for investigation into the feasibility for the construction of an Advanced Compressed Air Energy Storage (A-CAES) cavern. Hydrostor’s target depth for cavern construction is between the intervals of 2,000 and 2,500 ft below ground surface (bgs). Since depth is a function of surface elevation, this investigation will refer to subsurface elevations to maintain constant vertical measurements. Therefore, the “target cavern horizon” equates to an elevation of 570 to 60 ft AMSL

The geotechnical characterization in this report is constrained to the anticipated ground conditions within the target cavern horizon. The characterization of the overlying ground conditions for vertical shaft construction will require further field investigation with focus on these intervals. While the exploration program is ongoing for this site, the purpose of this report is to summarize our analysis of the data collected from the first three deep subsurface core holes and provide geotechnical design parameters for both empirical and numerical assessment methodologies. However unlikely, the summarized geotechnical design parameters could change based on the results and analysis of the ongoing exploration program.



951-20 Lane Hydrostor Zevsar[California-Nevada-Lane_Willow Rock.cdr]rjl(2-16-2024)

Figure 1-1. Location of the Willow Rock – Dawn Road Project Site

2 GEOTECHNICAL SETTING

2.1 Records Search

To obtain existing information on the geological and hydrological settings of the Willow Rock site, a literature search was performed that resulted in the following referenced sources:

- Geology of the Willow Springs and Rosamond Quadrangles California (Dibblee 1963).
- Areal Geology of the Western Mojave Desert California (Dibblee 1967).
- Willow Springs and Rosamond 15-minute quadrangle USGS maps (2008).

The following reference was provided by Hydrostor as part of their surface investigation:

- Geotechnical Data Report – Zevsar Energy Storage Project (Yeh and Associates, Inc 2023).

The information from Dibblee (1963) was collected during the U.S. Geological Survey's study of the areal geology of the western Mojave Desert. The aim of the study was to determine whether formations of Tertiary and Quaternary age might contain hidden saline deposits of economic value. A secondary aim was to determine the general character of the pre-Tertiary crystalline bedrock complex and to investigate the relationship of the complex to the depositional history and structure of the Cenozoic formations.

The information from Dibblee (1967) was part of a geologic investigation carried out by the U.S. Geological Survey of the known and potential deposits of borate minerals in the southern California desert regions.

The information from the geotechnical data report summarizes the results of a shallow subsurface geotechnical site investigation carried out by Yeh and Associates, Inc in 2023.

2.2 Regional and Local Geology

The Willow Rock site is located in the Antelope Valley in the Western Mojave Desert in California (see Figure 2-1). Antelope Valley is a structural basin filled with a hundred- to several thousand-foot thickness of Cenozoic alluvial sedimentary deposits (Dibblee 1963). The valley is bounded by the Garlock fault to the northwest and the San Andreas fault to the southwest, forming the "Mojave block" (Dibblee 1967). The Project site, shown in Figure 2-2 and within the 15-minute Rosamond quadrangle (USGS 2008), is situated on the remnants of an isolated low hill which is comprised of exposed quartz monzonite.

The quartz monzonite is a plutonic rock that is probably Mesozoic, possibly Cretaceous in age (Dibblee 1963). It is by far the most extensive plutonic rock in the area and is the primary rock type of the granitic batholith that underlies the Mojave Desert. Dibblee (1963) describes the quartz monzonite as a medium to coarse-grained holocrystalline granitic rock, gray-white when fresh but commonly buff white on weathering. It is composed of almost equal percentages of quartz, potassium feldspar, and plagioclase, a small percentage of biotite and trace hornblende can be found locally.

Near the Project site, the quartz monzonite is locally cut by dike swarms of pegmatite and aplite of the same mineralogic composition of almost entirely quartz and feldspar. The dikes range from

less than an inch (in.) to about 6 ft in width and are traceable from a few feet to half a mile (Dibblee 1963). They are typically parallel, trending to the northwest, and are vertical or steeply inclined to the southwest.

The Project site is situated along the northeastern side of the Rosamond Hills area (see Figure 2-2). The Rosamond Hills consist of a large eastward-trending uplifted area, possibly an upwarp, of quartz monzonite (Dibblee 1963). The hills are cut by many minor high-angle normal faults that trend either west-northwest or east-northeast. The largest fault within the Rosamond Hills is located immediately northeast of the Project site (see Figure 2-2). The fault trends northwest within the quartz monzonite for an approximate distance of 5 miles and appears to extend another mile northwestward through the recent alluvium. As shown in Figure 2-3, surface exposures of the fault are marked by a zone of pulverized quartz monzonite covered by a white caliche-like crust. This fault, nor any of the other faults within Rosamond Hills show evidence of recent activity (Dibblee 1963).

The 15-minute Rosamond quadrangle map indicates the Project site is underlain by a continuous massive unit of quartz monzonite (see Figure 2-4). The quartz monzonite forms the crystalline bedrock basement complex upon which assemblages of Cenozoic age rest unconformably (Dibblee 1963). Seismic reflection profiling of the western Mojave Desert indicates the basement rocks are between 15 and 20 miles thick (Cheadle et al. 1986).




Figure 2-1. Geologic Map of the Antelope Valley in the Western Mojave Desert Showing the Location of the Project Area




Figure 2-2. 15-minute Rosamond Quadrangle Geologic Map Showing the Location of the Project Area the Mapped and Inferred Location of the Northwest-Southeast Trending Normal Fault





Figure 2-3. Satellite Image Showing the Project Area and the Surface Exposure of the Northwest-Southeast Trending Normal Fault



951-20 Lane [Lane Hydrostor Geol Map Project Site2_Profile.cdr:rl] (2-16-2024)

Figure 2-4. Cross-section Showing the Bedrock Geology around the Project Area

3 SITE SPECIFIC GEOTECHNICAL CONDITIONS

The geotechnical conditions at the Willow Rock site have been determined from separate surface and subsurface geotechnical investigation programs. The surface geotechnical investigation collected information from the soil and weathered bedrock underlying the site that will be used to assist in the design of the surface infrastructure. The subsurface investigation involved core drilling to approximate depths of 3,000 ft below the surface. The results of the geotechnical investigations are summarized in the succeeding sections.

3.1 Surficial Geotechnical Investigation

The characterization of the surficial deposits at the Project site is based on a geotechnical investigation carried out by Yeh and Associates, Inc (2023). The logged and inferred geology of the surficial deposits determined from the investigation are shown in Figure 3-1. Most of the site is overlain by 3.0 to 7.5 ft of residual soils, which are comprised of loose to very dense, well graded sand with varying amounts of silt and clay (SW, SM, SC). Underlying the soils is 20 to 45 ft of decomposed to intensely weathered quartz monzonite. The unit was described as very soft to moderately hard, very slightly fractured to moderately fractured. The decomposed zones were logged as silty to clayey sand (SM, SC). The borings continued to a depth of between 51 and 71 ft, where most of the quartz monzonite was logged as slightly to moderately weathered, very soft to hard, and intensely to slightly fractured. Isolated zones of intensely weathered to decomposed quartz monzonite were logged in this interval. The depths of the borings did not penetrate fresh rock at any of the sample locations.

UCS tests carried out on rock core indicated intact strengths of between 70 and 5,770 pounds-per-square inch (psi), which is indicative of extremely weak to weak rock (ISRM 2007). The laboratory test results are provided in Table 3-1.

Monitoring wells indicate the groundwater depth at the site is approximately 40 ft below the surface (see Figure 3-1). Yeh and Associates, Inc. suggest that groundwater conditions at the site will vary seasonally due to variations in storm runoff, irrigation, and groundwater pumping in the site's vicinity.

3.2 Subsurface Geotechnical Investigation

CRUX Subsurface Drilling advanced three core holes (ZEV-CH-01-23, ZEV-CH-02-23, and ZEV-CH-03-23) between March 17, 2023, and October 21, 2023, at the locations shown in Figure 3-2. The core holes were started with rotary drilling and setting HW casing to depths of between 70 and 171 ft. The borings were drilled using HQ-3-sized diamond bits and 10-ft-long wireline core barrels. This resulted in 2.41-inch-diameter cores, which were stored in 5-ft-long wooden core boxes. The end depth of core drilling ranged between 3,015 and 3,167 ft for the core holes, which equates to elevations of between 445 and 607 ft below mean sea level (BMSL).

Core logging was performed by Lane and Carboniferous, LLC geologist Chris Messinger. Core logging consisted of identifying the mineralogy and rock type for each run of core, the alteration of discontinuities for each run, noting the percentage core recovery for each 10-ft run, and noting the Rock Quality Designation (RQD) for each run based on the percentage of the run comprised of pieces longer than 4 in..






Figure 3-1. Logged and Inferred Subsurface Geotechnical Conditions at the Project Site

Table 3-1. Laboratory UCS Test Results from the Surface Geotechnical Investigation Program (Yeh and Associates, Inc 2023)

Borehole	Material	Depth (ft)		Unit Weight (pcf)	Unconfined Compressive Strength (psi)
		From	To		
23E-02	Quartz monzonite, moderately weathered	67.5	68.0	153.4	77
23E-03	Quartz monzonite, moderately weathered	52.8	53.3	154.3	147
23E-04	Quartz monzonite, moderately weathered	39.0	39.5	155.3	647
23E-05	Quartz monzonite, moderately weathered	55.5	56.0	160.9	1,940
23E-05	Quartz monzonite, intensely weathered	57.2	57.7	155.2	97
23E-05	Quartz monzonite, fresh	65.0	65.5	162.9	5,770
23E-06	Quartz monzonite, slightly weathered	55.1	56.1	158.7	866
23E-06	Quartz monzonite, slightly weathered	59.1	59.6	158.4	218
23E-06	Quartz monzonite, moderately weathered	60.6	61.1	147.7	209

3.2.1 Core Hole Lithology

The detailed lithology is logged for each of the core holes and is provided in the geotechnical logs found in Appendix A. A summary of the lithology data is also provided in Table 3-2 (a-c).

All three core holes indicate the lithology in the target cavern horizon is comprised of quartz monzonite. The only exception to this is in core hole ZEV-CH-02-23, where the target interval was intersected by two thin diorite dikes. Additionally, the quartz monzonite in the lower part of the target interval in this hole has undergone recrystallization and is dominated by the mineral monazite. Monazite is a hard and resistant mineral that forms when igneous rocks undergo crystallization.

In all three core holes, the quartz monzonite has undergone various degrees of hydrothermal alteration. Hydrothermal alteration occurs when hot, mineral-rich fluids interact with rocks and minerals, causing them to change in terms of their mineral composition, texture, and structure. Dibble (1963) suggested that much of the alteration in the area occurs along fault or fracture zones. Table 3-3 outlines the various degrees of alteration used to classify the rock (ISRM 2007).

Within the target cavern horizon, the alteration of the quartz monzonite in ZEV-CH-01-23 is almost entirely fresh to slightly altered (see Figure 3-3). In ZEV-CH-02-23, thick zones of moderately to highly altered quartz monzonite were logged between the elevations of 456 to 401 ft AMSL, and 325 to 251 ft AMSL (see Figure 3-4). In ZEV-CH-03-23, the quartz monzonite between the elevations of 570 and 455 ft AMSL was logged as moderately to highly altered. Elsewhere in the target interval, most of the core was logged as fresh to slightly altered (see Figure 3-5).




Figure 3-2. Location of Deep Subsurface Exploration Core Holes at the Project Site

Table 3-2a. Summary of Lithology in ZEV-CH-01-23

Depth (ft)		Elevation (ft MSL)		Lithology
From:	To:	From:	To:	
Core Hole: ZEV-CH-01-23				
0	71	2,560	2489	HW casing
71	140	2,489	2,420	Quartz monzonite, most of the core is moderately to highly altered
140	1,327	2,420	1,233	Quartz monzonite, most of the core is slightly to moderately altered
1,327	1,541	1,233	1,019	Quartz monzonite, most of the core is moderately to highly altered
1,541	1,829	1,019	731	Quartz monzonite, most of the core is fresh to slightly altered
1,829	1,847	731	713	Diorite
1,847	2,532	713	28	Quartz monzonite, most of the core is fresh to slightly altered
2,532	2,682	28	-122	Quartz monzonite, most of the core is slightly to moderately altered
2,682	2,707	-122	-147	Pegmatite dike
2,707	2,721	-147	-161	Quartz monzonite, most of the core is fresh to slightly altered
2,721	2,777	-161	-217	Diorite
2,777	3,167	-217	-607	Quartz monzonite, most of the core is fresh to slightly altered

Table 3-2b. Summary of Lithology in ZEV-CH-02-23


Depth (ft)		Elevation (ft MSL)		Lithology
From:	To:	From:	To:	
Core Hole: ZEV-CH-02-23				
0	70	2,570	2500	HW casing
70	160	2,500	2,410	Quartz monzonite, most of the core is moderately to highly altered
160	895	2,410	1,675	Quartz monzonite, most of the core is fresh to slightly altered
895	1,000	1,675	1,570	Quartz monzonite, most of the core is moderately to highly altered
1,000	1,186	1,570	1,384	Quartz monzonite, most of the core is fresh to slightly altered
1,186	1,225	1,384	1,345	Diorite
1,225	1,270	1,345	1,300	Quartz monzonite, most of the core is moderately to highly altered
1,270	1,791	1,300	779	Quartz monzonite, most of the core is fresh to slightly altered
1,791	1,795	779	775	Dolerite
1,795	2,114	775	456	Quartz monzonite, most of the core is fresh to slightly altered
2,114	2,215	456	355	Quartz monazite
2,215	2,320	355	250	Quartz monzonite, most of the core is slightly to moderately altered
2,320	2,330	250	240	Dolerite
2,330	2,351	240	219	Quartz monzonite, most of the core is fresh to slightly altered
2,351	2,358	219	212	Diorite
2,358	2,650	212	-80	Quartz monzonite, most of the core is fresh to slightly altered
2,650	2,755	-80	-185	Quartz monzonite, most of the core is moderately to highly altered
2,755	2,921	-185	-351	Quartz monzonite, most of the core is fresh to slightly altered
2,921	2,930	-351	-360	Diabase dike
2,930	3,045	-360	-475	Quartz monzonite, most of the core is slightly altered

Table 3-2c. Summary of Lithology in ZEV-CH-03-23

Depth (ft)		Elevation (ft MSL)		Lithology
From:	To:	From:	To:	
Core Hole: ZEV-CH-03-23				
0	171	2,570	2399	HW casing
171	264	2,399	2,306	Quartz monzonite, most of the core is fresh to slightly altered
264	306	2,306	2,264	Quartz monzonite, most of the core is moderately to highly altered
306	590	2,264	1,980	Quartz monzonite, most of the core is fresh to slightly altered
590	621	1,980	1,949	Quartz monzonite, most of the core is moderately to highly altered
621	1,195	1,949	1,375	Quartz monzonite, most of the core is fresh to slightly altered
1,195	1,197	1,375	1,373	Dolerite dike
1,197	1,216	1,373	1,354	Quartz monzonite, most of the core is fresh to slightly altered
1,216	1,229	1,354	1,341	Dolerite dike
1,229	1,246	1,341	1,324	Quartz monzonite, most of the core is fresh to slightly altered
1,246	1,251	1,324	1,319	Dolerite dike
1,251	1,321	1,319	1,249	Quartz monzonite, most of the core is fresh to moderately altered
1,321	1,328	1,249	1,242	Dolerite dike
1,328	1,461	1,242	1,109	Quartz monzonite, most of the core is slightly to moderately altered
1,461	1,814	1,109	756	Quartz monzonite, most of the core is fresh to slightly altered
1,814	1,886	756	684	Quartz monzonite, most of the core is slightly to moderately altered
1,886	1,895	684	675	Diorite dike
1,895	2,000	675	570	Quartz monzonite, most of the core is fresh to slightly altered
2,000	2,151	570	419	Quartz monzonite, most of the core is moderately to highly altered
2,151	2,496	419	74	Quartz monzonite, most of the core is fresh to slightly altered
2,496	2,525	74	45	Diorite dike
2,525	2,766	45	-196	Quartz monzonite, most of the core is fresh to slightly altered
2,766	2,841	-196	-271	Quartz monzonite, most of the core is moderately altered to decomposed
2,841	2,906	-271	-336	Quartz monzonite, most of the core is fresh to slightly altered
2,906	3,015	-336	-445	Quartz monzonite, most of the core is slightly to moderately altered

Table 3-3: Effect of Alteration on Fresh Rock (ISRM 2007)

Classification	Symbol	Description
Fresh	Fr	No visible signs of alteration; perhaps slight discoloration on defect surfaces.
Slightly Altered	SA	Alteration confined to veins and/or veinlets. Little or no penetration of alteration beyond vein/veinlet boundaries. No discernable effect on the strength properties of the parent rock type.
Moderately Altered	MA	Alteration is controlled by veins and may penetrate wall rock as narrow vein selvages or envelopes. Alteration may also be pervasive but weakly developed. Modifications to the rock are small.
Highly Altered	HA	Pervasive alteration of rock-forming minerals and intact rock to assemblages that significantly change the strength properties of the parent rock type.
Completely Altered	CA	Intensive, pervasive, complete alteration of rock-forming minerals. The rock mass may resemble soil. For hydrothermal alteration, any alteration assemblages that results in the nearly complete or complete change in rock strength relative to the parent rock type.

**Figure 3-3. Degree of Alteration Logged in Core Hole ZEV-CH-01-23**




Figure 3-4. Degree of Alteration Logged in Core Hole ZEV-CH-02-23




Figure 3-5. Degree of Alteration Logged in Core Hole ZEV-CH-03-23

3.2.2 Rock Quality

The RQD classification system has been used to classify the degree of jointing or block size of the recovered core (Deere 1963). The rock quality descriptors corresponding to the RQD values are given in Table 3-4. In core holes ZEV-CH-01-23 and ZEV-CH-02-23, the logging indicates decreasing rock quality as depth increases through the cavern target horizon (see Figures 3-6 and 3-7). The rock quality is “Good” to “Excellent” in the upper part of the target interval, and progressively decreases to “Poor” to “Very Poor” at the lower part of the target interval. The rock quality within the target horizon in ZEV-CH-03-23 is markedly lower than the previous core holes with a vast majority of the core being classed as “Very Poor” to “Poor” to an elevation of 215 ft AMSL (see Figure 3-8). Below this elevation, the rock quality improves to “Fair” to “Good” (see Figure 3-8).

3.2.3 Packer Testing

Packer testing was performed by project geologist Chris Messinger. Packers were set to isolate the interval being tested, which was approximately 21.8 ft. A small amount of water was added to the test interval after which the interval was pressurized to 80 psi over the hydrostatic pressure. The water level was then measured, first at 1-minute intervals for 5 minutes and 5-minute intervals thereafter, until the flow rate into the rock stabilized.

The recorded flow rates in all three core holes within the cavern target horizon are all less than 4.5 gallons-per-hour (gph), with most of the rates less than 2.0 gph (see Figures 3-9 to 3-11). The packer test results indicate that the hydraulic conductivity of the rock mass ranges between 1.90×10^{-8} and 8.55×10^{-7} centimeters per second (cm/s) (see Figures 3-9 to 3-11). The hydraulic conductivity values can be used to infer the condition of the rock mass discontinuities according to Table 3-5 (Quinones-Rozo 2010). The condition of the rock mass discontinuities within the cavern target horizon can therefore be classed as “Very Tight”.

3.2.4 Geophysical Logging

Geophysical logging was performed by GEOVision, Inc. (GEOVision). The core hole geophysical logging program consisted of running a sonde containing temperature and conductivity sensors, optical (OTV) and acoustic (ATV) televewers, an acoustic caliper, and a borehole deviation sensor. The interpretation of the directions and inclinations of discontinuities in the rock was plotted as tadpoles (filled circles with tails indicating dip direction) on plots of dip versus depth. The OTV and ATV logs for the three core holes are included in Appendix B.

Table 3-4. RQD Classification System (Deere and Deere 1988)

RQD	Description of Rock Quality
0 to <25	Very Poor
25 to <50	Poor
50 to <75	Fair
75 to <90	Good
90 to 100	Excellent




Figure 3-6. Rock Quality Logged in Core Hole ZEV-CH-01-23




Figure 3-7. Rock Quality Logged in Core Hole ZEV-CH-02-23




Figure 3-8. Rock Quality Logged in Core Hole ZEV-CH-03-23




Figure 3-9. Flow Rate and Permeability Recorded in Core Hole ZEV-CH-01-23




Figure 3-10. Flow Rate and Permeability Recorded in Core Hole ZEV-CH-02-23





Figure 3-11. Flow Rate and Permeability Recorded in Core Hole ZEV-CH-03-23

Table 3-5. Condition of Rock Mass Discontinuities Associated with Different Hydraulic Conductivities (Quinones-Rozo 2010)

Hydraulic Conductivity Range (cm/s)	Condition of Rock Mass Discontinuities
$<1 \times 10^{-5}$	Very Tight
1×10^{-5} to 6×10^{-5}	Tight
6×10^{-5} to 2×10^{-4}	Few Partly Open
2×10^{-4} to 6×10^{-4}	Some Open
6×10^{-4} to 1×10^{-3}	Many Open
$>1 \times 10^{-3}$	Open Closely Spaced or Voids

3.2.5 Structural Defects

Utilizing the ATV and OTV logs for the three core holes, discontinuities in the core hole wall and their inclination were identified by GEOVision. The summary data for the discontinuities are presented in the geophysical reports included in Appendix B. Agapito grouped the discontinuities together for each core hole and plotted the joints on stereonet and rose diagrams to confirm dip and dip azimuth of the structure, and to identify joint sets within the fracture data. Representative stereonet and rose diagrams are provided in Figures 3-12 to 3-15. A summary of the joint set trends identified is given in Table 3-6.

**Figure 3-12. Stereonet (left) and Rose Diagram (right) of the Joints within the Cavern Target Horizon for ZEV-CH-01-23**




Figure 3-13. Stereonet (left) and Rose Diagram (right) of the Joints within the Cavern Target Horizon for ZEV-CH-02-23




Figure 3-14. Stereonet (left) and Rose Diagram (right) of the Joints within the Cavern Target Horizon for ZEV-CH-03-23




Figure 3-15. Stereonet (left) and Rose Diagram (right) of the Joints within the Cavern Target Horizon for all Core Holes Combined

Table 3-6. Summary of Structure Orientation and Dip in the Cavern Target Interval

Borehole	Joints			
	Joint Set	Dip Direction	Strike	Dip (°)
ZEV-CH-01-23	JS1	242	N28°W	71
	JS2	256	N14°W	52
	JS3	40	S50°E	75
	JS4	356	N86°E	63
ZEV-CH-02-23	JS1	242	N28°W	62
	JS2	290	N20°E	56
	JS3	44	S46°E	78
	JS4	94	S04°W	76
	JS5	143	N53°E	72
ZEV-CH-03-23	JS1	274	N04°E	58
	JS2	237	N33°W	75
	JS3	55	S35°E	77
COMBINED	JS1	238	N32°W	65
	JS2	277	N07°E	59
	JS3	43	S47°E	76
	JS4	96	S06°W	74
	JS5	141	N51°E	73

From Table 3-6, the predominate joint set within the target cavern horizon has a strike averaging N32°W and a dip averaging 65° to the west-southwest. A secondary joint set has an average strike of N07°E and dip averaging 59° to the west. A tertiary set, which is evident in all three core holes, has a strike averaging S47°E and a dip averaging 76° to the northeast. Other random steeply dipping joints were measured in all three core holes.

The discontinuity spacing can be classified using the descriptions provided in Table 3-7. The spacing of the combined joints in the target cavern horizon can therefore be classed as close to moderate with the majority of the discontinuities spaced between 100 and 400 mm (0.3 and 1.3 ft). The maximum spacing is 600 millimeters (mm [2 ft]), which is classified as borderline moderate to wide spacing. A histogram showing the distribution of all joints is provided in Figure 3-16. A similar spacing distribution is evident for joints sets 1 and 2 within the target horizon (see Figures 3-17 and 3-18).

The persistence, or length, of the joints cannot be determined from the core drilling. This could be estimated from nearby extensive surface exposures of the quartz monzonite, but Agapito is not aware of any such studies.

Table 3-7. Discontinuity Spacing Classification (ISRM 2007)

Description of Discontinuity Spacing	Spacing (mm)
Extremely Close	< 20
Very Close	20 to < 60
Close	60 to < 200
Moderate	200 to < 600
Wide	600 to < 2000
Very Wide	2000 to < 6000
Extremely Wide	> 6000




Figure 3-16. Histogram Showing the Distribution of Discontinuity Spacing for All Joint Sets in the Target Cavern Horizon




Figure 3-17. Histogram Showing the Distribution of Discontinuity Spacing for Joint Set 1 in the Target Cavern Horizon




Figure 3-18. Histogram Showing the Distribution of Discontinuity Spacing for Joint Set 2 in the Target Cavern Horizon

4 GEOTECHNICAL CHARACTERIZATION

4.1 Geomechanical Properties of the Intact Rock

Agapito conducted laboratory testing on a large number of core samples collected from the three core holes. The core samples were collected from each hole beginning at depths of around 1,500 ft. The sampling frequency was increased between the depths of 2,000 and 3,000 ft to account for the investigation of various cavern horizons. The samples were packaged and shipped to Agapito's laboratory in Grand Junction, Colorado, for testing according to Agapito testing recommendations. The samples were tested for uniaxial compressive strength (UCS), splitting tensile strength (Brazilian), triaxial compression strength, slake durability index, axial point load strength index (PLT-A), density, moisture content, Young's modulus (E), and Poisson's ratio (ν). Table 4-1 summarizes all data from the testing program for each rock type with the detailed test results provided in Appendix C. A summary of the Mohr-Coulomb failure criteria for intact rock derived from the triaxial data from the tests performed, with confining pressures ranging from 1,500 to 2,500 psi, are shown in Table 4-2.

Table 4-1. Summary of Laboratory Rock Mechanics Testing Results from the Exploration Core Holes

Rock Type	Density (pcf)	UCS (psi)	E ($\times 10^6$ psi)	ν	Tensile Strength (psi)	PLT-A $I_{s(50)}$	Moisture (%)	Slake Durability Index (%)	Durability
Quartz Monzonite (all)	165.7	17,522	8.29	0.25	1,103	687	0.45%	94.6	Medium High
Quartz Monzonite (Fr to SA)	165.9	17,619	9.37	0.25	1,060	711	0.38%	96.8	High
Quartz Monzonite (SA to MA)	164.5	12,524	6.56	0.25	1,179	635	0.64%	91.2	Medium High
Quartz Monzonite (MA to HA)	162.5	-	-	-	1,154	638	0.70%	82.0	Medium
Quartz Monzonite (HA to CA)	153.0	-	-	-	-	83	-	-	-
Quartz Monazite	167.8	22,922	9.91	0.26	1,356	936	0.33%	99.1	Very High
Diorite	163.9	21,587	10.88	0.17	1,298	714	0.21%	99.1	Very High
Pegmatite	157.4	12,090	6.97	0.25	-	173	0.41%	94.8	Medium High

Table 4-2. Summary of Triaxial Test Results from the Exploration Core Holes

Rock Type	ϕ (degrees)	c (psi)
Quartz Monzonite (all)	30.2	8,874
Quarz Monazite	24.0	9,019

4.1.1 Unit Weight

The density of the quartz monzonite was determined from laboratory testing on a total of 228 samples. The density ranged from 138.0 pounds-per-cubic foot (pcf) to 174.6 pcf with a mean of 165.7 pcf.

4.1.2 Uniaxial Compressive Strength

UCS tests were performed on rock core samples and the individual test results are summarized in Appendix C. Samples were prepared from as-shipped core. Failures were denoted as being “pre-existing” where failure occurred along obvious pre-existing planes of weakness (i.e. joints). These results were omitted from the analysis.

A correlation factor can be used to convert the axial point load strength ($I_{s(50)}$) to UCS for rock. A graphical comparison of the UCS and corrected axial point load strength for each core hole indicates a correlation factor of 20 is appropriate (see Figures 4-1 to 4-3). As shown in the figures, most of the intact rock can be classed as medium to high strength (ISRM 2007). The low to moderate intact rock strength recorded in the core is indicative of areas that have undergone high to complete alteration.




Figure 4-1. Intact Rock Strength Recorded in Core Hole ZEV-CH-01-23




Figure 4-2. Intact Rock Strength Recorded in Core Hole ZEV-CH-02-23




Figure 4-3. Intact Rock Strength Recorded in Core Hole ZEV-CH-03-23

4.1.3 Elastic Properties

Laboratory testing for UCS rock samples produced plots of stress versus strain up to a peak strength level in the unconfined state. The average slope of these lines, between the 0 and 55% ultimate strength level, was used to derive the intact elastic properties. The individual test results for both Young's modulus and Poisson's ratio are summarized in Appendix C. As shown in Table 4-1 above, stiffness decreases in the slightly to moderately altered quartz monzonite.

4.1.4 Slake Durability

The slake durability test is used to estimate qualitatively the durability of weak rocks through weakening and disintegration resulting from cycles of wetting and drying. This is an important test to help understand the rock's behavior in the A-CAES cavern that will be subjected to daily cycles of water infiltration and hot compressed air. Most of the anticipated rock in the cavern horizon can be classed as medium high to very high durability (see Figures 4-4 to 4-6). The quartz monzonite that has been logged as moderately to highly altered typically exhibits medium durability. Medium durability is indicative of a specimen that contains large and small fragments after two-cycles of wetting and drying (ASTM D4644-08). This means that some of the sample fragments broke down into smaller fragments.




Figure 4-4. Slake Durability Index Recorded in Core Hole ZEV-CH-01-23



Figure 4-5. Slake Durability Index Recorded in Core Hole ZEV-CH-02-23




Figure 4-6. Slake Durability Index Recorded in Core Hole ZEV-CH-03-23

4.2 Rock Mass Characterization

Two rock mass classification systems have been used to evaluate the competency of the rock mass anticipated in the target cavern horizon. These systems will be used to characterize the condition of the rock mass for the purpose of assessing ground behavior and establishing rock mass geomechanical properties for numerical modeling. These systems include the Rock Mass Rating (RMR) and the Tunneling Quality Index (Q). A summary of the rock mass classification results is presented in the following sections, and the details of the analysis are proved in Appendix D.

4.2.1 Rock Mass Rating (RMR)

The Rock Mass Rating (RMR) is a geomechanical classification system for rocks (Bieniawski 1976, 1989). The system uses the following six parameters to classify rock mass quality: UCS, the RQD, spacing of discontinuities, condition of discontinuities, groundwater condition, and orientation of discontinuities. The reported RMR values for this assessment does not consider the orientation of discontinuities.

The results of the analysis indicate that the rock mass in core holes ZEV-CH-01-23 and ZEV-CH-02-23 can be classified as “Fair” to “Good” within the target cavern horizon (see Figures 4-7 and 4-8). A higher percentage of “Good” rock mass is positioned near the top of the target horizon in both core holes. In core hole ZEV-CH-03-23, most of the rock mass reduces to borderline “Poor” to “Fair” (see Figure 4-9). The lower RMRs in this core hole can be attributed to increased fracturing of the rock mass.




Figure 4-7. Rock Mass Rating for Core Hole ZEV-CH-01-23




Figure 4-8. Rock Mass Rating for Core Hole ZEV-CH-02-23




Figure 4-9. Rock Mass Rating for Core Hole ZEV-CH-03-23

4.2.2 NGI Q-system

The Norwegian Geotechnical Institute's Q-system is an empirical rock mass classification system developed by Barton et al. (1974), which is used to facilitate the selection of ground support. The Q-system is based on a numerical evaluation of rock mass properties similar to RMR, except the system does not account directly for the strength of the intact rock. The system assigns a degree of rock quality based on six key parameters, specifically: the RQD, the number of joint sets, the roughness of the most unfavorable joint or discontinuity, the degree of joint alteration or infilling, water inflow, and the in-situ stress environment.

The parameters are grouped into three quotients to give the rock mass quality using the following equation:

$$Q = \frac{RQD}{J_n} \times \frac{J_r}{J_a} \times \frac{J_w}{SRF}$$

In core holes ZEV-CH-01-23 and ZEV-CH-02-23, most of the rock mass within the target cavern horizon is classed as "Poor" to "Fair" with isolated zones of "Good" rock mass near the top of the target horizon (see Figures 4-10 and 4-11). In core hole ZEV-CH-03-23, most of the rock mass in the target horizon is classed as "Poor" with localized zones of "Very Poor" and "Fair" rock (see Figure 4-12). Similar to the RMR rating system, the reduction in rock mass quality in this core hole is related to the increased fracturing of the rock mass.




Figure 4-10. Q Ratings for Core Hole ZEV-CH-01-23




Figure 4-11. Q Ratings for Core Hole ZEV-CH-02-23




Figure 4-12. Q Ratings for Core Hole ZEV-CH-03-23

4.3 In-situ Stress Conditions

4.3.1 Regional Stress

The maximum in-situ stress (σ_{hmax}) component near the San Andreas and Garlock Faults is horizontal. McGarr et al. (1982) indicate that σ_{hmax} is aligned in a N20°W direction (see Figure 4-13). Numerous measurements have been taken near the San Andreas Fault and other active faults in California. Using regression lines presented by McGarr et al. (1982) at the depths of the target cavern horizon, σ_{hmax} is estimated between 3,765 and 4,540 psi, the minimum horizontal stress (σ_{hmin}) between 2,340 and 2,930 psi, and the vertical stress (σ_v) between 2,305 and 2,880 psi. The ratio between the maximum horizontal stress and vertical stress is termed the K ratio, which in this case is around 1.6.




Figure 4-13. Map Showing the Measured Orientation of the In-situ Horizontal Stresses in the Antelope Valley (McGarr et al. 1982)

4.3.2 Borehole Breakout

Borehole breakout is the stress-induced deformation of a borehole cross section in a preferential direction, which occurs when the stress concentration around the borehole exceeds the rock strength (Ask et al., 2006; Babcock, 1978; Bell and Goug, 1979; Zoback et al., 1985). Breakout is the result of compressive failure along the borehole wall, with borehole spalling in the direction of minimum horizontal stress (see Figure 4-14). Maximum principal stress orientations from breakout have been shown to be consistent with the results of other more traditional stress measurement techniques such as hydraulic fracturing and overcoring (Zoback and Zoback, 1980; Plumb and Hickman, 1985; Zajac and Stock, 1997).

Breakout is formed by the spalling of fragments from the borehole wall in the direction of minimum horizontal stress (σ_h), as shown in Figure 4-14 (Fowler and Wier 2008). In crystalline rocks, such as quartz monzonite, breakout is initially observed as small pits or irregular chips at the borehole wall (Plumb, 1989). Thus, breakout in crystalline rocks is thought to initiate at the borehole wall rather than in the interior as seen in sedimentary rocks.

In core holes ZEV-CH-01-23 and ZEV-CH-02-23, borehole breakout can be seen in the amplitude logs as two 180° opposed dark traces parallel to the borehole wall (see Figure 4-15). The breakout is oriented approximately N70°E, which is indicative of a major horizontal stress direction of N20°W. The logs indicate that this orientation is consistent throughout the target cavern horizon in both core holes. This orientation is in line with the regional major horizontal stress direction measured in Antelope Valley (see Figure 4-13).




Figure 4-14. Theoretical Borehole Cross-section, Showing the Relationship between the Major Principal Horizontal Stress (σ_H), the Minor Principal Horizontal Stress (σ_h) for (A) Borehole Breakout and (B) Tensile Fracture (Fowler and Weir, 2008)




Figure 4-15. Acoustic Televiewer Logs (ATV) Showing Borehole Breakout in the Amplitude Logs for Core Holes ZEV-CH-01-23 (left) and ZEV-CH-02-23 (right)

4.3.3 Sibra Overcore

The maximum and minimum horizontal stresses within the target cavern horizon were measured using the overcoring method in core hole ZEV-CH-03-23. The measurements were obtained using the in-situ stress measurement tool (IST2D) and downhole technique developed by Sibra, Pty. (Sibra) of Brisbane, Australia (Gray 2000). The IST technique measures the two-dimensional rock stresses in the plane perpendicular to the core hole wall, and because core holes are generally vertical, this technique provides the principal stresses in the horizontal plane at the testing depth.

The IST2D tool is a pilot hole overcoring device that automatically measures the deformation across the diameter of a 25 to 27 mm pilot hole at six locations during overcoring. The overcore samples are tested to determine the core's mechanical properties relating to Young's Moduli and Poisson's Ratio as well as uniaxial compressive strength. The analysis is in terms of axisymmetric anisotropic elastic, though not necessarily linearly elastic behavior. The derivation of core properties is described by Gray, Zhao, and Liu (2018).

Two successful measurements were taken at depths of 2,030.0 and 2,033.4 ft in core hole ZEV-CH-03-23. The results are given in Table 4-3, and the details of the testing are provided in Appendix E. Using the axial modulus values derived from the laboratory tests of the overcore samples, the average maximum horizontal stress (σ_1) is 1.2 times the minimum horizontal stress (σ_3) and 1.6 times the estimated vertical stress (σ_v). Thus, the ratio between the major maximum horizontal stress and vertical stress indicates a reasonably high horizontal stress regime, which aligns with the regional measurements collected by McGarr et al. (1982). Similarities were also measured in the major horizontal stress orientation, where the direction ranged between N20°W and N54°W. This suggests that the horizontal stresses at the roject site are related to tectonic activity associated with the San Andreas Fault.

Table 4-3. Summary of IST2D Stress Testing in Core Hole ZEV-CH-03-23

Hole Name	ZEV-CH-03-23	
Overcore Number	0052-070	0054-070
Date Tested	9/5/2022	9/5/2022
Depth (ft)	2,030.0	2,033.4
Unconfined Compressive Strength (psi)	26,468	12,696
Young's Modulus ($\times 10^6$ psi)†	10.38	9.31
Poisson's Ratio †	0.32	0.19
Estimated Vertical Stress (psi)	2,368	2,373
Self-loading Horizontal Stress σ_{hsw} (psi)	1,114	557
Maximum Horizontal Stress σ_1 (psi)	4,098.8	3,611
Minimum Horizontal Stress σ_3 (psi)	3,115.4	3,446
$\sigma_1:\sigma_3$ Ratio	1.3	1.0
True Bearing of Maximum Horizontal Stress	340.38°	303.98°
Maximum Horizontal Strain ϵ_1 (microstrain)	226.8	269.8
Minimum Horizontal Strain ϵ_2 (microstrain)	101.6	248.6
psi = pounds per square inch; ° = degree; E = East		
† Tangent Calculation Method		
magnetic declination of 11.68° E		

4.4 Seismic Risk

The risk of damage due to earthquakes is primarily restricted to surface or very near-surface structures (Dowding and Rozen 1978). Sharma and Judd (1991) have estimated that little real damage occurs to underground openings at depths greater than 200 to 300 ft, except where a tunnel intersects a fault directly affected by the earthquake. According to Dowding and Rozen (1978) and confirmed by Sharma and Judd (1991) and Jaramillo (2017), no damage occurs in deep rock tunnels for Peak Ground Accelerations (PGAs) less than 19% of the acceleration due to gravity (0.19 g) and only minor damage occurs for PGAs between 0.19 g and 0.50 g. PGA is by far the most widely accepted index of the ground shaking intensity and damage from earthquakes. Thus, heavy earthquake damage can be sustained by surface buildings, while any deep underground excavations could remain mostly unharmed.

The Project site is located in a region where the likelihood of a damaging earthquake in the next 100 years is one of the highest within the United States (see Figure 4-16). Furthermore, the PGA with a 2% probability of exceedance in 50 years (i.e., occurs once every 2,475 years) was determined to be 0.39 g using Applied Technology Council (ATC) software for the ASCE7-16 Design Standard. This assumes a site amplification factor at PGA of 0.8 for Site Class A material. As per ASCE7-10, Site Class A material includes hard rock with shear wave velocities of $> 5,000$ ft/s.

Based on the PGA values, earthquake damage to a cavern at the target depths is expected to be minor. In this case, minor damage due to shaking includes fall of stones and formation of new cracks. Conversely, damage to surface buildings at the site from earthquakes could be significant as the maximum expected earthquake magnitude within a 50-year period in the area is 7.5 Richter. Nevertheless, the risk of landslides and soil liquefaction is small.




Figure 4-16. Map Showing the Chance of any Level of Damaging Earthquake Shaking in 100 years from the 2023 50-State National Seismic Hazard Model (US National Seismic Hazard Model 2023)

4.5 Rock Mass Strength and Deformation Properties

4.5.1 Geological Strength Index (GSI)

The Geological Strength Index (GSI), first introduced by Hoek (1994), was developed to evaluate parameters for the Hoek-Brown strength criterion for rock masses (Hoek et al. 2002) as well as for estimating deformation modulus of a rock mass. The GSI is a complement to the Hoek-Brown strength criterion and can be used to estimate the parameters s , a , and m_b in the criterion.

GSI can be determined based on visual assessment of the rock mass and includes consideration of the degree of “blockiness” or mechanical interlock, as well as the discontinuity conditions following a procedure developed by Hoek and Marinos (2000). GSI can also be assessed using correlations with RMR and Q.

As there are no excavated exposures of the rock mass in the target cavern horizon, the GSI was defined based on correlations with the RMR and Q values determined from the core logging. RMR and Q include factors for in-situ and groundwater stresses, which are typically determined or

defined in the numerical modeling process (Hoek et al. 2000). Therefore, in order to consider only intrinsic rock and joint characteristics, modified Q' and RMR classifications were applied.

When RMR is used to estimate GSI, the last two parameters are adjusted so that a rating of 15 is assigned to groundwater and a rating of 0 for orientation (Hoek et al. 2000), which is known as the RMR_{89} term. The rating is then related to GSI using the following relationship when RMR_{89} is > 23 :

$$GSI = RMR_{89} - 5$$

For rock masses with $RMR_{89} < 23$, the RMR system cannot be used the Q-system should be used instead. When using the Q-system to estimate GSI, the joint water reduction factor (J_w) and the stress reduction factor (SRF) should both be set to 1 to obtain the modified tunneling quality index Q' . The following relationship can then be used to determine GSI (Hoek et al. 2000):

$$GSI = 9 \ln Q' + 44$$

Due to the “Fair” to “Good” quality of the rock mass (i.e. $RMR > 23$), only the RMR correlation was used for determining the respective GSI for each core run. The distribution of the calculated GSI values are provided in Figures 4-17 to 4-19.

The results for core holes ZEV-CH-01-23 and ZEV-CH-02-23 indicate that the GSI within the target cavern horizon ranges between 42 and 78 and the rock mass is anticipated to have a GSI of 59, on average. For core hole ZEV-CH-03-23, the GSI ranges between 41 and 67, with an average of 55.




Figure 4-17. GSI Ratings for Core Hole ZEV-CH-01-23




Figure 4-18. GSI Ratings for Core Hole ZEV-CH-02-23




Figure 4-19. GSI Ratings for Core Hole ZEV-CH-03-23

4.5.2 Hoek-Brown Criterion

Hoek et al (2002) proposed a method for determining estimates of the strength of jointed rock masses based on the assessment of the interlocking of rock blocks and the condition of the surfaces between the blocks. For most rocks of good to reasonable quality, in which the rock mass strength is controlled by tightly interlocking angular rock pieces, the Hoek-Brown failure criterion is defined by the following equation:

$$\sigma_1' = \sigma_3' + \sigma_c \left(m_b \frac{\sigma_3}{\sigma_c} + s \right)^{0.5}$$

Where σ_1' = maximum effective principal stress
 σ_3' = minimum effective principal stress
 σ_c = UCS of intact rock
 m_b = value of the constant m for the rock mass
 s = constant which depends upon the characteristics of the rock mass

For poor quality rock masses, in which the tight interlocking has been partially destroyed by shearing or weathering, the modified Hoek-Brown failure criterion is defined by the following equation:

$$\sigma'_1 = \sigma'_3 + \sigma_c \left(m_b \frac{\sigma_3}{\sigma_c} \right)^a$$

Where a = constant, which depends upon the characteristics of the rock mass

The relationships between m_b/m_i , s , and a and the GSI are as follows:

For $GSI > 25$ (Undisturbed rock masses)

$$m_b = m_i \exp \left(\frac{GSI - 100}{28 - 14D} \right)$$

$$s = \exp \left(\frac{GSI - 100}{9 - 3D} \right)$$

For $GSI < 25$ (Undisturbed rock masses)

$$a = 0.65 - \frac{GSI}{200}$$

Based on these relationships, four properties are required to use the Hoek-Brown criterion for estimating the strength and deformability of the rock mass. The four properties include the following:

- Uniaxial compressive strength of the intact rock, σ_{ci}
- Value of the Hoek-Brown constant m_i for the intact rock
- Value of the GSI for the rock mass
- Value of the disturbance factor, D

The uniaxial compressive strength of the intact rock as well as the GSI of the rock mass were previously discussed in the preceding sections, however the m_i term and the disturbance factor (D) are discussed below.

4.5.2.1 Definition of m_i

The m_i parameter is considered constant for a specific rock type and does not change with anisotropy direction (Saroglou and Tsiambaos 2008, and Saeidi et al. 2014). Saroglou et al. suggests that for an anisotropic rock, it is best determined by a set of triaxial compressive strength tests at various confining pressures on core samples. This represents the “true” intact strength with effects of anisotropy being removed as the sample will not fail structurally and will fail through the intact rock.

The triaxial tests ($\sigma_3 = 1,500$ and $2,500$ psi), uniaxial compressive strength tests, and average Brazilian tensile tests were used to define the Hoek-Brown strength envelope for the rock mass in the target cavern horizon (see Figure 4-20). The resulting m_i constant from a best fit line was determined to be 19.3. This result is consistent with the recommended range for coarse grained granites (20 ± 5) based on published values of m_i provided by Hoek and Marinos (2000).




Figure 4-20. Linear Regression Analysis for the Input and Derivation of m_i Constant

4.5.2.1 Disturbance Factor (D)

The disturbance factor, D , is a factor which depends on the degree of disturbance to the rock due to blast damage and stress relaxation around the excavation. The disturbance factor varies from 0 for undisturbed rock masses to 1 for very disturbed rock masses. It is important to note that the disturbance factor should only be applied to blast damaged zones and not to the entire rock mass. Applying the blast damage to the entire rock mass is inappropriate and results in overly conservative results.

Guidelines for estimating disturbance factor are provided by Hoek et al (2002) and are shown in Figure 4-21. For the purpose of this assessment, a disturbance factor of 0 has been assumed, which represents excellent quality-controlled blasting that results in minimal disturbance to the confined rock mass surrounding the excavation.

Appearance of rock mass	Description of rock mass	Suggested value of D
	Excellent quality controlled blasting or excavation by Tunnel Boring Machine results in minimal disturbance to the confined rock mass surrounding a tunnel.	$D = 0$
	Mechanical or hand excavation in poor quality rock masses (no blasting) results in minimal disturbance to the surrounding rock mass. Where squeezing problems result in significant floor heave, disturbance can be severe unless a temporary invert, as shown in the photograph, is placed.	$D = 0$ $D = 0.5$ No invert
	Very poor quality blasting in a hard rock tunnel results in severe local damage, extending 2 or 3 m, in the surrounding rock mass.	$D = 0.8$
	Small scale blasting in civil engineering slopes results in modest rock mass damage, particularly if controlled blasting is used as shown on the left hand side of the photograph. However, stress relief results in some disturbance.	$D = 0.7$ Good blasting $D = 1.0$ Poor blasting
	Very large open pit mine slopes suffer significant disturbance due to heavy production blasting and also due to stress relief from overburden removal. In some softer rocks excavation can be carried out by ripping and dozing and the degree of damage to the slopes is less.	$D = 1.0$ Production blasting $D = 0.7$ Mechanical excavation

Figure 4-21. Guidelines for Estimating Disturbance Factor (D) (Hoek et al. 2002)

4.5.2.2 Summary of Hoek-Brown Parameters

The Hoek-Brown parameters for the rock mass anticipated in the target cavern horizon were determined using the following values:

- GSI Range: 48 to 72
- UCS of Intact Rock Range: 10,000 to 24,000 psi
- m_i Parameter: 19.3
- Disturbance Factor, D : 0

The resulting Hoek-Brown parameters are summarized in Table 4-4.

Table 4-4. Hoek-Brown Parameters

Hoek-Brown Parameter	Typical Range	Representative Value
m_b	3.013 - 7.100	4.463
s	0.003 - 0.045	0.011
a	0.5	0.5

4.5.3 Mohr-Coulomb Criterion

Many geotechnical software programs are written in terms of the Mohr-Coulomb failure criterion, so it is necessary to determine equivalent angles of friction and cohesive strengths for each rock mass and stress range. Mohr-Coulomb parameters for the rock mass can be determined by using the following equations (Hoek, Carranza-Torres and Corkum, 2002):

$$\varphi' = \sin^{-1} \left(\frac{6am_b(s + m_b\sigma'_{3n})^{a-1}}{2(1+a)(2+a) + 6am_b(s + m_b\sigma'_{3n})^{a-1}} \right)$$

$$c' = \frac{\sigma_{ci}[(1+2a)s + (1-a)m_b\sigma'_{3n}](s + m_b\sigma'_{3n})^{a-1}}{(1+a)(2+a) \sqrt{1 + \left(\frac{6am_b(s + m_b\sigma'_{3n})^{a-1}}{((1+a)(2+a))} \right)}}$$

where $\sigma'_{3n} = \sigma'_{3max}/\sigma_{ci}$

The critical aspect of developing appropriate Mohr-Coulomb parameters is selecting the appropriate value of σ'_{3max} that is anticipated in the rock mass. Hoek-Brown suggests the following relationship for deep tunnels:

$$\frac{\sigma'_{3max}}{\sigma'_{cm}} = 0.47 \left(\frac{\sigma'_{cm}}{\gamma H} \right)^{-0.94}$$

where σ'_{cm} is the rock mass strength determined by the Hoek-Brown failure criterion, γ is the unit weight of the rock mass and H is the depth of the tunnel below the surface.

For the target cavern horizons, this relationship results in a σ'_{3max} range of between 1,200 and 1,500 psi for the nominal rock mass strengths determined at a unit weight of 166 pcf. This stress is considerably lower than the major horizontal stress measured through the in-situ stress testing. Hoek and Brown (2002) state that where the horizontal stress is higher than the vertical stress, the horizontal stress value should be used in place of γH . On this basis, a range of stresses between 2,000 and 2,500 psi were assumed for determining Mohr-Coulomb parameters.

4.5.3.1 Intact Mohr-Coulomb Parameters

The intact Mohr-Coulomb Parameters were calculated for the assumed stress range for intact rock (i.e. $GSI=100$, $m_b = m_i$, $a = 0.5$, and $s = 1$). Table 4-5 provides a summary of the Mohr-Coulomb parameters for intact rock for the various stresses.

Table 4-5. Intact Mohr-Coulomb Properties for Various Stresses

Depth (ft)	s_{3max} (psi)	Range of Anticipated Values		Range of Anticipated Values	
		Cohesion, C' (psi)	Friction Angle, f' (°)	Cohesion, C' (psi)	Friction Angle, f' (°)
2,000	2,032	1,758 - 3,555	51.2 - 55.6	2,724	54.2
2,100	2,126	1,780 - 3,578	50.9 - 55.4	2,747	53.9
2,200	2,222	1,804 - 3,600	50.6 - 55.2	2,770	53.7
2,300	2,318	1,827 - 3,623	50.3 - 55.0	2,793	53.5
2,400	2,412	1,850 - 3,646	50.1 - 54.8	2,819	53.3
2,500	2,506	1,873 - 3,669	49.8 - 54.6	2,840	53.0

4.5.3.1 Rock Mass Mohr-Coulomb Parameters

The Mohr-Coulomb properties were calculated for the assumed stress range for the rock mass in the target cavern horizon. Table 4-6 provides a summary of the Mohr-Coulomb parameters for an isotropic rock mass (i.e. $GSI = 48$ to 72 , $UCS = 10,000$ to $24,000$ psi, $m_i = 19.3$, and $D=0$).

Table 4-6. Rock Mass Mohr-Coulomb Properties for Various Stresses

Depth (ft)	s_{3max} (psi)	Range of Anticipated Values		Range of Anticipated Values	
		Cohesion, C' (psi)	Friction Angle, f' (°)	Cohesion, C' (psi)	Friction Angle, f' (°)
2,000	2,032	518 - 1,115	38.5 - 51.6	741	46.0
2,100	2,126	535 - 1,142	38.1 - 51.2	764	45.6
2,200	2,222	552 - 1,170	37.7 - 50.9	787	45.3
2,300	2,318	569 - 1,196	37.4 - 50.6	809	44.9
2,400	2,412	586 - 1,223	37.0 - 50.3	831	44.6
2,500	2,506	602 - 1,249	36.7 - 50.0	853	44.3

4.5.4 Rock Mass Elastic Modulus

The elastic modulus (E_{rm}) of the rock mass within the target cavern horizon was determined based on the following relationship (Hoek and Diederichs, 2006):

$$E_{rm} = E_i \left(0.02 + \frac{1 - \frac{D}{2}}{1 + e^{\left(\frac{(60+15D-GSI)}{11} \right)}} \right)$$

where E_i is the intact rock modulus, which was determined using the modulus ratio (MR) (ratio of elastic modulus and unconfined compressive strength) developed from UCS testing and the compressive strength of the rock using the following equation:

$$E_i = (MR)\sigma_{ci}$$

The average ratio of the laboratory testing results of the UCS and Young's modulus of the intact rock within the target cavern horizon was determined to be 515. This is consistent with published recommended guideline value ranges of between 300 and 550 for granite (Deere, 1968). The rock mass elastic modulus was then determined using the following values:

- GSI Range: 48 to 72
- UCS of Intact Rock Range: 10,000 to 24,000 psi
- Modulus Ratio (MR): 515
- Disturbance Factor, D : 0

The resulting rock mass modulus values are summarized in Table 4-7.

Table 4-7. Rock Mass Modulus

Rock Mass Modulus	Typical Range (psi)	Representative Value (psi)
E_m	1,071 - 6,610	2,675

4.5.5 Joint Stiffness

The normal and shear stiffness of the joints in the target cavern horizon can be estimated from the rock mass modulus, the intact rock modulus, and the mean joint spacing (Ingrad and Kraushaar, 1960). It is assumed that the deformability of the overall mass is due to both elastic deformation of the intact rock mass and joint deformation. The following equation simplifies the rock mass into a system of two springs in series:

$$\frac{1}{E_{rm}} = \frac{1}{E_i} + \frac{1}{k_n L}$$

where E_{rm} is the rock mass modulus, E_i is the intact rock modulus, k_n is the joint normal stiffness, and L is the mean joint spacing. It is assumed that there is only one joint set oriented normal to the applied loading.

The same methodology can be followed to estimate the shear stiffness of the joints using the following equation:

$$\frac{1}{G_m} = \frac{1}{G_i} + \frac{1}{k_s L}$$

where G is the shear modulus and k_s is the joint shear stiffness.

The following relationship is used to relate E to G :

$$E = 2(1 + \nu)G$$

Based on the Young's modulus determined for the intact rock within the target cavern horizon through laboratory testing, the Young's modulus of the rock mass determined through the rock mass characterization, and an assumed mean joint spacing ranging between 0.3 and 1.3 ft, the joint normal and shear stiffnesses were calculated. A summary of the joint normal and shear stiffness values are provided in Table 4-8.

Table 4-8. Summary of Joint Normal Stiffness and Joint Shear Stiffness

Parameter	Range of Anticipated Values (psi/ft)	Representative Value (psi/ft)
k_n	$9.88 \times 10^6 - 3.95 \times 10^7$	2.32×10^7
k_s	$3.95 \times 10^6 - 1.58 \times 10^7$	9.30×10^6

4.5.6 Rock Mass Dilation

The rock mass dilation angle was not directly measured during laboratory testing, however, recommendations from Hoek (2001) can be used to estimate it. For average quality rock masses, the dilation angle can be estimated to be equal to the friction angle of the rock mass divided by eight. Based on the Mohr-Coulomb parameters determined above for various cavern depths, the rock mass dilation angle is estimated to range between 5.5 and 5.8 degrees.

5 CONCLUSIONS

Geological and geotechnical data were collected from three deep subsurface core holes at the Willow Rock site. The rock core was logged, and samples were selected for a full suite of geomechanical laboratory testing. Packer testing was carried out at key intervals to determine hydraulic conductivity, and each hole was surveyed with downhole geophysical tools. In one of the core holes, IST2D overcore testing was carried out to measure horizontal stress directions and magnitudes. This data was used to develop a preliminary geotechnical model for the proposed A-CAES cavern construction.

These geotechnical design parameters were developed and presented within this report to support the pre-FEED study for cavern construction. These values should be reevaluated as new information is collected from the ongoing core drilling program, and as additional information becomes available during project design.

Consistent with the information outlined in this report, it is Agapito's assessment that the geotechnical conditions anticipated in the target cavern horizon are conducive for cavern construction.

6 REFERENCES

- Ask, M.V.S., Ask, D. and Christiansson, R. (2006) Detection of borehole breakouts at Forsmark site, Sweden. In-situ Rock Stress - Measurement, Interpretation and Application, Lu, Li, Kjølholt and Dhale (editors), Taylor & Francis, London, pp. 79–86.
- Babcock, E.A. (1978) Measurement of subsurface fractures from dipmeter logs: AAPG Bulletin, 62(7), pp. 111–1126. Reprinted 1990 in Foster, N.H. and Beaumont, E.A. (editors) Formation evaluation II – log interpretation: AAPG Treatise of Petroleum Geology Reprint Series 17, pp. 457–472.
- Barton, N., Lien, R., and Lunde, J. (1974). “Engineering classification of rock masses for the design of tunnel support”. Rock Mech. 6. pp. 189-236.
- Bieniawski, Z.T. (1976). ”Rock mass classifications in rock engineering”. *Proc. of Symposium on Exploration for Rock Engineering*, Belkema, Rotterdam, Vol. 1, pp 97-106.
- Bieniawski, Z. T. (1989). Engineering Rock Mass Classifications. J.W. Wiley & Sons. New York.
- Bell, J.S. and Gough, D.I. (1979) Northeast-southwest compressive stress in Alberta: Evidence from oil wells. Earth and Planetary Science Letters 45(2), pp. 475–482.
- Deere D.U. 1968. Chapter 1: Geological considerations. In Rock Mechanics in Engineering Practice (eds. Stagg K.G. and Zienkiewicz, O.C.), 1-20. London: John Wiley and Sons.
- Deere, D. U., and D. W. Deere (1988), “The Rock Quality Designation (RQD) Index in Practice,” *Rock Classification Systems for Engineering Purposes*, ASTM STP 984, Louis Kirkaldie Ed., American Society for Testing and Materials, Philadelphia, 1988, pp. 91-101.
- Dibblee, Jr., T. W. (1963), Geology of the Willow Springs and Rosamond Quadrangles, Geological Survey Bulletin 1089-C, Washington, DC: US Government Printing Office, 117 pp.
- Dibblee, Jr., T. W. (1967), Areal Geology of the Western Mojave Desert, Plate 1 (West-Half), Geological Survey Professional Paper 522, Washington, DC: US Government Printing Office, 1 sheet.
- Dowding, C. H. and A. Rozen (1978), “Damage to Rock Tunnels from Earthquake Shaking,” *J. Geotech. Eng. Div.*, 104(GT2):175–191.
- Fowler, MJ & Weir, FM 2008, 'The Use of Borehole Breakout for Geotechnical Investigation of an Open Pit Mine', in Y Potvin, J Carter, A Dyskin & R Jeffrey (eds), *SHIRMS 2008: Proceedings of the First Southern Hemisphere International Rock Mechanics Symposium*, Australian Centre for Geomechanics, Perth, pp. 541-550.
- Gray, I. (2000), “The Measurement and Interpretation of Stress,” *Bowen Basin Symposium on Seam Gas*, pp. 321–324.

- Gray, I., Zhao, X., and Liu, L. (2018) Mechanical Properties of Coal Measure Rocks Containing Fluids at Pressure, Proceedings of the 18th Coal Operators' Conference, Mining Engineering, University of Wollongong, 195-204.
- Hoek, E. (1994). "Strength of rock and rock masses". *ISRM News Journal*. 2 (2). Pp. 4-16.
- Hoek, E., Carranza-Torres C., Corkum B. (2002), "Hoek-Brown criterion – 2002 Edition", Proc. NARMS-TAC Conference, Toronto, 2002, 1, 267-273.
- Hoek, E. and Marinos, P. (2000) "Predicting Tunnel Squeezing". *Tunnels and Tunneling International*. Part 1 – November 2000, Part 2 – December 2000.
- Hoek, E., Kaiser, P.K., and Bawden, W.F. (2000). Support of Underground Excavations in Hard Rock. A.A. Balkema. Rotterdam.
- Hoek, E. (2001) "Rock mass properties for underground mines". *Underground Mining Methods: Engineering Fundamentals and International Case Studies*. (Edited by W. A. Hustrulid and R.L. Bullock), Littleton, Colorado: Society for Mining, Metallurgy, and Exploration (SME) 2001.
- Hoek, E. and Diederichs, M.S. (2006). "Empirical estimation of rock mass modulus". *International Journal of Rock Mechanics and Mining Sciences*. 43. Pp. 2013-215.
- Ingard, U and Kraushaar, W.L. (1960), *Introduction to Mechanics, Matter, and Waves*. Addison Wesley, London p76.
- ISRM (2007), The Complete ISRM Suggested Methods for Rock Classification, Testing and Monitoring: 1974-2006 (eds R Ulusay & JA Hudson). ISRM Turkish National Group, Ankara, Turkey.
- Jaramillo, C. A. (2017), "Impact of Seismic Design on Tunnels in Rock – Case Histories," *Underground Space*, Vol. 2, pp. 106–114.
- Marinos. P., and Hoek, E. (2000) "GSI: A geologically friendly tool for rock mass strength estimation". *Proc. GeoEng 2000 Conference*, Melbourne. 1422-1442.
- McGarr, A., M. D. Zoback, and T. C. Hanks (1982), "Implications of an Elastic Analysis of In Situ Stress Measurements near the San Andreas Fault," *J. Geophys. Res.*, 87(B9):7797–7806.
- Plumb, R.A. (1989) Fracture patterns associated with incipient borehole breakouts. *Rock at Great Depth*, V. Maury and D. Fourmantaux (editors), 2, Balkema, Rotterdam, pp. 761–768.
- Plumb, R.A. and Hickman, S.H. (1985) Stress-induced borehole elongation: A comparison between the four-arm dipmeter and the borehole televiwer in the Auburn Geothermal well. *Journal of Geophysical Research* 90(B7), pp. 5513–5522.

- Quiñones-Rozo, C., (2010), Lugeon test interpretation, revisited, in: Collaborative Management of Integrated Watersheds, US Society of Dams, 30th Annual Conference, 2010, pp. 405–414.
- Saeidi, O., Rasouli, V., Vaneghi, R.G., Gholami, R., and Torabi, S.R. (2014). “A modified failure criterion for transversely isotropic rocks”. *Geoscience Frontiers*. 5. Pp. 215-225.
- Saraglou, H. and Tsiambaos, G. (2008). “Modified Hoek-Brown failure criterion for anisotropic intact rock” *International Journal of Rock Mechanics and Mining Sciences*. 45. Pp. 223-234.
- Sharma, S. and W. R. Judd (1991), “Underground Opening Damage from Earthquakes,” *Engineering Geology*, Vol. 30, pp. 263-276.
- Yeh and Associates, Inc (2023). Geotechnical Data Report. Zevsar Energy Storage Project Seirra Highway and Dawn Road, Kern County, California. Yeh Project No.: 223-202. November 17, 2023.
- Zajac, B.J. and Stock, J.M. (1997) Using borehole breakouts to constrain the complete stress tensor: Results from the Sijan Deep Drilling Project and offshore Santa Maria Basin, California. *Journal of Geophysical Research* 102(B5), pp. 10083–10100.
- Zoback, M.L. and Zoback, M.D. (1980) State of stress in the conterminous United States. *Journal of Geophysical Research* 85(B11), pp. 6113–6156.
- Zoback, M.D., Moos, D., Mastin, L. and Anderson, R.N. (1985) Well bore breakouts and in situ stress. *Journal of Geophysical Research* 90, pp. 5523–5530

APPENDIX A

GEOTECHNICAL LOGS



CLIENT: Lane Power & Energy Solutions

SURFACE ELEVATION (ft): 2560

PROJECT No: 951-20

PROJECT: Hydrostor Zevsar

NORTHING: 2153552.632

DATE: 3/17/2023 - 5/19/2023

PROJECT LOCATION: Rosamod, CA

EASTING: 6514916.08

DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
5 2555																					
10 2550																					
15 2545																					
20 2540																					
25 2535																					
30 2530																					

BORING TYPE: HQ3

DRILLER: CruX

LOGGED BY: Chris Messenger

HOLE DEPTH (ft): 3167

WATER OBSERVATIONS: 1902 ft, 2592 ft

CASING: HW to 71 ft

REMARKS: _____

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type <u> </u>)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions

SURFACE ELEVATION (ft): 2560

PROJECT No: 951-20

PROJECT: Hydrostor Zevsar

NORTHING: 2153552.632

DATE: 3/17/2023 - 5/19/2023

PROJECT LOCATION: Rosamod, CA

EASTING: 6514916.08

DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
40 2520																					
45 2515																					
50 2510																					
55 2505																					
60 2500																					
65 2495																					

BORING TYPE: HQ3

DRILLER: CruX

LOGGED BY: Chris Messenger

HOLE DEPTH (ft): 3167

WATER OBSERVATIONS: 1902 ft, 2592 ft

CASING: HW to 71 ft

REMARKS: _____

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type <u> </u>)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)

CLIENT: Lane Power & Energy Solutions

SURFACE ELEVATION (ft): 2560

PROJECT No: 951-20

PROJECT: Hydrostor Zevsar

NORTHING: 2153552.632

DATE: 3/17/2023 - 5/19/2023

PROJECT LOCATION: Rosamod, CA

EASTING: 6514916.08

DIP/AZIMUTH: -90 /

EL	DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)			Discontinuities		Sampling & In Situ Testing					
			Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard		0.05	0.25	0.50	2.50	5.00	B - Bedding	J - Joint	Type	Core Rec. %	RQD %	Test Results & Comments
																					S - Shear	F - Fault				
	71	QTZ MONZONITE, medium - coarse grained, white to light gray, phaneritic, biotite/muscovite phenocrysts and large K-spar crystals																								
		From 74' to 82': Large biotite crystals																		C	100	80				
'2485'	75																		77.85': 3°-5° Planar							
		From 82' to 86': Chlorite																	From 81' to 82': Planar irregular							
																			From 83.67' to 84.62': 30°-42° Angled-slickensides	C	100	68				
		From 86' to 96': Breaking down into clays																	85.24': 45°							
'2475'	85																		89': 80°-82° Rev. fracture							
																			89.9': Planar							
'2470'	90																		91.45': Planar							
																			92': Planar							
																			93.15': Planar	C	85	64				
		From 96' to 101': Chalky																	94.45': 10° Planar							
'2465'	95																									
	97	CORE LOSS																								
	98.5																									
'2460'	100																		99.85': 45° Joint fracture, J.							
																			From 100' to 101': 38° Joint fracture, J.							
																			102': J. at 40°							
																			102.67': J. at 22°	C	100	82				
																			103.67': J. at 17°							

BORING TYPE: HQ3

DRILLER: Crux

LOGGED BY: Chris Messenger

HOLE DEPTH (ft): 3167

WATER OBSERVATIONS: 1902 ft, 2592 ft

CASING: HW to 71 ft

REMARKS:

SAMPLING & IN SITU TESTING LEGEND			
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)
		SLK	Slake durability test (Type _____)
		TRI	Triaxial stress test (psi)
		UCS	Uniaxial stress test (psi)

(Continued Next Page)

CLIENT: Lane Power & Energy Solutions

SURFACE ELEVATION (ft): 2560

PROJECT No: 951-20

PROJECT: Hydrostor Zevsar

NORTHING: 2153552.632

DATE: 3/17/2023 - 5/19/2023

PROJECT LOCATION: Rosamod, CA

EASTING: 6514916.08

DIP/AZIMUTH: -90 /

[illegible]

BORING TYPE: HQ3

DRILLER: Crux

LOGGED BY: Chris Messenger

HOLE DEPTH (ft): 3167

WATER OBSERVATIONS: 1902 ft, 2592 ft

CASING: HW to 71 ft

REMARKS:

SAMPLING & IN SITU TESTING LEGEND			
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)
		SLK	Slake durability test (Type _____)
		TRI	Triaxial stress test (psi)
		UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions

SURFACE ELEVATION (ft): 2560

PROJECT No: 951-20

PROJECT: Hydrostor Zevsar

NORTHING: 2153552.632

DATE: 3/17/2023 - 5/19/2023

PROJECT LOCATION: Rosamod, CA

EASTING: 6514916.08

DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
	From 140' to 207': Biotite/chlorite																				
145																		C	100	95	
150																		C	100	86	
155																		C	100	86	
160																		C	100	86	
165																		C	100	86	
170																		C	100	86	

From 163' to 164':
Multiple planar fractures
32°-41°

171.25': Planar

172': Planar irregular

BORING TYPE: HQ3

DRILLER: Crux

LOGGED BY: Chris Messenger

HOLE DEPTH (ft): 3167

WATER OBSERVATIONS: 1902 ft, 2592 ft

CASING: HW to 71 ft

REMARKS: _____

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type <u> </u>)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
WL	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2560
NORTHING: 2153552.632
EASTING: 6514916.08

PROJECT No: 951-20
DATE: 3/17/2023 - 5/19/2023
DIP/AZIMUTH: -90 /

EL	DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities	Sampling & In Situ Testing																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																				
			Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard				B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																															

BORING TYPE: HQ3
HOLE DEPTH (ft): 3167
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 1902 ft, 2592 ft

LOGGED BY: Chris Messenger
CASING: HW to 71 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type ___)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
WL	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)

CLIENT: Lane Power & Energy Solutions

SURFACE ELEVATION (ft): 2560

PROJECT No: 951-20

PROJECT: Hydrostor Zevsar

NORTHING: 2153552.632

DATE: 3/17/2023 - 5/19/2023

PROJECT LOCATION: Rosamod, CA

EASTING: 6514916.08

DIP/AZIMUTH: -90 /

[illegible]

BORING TYPE: HQ3

DRILLER: Crux

LOGGED BY: Chris Messenger

HOLE DEPTH (ft): 3167

WATER OBSERVATIONS: 1902 ft, 2592 ft

CASING: HW to 71 ft

REMARKS:

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type _____)
W	Water seep	PL(A)	Point load axial test (s(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test (s(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions

SURFACE ELEVATION (ft): 2560

PROJECT No: 951-20

PROJECT: Hydrostor Zevsar

NORTHING: 2153552.632

DATE: 3/17/2023 - 5/19/2023

PROJECT LOCATION: Rosamod, CA

EASTING: 6514916.08

DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
250	From 252' to 267': Biotite/chlorite present															245': Planar					
255																248.1': Planar					
260																249': Planar					
265																249.62': Planar					
270																250.9': 41° NW-SE					
275	From 267' to 270': Increase in chlorite															From 252' to 267': Fracture jointing					
																255.9': 42° Planar					
																From 256' to 257': 4 J. at 24°-30°					
																258.7': Planar					
																258.8': Angled biotite/chlorite bands 11°-30° - shear/slip					
	From 267' to 270': Increase in chlorite															259': 32° band					
																260': Planar					
																261.3': Planar					
																262.8': 11°					
																From 263' to 264': 3 Planar fractures					
	From 267' to 270': Increase in chlorite															From 267' to 270': 2 J., 17° planar					
																270': Shear/slip J. 11°-32°					
																273': 3 J.					
	From 277' to 280': Increase in plagioclase feldspar															From 278' to 281': 12 Planar-J. fractures					

BORING TYPE: HQ3

DRILLER: Crux

LOGGED BY: Chris Messenger

HOLE DEPTH (ft): 3167

WATER OBSERVATIONS: 1902 ft, 2592 ft

CASING: HW to 71 ft

REMARKS: _____

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type ___)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
WL	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions

SURFACE ELEVATION (ft): 2560

PROJECT No: 951-20

PROJECT: Hydrostor Zevsar

NORTHING: 2153552.632

DATE: 3/17/2023 - 5/19/2023

PROJECT LOCATION: Rosamod, CA

EASTING: 6514916.08

DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
284	CORE LOSS																				
285																					
289																		C	75	31	
290																					
294.4	CORE LOSS																				
295																					
298	QTZ MONZONITE, medium grained, white to light gray, porphyritic, increase in quartz and plagioclase content																	C	100	87	
300																					
305	From 302' to 303': Increase in plagioclase crystals																				
310																		C	100	90	

BORING TYPE: HQ3

DRILLER: Crux

LOGGED BY: Chris Messenger

HOLE DEPTH (ft): 3167

WATER OBSERVATIONS: 1902 ft, 2592 ft

CASING: HW to 71 ft

REMARKS:

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type ___)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)

CLIENT: Lane Power & Energy Solutions

SURFACE ELEVATION (ft): 2560

PROJECT No: 951-20

PROJECT: Hydrostor Zevsar

NORTHING: 2153552.632

DATE: 3/17/2023 - 5/19/2023

PROJECT LOCATION: Rosamod, CA

EASTING: 6514916.08

DIP/AZIMUTH: -90 /

[illegible]

BORING TYPE: HQ3

DRILLER: Crux

LOGGED BY: Chris Messenger

HOLE DEPTH (ft): 3167

WATER OBSERVATIONS: 1902 ft, 2592 ft

CASING: HW to 71 ft

REMARKS:

SAMPLING & IN SITU TESTING LEGEND			
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)
		SLK	Slake durability test (Type ___)
		TRI	Triaxial stress test (psi)
		UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2560
NORTHING: 2153552.632
EASTING: 6514916.08

PROJECT No: 951-20
DATE: 3/17/2023 - 5/19/2023
DIP/AZIMUTH: -90 /

EL	DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities	Sampling & In Situ Testing																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																														
			Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard				B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																									
		From 361' to 391': Increase in plagioclase feldspar, crystals of feldspar and diorite	Fr																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																													

BORING TYPE: HQ3
HOLE DEPTH (ft): 3167
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 1902 ft, 2592 ft

LOGGED BY: Chris Messenger
CASING: HW to 71 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type __)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2560
NORTHING: 2153552.632
EASTING: 6514916.08

PROJECT No: 951-20
DATE: 3/17/2023 - 5/19/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
390																385': Wedge rev angle 38°-42°					
395																386': 49° Planar					
400																From 387' to 397': Broken fractured, decomposed weathered, 20-30 fractures		C	100	56	
405																398.9': Planar		C	95	80	
410																401.8': Planar					
415																From 402' to 417': Increased weathered decomposed (at 404.5)		C	100	73	
417	CORE LOSS															From 418' to 432': Weathered decomposed softened					
418																		C	90	67	

BORING TYPE: HQ3
HOLE DEPTH (ft): 3167
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 1902 ft, 2592 ft

LOGGED BY: Chris Messenger
CASING: HW to 71 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type ___)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
WL	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions

SURFACE ELEVATION (ft): 2560

PROJECT No: 951-20

PROJECT: Hydrostor Zevsar

NORTHING: 2153552.632

DATE: 3/17/2023 - 5/19/2023

PROJECT LOCATION: Rosamod, CA

EASTING: 6514916.08

DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
425 2135																					
430 2130																		C	100	49	
432	QTZ MONZONITE, light gray to white, phaneritic, increase in plagioclase feldspar, porphyritic biotite crystals, quartz feldspar, biotite, muscovite with trace amounts of chlorite and epidote															From 432' to 434.9': Multiple fractures and orientations, crumbled					
435 2125																435.4': 47° Planar 435.7': 90° S.					
440 2120																From 437' to 442': Fragmented 45°-23°-17° planar irregular, 21 total breaks in this 5' span		C	100	31	
445 2115																444.62': Planar irregular along K feldspar contacts 444.9': 17° Planar					
450 2110																From 445.1' to 445.67': 2 47° J., 2 45° J., 45° wedge, 32° wedge 446': 31° Planar 446.6': 18° Planar From 449' to 449.72': Vertical S. at 90° 450': 48° Planar From 451.1' to 452': Vertical S. at 90° and multiple perpendicular fractures		C	100	67	

BORING TYPE: HQ3

DRILLER: Crux

LOGGED BY: Chris Messenger

HOLE DEPTH (ft): 3167

WATER OBSERVATIONS: 1902 ft, 2592 ft

CASING: HW to 71 ft

REMARKS: _____

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type _____)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
WL	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2560
NORTHING: 2153552.632
EASTING: 6514916.08

PROJECT No: 951-20
DATE: 3/17/2023 - 5/19/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
460	QTZ MONZONITE, light gray-white-green														0.05	From 452' to 454.7': Multiple fractures (11)					
462															0.25	From 456' to 458': Crumbled					
465															0.50	458.7': 42° Irregular		C	100	61	
470															2.50	459.7': 48° Irregular					
475															5.00	461': 11° Irregular					
480																		C	100	22	
485																		C	100	50	
																		C	100	61	

BORING TYPE: HQ3
HOLE DEPTH (ft): 3167
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 1902 ft, 2592 ft

LOGGED BY: Chris Messenger
CASING: HW to 71 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type ___)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
WL	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2560
NORTHING: 2153552.632
EASTING: 6514916.08

PROJECT No: 951-20
DATE: 3/17/2023 - 5/19/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
492	QTZ MONZONITE, white to light gray, phaneritic, with biotite hornblende porphyry, trace amounts of chlorite and epidote, mineral concentrations medium-high in qtz, plagioclase feldspar, biotite and oligoclase																				
495																					
500																					
505																					
510																					
515	QTZ MONZONITE, light gray to white, massive phaneritic, with biotite mica porphyry, trace amounts of hornblende + muscovite mica and pyroxene																				
520																					
522																					
524	CORE LOSS																				
524.7																					

BORING TYPE: HQ3
HOLE DEPTH (ft): 3167
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 1902 ft, 2592 ft

LOGGED BY: Chris Messenger
CASING: HW to 71 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type __)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions

SURFACE ELEVATION (ft): 2560

PROJECT No: 951-20

PROJECT: Hydrostor Zevsar

NORTHING: 2153552.632

DATE: 3/17/2023 - 5/19/2023

PROJECT LOCATION: Rosamod, CA

EASTING: 6514916.08

DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
530	From 532' to 534': Plagioclase feldspar present															undulating surface J. fracture					
535																From 525' to 526': J. rubble					
536	From 536' to 537': Moving towards granite, increase in K feldspar															From 529' to 530': Increased veining		C	100	32	
539	GRANITE/GRANODIORITE, pink to light gray, phaneritic, increase in K feldspar, trace amounts of hornblende + muscovite and chlorite															From 531' to 531.6': Rubble, at J. (altered - soft)					
540	QTZ MONZONITE, light gray to white, phaneritic, increase in plagioclase and biotite/hornblende, Plagioclase-orthoclase feldspar, quartz and biotite, with trace amounts of muscovite + hornblende + pyroxene 'alteration' (chlorite/epidote)															From 532' to 534': Large 25" vein, intrusive plagioclase feldspar infill					
544	From 544' to 560.5': Biotite/chlorite present															From 533.6' to 534': 48° Undulating J. S. fracture, slickenside					
545	CORE LOSS															From 536' to 537': Rubble					
550																From 537' to 539': 6 planar fractures		C	94	67	
555																540.6': 47° smooth microfractures healed					
																541': 30° smooth					
																541.3': J. at 41°					
																542.9': 29° Undulating - smooth					
																543.67': Rough S. at 68°					
																From 544' to 560.5': Moderate veining, biotite/chlorite infill strongly detected					
																From 547' to 557': Planar undulating - rough - smooth		C	100	51	
																From 557' to 558': 4 Planar fractures					
																From 560.5' to 568.5':		C	90	79	

BORING TYPE: HQ3

DRILLER: Crux

LOGGED BY: Chris Messenger

HOLE DEPTH (ft): 3167

WATER OBSERVATIONS: 1902 ft, 2592 ft

CASING: HW to 71 ft

REMARKS: _____

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type _____)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2560
NORTHING: 2153552.632
EASTING: 6514916.08

PROJECT No: 951-20
DATE: 3/17/2023 - 5/19/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
	From 560.5' to 568.5': Biotite, chlorite, feldspar																				
562	CORE LOSS																				
563																					
565																					
570																					
575																					
580																					
585																					
590																					

BORING TYPE: HQ3
HOLE DEPTH (ft): 3167
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 1902 ft, 2592 ft

LOGGED BY: Chris Messenger
CASING: HW to 71 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type ___)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2560
NORTHING: 2153552.632
EASTING: 6514916.08

PROJECT No: 951-20
DATE: 3/17/2023 - 5/19/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
600	From 601' to 603': Soft-medium chlorite present															smooth					
605	From 605.3' to 606.3': Pegmatite/Qtz feldspar															From 590' to 592': Decomposed soft-medium					
610																From 593' to 593.9': Undulating 74° rough/smooth chlorite/biotite infill		C	100	82	
615																594.75': 22° J. NE-SW, 29° J. NW-SE					
620																595.33': Soft, brittle					
625																596': Planar irregular, rough					
627	QTZ MONZONITE, light gray to white, phaneritic, with biotite/hornblende porphyry, trace amounts of muscovite + chlorite + epidote + pyroxene															598.67': Planar smooth					
																604': S. at 88° rough/stepped shear fracture		C	100	93	
																613': 80° S. fracture undulating/smooth					
																614.4': Undulating/smooth					
																From 615' to 620.5': Brittle, low to moderate defects					
																		C	100	87	
																624.25': 45° planar smooth					
																625.25': 32° planar smooth					
																From 627' to 629': 45° inundated, smooth, J. fractures (6)					
																		C	100	91	

BORING TYPE: HQ3
HOLE DEPTH (ft): 3167
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 1902 ft, 2592 ft

LOGGED BY: Chris Messenger
CASING: HW to 71 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type ___)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
WL	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions

SURFACE ELEVATION (ft): 2560

PROJECT No: 951-20

PROJECT: Hydrostor Zevsar

NORTHING: 2153552.632

DATE: 3/17/2023 - 5/19/2023

PROJECT LOCATION: Rosamod, CA

EASTING: 6514916.08

DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)		Discontinuities		Sampling & In Situ Testing			
								Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard				B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
			Fr	SA	MA	HA		CA														
635																	From 631.25' to 632': Rough-stepped wedge, slickenside at 631.67'					
																	632.4': 17° stepped smooth					
																	633': 45° planar smooth					
																	From 633.4' to 634.1': Vertical 82° shear with slickenside (stepped)					
																	From 634' to 635.5': inundated smooth, then inundated S. 88°-90° fracture					
640																	637.1': Planar		C	100	50	
																	638.3': Planar					
																	640': Planar					
																	641': 45° planar smooth					
																	From 642' to 647': 20°-45° Planar inundated fracture, 12 J.					
645																						
																	647.25': Planar					
																	647.9': Planar		C	100	81	
650																	From 651' to 651.8': S. at 80°, planar smooth fracture					
																	From 653.2' to 655': 4 J.					
655																	655.7': Planar chlorite veins					
																	From 656' to 656.2': Rubble/K fedslpar intrusion					
																	From 658' to 658.75': 82° Vertical S. undulating smooth		C	100	52	
660																	659': Planar					
																	661': Planar					

BORING TYPE: HQ3

DRILLER: Crux

LOGGED BY: Chris Messenger

HOLE DEPTH (ft): 3167

WATER OBSERVATIONS: 1902 ft, 2592 ft

CASING: HW to 71 ft

REMARKS: _____

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type _____)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
L	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions

SURFACE ELEVATION (ft): 2560

PROJECT No: 951-20

PROJECT: Hydrostor Zevsar

NORTHING: 2153552.632

DATE: 3/17/2023 - 5/19/2023

PROJECT LOCATION: Rosamod, CA

EASTING: 6514916.08

DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
670																665': Planar From 665.25' to 668.5': Rubble J. fractures		C	100	64	
675																671': Planar 672.25': Planar 0° smooth 672.6': Planar 0° smooth 673.1': Planar 0° smooth					
680																675.82': Planar 0° From 677' to 680.25': 12 Planar 0°, 2 Planar-smooth 42°, altered From 678' to 687': Minor to moderate veining		C	100	40	
685																From 685.38' to 687': Vertical S. inundated smooth with 40°-45° J. fractures (4)					
690																687.9': Planar 688.6': Planar From 690.2' to 690.9': Stepped S. rough 691': S. at 77° smooth/planar 693.25': Planar		C	100	72	
695																695.7': Planar From 697' to 700': 3 Planar 0°, defected, minor veining		C	100	84	

BORING TYPE: HQ3

DRILLER: Crux

LOGGED BY: Chris Messenger

HOLE DEPTH (ft): 3167

WATER OBSERVATIONS: 1902 ft, 2592 ft

CASING: HW to 71 ft

REMARKS:

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type <u> </u>)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2560
NORTHING: 2153552.632
EASTING: 6514916.08

PROJECT No: 951-20
DATE: 3/17/2023 - 5/19/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
705																					
710																					
715																					
720																					
725																					
730																					
	From 732' to 747': Chlorite/epidote present																				

BORING TYPE: HQ3
HOLE DEPTH (ft): 3167
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 1902 ft, 2592 ft

LOGGED BY: Chris Messenger
CASING: HW to 71 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type ___)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2560
NORTHING: 2153552.632
EASTING: 6514916.08

PROJECT No: 951-20
DATE: 3/17/2023 - 5/19/2023
DIP/AZIMUTH: -90 /

EL	DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)		Discontinuities		Sampling & In Situ Testing				
			Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard		B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments			
		From 747' to 762': Chlorite present																						
	740																			C	100	10		
	745																							
	750																			C	100	53		
	755																							
	760																			C	100	58		
	765																							
	769.2																							

BORING TYPE: HQ3
HOLE DEPTH (ft): 3167
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 1902 ft, 2592 ft

LOGGED BY: Chris Messenger
CASING: HW to 71 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type ___)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
WL	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2560
NORTHING: 2153552.632
EASTING: 6514916.08

PROJECT No: 951-20
DATE: 3/17/2023 - 5/19/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
775	QTZ MONZONITE, light gray to white, massive phaneritic																				
777																					
780																		C	100	80	
785																					
790																		C	100	19	
795																					
800																		C	100	12	

BORING TYPE: HQ3
HOLE DEPTH (ft): 3167
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 1902 ft, 2592 ft

LOGGED BY: Chris Messenger
CASING: HW to 71 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type __)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
L	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2560
NORTHING: 2153552.632
EASTING: 6514916.08

PROJECT No: 951-20
DATE: 3/17/2023 - 5/19/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
810																		C	100	85	
815																					
820																		C	100	56	
825																					
830																		C	95	46	
835																					
836.5	CORE LOSS																	C	70	12	

BORING TYPE: HQ3
HOLE DEPTH (ft): 3167
REMARKS: _____

DRILLER: Crux
WATER OBSERVATIONS: 1902 ft, 2592 ft

LOGGED BY: Chris Messenger
CASING: HW to 71 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type ____)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
WL	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2560
NORTHING: 2153552.632
EASTING: 6514916.08

PROJECT No: 951-20
DATE: 3/17/2023 - 5/19/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
840	QTZ MONZONITE, light gray to white, massive phaneritic, with biotite porphyry phenocrysts, trace muscovite, pyroxene, chlorite, epidote, hornblende																				
845																					
850																		C	100	46	
852																					
855																					
860																		C	100	76	
865																					
870																		C	100	71	

BORING TYPE: HQ3
HOLE DEPTH (ft): 3167
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 1902 ft, 2592 ft

LOGGED BY: Chris Messenger
CASING: HW to 71 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type _____)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
L	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2560
NORTHING: 2153552.632
EASTING: 6514916.08

PROJECT No: 951-20
DATE: 3/17/2023 - 5/19/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
880																					
885																					
890																					
895																					
900																					
905																					

BORING TYPE: HQ3
HOLE DEPTH (ft): 3167
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 1902 ft, 2592 ft

LOGGED BY: Chris Messenger
CASING: HW to 71 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
L	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2560
NORTHING: 2153552.632
EASTING: 6514916.08

PROJECT No: 951-20
DATE: 3/17/2023 - 5/19/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities	Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard				B - Bedding S - Shear	J - Joint F- Fault	Type	Core Rec. %
915 1645	From 919' to 927': Increased biotite/chlorite QTZ MONZONITE, light gray to white, phaneritic, massive, with biotite porphyry crystals, trace pyroxene, hornblende, muscovite														910.1': Planar From 911' to 912': Rubble					
920 1640															From 915' to 920': J. fractures, inundated/smooth rubble, increased fractures, moderate veining					
925 1635															From 919' to 927': Moderate to mild veining	C	100	27		
930 1630															From 929' to 942': Fracturing along biotite/chlorite veins, moderate veining	C	100	67		
935 1625																				
940 1620																C	100	24		
															From 942' to 957': Moderate to severe veining					

BORING TYPE: HQ3
HOLE DEPTH (ft): 3167
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 1902 ft, 2592 ft

LOGGED BY: Chris Messenger
CASING: HW to 71 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type ___)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)



CLIENT: Lane Power & Energy Solutions

SURFACE ELEVATION (ft): 2560

PROJECT No: 951-20

PROJECT: Hydrostor Zevsar

NORTHING: 2153552.632

DATE: 3/17/2023 - 5/19/2023

PROJECT LOCATION: Rosamod, CA

EASTING: 6514916.08

DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
950																					
955																					
957	QTZ MONZONITE, light gray to white, phaneritic, massive, with biotite and hornblende porphyry phenocrysts, trace muscovite, pyroxene, and chlorite																				
960																					
965																					
970																					
975																					

BORING TYPE: HQ3

DRILLER: Crux

LOGGED BY: Chris Messenger

HOLE DEPTH (ft): 3167

WATER OBSERVATIONS: 1902 ft, 2592 ft

CASING: HW to 71 ft

REMARKS: _____

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type _____)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
WL	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions

SURFACE ELEVATION (ft): 2560

PROJECT No: 951-20

PROJECT: Hydrostor Zevsar

NORTHING: 2153552.632

DATE: 3/17/2023 - 5/19/2023

PROJECT LOCATION: Rosamod, CA

EASTING: 6514916.08

DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
985	QTZ MONZONITE, light gray to white, phaneritic, massive, with biotite and															From 981' to 982': Jointed planar smooth 45° fractures, rough					
																	-983': Rough irregular, stepped 32"				
																	From 984' to 986': Rubble				
990																	From 987.5' to 989.5': 5 Planar smooth 0°-4°	C	100	72	
																	991': Planar smooth				
																	From 992' to 992.75': 45° wedge				
995																	From 995' to 997': S. stepped				
																	From 996' to 997': 2 Planar smooth				
																	998': 13° Planar smooth				
1000																	999.6': 38° Planar smooth	C	100	72	
															1000.9': Planar smooth						
															From 1003' to 1005': Rubble decomposed, extreme veining						
1005															From 1005' to 1007': 4 Planar smooth 0°-3°						
															1008': 45° Planar smooth						
1010															1009.9': 48° Planar smooth	C	100	71			
															1011.38': 41° Planar smooth						
1014															From 1013' to 1014': 3 Planar smooth, moderate veining						
															From 1014' to 1032':						

BORING TYPE: HQ3

DRILLER: Crux

LOGGED BY: Chris Messenger

HOLE DEPTH (ft): 3167

WATER OBSERVATIONS: 1902 ft, 2592 ft

CASING: HW to 71 ft

REMARKS:

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2560
NORTHING: 2153552.632
EASTING: 6514916.08

PROJECT No: 951-20
DATE: 3/17/2023 - 5/19/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
1020	hornblende porphyry phenocrysts, trace muscovite, pyroxene, and chlorite														0.05	Highly fractured, all rubble					
1025															0.25						
1030															0.50						
1035	QTZ MONZONITE, fine grained, light green to gray, aphanitic														2.50	From 1032' to 1042.5': Rubble, J. fractures at 45°-90° throughout					
1040															5.00						
1045																					
1047	QTZ MONZONITE, fine grained, light green to gray, aphanitic															From 1047' to 1058': Decomposed					

BORING TYPE: HQ3
HOLE DEPTH (ft): 3167
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 1902 ft, 2592 ft

LOGGED BY: Chris Messenger
CASING: HW to 71 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type __)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2560
NORTHING: 2153552.632
EASTING: 6514916.08

PROJECT No: 951-20
DATE: 3/17/2023 - 5/19/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
1505																					
1058	QTZ MONZONITE, white to light gray, phaneritic, massive, with biotite and hornblende porphyry phenocrysts, trace muscovite, pyroxene, chlorite																				
1060																		C	100	94	
1065																1063': Planar smooth 1064.1': 21° Planar smooth 1064.72': Planar smooth 1066.1': 17° Slickenside smooth					
1070																1068.9': 42° inundated rough From 1069' to 1074': S. fracture at 90°, inundated rough		C	100	41	
1075	From 1074' to 1076': Presense of chlorite															From 1074' to 1077': Rubble, J. fractures 38°-0°, planar smooth					
1078	QTZ MONZONITE, light gray to greenish gray, phaneritic to aphanitic, massive, with an increase in chlorite and biotite, trace muscovite															1077.67': 42° Planar smooth From 1079' to 1082': Major veining		C	100	80	
1080																From 1082' to 1085': Minor to extreme veining					

BORING TYPE: HQ3
HOLE DEPTH (ft): 3167
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 1902 ft, 2592 ft

LOGGED BY: Chris Messenger
CASING: HW to 71 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type __)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
L	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2560
NORTHING: 2153552.632
EASTING: 6514916.08

PROJECT No: 951-20
DATE: 3/17/2023 - 5/19/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
1090	QTZ MONZONITE, white to light gray, phaneritic, massive, biotite porphyry with monzonite, trace muscovite, hornblended, pyroxene, and chlorite																				
1092																					
1095																					
1100																					
1105																					
1110	From 1109' to 1120': Intrusive pegmatite																				
1115																					
1120																					
1125																					
1130																					
1135																					

BORING TYPE: HQ3
HOLE DEPTH (ft): 3167
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 1902 ft, 2592 ft

LOGGED BY: Chris Messenger
CASING: HW to 71 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)



CLIENT: Lane Power & Energy Solutions

SURFACE ELEVATION (ft): 2560

PROJECT No: 951-20

PROJECT: Hydrostor Zevsar

NORTHING: 2153552.632

DATE: 3/17/2023 - 5/19/2023

PROJECT LOCATION: Rosamod, CA

EASTING: 6514916.08

DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F- Fault	Type	Core Rec. %	RQD %	Test Results & Comments
	From 1120' to 1122': Increase in chlorite																				
1125																					
1130																					
1132	CORE LOSS																				
1135																					
1140																					
1145																					
1150																					

BORING TYPE: HQ3

DRILLER: CruX

LOGGED BY: Chris Messenger

HOLE DEPTH (ft): 3167

WATER OBSERVATIONS: 1902 ft, 2592 ft

CASING: HW to 71 ft

REMARKS: _____

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type _____)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2560
NORTHING: 2153552.632
EASTING: 6514916.08

PROJECT No: 951-20
DATE: 3/17/2023 - 5/19/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities	Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard				B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %
1160	QTZ MONZONITE, white to light gray, phaneritic, massive														1155': 22° vertical, 4" From 1159' to 1161': S. fracture, inundated smooth From 1163.5' to 1164': S. at 90° planar smooth From 1165' to 1167': Vertical S. at 90° planar smooth From 1167' to 1227': Highly fractured, vertical to 45° J. fractures throughout, hydrothermal activity					
1165																C	100	61		
1167																	C	100		20
1170																	C	100		28
1175																	C	100		17

BORING TYPE: HQ3
HOLE DEPTH (ft): 3167
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 1902 ft, 2592 ft

LOGGED BY: Chris Messenger
CASING: HW to 71 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type ___)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
WL	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)



CLIENT: Lane Power & Energy Solutions

SURFACE ELEVATION (ft): 2560

PROJECT No: 951-20

PROJECT: Hydrostor Zevsar

NORTHING: 2153552.632

DATE: 3/17/2023 - 5/19/2023

PROJECT LOCATION: Rosamod, CA

EASTING: 6514916.08

DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
1195																					
1200																		C	100	12	
1205																					
1210																		C	100	31	
1215																					
1220																		C	100	70	

BORING TYPE: HQ3

DRILLER: CruX

LOGGED BY: Chris Messenger

HOLE DEPTH (ft): 3167

WATER OBSERVATIONS: 1902 ft, 2592 ft

CASING: HW to 71 ft

REMARKS: _____

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type <u> </u>)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
WL	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)

CLIENT: Lane Power & Energy Solutions

SURFACE ELEVATION (ft): 2560

PROJECT No: 951-20

PROJECT: Hydrostor Zevsar

NORTHING: 2153552.632

DATE: 3/17/2023 - 5/19/2023

PROJECT LOCATION: Rosamod, CA

EASTING: 6514916.08

DIP/AZIMUTH: -90 /

EL	DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)				Discontinuities		Sampling & In Situ Testing				
			Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard		0.05	0.25	0.50	2.50	5.00	B - Bedding S - Shear	J - Joint F- Fault	Type	Core Rec. %	RQD %	Test Results & Comments
	1227	QTZ MONZONITE, white to light gray, phaneritic, massive, with biotite porphyry, trace muscovite, hornblende, chlorite, and pyroxene																								
	1230																				C	100	55			
	1235																									
	1240																				C	100	57			
	1245																									
	1250																				C	100	31			
	1255																									
																					C	100	87			

BORING TYPE: HQ3

DRILLER: Crux

LOGGED BY: Chris Messenger

HOLE DEPTH (ft): 3167

WATER OBSERVATIONS: 1902 ft, 2592 ft

CASING: HW to 71 ft

REMARKS:

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type _____)
W	Water seep	PL(A)	Point load axial test (s(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test (s(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions

SURFACE ELEVATION (ft): 2560

PROJECT No: 951-20

PROJECT: Hydrostor Zevsar

NORTHING: 2153552.632

DATE: 3/17/2023 - 5/19/2023

PROJECT LOCATION: Rosamod, CA

EASTING: 6514916.08

DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
1265																1259.81': Planar smooth					
																1261.2': Planar smooth					
																1262.2': Planar smooth					
																From 1262.4' to 1263': J. wedge rev angle fracture					
1270																1266.1': 38° Planar smooth					
																From 1267.4' to 1268': Planar smooth, decomposed, minor veining					
																From 1269.4' to 1270': Jointed 45°-37° fracture inundated smooth	C	100	77		
1275																1275.9': 71° Planar smooth					
1280																1279.8': Planar smooth					
																1280.9': inundated smooth					
																From 1282' to 1283': Decomposed, minor veining					
1285																From 1287' to 1317': Minor to moderate veining					
1287	QTZ MONZONITE, light gray to green, aphanitic, massive, with high concentrations of qtz feldspar																				
1290																					
1290																		C	100	59	

BORING TYPE: HQ3

DRILLER: Crux

LOGGED BY: Chris Messenger

HOLE DEPTH (ft): 3167

WATER OBSERVATIONS: 1902 ft, 2592 ft

CASING: HW to 71 ft

REMARKS: _____

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type ____)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
WL	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2560
NORTHING: 2153552.632
EASTING: 6514916.08

PROJECT No: 951-20
DATE: 3/17/2023 - 5/19/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
1300																		C	100	72	
1305																					
1310																		C	100	54	
1315																					
1317	From 1312' to 1317': K feldspar																				
1320	QTZ MONZONITE, light gray to white/pink, phaneritic, massive																	C	100	32	From 1317' to 1327': Fractured rubble throughout most of sequence
1325																					
1327	GRANITE, red to pink																	C	100	12	From 1327' to 1332': Soil like

BORING TYPE: HQ3
HOLE DEPTH (ft): 3167
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 1902 ft, 2592 ft

LOGGED BY: Chris Messenger
CASING: HW to 71 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type ___)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
WL	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2560
NORTHING: 2153552.632
EASTING: 6514916.08

PROJECT No: 951-20
DATE: 3/17/2023 - 5/19/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
1332	GRANITE, light gray to white with pink, massive, infused with qtz feldspar pegmatites and K feldspar, trace muscovite, hornblende, and pyroxene																				
1335																					
1340																		C	100	77	
1345																					
1347	QTZ MONZONITE, light gray to green with pink, aphanitic, massive, infiltration of K feldspar																				
1350																		C	100	69	
1355	From 1352' to 1353': Qtz feldspar pegmatite																				
1360																		C	100	50	
1361	QTZ MONZONITE, light gray to green, aphanitic, massive, with high concentrations of qtz feldspar																				

BORING TYPE: HQ3
HOLE DEPTH (ft): 3167
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 1902 ft, 2592 ft

LOGGED BY: Chris Messenger
CASING: HW to 71 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type ___)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
WL	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2560
NORTHING: 2153552.632
EASTING: 6514916.08

PROJECT No: 951-20
DATE: 3/17/2023 - 5/19/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
1370																		C	100	0	
1375																		C	100	0	
1380																		C	100	0	
1385																		C	100	42	
1390	QTZ MONZONITE, light gray to white to pink, phaneritic																	C	100	82	
1395																		C	100	82	

BORING TYPE: HQ3
HOLE DEPTH (ft): 3167
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 1902 ft, 2592 ft

LOGGED BY: Chris Messenger
CASING: HW to 71 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type ___)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
WL	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2560
NORTHING: 2153552.632
EASTING: 6514916.08

PROJECT No: 951-20
DATE: 3/17/2023 - 5/19/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)		Discontinuities		Sampling & In Situ Testing																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																										
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard		0.05 0.25 0.50 2.50 5.00	B - Bedding S - Shear	J - Joint F- Fault	Type	Core Rec. %	RQD %	Test Results & Comments																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																								
1405	QTZ MONZONITE, light gray to green with pink, aphanitic, with K feldspar, biotite, chlorite, and epidote																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																												</

BORING TYPE: HQ3
HOLE DEPTH (ft): 3167
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 1902 ft, 2592 ft

LOGGED BY: Chris Messenger
CASING: HW to 71 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type ___)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
WL	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions

SURFACE ELEVATION (ft): 2560

PROJECT No: 951-20

PROJECT: Hydrostor Zevsar

NORTHING: 2153552.632

DATE: 3/17/2023 - 5/19/2023

PROJECT LOCATION: Rosamod, CA

EASTING: 6514916.08

DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities	Sampling & In Situ Testing					
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard				B - Bedding S - Shear	J - Joint F- Fault	Type	Core Rec. %	RQD %	Test Results & Comments
1440	From 1437' to 1442': Qtz feldspar pegmatite														From 1442' to 1512': Moderate to severe veining, broken down into soil like quality							
1445																						
1450																						
1455																						
1460																						
1465																						

From 1442' to 1512':
Moderate to severe
veining, broken down
into soil like quality

BORING TYPE: HQ3

DRILLER: Crux

LOGGED BY: Chris Messenger

HOLE DEPTH (ft): 3167

WATER OBSERVATIONS: 1902 ft, 2592 ft

CASING: HW to 71 ft

REMARKS: _____

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type <u> </u>)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2560
NORTHING: 2153552.632
EASTING: 6514916.08

PROJECT No: 951-20
DATE: 3/17/2023 - 5/19/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
1475																					
1480																		C	100	77	
1485																		C	100	71	
1490																		C	100	40	
1495																		C	100	60	
1500																		C	100	60	

BORING TYPE: HQ3
HOLE DEPTH (ft): 3167
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 1902 ft, 2592 ft

LOGGED BY: Chris Messenger
CASING: HW to 71 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type <u> </u>)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
WL	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions

SURFACE ELEVATION (ft): 2560

PROJECT No: 951-20

PROJECT: Hydrostor Zevsar

NORTHING: 2153552.632

DATE: 3/17/2023 - 5/19/2023

PROJECT LOCATION: Rosamod, CA

EASTING: 6514916.08

DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
1510																					
1512	QTZ MONZONITE, light gray to white, phaneritic, massive, with biotite porphyry, increased K feldspar replacing plagioclase, small qtz feldspar pegmatite, trace pyroxene, muscovite, chlorite, and hornblende																				
1515																					
1520	From 1520' to 1523.5': Qtz feldspar pegmatite																				
1525																					
1530																					
1533	QTZ MONZONITE, light gray to green, aphanitic to phaneritic, massive																				
1535																					

BORING TYPE: HQ3

DRILLER: Crux

LOGGED BY: Chris Messenger

HOLE DEPTH (ft): 3167

WATER OBSERVATIONS: 1902 ft, 2592 ft

CASING: HW to 71 ft

REMARKS:

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions

SURFACE ELEVATION (ft): 2560

PROJECT No: 951-20

PROJECT: Hydrostor Zevsar

NORTHING: 2153552.632

DATE: 3/17/2023 - 5/19/2023

PROJECT LOCATION: Rosamod, CA

EASTING: 6514916.08

DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
1541	QTZ MONZONITE, light gray to white, phaneritic, massive																				
1545																From 1545' to 1546': Vertical S. at 90°, inundated rough		C	100	80	
1550																1546.4': 32° and 38° Planar smooth wedge					
1555																1548.6': 47° Planar					
1560																1549': 27° Planar smooth					
1565																1549.2': 4° Planar smooth					
1570																1550': 0° Planar smooth					
																From 1552' to 1553.5': Rubble J. fracture		C	100	41	
																1555': 42° Planar smooth, S. at 61°					
																1555.9': 0° Planar smooth					
																From 1556' to 1557': Rubble J. fracture					
																From 1557' to 1559.5': (6) 31°-47° fractures, rubble					
																1560.4': 47° Planar smooth					
																1561.5': 39° and 42° Wedge					PL(A) = 379
																1562.3': Planar smooth					
																1563.47': 21° Planar smooth		C	100	78	
																From 1564' to 1565.3': (4) 20°-30° Planar smooth					PL(A) = 141
																1565.6': 68° inundated smooth					
																From 1567' to 1569.3': S. at 90° to 45° inundated smooth J. fractures					
																1571.6': Planar smooth					
																From 1573' to 1574': 4 Rubble J. planar smooth		C	100	69	

BORING TYPE: HQ3

DRILLER: Crux

LOGGED BY: Chris Messenger

HOLE DEPTH (ft): 3167

WATER OBSERVATIONS: 1902 ft, 2592 ft

CASING: HW to 71 ft

REMARKS:

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type <u> </u>)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
WL	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2560
NORTHING: 2153552.632
EASTING: 6514916.08

PROJECT No: 951-20
DATE: 3/17/2023 - 5/19/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
1580															From 1578' to 1581': (6) 42°-26°-90° S. fractures, planar smooth 1578.1': 47° Planar smooth				PL(A) = 1,025		
1585														From 1582' to 1584': Rubble, S. at 45°-90°							
1590														From 1584.5' to 1585.5': Vertical slickenside biotite/chlorite at 90° From 1587' to 1589': S. fracture at 90°-77° planar smooth	C	100	29				
1595															1591': Planar smooth 1592.9': 41° Planar smooth From 1593.3' to 1593.5': 2 J. fractures at 41° 1594': 42° Planar smooth From 1595.6' to 1597': Rubble From 1597' to 1602': (15) 39°-49° S. J. fractures planar smooth	C	100	56			
1600															From 1602' to 1605': S. J. fractures at 32°-90° along pegmatite intrusions (10), rubble 1606': 44° Planar smooth From 1608' to 1610.9': 6 S. at 38°-90°	C	100	56			
1605																					

BORING TYPE: HQ3
HOLE DEPTH (ft): 3167
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 1902 ft, 2592 ft

LOGGED BY: Chris Messenger
CASING: HW to 71 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type ___)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2560
NORTHING: 2153552.632
EASTING: 6514916.08

PROJECT No: 951-20
DATE: 3/17/2023 - 5/19/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
1615	From 1613' to 1616': Qtz feldspar pegmatite																				
1620																					
1625																					
1630																					
1635																					
1640																					
																					PL(A) = 932

BORING TYPE: HQ3
HOLE DEPTH (ft): 3167
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 1902 ft, 2592 ft

LOGGED BY: Chris Messenger
CASING: HW to 71 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type ___)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
L	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2560
NORTHING: 2153552.632
EASTING: 6514916.08

PROJECT No: 951-20
DATE: 3/17/2023 - 5/19/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F- Fault	Type	Core Rec. %	RQD %	Test Results & Comments
1650																					PL(A) = 710 PL(A) = 858
1655																From 1654' to 1657': 12 J. fractures planar smooth		C	100	41	
1660																From 1657' to 1659.6': Alteration appears as fracture, no true fracture					
1665																From 1659.6' to 1661': 6 J. fractures at 57° planar smooth					
1670																From 1662.5' to 1666': Rubble J. planar smooth fractures		C	100	62	
1675																1669.7': inundated smooth 1670': 0° Planar smooth 1670.7': 0° Planar smooth 1671.2': 0° Planar smooth 1672.3': 0° Planar smooth 1672.6': 0° Planar smooth 1674': Planar smooth 1675.2': 23° Planar smooth 1675.6': 17° Planar smooth		C	100	66	UCS = 3,022

BORING TYPE: HQ3
HOLE DEPTH (ft): 3167
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 1902 ft, 2592 ft

LOGGED BY: Chris Messenger
CASING: HW to 71 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type ___)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions

SURFACE ELEVATION (ft): 2560

PROJECT No: 951-20

PROJECT: Hydrostor Zevsar

NORTHING: 2153552.632

DATE: 3/17/2023 - 5/19/2023

PROJECT LOCATION: Rosamod, CA

EASTING: 6514916.08

DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
1685	From 1680' to 1681': Qtz feldspar pegmatite															1676': 21° Planar smooth					
1690																1676.8': 41° Planar smooth		C	100	56	
1692	QTZ MONZONITE, light gray to white, phaneritic, massive, with biotite and hornblende porphyry, trace muscovite, pyroxene, chlorite, and lower percentage of K feldspar																				
1695																		C	100	51	
1700																From 1697.4' to 1700.4': Rubble J. fractures planar smooth					
1705																1702.1': 49° inundated stepped rough					
1710																1703.25': 12° Planar smooth					
																1704': 27° Planar smooth		C	100	70	
																From 1704.8' to 1705': Jointed 39° S. fractures planar smooth					
																From 1705' to 1707': Vertical S. at 90° inundated smooth					
																		C	100	73	

BORING TYPE: HQ3

DRILLER: Crux

LOGGED BY: Chris Messenger

HOLE DEPTH (ft): 3167

WATER OBSERVATIONS: 1902 ft, 2592 ft

CASING: HW to 71 ft

REMARKS: _____

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type ____)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
WL	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2560
NORTHING: 2153552.632
EASTING: 6514916.08

PROJECT No: 951-20
DATE: 3/17/2023 - 5/19/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
1720																					
1725																		C	100	81	
1730																					
1735																		C	100	74	
1740																From 1737' to 1739': Rubble					
1745																1739.2': 49° Planar smooth 1739.7': 41° Planar smooth From 1740.7' to 1743.7': Rubble					
																From 1744.8' to 1745.2': 45°K feldspar sheeting - 46° Plagioclase sheeting wedge 1745.7': Planar irregular From 1746' to 1746.3': (3) 51° stress fractures, smooth planar From 1747' to 1749': Rubble		C	100	71	

BORING TYPE: HQ3
HOLE DEPTH (ft): 3167
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 1902 ft, 2592 ft

LOGGED BY: Chris Messenger
CASING: HW to 71 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type ___)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
WL	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions

SURFACE ELEVATION (ft): 2560

PROJECT No: 951-20

PROJECT: Hydrostor Zevsar

NORTHING: 2153552.632

DATE: 3/17/2023 - 5/19/2023

PROJECT LOCATION: Rosamod, CA

EASTING: 6514916.08

DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
1755																					UCS = 11,631
1757	CORE LOSS																				PL(A) = 453
1758.7	From 1759.2' to 1760': Pegmatite																				
1760																					PL(A) = 821
1765																					
1770																					
1775																					
1780																					PL(A) = 610

BORING TYPE: HQ3

DRILLER: Crux

LOGGED BY: Chris Messenger

HOLE DEPTH (ft): 3167

WATER OBSERVATIONS: 1902 ft, 2592 ft

CASING: HW to 71 ft

REMARKS:

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type <u> </u>)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2560
NORTHING: 2153552.632
EASTING: 6514916.08

PROJECT No: 951-20
DATE: 3/17/2023 - 5/19/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities	Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard				B - Bedding S - Shear	J - Joint F- Fault	Type	Core Rec. %
1790	From 1785.7' to 1786.5': Pegmatite														Vertical S. at 90°, rubble				ITS = 1,278	
															1788.1': 17° Planar smooth					
															From 1789.4' to 1789.5': 2 Planar smooth 0°-1°					
															1790': 29° Planar smooth					
															1790.61': 58° Planar smooth					
1795															1791': Rev angle 42° smooth planar					
															1791.5': Wedge mean break	C	100	55		
															1794.1': 68° Planar smooth					
															1796': Planar irregular					
															From 1797.5' to 1801': 90°-42° J. fractures, almost rubble					
1800	From 1798' to 1800': Pegmatite																			
															From 1802' to 1807': Hairline healed 90°-69° vertical fracture mostly expanded, some area slightly separated					
1805																	C	100	24	
															1808': Planar smooth					
															From 1808.4' to 1809.2': Rubble					
1810															From 1810' to 1812': Hairline 90° healed, plagioclase infill fracturing system					
															1812.4': 46° Planar smooth					
															1813.1': 29° Planar smooth					
1815															1816': Vertical S. at 90°, healed fracturing					
															1818': Planar smooth					
															1818.2': 30° Planar smooth					

BORING TYPE: HQ3
HOLE DEPTH (ft): 3167
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 1902 ft, 2592 ft

LOGGED BY: Chris Messenger
CASING: HW to 71 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)

CLIENT: Lane Power & Energy Solutions

SURFACE ELEVATION (ft): 2560

PROJECT No: 951-20

PROJECT: Hydrostor Zevsar

NORTHING: 2153552.632

DATE: 3/17/2023 - 5/19/2023

PROJECT LOCATION: Rosamod, CA

EASTING: 6514916.08

DIP/AZIMUTH: -90 /

[illegible]

BORING TYPE: HQ3

DRILLER: Crux

LOGGED BY: Chris Messenger

HOLE DEPTH (ft): 3167

WATER OBSERVATIONS: 1902 ft, 2592 ft

CASING: HW to 71 ft

REMARKS:

SAMPLING & IN SITU TESTING LEGEND			
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)
		SLK	Slake durability test (Type _____)
		TRI	Triaxial stress test (psi)
		UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2560
NORTHING: 2153552.632
EASTING: 6514916.08

PROJECT No: 951-20
DATE: 3/17/2023 - 5/19/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
1860																1855.1': Vertical fracture					PL(A) = 860
1865																1855.4': Reverse angle fracture at 45°					
1870																1856.1': 45° fracture, creating wedge with 1855.4'					
1875																From 1857' to 1859': (10) 22°-34° Planar smooth					
1880																From 1863.7' to 1864.1': 3 Planar smooth					PL(A) = 860
																From 1865' to 1865.6': Planar smooth		C	100	50	
																1865.2': 22° Planar smooth					
																1866': 0° Planar smooth					
																1866.1': 51°-45° Wedge reverse angle inundated smooth					PL(A) = 860
																1867.45': Planar smooth					
																1868.6': 2 Planar smooth					
																From 1869.2' to 1872': Vertical S. at 90°, (3) 45° Stress J.					
																From 1872' to 1877': Rubble		C	100	34	PL(A) = 860
																1878': 32° Planar smooth					
																From 1880' to 1885': Stress J. fractures at 45°-90°					
																1886.2': 1/2 Rubble					
1885																1886.6': 41°-32°		C	100	16	

BORING TYPE: HQ3
HOLE DEPTH (ft): 3167
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 1902 ft, 2592 ft

LOGGED BY: Chris Messenger
CASING: HW to 71 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2560
NORTHING: 2153552.632
EASTING: 6514916.08

PROJECT No: 951-20
DATE: 3/17/2023 - 5/19/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
1930														1925.2': 11° Planar smooth From 1925.4' to 1926': 90° inundated smooth From 1927' to 1928.1': 27°, 78° Rev angle 59° wedge planar smooth From 1930.2' to 1930.4': 0°-5° Planar smooth				ITS = 1,256			
1935														1932.1': 42°-45° Planar smooth 1932.2': Planar smooth From 1933.2' to 1934.6': (3) 78° J. fractures with K feldspar infill, smooth planar From 1934.6' to 1934.8': (2) 84° J. fractures planar smooth 1935.7': Vertical S. 1936.1': inundated smooth From 1936.2' to 1936.6': 71°-48° Rev angle, smooth planar 1938': 0° Planar smooth From 1938.4' to 1939': (3) 45° J. fractures with K feldspar infill, planar smooth 1939.5': 45° Planar 1940.2': 32° inundated smooth 1940.25': 55° J. fracture 1940.3': 55° J. fracture 1940.4': 55° J. fracture 1940.9': 17° Planar From 1941' to 1942': (6) 71° J. fractures, (3) 45° Planar smooth From 1943.1' to 1943.4': 90°-47°-38° (3) Planar smooth - K feldspar contact 1946.2': Planar irregular 1949': 51° inundated rough From 1949.2' to 1946': 49° inundated smooth, multiple headed fractures (K feldspar) From 1950' to 1954': Rubble	C	100	61	PL(A) = 1,073 PL(A) = 559 UCS = 17,783 PL(A) = 23,502			
1945															C	100	56				
1950																					
1955															C	100	34				

BORING TYPE: HQ3
HOLE DEPTH (ft): 3167
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 1902 ft, 2592 ft

LOGGED BY: Chris Messenger
CASING: HW to 71 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type ___)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
L	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

CLIENT: Lane Power & Energy Solutions

SURFACE ELEVATION (ft): 2560

PROJECT No: 951-20

PROJECT: Hydrostor Zevsar

NORTHING: 2153552.632

DATE: 3/17/2023 - 5/19/2023

PROJECT LOCATION: Rosamod, CA

EASTING: 6514916.08

DIP/AZIMUTH: -90 /

[illegible]

BORING TYPE: HQ3

DRILLER: Crux

LOGGED BY: Chris Messenger

HOLE DEPTH (ft): 3167

WATER OBSERVATIONS: 1902 ft, 2592 ft

CASING: HW to 71 ft

REMARKS:

SAMPLING & IN SITU TESTING LEGEND			
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)
		SLK	Slake durability test (Type ___)
		TRI	Triaxial stress test (psi)
		UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions

SURFACE ELEVATION (ft): 2560

PROJECT No: 951-20

PROJECT: Hydrostor Zevsar

NORTHING: 2153552.632

DATE: 3/17/2023 - 5/19/2023

PROJECT LOCATION: Rosamod, CA

EASTING: 6514916.08

DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
560 2000																					
555 2005																					
550 2010																					
545 2015																					
540 2020																					
535 2025																					

BORING TYPE: HQ3

DRILLER: CruX

LOGGED BY: Chris Messenger

HOLE DEPTH (ft): 3167

WATER OBSERVATIONS: 1902 ft, 2592 ft

CASING: HW to 71 ft

REMARKS: _____

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type _____)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)

CLIENT: Lane Power & Energy Solutions

SURFACE ELEVATION (ft): 2560

PROJECT No: 951-20

PROJECT: Hydrostor Zevsar

NORTHING: 2153552.632

DATE: 3/17/2023 - 5/19/2023

PROJECT LOCATION: Rosamod, CA

EASTING: 6514916.08

DIP/AZIMUTH: -90 /[illegible]

BORING TYPE: HQ3

DRILLER: Crux

LOGGED BY: Chris Messenger

HOLE DEPTH (ft): 3167

WATER OBSERVATIONS: 1902 ft, 2592 ft

CASING: HW to 71 ft

REMARKS:

SAMPLING & IN SITU TESTING LEGEND			
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)
	Water seep	SLK	Slake durability test (Type _____)
	Water level	PL(A)	Point load axial test (s/50) (psi)
		PL(D)	Point load diametral test (s/50) (psi)
		TRI	Triaxial stress test (psi)
		UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions

SURFACE ELEVATION (ft): 2560

PROJECT No: 951-20

PROJECT: Hydrostor Zevsar

NORTHING: 2153552.632

DATE: 3/17/2023 - 5/19/2023

PROJECT LOCATION: Rosamod, CA

EASTING: 6514916.08

DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
2070	From 2083' to 2083.2': K feldspar															2064.1': 0° Planar smooth				ITS = 1,364 UCS = 17,449 SLK = Type I TRI = 32,052	
2075																2064.4': 0° Planar smooth					
																2064.8': 0° Planar smooth					
																2066.7': 0° Planar smooth					
																2070': Planar smooth					
																2071': Planar smooth					
2074.1': Planar smooth																C	100	78			
2080																From 2077' to 2079': (6) 15°-30° J. fracture, pegmatite	C	100	81		PL(A) = 458 ITS = 1,247 UCS = 16,552
																2081': K feldspar, epidote - planar					
																2083': 3 Planar					
																2084.9': 32° Planar smooth					
																2086': 61° inundated smooth					
2089.7': 0° Planar smooth, 61° Stress fracture	C	100	77																		
2090': Stress healed fractures from pegmatite																					
2091': 47° Planar smooth																					
2093.6': 42° Planar																					
2094': 68° Healed K feldspar																					
From 2098.6' to 2098.9': Planar smooth																					

BORING TYPE: HQ3

DRILLER: Crux

LOGGED BY: Chris Messenger

HOLE DEPTH (ft): 3167

WATER OBSERVATIONS: 1902 ft, 2592 ft

CASING: HW to 71 ft

REMARKS:

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type <u> </u>)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
WL	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions

SURFACE ELEVATION (ft): 2560

PROJECT No: 951-20

PROJECT: Hydrostor Zevsar

NORTHING: 2153552.632

DATE: 3/17/2023 - 5/19/2023

PROJECT LOCATION: Rosamod, CA

EASTING: 6514916.08

DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
2105																From 2100' to 2102': Vertical S. at 90° planar smooth					SLK = Type I TRI = 42,196
2110	From 2108.6' to 2112': Qtz feldspar pegmatite															From 2103.1' to 2103.4': Planar smooth, slickenside		C	100	79	
2115	From 2112' to 2116': Qtz feldspar pegmatite															From 2108' to 2112': (9) 38°-42° J. fractures, pegmatite infusion					
2120																From 2112' to 2117': Qtz feldspar pegmatite hairline healed fractures throughout					ITS = 1,361 UCS = 24,510 PL(A) = 963
2125																From 2112.1' to 2113.5': (4) 30°-42° fracture points		C	100	51	
2130																2115': Planar smooth 2116.1': 51° Planar smooth From 2117' to 2120.6': Vertical S. at 90° K feldspar infill					
																2122.7': Planar smooth 2123': Planar smooth		C	100	64	ITS = 1,361 UCS = 24,510 PL(A) = 963
																2126.4': Vertical S. From 2127' to 2128.3': 3 Planar smooth, (1) 38° planar smooth					
																2129.3': Planar smooth From 2130.65' to 2131': (3) 0°-3° Planar smooth					
																2133.8': 79° Planar smooth		C	100	80	

BORING TYPE: HQ3

DRILLER: Crux

LOGGED BY: Chris Messenger

HOLE DEPTH (ft): 3167

WATER OBSERVATIONS: 1902 ft, 2592 ft

CASING: HW to 71 ft

REMARKS:

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type <u> </u>)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
L	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2560
NORTHING: 2153552.632
EASTING: 6514916.08

PROJECT No: 951-20
DATE: 3/17/2023 - 5/19/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
2140	QTZ MONZONITE, light gray to white, phaneritic, with porphyritic biotite mica, quartz, K feldspar, and plagioclase, trace amounts of pyrite															From 2134.5' to 2137': Vertical S. and (2) 51° angle					SLK = Type I
																2137.6': Planar smooth					
																2140': Planar smooth					
2142																From 2142' to 2144': Vertical 90° inundated smooth					C 100 48
2145																2145': 67° Shear-stress into 90° at 2145.75					
																2147': Planar irregular					
																2148': 26° Planar smooth					C 100 41
																2149': 79° J. fracture					
2150																2150.7': (2) 40° Planar smooth					
																2151.5': Planar smooth					C 100 21
																2152.4': Planar smooth					
																2152.8': Planar smooth					
2155																From 2153.7' to 2154.8': Reverse F. occurring					C 100 21
																From 2154' to 2156': 4 Planar smooth at 0, 38°, 41°, 67°					
																From 2157' to 2159': Highly fractured rubble					
2160																From 2160.4' to 2160.6': 38°-43° Planar smooth					ITS = 1,066 UCS = 15,267
																From 2163.2' to 2172': Vertical 90°-80°, compiled with 45°-65° stress J. fractures, partially rubble					
2165																From 2165.3' to 2166.3': High degree/vertical fractures					
	From 2169.7' to 2170': Pegmatite																				

BORING TYPE: HQ3
HOLE DEPTH (ft): 3167
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 1902 ft, 2592 ft

LOGGED BY: Chris Messenger
CASING: HW to 71 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)



CLIENT: Lane Power & Energy Solutions

SURFACE ELEVATION (ft): 2560

PROJECT No: 951-20

PROJECT: Hydrostor Zevsar

NORTHING: 2153552.632

DATE: 3/17/2023 - 5/19/2023

PROJECT LOCATION: Rosamod, CA

EASTING: 6514916.08

DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
2172	QTZ MONZONITE, light gray to white, phaneritic, with porphyritic biotite mica, K-feldspar, plagioclase, and quartz, trace chlorite																				
2175																		C	100	68	SLK = Type I
2180																					PL(A) = 255
2185																		C	100	74	ITS = 782
2190																					
2195																		C	100	91	UCS = 13,136
2200																					PL(A) = 693
																					SLK = Type I
																					TRI = 20,972

BORING TYPE: HQ3

DRILLER: Crux

LOGGED BY: Chris Messenger

HOLE DEPTH (ft): 3167

WATER OBSERVATIONS: 1902 ft, 2592 ft

CASING: HW to 71 ft

REMARKS: _____

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type _____)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2560
NORTHING: 2153552.632
EASTING: 6514916.08

PROJECT No: 951-20
DATE: 3/17/2023 - 5/19/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
2210																From 2205' to 2206.4': 10°-18° Planar					
2215																2208.2': inundated 2209': 6° inundated 2209.8': inundated 2211.2': 7° Planar 2211.8': 19° Planar					
2220																2215.2': Planar smooth 2216.2': Planar smooth		C	100	94	ITS = 590 UCS = 13,570
2225																2221.2': Planar smooth 2222.2': Planar smooth 2223.1': 17° Planar smooth 2223.8': 52° Planar 2224': 40° Planar smooth 2225.81': 9° Planar smooth 2226.4': Planar smooth 2227.4': 32° Planar smooth 2229.1': 6° Planar smooth		C	100	92	SLK = Type I
2230																					
2235																From 2235.7' to 2237': (8) 22°-25° Stress J. fractures, planar smooth From 2236' to 2237': (6) 70°-80° Stress J. fractures, rubble 2237.9': 59° Stress J. planar smooth		C	100	41	TRI = 37,349 PL(A) = 826

BORING TYPE: HQ3
HOLE DEPTH (ft): 3167
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 1902 ft, 2592 ft

LOGGED BY: Chris Messenger
CASING: HW to 71 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type <u> </u>)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2560
NORTHING: 2153552.632
EASTING: 6514916.08

PROJECT No: 951-20
DATE: 3/17/2023 - 5/19/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
2245																					ITS = 1,174 PL(A) = 459
2250																		C	100	81	SLK = Type I UCS = 19,149
2255																		C	100	72	
2260																					
2262	QTZ MONZONITE, light gray to white, phaneritic, with porphyritic biotite, K-feldspar, quartz, and plagioclase, trace chlorite and epidote																				
2265	From 2263' to 2264': Qtz feldspar pegmatite																	C	100	38	PL(A) = 310
2270																		C	100	18	

BORING TYPE: HQ3
HOLE DEPTH (ft): 3167
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 1902 ft, 2592 ft

LOGGED BY: Chris Messenger
CASING: HW to 71 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type ___)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2560
NORTHING: 2153552.632
EASTING: 6514916.08

PROJECT No: 951-20
DATE: 3/17/2023 - 5/19/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
2280																					SLK = Type I
2285																		C	100	84	ITS = 499
2290																					
2294	QTZ MONZONITE, light to dark gray, phaneritic, with porphyritic biotite, quartz, and plagioclase															From 2294' to 2297': Chlorite visible along fractures		C	100	56	
2295																					
2297	QTZ MONZONITE, light gray to white, phaneritic, with porphyritic biotite mica, K-feldspar, plagioclase, and quartz, trace chlorite and epidote															From 2297' to 2322': Some pegmatite veining, minor fracturing					UCS = 582
2300																					
2305																		C	100	71	ITS = 190

BORING TYPE: HQ3
HOLE DEPTH (ft): 3167
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 1902 ft, 2592 ft

LOGGED BY: Chris Messenger
CASING: HW to 71 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type ___)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
WL	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2560
NORTHING: 2153552.632
EASTING: 6514916.08

PROJECT No: 951-20
DATE: 3/17/2023 - 5/19/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
2315																					PL(A) = 111
2320	From 2318' to 2319.3': Qtz feldspar pegmatite																	C	100	68	SLK = Type II
2322	From 2322' to 2324': Pegmatite																				ITS = 244
2325	QTZ MONZONITE, light gray to white, phaneritic, massive, with biotite/hornblende porphyry, trace K-feldspar, chlorite, epidote, pyrite, pyroxene																	C	100	56	UCS = 2,990
2330	From 2325' to 2356': Pegmatite																				UCS = 3,805
2335																					
2340																					PL(A) = 735

BORING TYPE: HQ3
HOLE DEPTH (ft): 3167
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 1902 ft, 2592 ft

LOGGED BY: Chris Messenger
CASING: HW to 71 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type __)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2560
NORTHING: 2153552.632
EASTING: 6514916.08

PROJECT No: 951-20
DATE: 3/17/2023 - 5/19/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
2350	From 2374.75' to 2380': Qtz feldspar pegmatite															From 2348' to 2348.75': 40°-42° inundated smooth					SLK = Type I UCS = 22,117
2355																From 2349.8' to 2350.2': 79° S. fracture					
2360																From 2350.4' to 2351.8': Planar smooth					SLK = Type I
2365																2352.2': Planar smooth					
2370																2353': 61° inundated smooth					PL(A) = 950 ITS = 840
2375																From 2354' to 2356': (6) Planar smooth	C	100	39		
																From 2357' to 2359': (4) 39°-48° J. stress fracture planar smooth					PL(A) = 950 ITS = 840
																From 2361' to 2364': S. at 87° inundated smooth					
																From 2365' to 2365.9': (3) 77° Stress fractures	C	100	51		PL(A) = 950 ITS = 840
																From 2366' to 2367': 2 Planar					
																2366.6': S. at 58°					PL(A) = 950 ITS = 840
																2367.4': Planar smooth					
																2367.8': Planar smooth					PL(A) = 950 ITS = 840
																From 2370' to 2371': Rubble					
																2372.7': Planar smooth					PL(A) = 950 ITS = 840
																From 2374' to 2382': Rubble (pegmatite)	C	100	17		

BORING TYPE: HQ3
HOLE DEPTH (ft): 3167
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 1902 ft, 2592 ft

LOGGED BY: Chris Messenger
CASING: HW to 71 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type ___)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
L	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

CLIENT: Lane Power & Energy Solutions

SURFACE ELEVATION (ft): 2560

PROJECT No: 951-20

PROJECT: Hydrostor Zevsar

NORTHING: 2153552.632

DATE: 3/17/2023 - 5/19/2023

PROJECT LOCATION: Rosamod, CA

EASTING: 6514916.08

DIP/AZIMUTH: -90 /

EL	DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)		Discontinuities		Sampling & In Situ Testing											
			Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard		0.05	0.25	0.50	2.50	5.00	B - Bedding S - Shear	J - Joint F- Fault	Type	Core Rec. %	RQD %	Test Results & Comments					
	2382	From 2382' to 2383': Pegmatite QTZ MONZONITE, light gray, phaneritic, massive, with interbedded qtz feldspar pegmatites, dominant in plagioclase, biotite, hornblende, and quartz, trace pyrite, chlorite, epidote, pyroxene, and muscovite																			From 2382' to 2383.75': Rubble		100	71	UCS = 12,604						
	2385																									2385': Rev angle fracture 58°-49° wedge, planar smooth	C	100	71		
																														From 2385.5' to 2387.2': Rubble	
																															2388.7': 40° Smooth planar with plagioclase infill
	2390																														
		2391': (3) 32° J. fractures 4"	C	100	42	ITS = 756																									
		2391.8': 45° Planar rough, large crystallizations																													
	2395	From 2392' to 2397': (16) 21°-45° J. fractures planar smooth																													
		2397.4': Planar smooth																													
		2399.2': Planar smooth																													
	2400	2400.1': 67° inundated smooth	C	100	59		SLK = Type I																								
		From 2400.5' to 2401': S. at 90°																													
		From 2402' to 2405': Rubble																													
	2405	2406': 7° Planar smooth																													
		2410.3': Planar smooth																													
	2410	From 2412' to 2472': Best zone																				2412.5': 79° Vertical S.									
		2414.6': 6° Planar																				C				100	70				

BORING TYPE: HQ3

DRILLER: Crux

LOGGED BY: Chris Messenger

HOLE DEPTH (ft): 3167

WATER OBSERVATIONS: 1902 ft, 2592 ft

CASING: HW to 71 ft

REMARKS:

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type _____)
W	Water seep	PL(A)	Point load axial test (s(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test (s(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2560
NORTHING: 2153552.632
EASTING: 6514916.08

PROJECT No: 951-20
DATE: 3/17/2023 - 5/19/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
140 -2420																smooth/inundated					UCS = 5,349
																2415': 27° Planar smooth					ITS = 1,440
																2416.1': 0° Planar smooth					
																2417.7': 7° Planar smooth					
																2419': 52° Planar smooth					
																2420.2': 47° Planar smooth					
																2421.2': 48° Planar smooth					PL(A) = 1,281
135 -2425																From 2423' to 2425': Vertical S. at 88° inundated smooth with plagioclase infill	C	100	67		
																2428.2': 69° Planar smooth					
																2429.08': Stress fracture 71°-61°					
130 -2430																2429.4': J. fractures - 71° S.					
																2431.7': S. at 87° planar smooth					SLK = Type I
																2432.9': S. at 67°					
																2433.4': Multiple fractures on 45°	C	100	85		
125 -2435																2433.6': S. at 66°					
																2434': S. at 71°, stress joints, planar smooth					
																From 2436.2' to 2438': (3) 71°-74° S. inundated smooth					TRI = 31,409
120 -2440																2440.9': Planar smooth					
																From 2442.5' to 2443': 69°-71° inundated smooth					
115 -2445																2446.75': S. at 67°					
																2448': Planar irregular					PL(A) = 1,230
																From 2450' to 2450.3':					SLK = Type I

BORING TYPE: HQ3
HOLE DEPTH (ft): 3167
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 1902 ft, 2592 ft

LOGGED BY: Chris Messenger
CASING: HW to 71 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type ___)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)

CLIENT: Lane Power & Energy Solutions

SURFACE ELEVATION (ft): 2560

PROJECT No: 951-20

PROJECT: Hydrostor Zevsar

NORTHING: 2153552.632

DATE: 3/17/2023 - 5/19/2023

PROJECT LOCATION: Rosamod, CA

EASTING: 6514916.08

DIP/AZIMUTH: -90 /

[illegible]

BORING TYPE: HQ3

DRILLER: Crux

LOGGED BY: Chris Messenger

HOLE DEPTH (ft): 3167

WATER OBSERVATIONS: 1902 ft, 2592 ft

CASING: HW to 71 ft

REMARKS:

SAMPLING & IN SITU TESTING LEGEND			
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)
W	Water seep	PL(A)	Point load axial test (s/50) (psi)
W	Water level	PL(D)	Point load diametral test (s/50) (psi)
		SLK	Slake durability test (Type _____)
		TRI	Triaxial stress test (psi)
		UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions

SURFACE ELEVATION (ft): 2560

PROJECT No: 951-20

PROJECT: Hydrostor Zevsar

NORTHING: 2153552.632

DATE: 3/17/2023 - 5/19/2023

PROJECT LOCATION: Rosamod, CA

EASTING: 6514916.08

DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
2490																					ITS = 1,265
2495																					
2500																					
2502	CORE LOSS																				
2505																					
2508																					
2510																					
2515																					SLK = Type I

BORING TYPE: HQ3

DRILLER: Crux

LOGGED BY: Chris Messenger

HOLE DEPTH (ft): 3167

WATER OBSERVATIONS: 1902 ft, 2592 ft

CASING: HW to 71 ft

REMARKS: _____

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type ___)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
L	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions

SURFACE ELEVATION (ft): 2560

PROJECT No: 951-20

PROJECT: Hydrostor Zevsar

NORTHING: 2153552.632

DATE: 3/17/2023 - 5/19/2023

PROJECT LOCATION: Rosamod, CA

EASTING: 6514916.08

DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
2525	QTZ MONZONITE, light gray, phaneritic, massive, with trace chlorite, muscovite, and pyroxene																				UCS = 23,472
2530																					ITS = 1,314
2532																					PL(A) = 119
2535																					ITS = 999
2540																					
2545																					
2550																					
																					UCS = 2,607

BORING TYPE: HQ3

DRILLER: Crux

LOGGED BY: Chris Messenger

HOLE DEPTH (ft): 3167

WATER OBSERVATIONS: 1902 ft, 2592 ft

CASING: HW to 71 ft

REMARKS:

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type <u> </u>)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
L	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2560
NORTHING: 2153552.632
EASTING: 6514916.08

PROJECT No: 951-20
DATE: 3/17/2023 - 5/19/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
0 -2560																planar smooth					SLK = Type II
																From 2553.2' to 2554': Vertical S., pegmatite then decomposed monzonite to 2557'					
																From 2553.7' to 2553.9': 2 Planar smooth					
																From 2554' to 2555': Vertical 90° fracture					
																2555': 48° Planar smooth					
																2555.7': 38° Planar smooth					
																From 2562' to 2577': All rubble		C	100	16	SLK = Type I
-5 -2565																					
-10 -2570																					
-15 -2575																		C	100	25	UCS = 2,960
																From 2577.3' to 2577.9': 61°-57° Planar smooth					
																From 2579' to 2582': Rubble					
-20 -2580																					
																2583': Planar irregular					
-25 -2585																		C	100	82	ITS = 112
																2586.7': S. at 88°					

BORING TYPE: HQ3
HOLE DEPTH (ft): 3167
REMARKS: _____

DRILLER: Crux
WATER OBSERVATIONS: 1902 ft, 2592 ft

LOGGED BY: Chris Messenger
CASING: HW to 71 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type ____)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2560
NORTHING: 2153552.632
EASTING: 6514916.08

PROJECT No: 951-20
DATE: 3/17/2023 - 5/19/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
	From 2592' to 2596': Very wet, possible aquifer																				PL(A) = 23
-35 -2595																		C	100	23	
-40 -2600																					
-45 -2605																		C	100	31	PL(A) = 177
-50 -2610																					
-55 -2615	From 2615' to 2615.2': Qtz feldspar pegmatite																	C	100	70	
-56 -2616	QTZ MONZONITE, light gray to white, phaneritic, massive, with biotite/hornblende porphyry, trace chlorite, muscovite, pyroxene, and pyrite																				UCS = 17,917 ITS = 1,103
-60 -2620																					ITS = 1,366

BORING TYPE: HQ3
HOLE DEPTH (ft): 3167
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 1902 ft, 2592 ft

LOGGED BY: Chris Messenger
CASING: HW to 71 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



PAGE 76 OF 91

DIP/AZIMUTH: -90 /

BORING TYPE: <u>HQ3</u>		DRILLER: <u>Crux</u>	LOGGED BY: <u>Chris Messenger</u>
HOLE DEPTH (ft): <u>3167</u>		WATER OBSERVATIONS: <u>1902 ft, 2592 ft</u>	CASING: <u>HW to 71 ft</u>
REMARKS:			

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type _____)
W	Water seep	PL(A)	Point load axial test 1s(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test 1s(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2560
NORTHING: 2153552.632
EASTING: 6514916.08

PROJECT No: 951-20
DATE: 3/17/2023 - 5/19/2023
DIP/AZIMUTH: -90 /

EL	DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
			Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
2694.8																	smooth					
																	2695': 0.3'					
																	2696.1': Planar irregular					
																	From 2696.7' to 2697': Rubble					
-140	2700																					UCS = 12,090
-145	2705																		C	95	26	
	2707	QTZ MONZONITE, light gray to white, phaneritic, massive															From 2708.6' to 2708.9': (2) 39° Planar smooth					
-150	2710																From 2709.6' to 2710': (2) 50° Planar smooth					
	2710.5	CORE LOSS																				
	2711																2711.4': 45° Planar smooth					
																	From 2712' to 2715': Rubble					
-155	2715																From 2715' to 2715.68': Vertical S. at 71°		C	100	31	
																	From 2718' to 2721': 47° Planar smooth, rev angle fractures, rubble					
-160	2720																From 2721' to 2722': Rubble					
	2721	DIORITE, light gray, phaneritic, massive, with trace biotite/hornblende porphyry phenocrysts															From 2722' to 2723': Diorite with biotite/hornblende infill					PL(A) = 1,039
																	From 2724' to 2725': Multiple angle/planar fractures (6)		C	100	51	
-165	2725																From 2725' to 2726': Rubble					
																	2726.5': Planar smooth					
																	2727': Planar smooth					
																	2727.5': Rev angle fracture at 27° and 45° planar smooth					UCS = 9,219

BORING TYPE: HQ3
HOLE DEPTH (ft): 3167
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 1902 ft, 2592 ft

LOGGED BY: Chris Messenger
CASING: HW to 71 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type)
W	Water seep	PL(A)	Point load axial test (50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test (50) (psi)	UCS	Uniaxial stress test (psi)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2560
NORTHING: 2153552.632
EASTING: 6514916.08

PROJECT No: 951-20
DATE: 3/17/2023 - 5/19/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
-175							*									-2730.5': 0° Planar smooth					SLK = Type I
-175							*									-2733': 38° Planar smooth					
-175							*									-2734': Planar smooth					
-175							*									-2734.5': 61° Planar smooth					
-175							*									From 2735' to 2737': Multiple healed and open 70°-80° vertical S. fractures					ITS = 1,582
-175							*									-2739.5': 55° Planar smooth					
-175							*									From 2739.7' to 2740': Vertical S. at 51°-55° inundated smooth					
-175							*									-2741.5': inundated irregular rough					
-175							*									From 2742' to 2743.1': Rubble					UCS = 21,587
-175							*									-2744': 78° Healed/62° vertical S.					
-175							*									From 2744.9' to 2745.75': Vertical S.					
-175							*									From 2747' to 2749': Rubble, 40°-50° angle planar smooth					
-175							*									-2750.1': S. at 67° planar smooth					PL(A) = 750
-175							*									From 2751' to 2752': 38°-46° Planar smooth					
-175							*									-2752.7': 32° Planar smooth					
-175							*									-2754.3': 67° Planar smooth					
-175							*									From 2755' to 2756': Multiple S. fractures at 90°-80° inundated					PL(A) = 750
-175							*									-2758': Planar smooth					
-175							*									-2759': 67° inundated smooth					
-175							*									From 2760' to 2762': S. fracture					
-175							*									-2764.5': 67° Planar					

BORING TYPE: HQ3
HOLE DEPTH (ft): 3167
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 1902 ft, 2592 ft

LOGGED BY: Chris Messenger
CASING: HW to 71 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)



CLIENT: Lane Power & Energy Solutions

SURFACE ELEVATION (ft): 2560

PROJECT No: 951-20

PROJECT: Hydrostor Zevsar

NORTHING: 2153552.632

DATE: 3/17/2023 - 5/19/2023

PROJECT LOCATION: Rosamod, CA

EASTING: 6514916.08

DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
-2770	QTZ MONZONITE, light gray to white, phaneritic, massive, with biotite/hornblende porphyry phenocrysts From 2778.4' to 2779': Shiny luster, black in color														2765': 45° Planar smooth, K-feldspar				SLK = Type I ITS = 1,042 PL(A) = 499		
-2775															2766': 61° Planar smooth						
-2777															2767': 2 J. fractures						
-2780															2768': 32° inundated smooth						
-2785	From 2782' to 2802': Biotite/chlorite present														2768.4': S. fracture				C 100 61		
-2790															2769.1': 90° Planar smooth						
-2795															From 2769.7' to 2770.6': Rubble						
-2800															From 2771' to 2772': S. at 67° planar smooth						
-2805														From 2777.7' to 2778': Clay like, altered				C 100 71			
-2810														From 2778.4' to 2779': Slickensided, deformed							
-2815														From 2782' to 2787': Healed vertical fracture (chlorite)							
-2820														From 2787' to 2787.4': Planar smooth							
-2825														From 2790' to 2791.6': 6 Planar smooth				UCS = 3,927			
-2830														2793.1': 47° Planar smooth, K-feldspar contact							
-2835														From 2794' to 2797': Fractured rubble, chlorite rich, healed fracturing, moderate veining				C 100 30			

BORING TYPE: HQ3

DRILLER: Crux

LOGGED BY: Chris Messenger

HOLE DEPTH (ft): 3167

WATER OBSERVATIONS: 1902 ft, 2592 ft

CASING: HW to 71 ft

REMARKS:

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type <u> </u>)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2560
NORTHING: 2153552.632
EASTING: 6514916.08

PROJECT No: 951-20
DATE: 3/17/2023 - 5/19/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
2802	QTZ MONZONITE, light gray to white, phaneritic, massive, with sections of pegmatite and decomposed biotite/hornblende phenocrysts, trace muscovite, chlorite, and pyroxene																				ITS = 1,023 PL(A) = 712
																					UCS = 22,772
																					SLK = Type I

BORING TYPE: HQ3
HOLE DEPTH (ft): 3167
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 1902 ft, 2592 ft

LOGGED BY: Chris Messenger
CASING: HW to 71 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type ___)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2560
NORTHING: 2153552.632
EASTING: 6514916.08

PROJECT No: 951-20
DATE: 3/17/2023 - 5/19/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
-2840																rubble, healed plagioclase/K-feldspar infill 2-4mm					
-2845																-2843.9': Defected crumple/rubble		C	100	36	PL(A) = 591
-2850																From 2847' to 2852': 40° Planar smooth, 60° inundated rough					
-2855																From 2852' to 2857': (4) 0°-3° Planar smooth					
-2860																From 2853' to 2855.7': Hairline stress fractures, planar smooth along mineralized infill		C	100	36	
-2865																From 2857' to 2860.4': Rubble					
-2870																From 2860.4' to 2861': (4) 38°-42° Planar smooth					
-2875																2862.2': 51° Planar smooth					
-2880																2862.7': 48° Planar smooth with stress line fracture					
-2885																2864': inundated rough irregular					
-2890																2865.7': Biotite slickenside at 49° planar smooth					
-2895																2867.3': Planar irregular					
-2900																2868': Planar irregular					

BORING TYPE: HQ3
HOLE DEPTH (ft): 3167
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 1902 ft, 2592 ft

LOGGED BY: Chris Messenger
CASING: HW to 71 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
L	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2560
NORTHING: 2153552.632
EASTING: 6514916.08

PROJECT No: 951-20
DATE: 3/17/2023 - 5/19/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength					Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing				
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard			Ex Hard	B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
-2875	From 2878' to 2881': Pegmatite														From 2869' to 2870': (5) 0°-10° Planar smooth, K-feldspar				PL(A) = 138 ITS = 417		
															From 2871' to 2872': Vertical S. 78°-88° inundated rough						
															From 2872.4' to 2873': Healed fractures						
															2874': 4° Planar smooth	C	100	66			
															2876': 17° inundated rough				UCS = 4,611 SLK = Type II		
															2876.4': 3° Planar smooth						
															2876.9': 0° Planar smooth						
-2880															From 2878' to 2878.2': Fragmented						
															2879': Fragmented, rough irregular						
															From 2880' to 2881.6': (6) 0°-3° Planar breaks fragmented						
-2885															2880.9': 1° Planar smooth	C	100	61			
															From 2882' to 2883': Rubble						
															From 2885.6' to 2886.4': (3) 38°-40° Planar smooth on K-feldspar infill						
															From 2887' to 2888': Decomposed rubble						
-2890														2889.1': Planar irregular							
														2890': Rev angle planar irregular							
														2891': 3° Planar, defected							
-2895	From 2894.8' to 2895.8': Qtz feldspar pegmatite													From 2892' to 2893': 30°-40° Planar irregular break, healed K-feldspar fractures							
														2893.5': Planar rough							
														From 2893.7' to 2894': Rubble							
														2896.1': 52° Planar smooth							
														From 2897' to 2898.2': 80°-90° Vertical fracture inundated rough							
														From 2899' to 2902.6': (16) 3°-0° Planar smooth fractures, K-feldspar contact							
-2900														2903.8': Planar irregular	C	100	46	ITS = 1,454 SLK = Type I			

BORING TYPE: HQ3
HOLE DEPTH (ft): 3167
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 1902 ft, 2592 ft

LOGGED BY: Chris Messenger
CASING: HW to 71 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type ___)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2560
NORTHING: 2153552.632
EASTING: 6514916.08

PROJECT No: 951-20
DATE: 3/17/2023 - 5/19/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing							
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F- Fault	Type	Core Rec. %	RQD %	Test Results & Comments				
																2904.2': Vertical S. rough, 39° Planar smooth biotite				PL(A) = 224					
-2910																From 2904.9' to 2906': Rubble, defected									
																From 2905' to 2906': Rev angle fracture									
																From 2907' to 2910.2': Broken fragmented 0°-19°, healed K-feldspar and 7 open fractures									
																From 2911' to 2911.4': (2) 71° Planar smooth fractures				C	100	20			
-2915																From 2912' to 2912.6': 61° Planar smooth									
																From 2913.6' to 2917': Rubble, stress J. fractures									
																From 2917' to 2918.2': 90° Vertical inundated rough									
																2918': 16°-31° J. stress fractures, rubble					C	100	36		
-2920																From 2922' to 2923': Vertical fracture inundated rough									
																From 2925.3' to 2928': Rubble									
																From 2929' to 2931': Vertical S. inundated rough (pegmatite)									
-2925																From 2932' to 2932.7': Rubble					C	100	44		
																From 2934' to 2935': inundated rough									
																2935.6': inundated rough									
																From 2936' to 2937': Vertical S. inundated rough									
-2930																From 2937' to 2942': Healed multiline fractures, healed K-feldspar					SLK = Type II				
-2935																									

BORING TYPE: HQ3
HOLE DEPTH (ft): 3167
REMARKS: _____

DRILLER: Crux
WATER OBSERVATIONS: 1902 ft, 2592 ft

LOGGED BY: Chris Messenger
CASING: HW to 71 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type ____)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2560
NORTHING: 2153552.632
EASTING: 6514916.08

PROJECT No: 951-20
DATE: 3/17/2023 - 5/19/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
2945																					ITS = 877
2950																					
2952	QTZ MONZONITE, light gray to white, phaneritic, massive, with biotite/hornblende, trace muscovite chlorite, pyroxene																				UCS = 23,002
2955																					
2960																					
2965																					
2970																					

BORING TYPE: HQ3
HOLE DEPTH (ft): 3167
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 1902 ft, 2592 ft

LOGGED BY: Chris Messenger
CASING: HW to 71 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type ___)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
L	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)



CLIENT: Lane Power & Energy Solutions

SURFACE ELEVATION (ft): 2560

PROJECT No: 951-20

PROJECT: Hydrostor Zevsar

NORTHING: 2153552.632

DATE: 3/17/2023 - 5/19/2023

PROJECT LOCATION: Rosamod, CA

EASTING: 6514916.08

DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
2980	From 2986.6' to 2987.2': Qtz feldspar pegmatite																				SLK = Type I PL(A) = 717 TRI = 26,949 UCS = 23,574
2985																		C	100	81	
2990																					
2995																		C	100	92	
3000																					
3005																		C	100	90	ITS = 1,319 SLK = Type I
																					TRI = 36,097

BORING TYPE: HQ3

DRILLER: Crux

LOGGED BY: Chris Messenger

HOLE DEPTH (ft): 3167

WATER OBSERVATIONS: 1902 ft, 2592 ft

CASING: HW to 71 ft

REMARKS: _____

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type ____)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
L	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2560
NORTHING: 2153552.632
EASTING: 6514916.08

PROJECT No: 951-20
DATE: 3/17/2023 - 5/19/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
3015																(2) 38°-32° J. stress fractures planar smooth, (2) 90° vertical fractures					
																3009.2': 4° Planar smooth					
																From 3010' to 3011.1': (5) 3°-11° J. stress fractures, planar smooth		C	100	71	
																From 3012.8' to 3013': Rubble, pegmatite					
																3014': 0° Planar smooth					
																3015.1': 4°-8° Planar irregular					
																3015.5': 77° Planar					
																3016.25': inundated rough-smooth (K-feldspar white infill)					
																From 3016.8' to 3017': 45° Planar smooth					
																3018.55': 51° Planar					
																From 3019' to 3020.2': Partially healed 38° fracture		C	100	40	
																From 3020' to 3022': 90°-80° Vertical fractures, healed white K-feldspar infill, increase in pink K-feldspar					
																From 3023' to 3023.4': (3) 38° J. fractures planar smooth					
																From 3024.1' to 3026': (13) 45°-65° J. stress fractures planar smooth					
																From 3027.1' to 3027.9': Planar irregular smooth					
																From 3028.4' to 3031': 30° - Rev angle 60° (6)					
																From 3033' to 3038': Multiple 90°-45°-0° fractures, rubble		C	100	25	
																From 3039.7' to 3039.9': 4°-11° Planar irregular rough					
																From 3040.4' to 3040.9': 22°-11° Stepped-planar rough-smooth					
																3042.1': Planar rough					
																3042.7': 45° Planar rough		C	100	50	

BORING TYPE: HQ3
HOLE DEPTH (ft): 3167
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 1902 ft, 2592 ft

LOGGED BY: Chris Messenger
CASING: HW to 71 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type ___)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
L	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions

SURFACE ELEVATION (ft): 2560

PROJECT No: 951-20

PROJECT: Hydrostor Zevsar

NORTHING: 2153552.632

DATE: 3/17/2023 - 5/19/2023

PROJECT LOCATION: Rosamod, CA

EASTING: 6514916.08

DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities	Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard				Type	Core Rec. %	RQD %	Test Results & Comments
3050																3043.5': 35° Planar rough 3044.5': 90° Vertical From 3046' to 3047': Rubble 3046.1': S. at 90° rough From 3048' to 3049.2': Vertical S. fractures at 90°-79°, inundated rough				
3055																3052.48': Planar smooth 3053.51': Planar smooth From 3054' to 3056': Vertical stepped stress fractures, rubble, inundated smooth-rough 3056.7': 45° Planar smooth 3057.2': (2) 0° Planar smooth 3057.9': 0° Planar smooth From 3059' to 3059.6': Rubble	C	100	60	
3060																3061': Planar irregular-smooth 0°-4° From 3061.6' to 3082': (2) 6°-0° Planar smooth 3062.8': Planar smooth at pegmatite contact From 3063.9' to 3065.6': (5) 40°-60° Stress J. fractures - planar smooth, increase in K-feldspar, hairline healed throughout From 3066' to 3068': Vertical S. at 90°, slickenside planar smooth From 3069' to 3072': (7) 0° Planar smooth	C	100	68	
3065																				
3070																				
3075																3073': Planar smooth 3073.78': 4° Planar smooth 3075.1': Planar rough	C	100	97	

BORING TYPE: HQ3

DRILLER: Crux

LOGGED BY: Chris Messenger

HOLE DEPTH (ft): 3167

WATER OBSERVATIONS: 1902 ft, 2592 ft

CASING: HW to 71 ft

REMARKS:

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type <u> </u>)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions

SURFACE ELEVATION (ft): 2560

PROJECT No: 951-20

PROJECT: Hydrostor Zevsar

NORTHING: 2153552.632

DATE: 3/17/2023 - 5/19/2023

PROJECT LOCATION: Rosamod, CA

EASTING: 6514916.08

DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)				Discontinuities		Sampling & In Situ Testing			
																			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard		0.05	0.25	0.50	1.00	2.50	5.00				
3085																		3080.4': 4° Planar smooth						
																		3081': Planar irregular smooth						
																		3082.3': 6° Planar smooth						
																		3083': 0° Planar smooth	C	100	63			
																		3083.3': 58° inundated smooth						
																		From 3083.9' to 3084.3': Rev angle 22° and 57° planar smooth						
3090																		From 3085' to 3087': Vertical S. at 90°, rubble inundated rough						
																		From 3085.7' to 3086.2': 51° Planar smooth, offset healed fractures						
																		3090': Stepped-rough-smooth (mineralization)						
																		3090.9': 0° Planar smooth	C	100	27			
3095																		From 3092' to 3092.5': Rubble						
																		From 3093.5' to 3093.9': 30° J. fracture planar rough						
																		From 3094' to 3097': 2 Stress J. fractures fully healed at contact, planar smooth						
3100																		3097.9': 69° S. fracture planar smooth						
																		3099.7': 32° Planar smooth						
																		From 3101' to 3102': Rubble						
3105																		From 3102' to 3117': Hairline vertical/horizontal stress fractures multi directional, healed fractures	C	100	0			
3110																								
																			C	100	37			

BORING TYPE: HQ3

DRILLER: Crux

LOGGED BY: Chris Messenger

HOLE DEPTH (ft): 3167

WATER OBSERVATIONS: 1902 ft, 2592 ft

CASING: HW to 71 ft

REMARKS: _____

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type _____)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
WL	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2560
NORTHING: 2153552.632
EASTING: 6514916.08

PROJECT No: 951-20
DATE: 3/17/2023 - 5/19/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
3120																					
3125																					
3130																					
3132	QTZ MONZONITE, light gray to white, massive, with biotite/hornblende porphyry, trace muscovite, pyroxene, and pyrite																				
3135																					
3140																					
3145	From 3144' to 3148.5': Qtz feldspar pegmatite																				

BORING TYPE: HQ3
HOLE DEPTH (ft): 3167
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 1902 ft, 2592 ft

LOGGED BY: Chris Messenger
CASING: HW to 71 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2560
NORTHING: 2153552.632
EASTING: 6514916.08

PROJECT No: 951-20
DATE: 3/17/2023 - 5/19/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength					Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard		B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
3155 -595 3160 -600 3165 -605															From 3150.1' to 3152': 26° inundated smooth-rough, healed					
															3153': 90°-70°					
															3155': 41° Irregular stepped-rough		C	100	70	
															3155.9': 12° K-feldspar contact planar smooth					
															3157.6': Planar irregular					
															From 3158.9' to 3159.2': Large headed 4mm, 48° offset fractures					
															3159.9': Planar irregular					
															3160.75': 44° Planar smooth					
															From 3161' to 3162': 87° Vertical inundated rough					
Bottom of borehole at 3167.0 feet.																				
-610 -615 -620																				

BORING TYPE: HQ3
HOLE DEPTH (ft): 3167
REMARKS: _____

DRILLER: Crux
WATER OBSERVATIONS: 1902 ft, 2592 ft

LOGGED BY: Chris Messenger
CASING: HW to 71 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type ____)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)



CLIENT: Lane Power & Energy Solutions

SURFACE ELEVATION (ft): 2570

PROJECT No: 951-20

PROJECT: Hydrostor Zevsar

NORTHING: 2154898.691

DATE: 6/1/2023 - 7/25/2023

PROJECT LOCATION: Rosamod, CA

EASTING: 6515647.859

DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
0	Well Casing																				
5																					
10																					
15																					
20																					
25																					
30																					

BORING TYPE: HQ3

DRILLER: CruX

LOGGED BY: Chris Messenger

HOLE DEPTH (ft): 3045

WATER OBSERVATIONS: 795 ft, 826.5 ft

CASING: HW to 70 ft

REMARKS: _____

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type <u> </u>)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154898.691
EASTING: 6515647.859

PROJECT No: 951-20
DATE: 6/1/2023 - 7/25/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
40 2530																					
45 2525																					
50 2520																					
55 2515																					
60 2510																					
65 2505																					

BORING TYPE: HQ3
HOLE DEPTH (ft): 3045
REMARKS: _____

DRILLER: CruX
WATER OBSERVATIONS: 795 ft, 826.5 ft

LOGGED BY: Chris Messenger
CASING: HW to 70 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type __)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions

SURFACE ELEVATION (ft): 2570

PROJECT No: 951-20

PROJECT: Hydrostor Zevsar

NORTHING: 2154898.691

DATE: 6/1/2023 - 7/25/2023

PROJECT LOCATION: Rosamod, CA

EASTING: 6515647.859

DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
70	QTZ MONZONITE, light gray to white, phaneritic, massive, with biotite, chlorite, and epidote, trace hornblende and muscovite																	C	93	67	
75																					
76.3	CORE LOSS																				
77																					
80																		C	100	88	
85																					
90																		C	100	42	
95																					
100																		C	100	17	

From 100' to 140': High fracturing frequency, partly rubble

BORING TYPE: HQ3

DRILLER: Crux

LOGGED BY: Chris Messenger

HOLE DEPTH (ft): 3045

WATER OBSERVATIONS: 795 ft, 826.5 ft

CASING: HW to 70 ft

REMARKS: _____

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type ____)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
WL	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions

SURFACE ELEVATION (ft): 2570

PROJECT No: 951-20

PROJECT: Hydrostor Zevsar

NORTHING: 2154898.691

DATE: 6/1/2023 - 7/25/2023

PROJECT LOCATION: Rosamod, CA

EASTING: 6515647.859

DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
110																					
115																		C	100	32	
120																					
122.5	CORE LOSS																	C	90	21	
123.5																					
125																					
130																					
135	From 133' to 137': K feldspar																	C	100	40	

BORING TYPE: HQ3

DRILLER: Crux

LOGGED BY: Chris Messenger

HOLE DEPTH (ft): 3045

WATER OBSERVATIONS: 795 ft, 826.5 ft

CASING: HW to 70 ft

REMARKS: _____

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type <u> </u>)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
WL	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions

SURFACE ELEVATION (ft): 2570

PROJECT No: 951-20

PROJECT: Hydrostor Zevsar

NORTHING: 2154898.691

DATE: 6/1/2023 - 7/25/2023

PROJECT LOCATION: Rosamod, CA

EASTING: 6515647.859

DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
145 2425																		C	100	80	
150 2420																		C	100	80	
155 2415																					
160 2410	QTZ MONZONITE, light gray to white, phaneritic, massive, with biotite porphyry, trace epidote, chlorite, muscovite, and pyrite															From 160' to 161.9': Planar/smooth		C	100	70	
165 2405																From 165' to 169': (9) 20°-32° Planar/smooth joint					
170 2400																170.6': 0° Planar 171': 69° Planar 171.8': 72° Planar 172.6': Inundated/planar 58° 174.2': 42° Inundated		C	95	57	

BORING TYPE: HQ3

DRILLER: Crux

LOGGED BY: Chris Messenger

HOLE DEPTH (ft): 3045

WATER OBSERVATIONS: 795 ft, 826.5 ft

CASING: HW to 70 ft

REMARKS: _____

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type ____)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
WL	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154898.691
EASTING: 6515647.859

PROJECT No: 951-20
DATE: 6/1/2023 - 7/25/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
178.7 179.2	CORE LOSS															planar					
180																From 174.5' to 175': (3) 0° Planar					
185																From 175' to 178': (6) Planar 0°-20°					
190																From 180' to 182': (4) 0° Planar		C	100	57	
195																From 185' to 187': Rubble					
200																187': (5) 47°-62° J. fracture soft					
205																191': 0° Inundated planar		C	100	77	
																192': 4° Inundated planar					
																192.6': 22° Planar					
																From 194' to 194.6': Wedge rev 22° and 25° inundated rough					
																From 195' to 196': Rubble					
																197': 4° Planar					
																198.6': 0° Planar					
																From 199' to 200': (2) 0° Planar					
																201.9': 38° Planar smooth		C	100	66	
																From 202' to 203.5': (5) 0°-6° Planar smooth					
																204': 78° Vertical S. inundated rough					
																From 205' to 206': (2) 0°-4° Planar					
																206.7': 38° Planar rough					
																From 207' to 209': (4) 26°-32° J. fracture smooth planar					

BORING TYPE: HQ3
HOLE DEPTH (ft): 3045
REMARKS: _____

DRILLER: Crux
WATER OBSERVATIONS: 795 ft, 826.5 ft

LOGGED BY: Chris Messenger
CASING: HW to 70 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type _____)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
L	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154898.691
EASTING: 6515647.859

PROJECT No: 951-20
DATE: 6/1/2023 - 7/25/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
215 2355	QTZ MONZONITE, light gray to white, phaneritic, massive, with biotite, trace epidote, chlorite, hornblende, pyrite																	C	100	86	-213.4': 52° Planar smooth From 214' to 216': (4) 3°-10° Planar 217.1': Planar inundated 218.9': Planar inundated
220 2350																		C	100	75	222': 0° Planar 222.5': 58° Inundated rough 224.3': 17° Planar smooth From 225' to 228': (9) 0°-8° Planar From 228.5' to 229.5': (2) 22° and 38° Inundated/smooth From 230' to 231': (2) 0° Planar
225 2345																		C	100	71	From 232' to 233': (2) 40° and 81° Vertical S. inundated rough From 234' to 237': (6) 0°-17° Planar
230 2340																		C	100	94	241.1': 16°-21° Wedge 242': 0° Planar From 243' to 244': (2) 67° J. fracture
235 2335																					
240 2330																					

BORING TYPE: HQ3
HOLE DEPTH (ft): 3045
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 795 ft, 826.5 ft

LOGGED BY: Chris Messenger
CASING: HW to 70 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
L	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154898.691
EASTING: 6515647.859

PROJECT No: 951-20
DATE: 6/1/2023 - 7/25/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
250	From 256.4' to 256.9': Qtz feldspar																				
255																					
260																					
265																					
270																					
275																					

BORING TYPE: HQ3
HOLE DEPTH (ft): 3045
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 795 ft, 826.5 ft

LOGGED BY: Chris Messenger
CASING: HW to 70 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154898.691
EASTING: 6515647.859

PROJECT No: 951-20
DATE: 6/1/2023 - 7/25/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
285	From 295' to 296': Qtz feldspar pegmatite																	C	100	64	
285																					
285																					
285																					
290	From 295' to 296': Qtz feldspar pegmatite																	C	100	84	
290																					
290																					
290																					
295	From 295' to 296': Qtz feldspar pegmatite																				
295																					
295																					
295																					
300	From 308.7' to 309': Qtz feldspar pegmatite																				
300																					
300																					
300																					
305	From 308.7' to 309': Qtz feldspar pegmatite																	C	100	97	
305																					
305																					
305																					
310	From 308.7' to 309': Qtz feldspar pegmatite																	C	100	95	
310																					
310																					
310																					

BORING TYPE: HQ3
HOLE DEPTH (ft): 3045
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 795 ft, 826.5 ft

LOGGED BY: Chris Messenger
CASING: HW to 70 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154898.691
EASTING: 6515647.859

PROJECT No: 951-20
DATE: 6/1/2023 - 7/25/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
320																					
325																					
330																					
335																					
340																					
345																					

BORING TYPE: HQ3
HOLE DEPTH (ft): 3045
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 795 ft, 826.5 ft

LOGGED BY: Chris Messenger
CASING: HW to 70 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
WL	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154898.691
EASTING: 6515647.859

PROJECT No: 951-20
DATE: 6/1/2023 - 7/25/2023
DIP/AZIMUTH: -90 /

EL	DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)		Discontinuities		Sampling & In Situ Testing																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																											
			Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard		B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																										
355 2215		From 362' to 365': Qtz feldspar pegmatite																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																													

BORING TYPE: HQ3
HOLE DEPTH (ft): 3045
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 795 ft, 826.5 ft

LOGGED BY: Chris Messenger
CASING: HW to 70 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type __)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
WL	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154898.691
EASTING: 6515647.859

PROJECT No: 951-20
DATE: 6/1/2023 - 7/25/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
390 2180																					
395 2175																					
400 2170																					
405 2165																					
410 2160																					
415 2155																					
418.75 419	DIORITE																				

BORING TYPE: HQ3
HOLE DEPTH (ft): 3045
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 795 ft, 826.5 ft

LOGGED BY: Chris Messenger
CASING: HW to 70 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type ___)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154898.691
EASTING: 6515647.859

PROJECT No: 951-20
DATE: 6/1/2023 - 7/25/2023
DIP/AZIMUTH: -90 /

EL	DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																								
			Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																					
425	426	DIORITE																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																									</

BORING TYPE: HQ3
HOLE DEPTH (ft): 3045
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 795 ft, 826.5 ft

LOGGED BY: Chris Messenger
CASING: HW to 70 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type ___)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)

CLIENT: Lane Power & Energy Solutions

SURFACE ELEVATION (ft): 2570

PROJECT No: 951-20

PROJECT: Hydrostor Zevsar

NORTHING: 2154898.691

DATE: 6/1/2023 - 7/25/2023

PROJECT LOCATION: Rosamod, CA

EASTING: 6515647.859

DIP/AZIMUTH: -90 /

[illegible]

BORING TYPE: HQ3

DRILLER: Crux

LOGGED BY: Chris Messenger

HOLE DEPTH (ft): 3045

WATER OBSERVATIONS: 795 ft, 826.5 ft

CASING: HW to 70 ft

REMARKS:

SAMPLING & IN SITU TESTING LEGEND			
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)
		SLK	Slake durability test (Type _____)
		TRI	Triaxial stress test (psi)
		UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154898.691
EASTING: 6515647.859

PROJECT No: 951-20
DATE: 6/1/2023 - 7/25/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
495																From 491' to 493.7': 0°-8° Planar smooth		C	100	65	
500																From 494' to 495': Vertical speed rough					
505																From 495' to 496': (3) 0°-9° Planar slickenside					
510																From 496' to 497': 90° Vertical					
515																From 498' to 499': (3) 17°, 19°, 24° Inundated slickenside					
520																From 500.75' to 503': (6) 6°-9° Planar smooth		C	100	80	
																From 503.8' to 504.4': (3) 0°-7° Planar smooth					
																From 511' to 515': Calcite healed fracture 7-10mm thick		C	100	100	
																519': 52° Planar smooth					
																522': 41° Planar smooth		C	100	98	

BORING TYPE: HQ3
HOLE DEPTH (ft): 3045
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 795 ft, 826.5 ft

LOGGED BY: Chris Messenger
CASING: HW to 70 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type __)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
WL	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154898.691
EASTING: 6515647.859

PROJECT No: 951-20
DATE: 6/1/2023 - 7/25/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)			Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard		0.05	0.25	0.50	2.50	5.00	B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %
																		From 526' to 527': 84° Vertical S. veined					
530																		529': Multiple 70°-90° Vertical veined fractured healed and open					
																		533': 50° Planar smooth, 42° irregular smooth	C	100	90		
535																		536': 71° Wedge rev angle 69°					
																		From 540' to 541': 6" Vertical S. planar slickenside					
540																		541': 0° Planar 542': 0° Planar decomposed	C	95	51		
																		From 544' to 544.6': 48° Irregular inundated slickenside					
546.5 547	CORE LOSS																						
550																		From 551' to 552.7': (6) 0°-17° Planar smooth					
																		From 553' to 553.75': 79° Stepped slickenside	C	100	70		
555																							
																		From 559' to 560': Decomposed					

BORING TYPE: HQ3
HOLE DEPTH (ft): 3045
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 795 ft, 826.5 ft

LOGGED BY: Chris Messenger
CASING: HW to 70 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
WL	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154898.691
EASTING: 6515647.859

PROJECT No: 951-20
DATE: 6/1/2023 - 7/25/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
565	QTZ MONZONITE, light gray to white, phaneritic, massive, with rich plagioclase and deflection biotite, trace muscovite, pyrite, chlorite, and K feldspar CORE LOSS																				
566																					
567																					
570																					
575																					
580																					
585																					
590																					

BORING TYPE: HQ3
HOLE DEPTH (ft): 3045
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 795 ft, 826.5 ft

LOGGED BY: Chris Messenger
CASING: HW to 70 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
WL	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

CLIENT: Lane Power & Energy Solutions

SURFACE ELEVATION (ft): 2570

PROJECT No: 951-20

PROJECT: Hydrostor Zevsar

NORTHING: 2154898.691

DATE: 6/1/2023 - 7/25/2023

PROJECT LOCATION: Rosamod, CA

EASTING: 6515647.859

DIP/AZIMUTH: -90 /

[illegible]

BORING TYPE: HQ3

DRILLER: Crux

LOGGED BY: Chris Messenger

HOLE DEPTH (ft): 3045

WATER OBSERVATIONS: 795 ft, 826.5 ft

CASING: HW to 70 ft

REMARKS:

SAMPLING & IN SITU TESTING LEGEND			
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)
		SLK	Slake durability test (Type _____)
		TRI	Triaxial stress test (psi)
		UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154898.691
EASTING: 6515647.859

PROJECT No: 951-20
DATE: 6/1/2023 - 7/25/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
635	From 658' to 658.75': Qtz feldspar														0.05	From 630' to 637': (3) 0°-7° Planar smooth					
640															0.25	From 637' to 638': (4) 20°-24° J. fractures planar smooth		C	100	90	
645															0.50	639': 21° Planar smooth					
650															2.50	From 640' to 653': (2) 0°-7° Planar smooth					
655															5.00	From 653.3' to 654': 2°-6° Planar irregular stepped rev					
660																From 655.4' to 656': 40°-52° Stepped rough					
																From 656' to 657': Vertical healed Ca+2					
																From 658' to 659': (2) Vertical S. J. fractures stepped rough 79°-86°		C	100	78	
																660.3': 32° Planar smooth					

BORING TYPE: HQ3
HOLE DEPTH (ft): 3045
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 795 ft, 826.5 ft

LOGGED BY: Chris Messenger
CASING: HW to 70 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type ___)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
L	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154898.691
EASTING: 6515647.859

PROJECT No: 951-20
DATE: 6/1/2023 - 7/25/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
670	From 676' to 679': Qtz feldspar pegmatite															From 665' to 667': (3) 0°-12° Planar smooth		C	100	64	
675																-668.25': 48° Inundated slickenside					
680																-671': Healed fracture biotite/chlorite					
685	From 685' to 687': Qtz feldspar pegmatite															From 672' to 674': Vertical S. stepped rough					
690	From 690' to 691': Qtz feldspar pegmatite															From 674' to 675': (3) Planar slickenside defected					
695																From 676' to 677': Rubble		C	100	55	
																680': 14° Stepped rough					
																From 682' to 682.8': 7° Planar smooth					
																From 682.6' to 693.1': 89° Vertical S. inundated smooth					
																From 682.7' to 685': Deformed rubble					
																From 685' to 687': Hairline vertical fracture throughout		C	100	62	
																From 689' to 690': Vertical S.					
																From 690' to 690.25': Rubble					
																From 693.5' to 696': (5) 0°-22° Planar smooth					
																From 696.5' to 698': 90° Vertical S. inundated smooth		C	90	31	
																From 699' to 700': (2) 0° Planar smooth					

BORING TYPE: HQ3
HOLE DEPTH (ft): 3045
REMARKS: _____

DRILLER: Crux
WATER OBSERVATIONS: 795 ft, 826.5 ft

LOGGED BY: Chris Messenger
CASING: HW to 70 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type _____)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
WL	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions

SURFACE ELEVATION (ft): 2570

PROJECT No: 951-20

PROJECT: Hydrostor Zevsar

NORTHING: 2154898.691

DATE: 6/1/2023 - 7/25/2023

PROJECT LOCATION: Rosamod, CA

EASTING: 6515647.859

DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
704	CORE LOSS																				
705	From 705' to 707.8': Qtz feldspar pegmatite																				
710																		C	90	12	
712	CORE LOSS																				
713																					
715																					
720																					
725	From 725' to 726.7': K feldspar																				
730																					

BORING TYPE: HQ3

DRILLER: Crux

LOGGED BY: Chris Messenger

HOLE DEPTH (ft): 3045

WATER OBSERVATIONS: 795 ft, 826.5 ft

CASING: HW to 70 ft

REMARKS: _____

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type _____)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
WL	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154898.691
EASTING: 6515647.859

PROJECT No: 951-20
DATE: 6/1/2023 - 7/25/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
740	QTZ MONAZITE, light gray to white, phaneritic, massive, dominant in sodium and calcium rich plagioclase, biotite, and quartz, trace muscovite, chlorite, epidote, and hornblende																	C	100	64	
745																					
750																					
755																					
760																					
765																					
770																					
775																					

BORING TYPE: HQ3
HOLE DEPTH (ft): 3045
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 795 ft, 826.5 ft

LOGGED BY: Chris Messenger
CASING: HW to 70 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154898.691
EASTING: 6515647.859

PROJECT No: 951-20
DATE: 6/1/2023 - 7/25/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
775	From 778' to 779': Qtz feldspar pegmatite															From 771' to 775': (5) 12°-20° J. fractures planar smooth					
780																From 775.5' to 779': Rubble		C	100	47	
785																781': Planar irregular From 782.1' to 784': Hairline partially healed S. fracture 79°-90° inundated rough					
790	From 786.7' to 787.6': Qtz feldspar pegmatite															From 784' to 786.7': (4) 0°-7° Planar smooth					
795																From 786.7' to 788': Rubble		C	100	52	
796																From 789' to 790': 90° S. inundated stepped rough					
796.2	CORE LOSS															From 791' to 795': (6) 20° Planar smooth					
797																From 794' to 794.7': 44°					
800																From 797' to 798': (2) Planar irregular		C	98	71	
																From 801' to 805': (5) defected 0°-22° breaks					

BORING TYPE: HQ3
HOLE DEPTH (ft): 3045
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 795 ft, 826.5 ft

LOGGED BY: Chris Messenger
CASING: HW to 70 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154898.691
EASTING: 6515647.859

PROJECT No: 951-20
DATE: 6/1/2023 - 7/25/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
810																					
815																					
820																					
825																					
825.5	CORE LOSS																				
826.5																					
830																					
835	From 834' to 835': Qtz feldspar pegmatite																				

BORING TYPE: HQ3
HOLE DEPTH (ft): 3045
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 795 ft, 826.5 ft

LOGGED BY: Chris Messenger
CASING: HW to 70 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type __)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154898.691
EASTING: 6515647.859

PROJECT No: 951-20
DATE: 6/1/2023 - 7/25/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
845 1725	From 871' to 872': Qtz feldspar pegmatite															From 840' to 842': (3) 20° Planar smooth					
																842.6': 47° Inundated rough					
																From 843.7' to 846': (5) 50°-60° J. fractures planar slickensides, chlorite					
850 1720																847.1': Planar smooth	C	100	46		
																From 848.6' to 850': Vertical 90° S. fractures planar smooth					
855 1715																From 850' to 865': 45°-90° stress fractured exc 855'-857'					
																		C	100	34	
860 1710																					
865 1705																From 865' to 870': (13) 22°-51° Inundated smooth					
																		C	100	27	
870 1700																From 870' to 874': Rubble					

BORING TYPE: HQ3
HOLE DEPTH (ft): 3045
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 795 ft, 826.5 ft

LOGGED BY: Chris Messenger
CASING: HW to 70 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
WL	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154898.691
EASTING: 6515647.859

PROJECT No: 951-20
DATE: 6/1/2023 - 7/25/2023
DIP/AZIMUTH: -90 /

EL	DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing					
			Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	ROD %	Test Results & Comments		
1690	880	QTZ MONZONITE, light gray to white, phaneritic, massive, high in chlorite and epidote																		C	100	20	From 876' to 880': (16) 40°-90° Planar smooth From 880' to 890': Rubble exs 882'-885' (9) 40°-50° stress fractures, planar smooth	
1685	885																				C	100		10
1680	890																							
1675	895	From 906' to 908': Qtz feldspar																			C	100	0	From 895' to 905': Rubble, multiple fractures throughout From 905' to 915': Rubble, multiple fractures throughout
1670	900																							
1665	905																					C	100	

BORING TYPE: HQ3
HOLE DEPTH (ft): 3045
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 795 ft, 826.5 ft

LOGGED BY: Chris Messenger
CASING: HW to 70 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type ___)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
WL	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)

CLIENT: Lane Power & Energy Solutions

SURFACE ELEVATION (ft): 2570

PROJECT No: 951-20

PROJECT: Hydrostor Zevsar

NORTHING: 2154898.691

DATE: 6/1/2023 - 7/25/2023

PROJECT LOCATION: Rosamod, CA

EASTING: 6515647.859

DIP/AZIMUTH: -90 /

[illegible]

BORING TYPE: HQ3

DRILLER: Crux

LOGGED BY: Chris Messenger

HOLE DEPTH (ft): 3045

WATER OBSERVATIONS: 795 ft, 826.5 ft

CASING: HW to 70 ft

REMARKS:

SAMPLING & IN SITU TESTING LEGEND			
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)
		SLK	Slake durability test (Type _____)
		TRI	Triaxial stress test (psi)
		UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154898.691
EASTING: 6515647.859

PROJECT No: 951-20
DATE: 6/1/2023 - 7/25/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
950																					
955																					
960	From 959' to 960.3': Qtz feldspar																	C	100	8	
961 961.3	CORE LOSS																	C	97	0	
965																					
970	From 967' to 969': Qtz feldspar																	C	100	0	
975	From 970' to 980': Qtz feldspar																	C	100	12	

BORING TYPE: HQ3
HOLE DEPTH (ft): 3045
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 795 ft, 826.5 ft

LOGGED BY: Chris Messenger
CASING: HW to 70 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type ___)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
WL	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154898.691
EASTING: 6515647.859

PROJECT No: 951-20
DATE: 6/1/2023 - 7/25/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
1017.4	CORE LOSS																				
1018.9																					
1020																					
1025																					
1030																					
1035																					
1040	From 1040' to 1041': Qtz feldspar																				
1040.0	CORE LOSS																				
1041																					
1045																					

BORING TYPE: HQ3
HOLE DEPTH (ft): 3045
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 795 ft, 826.5 ft

LOGGED BY: Chris Messenger
CASING: HW to 70 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions

SURFACE ELEVATION (ft): 2570

PROJECT No: 951-20

PROJECT: Hydrostor Zevsar

NORTHING: 2154898.691

DATE: 6/1/2023 - 7/25/2023

PROJECT LOCATION: Rosamod, CA

EASTING: 6515647.859

DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
1055	From 1062.8' to 1064.1': Qtz feldspar														0.05 0.25 0.50 2.50 5.00	-1052.8': 4° Planar smooth		C	100	60	
1060																From 1054.5' to 1054.8': (2) 49° J. fractures undulating smooth					
																From 1055' to 1056': Rubble					
																1057': Planar irregular					
																From 1057.8' to 1060': 90°-67° Stress J. fracture, S. fracture stepped rough					
																From 1060' to 1061.7': Rubble		C	100	47	
1065																1063.8': Planar smooth					
																From 1066.6' to 1067.4': 90° S. fracture undulating rough					
1070																From 1067.4' to 1069': 90° S. fracture undulating smooth					
																From 1070' to 1072.9': 90° S. rubble					
																From 1072.9' to 1074.6': Undulating smooth large 90° healed fracture, calcite		C	100	26	
1075																From 1075' to 1076.8': (3) 45°-50° Undulating and 19° 84° undulating rough stress fracture					
																From 1077' to 1081': Multiple fracturing no 4" sample 0°-80° undulating smooth					
1080																From 1082' to 1085': 80°-90° Healed (biotite) defected fracture		C	100	49	
																From 1083.2' to 1085': (3) 84°-90° stacked stress J. fractures stepped rough					

BORING TYPE: HQ3

DRILLER: Crux

LOGGED BY: Chris Messenger

HOLE DEPTH (ft): 3045

WATER OBSERVATIONS: 795 ft, 826.5 ft

CASING: HW to 70 ft

REMARKS: _____

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type _____)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions

SURFACE ELEVATION (ft): 2570

PROJECT No: 951-20

PROJECT: Hydrostor Zevsar

NORTHING: 2154898.691

DATE: 6/1/2023 - 7/25/2023

PROJECT LOCATION: Rosamod, CA

EASTING: 6515647.859

DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
1090	From 1089' to 1090': Qtz feldspar																				
1095																					
1100																					
1101	CORE LOSS																				
1105																					
1110																					
1115																					

BORING TYPE: HQ3

DRILLER: Crux

LOGGED BY: Chris Messenger

HOLE DEPTH (ft): 3045

WATER OBSERVATIONS: 795 ft, 826.5 ft

CASING: HW to 70 ft

REMARKS: _____

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type _____)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154898.691
EASTING: 6515647.859

PROJECT No: 951-20
DATE: 6/1/2023 - 7/25/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
1125																					
1130																					
1135																					
1140																					
1145																					
1150																					

BORING TYPE: HQ3
HOLE DEPTH (ft): 3045
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 795 ft, 826.5 ft

LOGGED BY: Chris Messenger
CASING: HW to 70 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

CLIENT: Lane Power & Energy Solutions

SURFACE ELEVATION (ft): 2570

PROJECT No: 951-20

PROJECT: Hydrostor Zevsar

NORTHING: 2154898.691

DATE: 6/1/2023 - 7/25/2023

PROJECT LOCATION: Rosamod, CA

EASTING: 6515647.859

DIP/AZIMUTH: -90 /

[illegible]

BORING TYPE: HQ3

DRILLER: Crux

LOGGED BY: Chris Messenger

HOLE DEPTH (ft): 3045

WATER OBSERVATIONS: 795 ft, 826.5 ft

CASING: HW to 70 ft

REMARKS:

SAMPLING & IN SITU TESTING LEGEND			
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)
		SLK	Slake durability test (Type _____)
		TRI	Triaxial stress test (psi)
		UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154898.691
EASTING: 6515647.859

PROJECT No: 951-20
DATE: 6/1/2023 - 7/25/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F- Fault	Type	Core Rec. %	RQD %	Test Results & Comments
1195 1375	From 1202.5' to 1206': Qtz feldspar pegmatite															From 1190' to 1190.5': (2) 80°-90° Undulating smooth J. stress fractures	C	100	20		
															From 1191.3' to 1192.6': Planar irregular						
																From 1193' to 1195': Rubble					
																From 1195' to 1210': Multiple stacked 0°-22° planar smooth with calcite infill (4) 4" sections or > only					
1200 1370																	C	100	14		
1205 1365																	C	100	20		
1210 1360																	C	100	20		
1215 1355																	C	100	0		
1220 1350																	C	100	0		
																</					

BORING TYPE: HQ3
HOLE DEPTH (ft): 3045
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 795 ft, 826.5 ft

LOGGED BY: Chris Messenger
CASING: HW to 70 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154898.691
EASTING: 6515647.859

PROJECT No: 951-20
DATE: 6/1/2023 - 7/25/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
1225	QTZ MONZONITE, light gray to white, phaneritic, massive																				
1230																					
1233	CORE LOSS																	C	88	0	
1235																					
1236	CORE LOSS																				
1240																					
1245																					
1247	CORE LOSS																				
1250																					
1251																					
1255																					

BORING TYPE: HQ3
HOLE DEPTH (ft): 3045
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 795 ft, 826.5 ft

LOGGED BY: Chris Messenger
CASING: HW to 70 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
WL	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)

CLIENT: Lane Power & Energy Solutions

SURFACE ELEVATION (ft): 2570

PROJECT No: 951-20

PROJECT: Hydrostor Zevsar

NORTHING: 2154898.691

DATE: 6/1/2023 - 7/25/2023

PROJECT LOCATION: Rosamod, CA

EASTING: 6515647.859

DIP/AZIMUTH: -90 /

EL	DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)		Discontinuities		Sampling & In Situ Testing																											
			Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard		0.05	0.25	0.50	2.50	5.00	B - Bedding S - Shear	J - Joint F- Fault	Type	Core Rec. %	RQD %	Test Results & Comments																					
1305	-1265	QTZ MONAZITE, light gray to white, phaneritic, massive, sodium/calcium feldspar, quartz, hornblende, biotite, trace muscovite, chlorite, epidote, pyrite	.	.	.	.	.		.	.	.	.	.	.	.	.	.	.	From 1262' to 1264': (5) 0°-6° Planar smooth	C	100	8																									
1270	-1270		.	.	.	.	.		.	.	.	.	.	.	.	.	.	.						1270.9': Planar irregular 1272.25': 7° Planar smooth	C	100	78																				
1275	-1275		.	.	.	.	.		.	.	.	.	.	.	.	.	.	.											1275.5': 0° Planar smooth 1276': 38° Healed fractures 1277': 10° Undulating rough 1277.1': 0° Planar irregular 1278.9': 41° Planar smooth From 1280' to 1281': 67° and 90° Slip/S. J. fractures planar smooth 1281.7': 40° Planar smooth 1283.5': 12° Undulating smooth From 1284.7' to 1286': (8) Planar smooth 1285': 38° and 32° 1288.3': Planar smooth From 1289.1' to 1289.2': 1° and 17° Planar smooth	C	100	70															
1280	-1280		.	.	.	.	.		.	.	.	.	.	.	.	.	.	1293.6': 67° Undulating smooth calcite infill/mineralization																C	100	71											
1285	-1285		.	.	.	.	.		.	.	.	.	.	.	.	.	.																					1290									
1290	-1290		.	.	.	.	.		.	.	.	.	.	.	.	.	.																														
1295	-1295		.	.	.	.	.		.	.	.	.	.	.	.	.	.																														

BORING TYPE: HQ3

DRILLER: Crux

LOGGED BY: Chris Messenger

HOLE DEPTH (ft): 3045

WATER OBSERVATIONS: 795 ft, 826.5 ft

CASING: HW to 70 ft

REMARKS:

SAMPLING & IN SITU TESTING LEGEND			
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)
		SLK	Slake durability test (Type _____)
		TRI	Triaxial stress test (psi)
		UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154898.691
EASTING: 6515647.859

PROJECT No: 951-20
DATE: 6/1/2023 - 7/25/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
1300																1294': Planar smooth					
1270																From 1296.25' to 1296.7': 61° Planar smooth Ca+2 mineralization					
																From 1297' to 1300': (11) 9°-31° Planar smooth J. fractures					
																From 1300' to 1303': (17) 9°-22° Planar smooth J. fractures					
1305																		C	100	62	
1265																1304': 14° Planar smooth					
																1306.7': Planar smooth K feldspar healed fractures					
																From 1307' to 1308': (2) Planar smooth					
1310																					
1260																		C	100	52	
																From 1312.6' to 1313': (4) 13°-15° Planar smooth					
																From 1313.6' to 1313.9': 7°-9° Planar smooth along K feldspar infill contact					
1315																From 1315.2' to 1316': 44° Undulating smooth					
1255																From 1316' to 1317': 81° S. and (2) 27° J. fractures					
																From 1318' to 1320': Rubble					
1320	From 1319' to 1320': Qtz feldspar pegmatite															1320.3': 39° K feldspar planar smooth					
1250																1321': Planar irregular along calcite healed zones					
																1322': Healed Ca+2 open planar irregular					
																From 1322.1' to 1323': (3) 12° Planar irregular					
1325																From 1324' to 1325': 71° Biotite defected (gray-smooth) infill, multiple healed fractures					
1245																From 1325' to 1329': no 4" sample, 0°-19° J. fractures planar smooth					

BORING TYPE: HQ3
HOLE DEPTH (ft): 3045
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 795 ft, 826.5 ft

LOGGED BY: Chris Messenger
CASING: HW to 70 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154898.691
EASTING: 6515647.859

PROJECT No: 951-20
DATE: 6/1/2023 - 7/25/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
1335																1331.5': Vertical healed and 37° planar smooth		C	100	38	
1340																1332': 0° Planar smooth					
1345																From 1333' to 1333.6': 90° S, undulating rough					
1350																1334.2': Ca+2 Infill, 0° planar smooth					
1355																1336.1': 17° Planar smooth					
1360																From 1337.4' to 1337.9': 0°-4° Planar smooth					
																1339.4': 12° Planar smooth					
																1340': 57° Planar slickenside deflected biotite		C	100	65	
																1341.7': 27° Planar smooth					
																1342': Rev angle					
																1342.25': 22°-31° Planar smooth					
																From 1343.3' to 1343.9': 0°-17° Planar smooth Ca+2 mineralization					
																From 1345' to 1346.4': 81°-90° Undulating S, fracture mineralization smooth					
																1347.1': 41° Ca+2 Planar smooth					
																1347.3': Rev angle 33° Ca+2 planar smooth					
																From 1348.7' to 1349.6': 0°-2° Planar smooth		C	100	74	
																From 1351.7' to 1356.8': (13) 0°-29° Planar smooth, (3) 4" sections					
1355.5	DIORITE															1357.2': 17° Planar smooth					
1356																1358': 69° Ca+2 planar smooth					
1360																1361': Planar irregular					
																From 1362' to 1365': (5) 30°-35° Planar smooth		C	100	41	

BORING TYPE: HQ3
HOLE DEPTH (ft): 3045
REMARKS: _____

DRILLER: Crux
WATER OBSERVATIONS: 795 ft, 826.5 ft

LOGGED BY: Chris Messenger
CASING: HW to 70 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type _____)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
WL	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)

CLIENT: Lane Power & Energy Solutions

SURFACE ELEVATION (ft): 2570

PROJECT No: 951-20

PROJECT: Hydrostor Zevsar

NORTHING: 2154898.691

DATE: 6/1/2023 - 7/25/2023

PROJECT LOCATION: Rosamod, CA

EASTING: 6515647.859

DIP/AZIMUTH: -90 /

EL	DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities	Sampling & In Situ Testing					
			Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard				B - Bedding S - Shear	J - Joint F- Fault	Type	Core Rec. %	RQD %	Test Results & Comments
1370	1200	QTZ MONAZITE, light gray to white, phaneritic, massive															1365': K and Ca+2 infill healed fracture From 1366' to 1367': 90° S. fracture						
																		From 1370' to 1375': 3.5/5°	C	100		35	
	1375																		From 1375' to 1390': Decomposed				
	1380																			C		100	0
	1385																						
	1390																	From 1391' to 1393': Broken fragmented	C	100	44		
	1395																	1396.5': Planar smooth From 1396.7' to 1397.4': Undulating rough 1398': 42° Planar smooth					

BORING TYPE: HQ3

DRILLER: Crux

LOGGED BY: Chris Messenger

HOLE DEPTH (ft): 3045

WATER OBSERVATIONS: 795 ft, 826.5 ft

CASING: HW to 70 ft

REMARKS:

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type _____)
W	Water seep	PL(A)	Point load axial test 1s(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test 1s(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions

SURFACE ELEVATION (ft): 2570

PROJECT No: 951-20

PROJECT: Hydrostor Zevsar

NORTHING: 2154898.691

DATE: 6/1/2023 - 7/25/2023

PROJECT LOCATION: Rosamod, CA

EASTING: 6515647.859

DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing				
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments	
1405	QTZ MONZONITE, light gray to white, phaneritic, massive, with NaCa+ plagioclase, quartz, biotite, trace pyroxene, muscovite, and pyrite																From 1399' to 1400': 79° S. fracture planar smooth	C	100	57		
																	From 1401' to 1403': (5) 0°-7° Planar smooth					
																	1403.6': 61° Planar slickenside					
																	1404.2': 0° Planar smooth					
																	1405.4': 38° Planar smooth					
																	From 1406.1' to 1406.9': 0°-9° Smooth					
1410																	1407.8': Planar smooth					
																	From 1408' to 1411': Defected	C	100	47		
																	From 1412.6' to 1413.9': 90° S. fracture - rubble stepped rough					
																	From 1414' to 1416.2': (9) 0°-10° Planar rough					
1415																	1417.2': 39° Planar smooth					
																	1418.4': 29° Planar smooth					
																	From 1419' to 1420': (3) J. fractures stocked 80°-84° planar smooth					
1420																		1420.1': 0° Planar smooth	C	100		77
																		1421': 0° Planar smooth				
																	1422.9': 0° Planar smooth					
																	1423.9': (2) 38° J. fractures undulating smooth					
1425																	1424': 27° Planar smooth					
																	1427.1': 35° Planar smooth					
																	1428.7': 29° Planar smooth					
																	From 1429.5' to 1429.7': 22° Planar smooth					
1430																	1430.67': 39° Undulating smooth					
																1432': 12° Planar rough	C	100	61			
																From 1433' to 1437': 90° Undulating smooth S.						

BORING TYPE: HQ3

DRILLER: Crux

LOGGED BY: Chris Messenger

HOLE DEPTH (ft): 3045

WATER OBSERVATIONS: 795 ft, 826.5 ft

CASING: HW to 70 ft

REMARKS:

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type ___)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154898.691
EASTING: 6515647.859

PROJECT No: 951-20
DATE: 6/1/2023 - 7/25/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
1440																fracture					
1445																From 1437' to 1437.9': (3) 0°-4° Planar smooth					
1450																From 1440' to 1441': 90° S. fracture contact with 45° planar smooth					
1455																1442': Planar smooth	C	100	61		
1460																From 1444' to 1445.5': (4) 31° Planar smooth rev angle					
1465																1446.8': Planar smooth					
																From 1448' to 1450': (7) 0°-21° Planar smooth, (3) 4" section					
																1451': 38° Planar smooth					
																From 1452' to 1453.2': (5) 30°-42° Healed fractures undulating smooth	C	100	45		
																From 1454.1' to 1455': 51°-52°-43°					
																1455.2': Planar irregular					
																1456.4': Planar irregular					
																1457.7': 45° Planar irregular					
																1458': 32° Planar irregular					
																From 1459.1' to 1459.3': Rev angle 51°-42° planar undulating smooth					
																From 1460' to 1465': (15) 0°-45° Multifracture (1) 4" section undulating planar smooth mostly along healed Ca+2 infill structures	C	100	40		
																1465.5': 42° Undulating smooth					
																From 1466' to 1467': (3) 86°-79° J. fractures undulating rough					
																1469.5': 32° Planar					

BORING TYPE: HQ3
HOLE DEPTH (ft): 3045
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 795 ft, 826.5 ft

LOGGED BY: Chris Messenger
CASING: HW to 70 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type ___)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
L	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154898.691
EASTING: 6515647.859

PROJECT No: 951-20
DATE: 6/1/2023 - 7/25/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
1475																sllickenside					
1480																1470.6': Planar irregular					
1485																1473.1': 27° Planar smooth		C	100	72	
1490																1473.5': 4° Planar smooth					
1495																1473.9': 22° Planar smooth					
1500																1476': (2) J. fractures stepped rough 79°-64°					
																1479.1': Planar smooth					
																1481.2': Planar smooth					
																From 1482' to 1483.7': (5) 70°-80° Planar smooth J. fractures		C	100	66	
																From 1484' to 1486': Stepped rough 81° S. fracture					
																1486.7': 62° Undulating smooth					
																From 1488.2' to 1489': (2) 38°-42° Planar smooth					
																1489.6': 38° Planar smooth					
																From 1490' to 1494': Multiple 20°-45° rev angle fractures along mineralization infill (healed fracturing) K feldspar Ca+2		C	100	40	
																From 1492.8' to 1494': 45° Vertical S.					
																1495.5': 38° Planar smooth					
																1496': 45° Planar smooth					
																From 1499.3' to 1499.7': (3) 40° J. fractures					
																1500.5': 45° Planar rough					
																From 1501.1' to 1501.4': (4) 77° Healed J. fractures Ca+2		C	100	36	
																1501.9': 62° Planar smooth					

BORING TYPE: HQ3
HOLE DEPTH (ft): 3045
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 795 ft, 826.5 ft

LOGGED BY: Chris Messenger
CASING: HW to 70 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type ___)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154898.691
EASTING: 6515647.859

PROJECT No: 951-20
DATE: 6/1/2023 - 7/25/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F- Fault	Type	Core Rec. %	RQD %	Test Results & Comments
1510	From 1525.5' to 1526': Very damp after 2 days dry time														0.05	From 1503' to 1505': (4) 67° Undulating smooth					
1515															0.25	From 1505' to 1506': Rubble					
1520															0.50	1507.9': 28° Planar smooth					
1525															2.50	From 1509' to 1510': (6) Slip/step J. undulating smooth rough fractures					
1530															5.00	1510.85': 5° Planar smooth					
1535																From 1512' to 1513.4': (7) 9°-45° J. fractures planar smooth		C	100	61	
																1514': 20° Planar smooth					
																1514.1': 61° Planar smooth					
																1516.7': Undulating smooth along healed Ca+2 fracture					
																1517.67': 39° Planar smooth					
																From 1518' to 1518.9': (3) 0° Planar smooth					
																1519.2': Planar irregular					
																1521': 21° Undulating smooth (healed Ca+2)		C	100	45	
																1521.6': 0° Planar smooth					
																1522.4': 0° Planar smooth					
																1523.2': 0° Planar smooth					
																1523.9': 0° Planar smooth					
																From 1524' to 1525': (3) 61°-68° Planar smooth J. fractures					
																From 1525.4' to 1526': Rubble					
																From 1526.7' to 1526.7': 0°-19° Planar smooth					
																From 1527' to 1528': (3) 70°-80° Undulating smooth J. fractures		C	100	90	
																From 1529' to 1530.3': 70°-90° S. stepped rough					
																1532': 47° Planar smooth/ rough					
																1532.4': 17° Planar smooth healed fracture					
																From 1534' to 1535': Rubble, high stressed area with multiple					UCS = 20,223

BORING TYPE: HQ3
HOLE DEPTH (ft): 3045
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 795 ft, 826.5 ft

LOGGED BY: Chris Messenger
CASING: HW to 70 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type ___)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
WL	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154898.691
EASTING: 6515647.859

PROJECT No: 951-20
DATE: 6/1/2023 - 7/25/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing				
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F- Fault	Type	Core Rec. %	RQD %	Test Results & Comments	

BORING TYPE: HQ3
HOLE DEPTH (ft): 3045
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 795 ft, 826.5 ft

LOGGED BY: Chris Messenger
CASING: HW to 70 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
WL	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)



CLIENT: Lane Power & Energy Solutions

SURFACE ELEVATION (ft): 2570

PROJECT No: 951-20

PROJECT: Hydrostor Zevsar

NORTHING: 2154898.691

DATE: 6/1/2023 - 7/25/2023

PROJECT LOCATION: Rosamod, CA

EASTING: 6515647.859

DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
1580																1576.45': Planar smooth					PL(A) = 331
																1576.8': Planar smooth					
																1577.15': Planar smooth					
																1580.4': Planar smooth					
																1580.55': Planar smooth					
																1580.75': Planar smooth		C	100	92	
1585																1582.45': 22° Planar smooth					
																From 1586.55' to 1587': (2) 20°-22° Planar smooth					
																1587.4': Planar smooth					
																1588.7': 33° K feldspar healed fracture					
1590																1589.3': 30° Planar smooth		C	100	87	ITS = 1,214
																1594.4': 27° Along K feldspar infill planar smooth					
1595																1598.75': Undulating rough					
																From 1599' to 1600': (5) 0°-11° Planar smooth					
1600																From 1603' to 1603.2': 29° Planar slickenside		C	100	47	
																From 1603.4' to 1605': (7) 70°-84° High angle S. J. fractures following healed zones, undulating smooth to rough					
1605																From 1606.8' to 1607.2': (4) Planar rough					UCS = 22,921

BORING TYPE: HQ3

DRILLER: Crux

LOGGED BY: Chris Messenger

HOLE DEPTH (ft): 3045

WATER OBSERVATIONS: 795 ft, 826.5 ft

CASING: HW to 70 ft

REMARKS:

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type _____)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154898.691
EASTING: 6515647.859

PROJECT No: 951-20
DATE: 6/1/2023 - 7/25/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
1615																1612': Planar irregular		C	100	91	PL(A) = 1,333
1620																1612.9': 39° Planar smooth					
1625																1613': 47° Undulating rough					PL(A) = 867
1630																1624.1': Planar smooth		C	100	96	
1635																1628.3': 39° Planar smooth					PL(A) = 867
1640																1629.7': 90° S. planar smooth					
																1631': 62° Planar smooth		C	100	92	PL(A) = 867
																1632': Rev angle multi directional healed fractures undulating smooth					
																From 1633' to 1633.3': (2) 59°-67° S. J. fractures undulating smooth					PL(A) = 867
																1634.5': 47° Planar smooth					
																1636.55': 0° Planar smooth					PL(A) = 867
																1639.2': 29° Planar smooth					
																1639.5': 0° Planar smooth					PL(A) = 867
																1639.9': 0° Planar smooth		C	100	65	
																1640.2': Planar smooth					PL(A) = 867
																From 1641' to 1644': (4) 0°-22° Planar smooth					

BORING TYPE: HQ3
HOLE DEPTH (ft): 3045
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 795 ft, 826.5 ft

LOGGED BY: Chris Messenger
CASING: HW to 70 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type ___)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)

CLIENT: Lane Power & Energy Solutions

SURFACE ELEVATION (ft): 2570

PROJECT No: 951-20

PROJECT: Hydrostor Zevsar

NORTHING: 2154898.691

DATE: 6/1/2023 - 7/25/2023

PROJECT LOCATION: Rosamod, CA

EASTING: 6515647.859

DIP/AZIMUTH: -90 /

[illegible]

BORING TYPE: HQ3

DRILLER: Crux

LOGGED BY: Chris Messenger

HOLE DEPTH (ft): 3045

WATER OBSERVATIONS: 795 ft, 826.5 ft

CASING: HW to 70 ft

REMARKS:

SAMPLING & IN SITU TESTING LEGEND			
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)
		SLK	Slake durability test (Type _____)
		TRI	Triaxial stress test (psi)
		UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154898.691
EASTING: 6515647.859

PROJECT No: 951-20
DATE: 6/1/2023 - 7/25/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)		Discontinuities		Sampling & In Situ Testing					
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard		0.05	0.25	0.50	2.50	5.00	B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %
1685	QTZ MONZONITE, light gray to white, phaneritic, massive																			C	100	98	ITS = 1,545	
1690																					C	100		70
1695																								
1697																								
1700																								
1705																				C	100	20		
1710																								
																				C	100	40		

BORING TYPE: HQ3
HOLE DEPTH (ft): 3045
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 795 ft, 826.5 ft

LOGGED BY: Chris Messenger
CASING: HW to 70 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
WL	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)

CLIENT: Lane Power & Energy Solutions

SURFACE ELEVATION (ft): 2570

PROJECT No: 951-20

PROJECT: Hydrostor Zevsar

NORTHING: 2154898.691

DATE: 6/1/2023 - 7/25/2023

PROJECT LOCATION: Rosamod, CA

EASTING: 6515647.859

DIP/AZIMUTH: -90 /[illegible]

BORING TYPE: HQ3

DRILLER: Crux

LOGGED BY: Chris Messenger

HOLE DEPTH (ft): 3045

WATER OBSERVATIONS: 795 ft, 826.5 ft

CASING: HW to 70 ft

REMARKS:

SAMPLING & IN SITU TESTING LEGEND			
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)
W	Water seep	PL(A)	Point load axial test ts(50) (psi)
W	Water level	PL(D)	Point load diamet test ts(50) (psi)
		SLK	Slake durability test (Type _____)
		TRI	Triaxial stress test (psi)
		UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions

SURFACE ELEVATION (ft): 2570

PROJECT No: 951-20

PROJECT: Hydrostor Zevsar

NORTHING: 2154898.691

DATE: 6/1/2023 - 7/25/2023

PROJECT LOCATION: Rosamod, CA

EASTING: 6515647.859

DIP/AZIMUTH: -90 /

EL	DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
			Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
1750		QTZ MONZONITE, light gray to white, phaneritic, massive, with plagioclase, quartz, biotite, and hornblende, trace muscovite and pyrite															From 1750' to 1751.75': 90° Planar smooth S. fracture					
																	1752': 42° Planar smooth K feldspar		C	100	72	
																	From 1753' to 1754': 90° S. planar smooth epidote/chlorite					
1755																						PL(A) = 1,130
1760																	1760.2': Planar smooth					
1765																						
1770																	From 1767' to 1768': (3) 67° S. planar smooth Cl-3					
																	1769': 0° Planar smooth					
																	From 1769.2' to 1769.8': 77° Planar smooth					
																	From 1770.6' to 1771': 71° Undulating rough					
																	1771.1': 0° Planar smooth		C	100	69	
																	1771.4': 32° Planar smooth					
1775																	1773.6': 61° Undulating smooth					
																	From 1776.8' to 1777': 52° Planar smooth					
																	From 1777' to 1778': 82° Undulating smooth					
																	1778.7': Planar smooth					
1780																	1782': 4° Planar smooth					
																	1782.9': Planar smooth		C	100	71	
																	1784': 0° Planar smooth					
																						ITS = 1,309

BORING TYPE: HQ3

DRILLER: Crux

LOGGED BY: Chris Messenger

HOLE DEPTH (ft): 3045

WATER OBSERVATIONS: 795 ft, 826.5 ft

CASING: HW to 70 ft

REMARKS: _____

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type ____)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
WL	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154898.691
EASTING: 6515647.859

PROJECT No: 951-20
DATE: 6/1/2023 - 7/25/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
1790	DOLERITE/ DIABASE DIKE															From 1785' to 1788': (6) Planar smooth					
1791																1789.4': 81° Planar smooth S. fractures					
1793.8																					
1796.75	QTZ MONAZITE, light gray to white, phaneritic, massive															1796': 87° Planar					
1796.7																1796.7': Planar smooth					
1798'																1798': 7° Planar smooth					
1798.6'																From 1798.6' to 1799.4': 45°-90° Rev angle fracture, healed K feldspar fracture					
1800'																From 1800' to 1801': (3) 0° Planar smooth					
1802'																1802': 7° Planar smooth					
1802.7'																From 1802.7' to 1803.2': 69° Undulating rough					
1805.5'																1805.5': 0° Planar smooth					
1807'																From 1807' to 1808': Rubble					
1810.4'																From 1810.4' to 1811': 90° S. planar rough, fresh					
1811'	From 1811.5' to 1812.4': Qtz feldspar pegmatite															From 1811' to 1814': Rubble < 2"					
1816'																From 1816' to 1817.5': (3) 0° Planar smooth					
1818'																1818': Radiating 90°-70° Ca+2 healed, open fracture stepped rough					
1819'																From 1819' to 1820': (4)					

BORING TYPE: HQ3
HOLE DEPTH (ft): 3045
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 795 ft, 826.5 ft

LOGGED BY: Chris Messenger
CASING: HW to 70 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)

CLIENT: Lane Power & Energy Solutions

SURFACE ELEVATION (ft): 2570

PROJECT No: 951-20

PROJECT: Hydrostor Zevsar

NORTHING: 2154898.691

DATE: 6/1/2023 - 7/25/2023

PROJECT LOCATION: Rosamod, CA

EASTING: 6515647.859

DIP/AZIMUTH: -90 /

[illegible]

BORING TYPE: HQ3

DRILLER: Crux

LOGGED BY: Chris Messenger

HOLE DEPTH (ft): 3045

WATER OBSERVATIONS: 795 ft, 826.5 ft

CASING: HW to 70 ft

REMARKS:

SAMPLING & IN SITU TESTING LEGEND			
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)
		SLK	Slake durability test (Type _____)
		TRI	Triaxial stress test (psi)
		UCS	Uniaxial stress test (psi)

(Continued Next Page)

CLIENT: Lane Power & Energy Solutions

SURFACE ELEVATION (ft): 2570

PROJECT No: 951-20

PROJECT: Hydrostor Zevsar

NORTHING: 2154898.691

DATE: 6/1/2023 - 7/25/2023

PROJECT LOCATION: Rosamod, CA

EASTING: 6515647.859

DIP/AZIMUTH: -90 /

[illegible]

BORING TYPE: HQ3

DRILLER: Crux

LOGGED BY: Chris Messenger

HOLE DEPTH (ft): 3045

WATER OBSERVATIONS: 795 ft, 826.5 ft

CASING: HW to 70 ft

REMARKS:

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type _____)
W	Water seep	PL(A)	Point load axial test 1s(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test 1s(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)

CLIENT: Lane Power & Energy Solutions

SURFACE ELEVATION (ft): 2570

PROJECT No: 951-20

PROJECT: Hydrostor Zevsar

NORTHING: 2154898.691

DATE: 6/1/2023 - 7/25/2023

PROJECT LOCATION: Rosamod, CA

EASTING: 6515647.859

DIP/AZIMUTH: -90 /

EL	DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities	Sampling & In Situ Testing																																																																																																																																																																																																																																																																																																																																												
			Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard				B - Bedding S - Shear	J - Joint F- Fault	Type	Core Rec. %	RQD %	Test Results & Comments																																																																																																																																																																																																																																																																																																																																							
675	1895	From 1892' to 1892.6': Qtz-K feldspar pegmatite																																																																																																																																																																																																																																																																																																																																																												

BORING TYPE: HQ3

DRILLER: Crux

LOGGED BY: Chris Messenger

HOLE DEPTH (ft): 3045

WATER OBSERVATIONS: 795 ft, 826.5 ft

CASING: HW to 70 ft

REMARKS:

SAMPLING & IN SITU TESTING LEGEND			
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)
	Water seep	SLK	Slake durability test (Type _____)
	Water level	PL(A)	Point load axial test (s/50) (psi)
		PL(D)	Point load diametral test (s/50) (psi)
		TRI	Triaxial stress test (psi)
		UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154898.691
EASTING: 6515647.859

PROJECT No: 951-20
DATE: 6/1/2023 - 7/25/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
1930	QTZ MONAZITE, light gray to white, phaneritic, massive, with plagioclase, K feldspar, biotite, hornblende, and quartz, trace mica/muscovite, pyrite, chlorite, and epidote																	C	100	8	UCS = 18,272
1935																		C	100	8.5	
1940																		C	100	43	
1945																		C	100	23	
1950																		C	100	23	
1955	From 1957' to 1958': Qtz feldspar pegmatite																	C	100	23	

BORING TYPE: HQ3
HOLE DEPTH (ft): 3045
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 795 ft, 826.5 ft

LOGGED BY: Chris Messenger
CASING: HW to 70 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
WL	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154898.691
EASTING: 6515647.859

PROJECT No: 951-20
DATE: 6/1/2023 - 7/25/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities	Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard				B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %
605	From 1964' to 1966.5': Qtz feldspar / monazite														From 1957' to 1980': K feldspar high percentage 1960': 71° 1961': 42° Rubble stepped rough 1963': 44° Planar smooth				SLK = Type I PL(A) = 875	
600																C	100	80		
595																				
590	From 1980' to 1981.5': Qtz feldspar pegmatite														1978.7': 47° Planar smooth From 1980' to 1981': Defected 1981.2': 84° Stepped rough 1983': Rev angle at 42° and 49° undulating rough From 1983.2' to 1984': Undulating smooth From 1985' to 1986': (3) 20°-30° Planar smooth From 1986.6' to 1987.1': (4) J. fracture 1988.6': 51° Planar smooth				SLK = Type I PL(A) = 643	
585																C	100	55		
580																				
575	From 1991.5' to 1991.8': Qtz feldspar pegmatite																		PL(A) = 1,155 ITS = 1,433	
570																				
565																				

BORING TYPE: HQ3
HOLE DEPTH (ft): 3045
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 795 ft, 826.5 ft

LOGGED BY: Chris Messenger
CASING: HW to 70 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type ___)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions

SURFACE ELEVATION (ft): 2570

PROJECT No: 951-20

PROJECT: Hydrostor Zevsar

NORTHING: 2154898.691

DATE: 6/1/2023 - 7/25/2023

PROJECT LOCATION: Rosamod, CA

EASTING: 6515647.859

DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
2000	From 2004' to 2005': Qtz feldspar pegmatite																	C	100	95	TRI = 37,314
570																					
2005																					TRI = 24,460
565																					
2010																					
560																					
2015																					
555																					
2020																					
550																					
2025	From 2027' to 2028': Qtz feldspar pegmatite																				
545																					

BORING TYPE: HQ3

DRILLER: Crux

LOGGED BY: Chris Messenger

HOLE DEPTH (ft): 3045

WATER OBSERVATIONS: 795 ft, 826.5 ft

CASING: HW to 70 ft

REMARKS: _____

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type _____)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
L	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154898.691
EASTING: 6515647.859

PROJECT No: 951-20
DATE: 6/1/2023 - 7/25/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
2035																					IRI = 40,255
2040																					UCS = 27,231
2045																					
2050																					PL(A) = 1,150
2055																					
2060																					ITS = 1,515 SLK = Type I

BORING TYPE: HQ3
HOLE DEPTH (ft): 3045
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 795 ft, 826.5 ft

LOGGED BY: Chris Messenger
CASING: HW to 70 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
L	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154898.691
EASTING: 6515647.859

PROJECT No: 951-20
DATE: 6/1/2023 - 7/25/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
500 -2070																		C	100	100	UCS = 22,671 TRI = 37,335
495 -2075																					
490 -2080																		C	100	95	PL(A) = 1,157 ITS = 879
485 -2085																					
480 -2090																		C	100	92	SLK = Type I
475 -2095																					
																		C	100	100	TRI = 28,355 UCS = 16,566

BORING TYPE: HQ3
HOLE DEPTH (ft): 3045
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 795 ft, 826.5 ft

LOGGED BY: Chris Messenger
CASING: HW to 70 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type I)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)

CLIENT: Lane Power & Energy Solutions

SURFACE ELEVATION (ft): 2570

PROJECT No: 951-20

PROJECT: Hydrostor Zevsar

NORTHING: 2154898.691

DATE: 6/1/2023 - 7/25/2023

PROJECT LOCATION: Rosamod, CA

EASTING: 6515647.859

DIP/AZIMUTH: -90 /

[illegible]

BORING TYPE: HQ3

DRILLER: Crux

LOGGED BY: Chris Messenger

HOLE DEPTH (ft): 3045

WATER OBSERVATIONS: 795 ft, 826.5 ft

CASING: HW to 70 ft

REMARKS:

SAMPLING & IN SITU TESTING LEGEND			
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)
		SLK	Slake durability test (Type _____)
		TRI	Triaxial stress test (psi)
		UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154898.691
EASTING: 6515647.859

PROJECT No: 951-20
DATE: 6/1/2023 - 7/25/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
430 2140																smooth					PL(A) = 1,421
																2135.5': 0° Planar smooth		C	100	90	
																2138.3': 11° Planar smooth					
																2139': 47° Chlorite slickenside					
																2139.5': 27° Planar smooth					ITS = 1,618
																2140.2': 0° Planar					
																2141.7': Planar smooth					
425 2145																2143': 11° and 0° smooth					
																		C	100	100	SLK = Type I
420 2150																2151.2': 0° Planar					TRI = 24,335
																2154': 0° Planar smooth					
415 2155																2158': 17°-12° Planar 10° smooth		C	100	95	
																2159': 17° Planar smooth					UCS = 23,626
410 2160																2162': 0° Planar smooth					
																From 2162.4' to 2163': (4) 22°-27° K feldspar fractures planar smooth					PL(A) = 937
405 2165																2165.5': 42° Planar smooth					
																2165.9': 31° Planar smooth		C	100	80	
																From 2166' to 2167': 90° S. undulating rough					
																2168': 27° Planar					

BORING TYPE: HQ3
HOLE DEPTH (ft): 3045
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 795 ft, 826.5 ft

LOGGED BY: Chris Messenger
CASING: HW to 70 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154898.691
EASTING: 6515647.859

PROJECT No: 951-20
DATE: 6/1/2023 - 7/25/2023
DIP/AZIMUTH: -90 /

EL	DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities	Sampling & In Situ Testing																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																							
			Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard				B - Bedding S - Shear	J - Joint F- Fault	Type	Core Rec. %	RQD %	Test Results & Comments																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																		
		From 2178' to 2180': Qtz feldspar pegmatite																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																							

BORING TYPE: HQ3
HOLE DEPTH (ft): 3045
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 795 ft, 826.5 ft

LOGGED BY: Chris Messenger
CASING: HW to 70 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type __)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
L	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)



CLIENT: Lane Power & Energy Solutions

SURFACE ELEVATION (ft): 2570

PROJECT No: 951-20

PROJECT: Hydrostor Zevsar

NORTHING: 2154898.691

DATE: 6/1/2023 - 7/25/2023

PROJECT LOCATION: Rosamod, CA

EASTING: 6515647.859

DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
360 2210	QTZ MONZONITE, light gray to white and pink, phaneritic, massive, with high K feldspar and increased chlorite and epidote																	C	100	100	SLK = Type I
355 2212.15																-2211.3': Undulating stepped rough Ca+2					TRI = 24,657
350 2220																2216': Planar smooth					UCS = 20,384
345 2225																2216.7': Decomposed 42° planar irregular		C	100	78	
340 2230																2220.3': 47° Undulating smooth					PL(A) = 322
335 2235																2221': 52° Planar smooth					
																2222': Planar smooth					
																2222.75': 76° Planar smooth					
																From 2223.2' to 2224': 79° Undulating smooth healed fractures - vertical and 45° K and chlorite infill					
																2228': 12° Planar smooth		C	100	50	UCS = 5,697
																2231.2': 45°-47° Planar smooth					SLK = Type I
																From 2232' to 2236': Decomposed					SLK = Type II
																		C	100	40	ITS = 204

BORING TYPE: HQ3

DRILLER: Crux

LOGGED BY: Chris Messenger

HOLE DEPTH (ft): 3045

WATER OBSERVATIONS: 795 ft, 826.5 ft

CASING: HW to 70 ft

REMARKS:

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type ___)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
WL	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154898.691
EASTING: 6515647.859

PROJECT No: 951-20
DATE: 6/1/2023 - 7/25/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
2245																2240.2': 47° Undulating decomposed smooth					
2250																From 2245' to 2248': Defected		C	100	30	SLK = Type I
2255																2249': 32° Planar smooth brittle					
2260																2251': 42° Planar smooth					
2265																2252.6': 47° Planar along chlorite infill					
2270																2253.7': 42° Planar smooth					
																From 2256' to 2260': (7) 20°-40° along chlorite and veining planar smooth defected		C	100	53	PL(A) = 176
																From 2261.8' to 2262.4': Stepped smooth					ITS = 1,322
																From 2261.9' to 2267': (19) 5°-30° Planar					
																From 2267' to 2269.2': (12) 0°-14° Planar smooth		C	100	40	
																From 2269.2' to 2269.7': 69° Undulating smooth					
																From 2270' to 2275': (10) 10°-35° Planar smooth					
																From 2275' to 2280':					

BORING TYPE: HQ3
HOLE DEPTH (ft): 3045
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 795 ft, 826.5 ft

LOGGED BY: Chris Messenger
CASING: HW to 70 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
L	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154898.691
EASTING: 6515647.859

PROJECT No: 951-20
DATE: 6/1/2023 - 7/25/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
2280																(20) 10°-45° Undulating smooth					
2285																From 2278' to 2280': Healed 90° J. fracture planar smooth		C	100	58	PL(A) = 74
2290																2281.1': 42° Planar smooth 2281.6': 16° Planar smooth 2283.2': 0°-4° Planar smooth					SLK = Type I
2295																From 2284' to 2284.6': Planar slickenside From 2285' to 2290': (17) 0°-24° Planar smooth		C	100	37	
2300																From 2291' to 2291.2': (2) 40°-35° Planar Ca+2 smooth 2291.2': (15) 0°-15° Planar smooth					TRI = 19,035 ITS = 942
2305																2296.4': Planar smooth From 2297.4' to 2297.7': 61° Planar smooth From 2297.7' to 2298.4': Vertical healed fracture From 2298.4' to 2301': (5) 17°-37° Planar smooth		C	100	41	
																From 2306' to 2308': Diorite From 2306.1' to 2310': (8) 0° Planar smooth, (4) 32°-44° planar smooth		C	100	35	UCS = 1,888

BORING TYPE: HQ3
HOLE DEPTH (ft): 3045
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 795 ft, 826.5 ft

LOGGED BY: Chris Messenger
CASING: HW to 70 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
L	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions

SURFACE ELEVATION (ft): 2570

PROJECT No: 951-20

PROJECT: Hydrostor Zevsar

NORTHING: 2154898.691

DATE: 6/1/2023 - 7/25/2023

PROJECT LOCATION: Rosamod, CA

EASTING: 6515647.859

DIP/AZIMUTH: -90 /

EL	DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
			Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
255	2315																					PL(A) = 987 SLK = Type I
250	2320	DIORITE																				ITS = 923
245	2325																					UCS = 21,408 PL(A) = 792
240	2330																					
235	2335	QTZ MONZONITE, light gray to white, phaneritic, massive, with K feldspar, biotite, hornblende, quartz, trace muscovite, pyroxene, chlorite, and pyrite																				
230	2340	From 2342' to 2344': Qtz pegmatite																				

BORING TYPE: HQ3

DRILLER: Crux

LOGGED BY: Chris Messenger

HOLE DEPTH (ft): 3045

WATER OBSERVATIONS: 795 ft, 826.5 ft

CASING: HW to 70 ft

REMARKS:

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
L	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions

SURFACE ELEVATION (ft): 2570

PROJECT No: 951-20

PROJECT: Hydrostor Zevsar

NORTHING: 2154898.691

DATE: 6/1/2023 - 7/25/2023

PROJECT LOCATION: Rosamod, CA

EASTING: 6515647.859

DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
2350	DIORITE														2344.5': 61° Planar smooth	C	100	62	SLK = Type I		
2351															From 2345.2' to 2345.6': Planar rough						
															2346.7': Planar irregular smooth/ rough						
															2347.3': 51° Planar smooth						
															2349': 49° Undulating rough						
															From 2349.8' to 2350': (3) 40°-45° Planar J. smooth				ITS = 1,088		
2355															From 2350' to 2351.5': (7) 30°-0° Planar smooth						
															2351': 32° Stepped rough at K feldspar contact	C	100	61	TRI = 8,838		
2358															From 2352.35' to 2353': Rubble						
															From 2353' to 2353.75': (3) 48°-51° Planar smooth						
2360															From 2355' to 2356.75': Rubble						
															From 2357.3' to 2358': (6) Healed / open 0° planar smooth						
															2358.4': 39° Planar smooth						
2365															2359.8': 33° Planar smooth	C	100	38			
															2361.8': 17° Planar smooth						
															From 2362.5' to 2362.75': 39° Planar smooth						
															2363.6': Planar smooth						
2370															2364.5': 32° Slickenside						
															From 2365' to 2366': Rubble						
															2366.5': Planar smooth						
															2367.2': Undulating rough						
2375															From 2367.5' to 2367.9': 12°-22° Planar smooth	C	100	70	PL(A) = 143		
															From 2373.2' to 2373.75': 30°-42° Planar slickenside						
															2374.1': 32° Planar smooth						
															2374.7': Planar smooth						
															2375.4': Planar rough						

BORING TYPE: HQ3

DRILLER: Crux

LOGGED BY: Chris Messenger

HOLE DEPTH (ft): 3045

WATER OBSERVATIONS: 795 ft, 826.5 ft

CASING: HW to 70 ft

REMARKS:

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
L	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154898.691
EASTING: 6515647.859

PROJECT No: 951-20
DATE: 6/1/2023 - 7/25/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities	Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard				Type	Core Rec. %	RQD %	Test Results & Comments
185 -2385																2376.2': 42° Planar slickenside From 2377' to 2378': (2) Planar smooth From 2378.8' to 2379.2': 22° and 45° Planar smooth 2379.8': 17° Planar smooth 2380.5': Planar rough From 2381.4' to 2382.1': 90° S. From 2382.1' to 2382.4': Rubble 2385.4': 42° Planar smooth 2386': 44° Planar smooth 2386.7': 42° Planar smooth 2387.1': 42° Planar smooth From 2388' to 2388.6': 79° Stepped rough 2389': 87° Planar smooth 2390': Planar smooth From 2390.1' to 2392': 90° Stress J. fracture undulating smooth From 2393.5' to 2394.1': 45° Stepped rough 2394.9': Planar rough From 2401.8' to 2402.2': Pegmatite contact / healed 90° fractures From 2403.4' to 2403.6': Rubble 2410.6': Planar smooth From 2414' to 2419': Rubble, 2 identifiable fractures				UCS = 9,099 SLK = Type I ITS = 507
2389 -2389	DIORITE																C	100	62	
2390 -2390																				TRI = 10,855
2395 -2395																				UCS = 2,344
2400 -2400	From 2400' to 2405': Qtz feldspar pegmatite																C	100	57	PL(A) = 152
2405 -2405																				ITS = 256
2410 -2410																	C	100	45	SLK = Type I

BORING TYPE: HQ3
HOLE DEPTH (ft): 3045
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 795 ft, 826.5 ft

LOGGED BY: Chris Messenger
CASING: HW to 70 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type ___)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154898.691
EASTING: 6515647.859

PROJECT No: 951-20
DATE: 6/1/2023 - 7/25/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
2420	QTZ MONZONITE, light gray to white, phaneritic, massive, with plagioclase, biotite, hornblende, and quartz, trace muscovite, chlorite, and pyrite From 2427' to 2431': Qtz feldspar pegmatite																				
2425																		C	100	38	
2430																					
2435																					
2436	CORE LOSS																				
2437																					
2440																		C	90	12	SLK = Type I UCS = 11,872 SLK = Type I
2445																					
																		C	100	25	PL(A) = 921

BORING TYPE: HQ3
HOLE DEPTH (ft): 3045
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 795 ft, 826.5 ft

LOGGED BY: Chris Messenger
CASING: HW to 70 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
L	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154898.691
EASTING: 6515647.859

PROJECT No: 951-20
DATE: 6/1/2023 - 7/25/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
115 -2455																Rubble					SLK = Type II
																From 2450' to 2453': Multiple 90° stepped and undulating smooth					
																From 2455' to 2460': (17) 0°-28° Planar smooth					
110 -2460																From 2457' to 2458': 4" >		C	100	25	PL(A) = 155
																2461.8': 0° Planar smooth					
																2462.1': 0° Planar smooth					
105 -2465																2463': Decomposed					ITS = 639
																2463.75': 45° Slickenside stepped		C	100	10	
																From 2464' to 2466': 78° Undulating smooth					
100 -2470																2464.1': 0° Planar smooth					
																From 2466' to 2470': Rubble					
																From 2470' to 2472': Rubble					
95 -2475																2472.9': 38° Planar smooth					
																From 2473.2' to 2474': (4) Undulating 60°-70° smooth J. fractures					
																From 2475' to 2478': Rubble		C	100	0	
90 -2480																2478': 90° S. planar rough					
																2480': 69°-78° S. planar rough					
																From 2480.1' to 2484': Rubble					
																From 2484.6' to 2485':					

BORING TYPE: HQ3
HOLE DEPTH (ft): 3045
REMARKS: _____

DRILLER: CruX
WATER OBSERVATIONS: 795 ft, 826.5 ft

LOGGED BY: Chris Messenger
CASING: HW to 70 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type _____)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154898.691
EASTING: 6515647.859

PROJECT No: 951-20
DATE: 6/1/2023 - 7/25/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
80 2490	From 2504' to 2508': Qtz feldspar pegmatite															84° Undulating smooth					
																2485.8': Planar smooth					
																From 2486.9' to 2488': Rubble		C	100	18	
																2489.1': 32° Planar smooth					
																2491': (3) 67° J. fracture					
																2491.3': Planar rough					
																From 2492' to 2493.7': Rubble					
75 2495																From 2494' to 2496.8': (2) 35° Planar smooth					
																From 2496.8' to 2498': Rubble (0° Planar smooth fraction)		C	100	8	PL(A) = 188
																From 2499.1' to 2499.8': 80° Stepped rough					
70 2500																2500.2': 39° Planar smooth					ITS = 657
																From 2503.6' to 2509': Rubble		C	100	30	
65 2505																From 2510' to 2512': (3) 10°-32° Planar smooth					UCS = 11,075
																2512': Mostly planar 0° smooth					SLK = Type I
60 2510																From 2515' to 2517': (6) 30°-49° Planar rough / undulating rough					
																From 2517' to 2523': Rubble defected		C	100	0	UCS = 1,152
55 2515																					

BORING TYPE: HQ3
HOLE DEPTH (ft): 3045
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 795 ft, 826.5 ft

LOGGED BY: Chris Messenger
CASING: HW to 70 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type ___)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
L	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)

CLIENT: Lane Power & Energy Solutions

SURFACE ELEVATION (ft): 2570

PROJECT No: 951-20

PROJECT: Hydrostor Zevsar

NORTHING: 2154898.691

DATE: 6/1/2023 - 7/25/2023

PROJECT LOCATION: Rosamod, CA

EASTING: 6515647.859

DIP/AZIMUTH: -90 /

[illegible]

BORING TYPE: HQ3

DRILLER: Crux

LOGGED BY: Chris Messenger

HOLE DEPTH (ft): 3045

WATER OBSERVATIONS: 795 ft, 826.5 ft

CASING: HW to 70 ft

REMARKS:

SAMPLING & IN SITU TESTING LEGEND			
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)
W	Water seal	SLK	Slake durability test (Type _____)
W	Water level	TRI	Triaxial stress test (psi)
		PL(A)	Point load axial test Is(50) (psi)
		PL(D)	Point load diametral test Is(50) (psi)
		UCS	Uniaxial stress test (psi)

(Continued Next Page)

CLIENT: Lane Power & Energy Solutions

SURFACE ELEVATION (ft): 2570

PROJECT No: 951-20

PROJECT: Hydrostor Zevsar

NORTHING: 2154898.691

DATE: 6/1/2023 - 7/25/2023

PROJECT LOCATION: Rosamod, CA

EASTING: 6515647.859

DIP/AZIMUTH: -90 /

[illegible]

BORING TYPE: HQ3

DRILLER: Crux

LOGGED BY: Chris Messenger

HOLE DEPTH (ft): 3045

WATER OBSERVATIONS: 795 ft, 826.5 ft

CASING: HW to 70 ft

REMARKS:

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type _____)
W	Water seep	PL(A)	Point load axial test (s(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test (s(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154898.691
EASTING: 6515647.859

PROJECT No: 951-20
DATE: 6/1/2023 - 7/25/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
-2595																Rubble continued high 90° vertical fractures 2592'-2594'					SLK = Type I
-2600																From 2597' to 2599': Ca+2 large infill along fracture stepped rough 80°-90°, remainder rubble		C	100	38	
-2605																From 2605' to 2607': Rubble					UCS = 6,160 PL(A) = 802
-2610																From 2607.2' to 2608.7': 90° Planar slickenside		C	100	44	
-2615																From 2616.2' to 2616.7': Planar smooth					
-2620																From 2618.3' to 2620': Rubble		C	100	33	
																From 2620' to 2629': Rubble					
	From 2622' to 2625': Qtz feldspar pegmatite																				

BORING TYPE: HQ3
HOLE DEPTH (ft): 3045
REMARKS: _____

DRILLER: Crux
WATER OBSERVATIONS: 795 ft, 826.5 ft

LOGGED BY: Chris Messenger
CASING: HW to 70 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type ___)
W	Water seep	PL(A)	Point load axial test (50) (psi)	TRI	Triaxial stress test (psi)
L	Water level	PL(D)	Point load diametral test (50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions

SURFACE ELEVATION (ft): 2570

PROJECT No: 951-20

PROJECT: Hydrostor Zevsar

NORTHING: 2154898.691

DATE: 6/1/2023 - 7/25/2023

PROJECT LOCATION: Rosamod, CA

EASTING: 6515647.859

DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
-60																		C	100	37	SLK = Type II SLK = Type II
-630																From 2629' to 2630': Defected					
																-2631': 45° Planar smooth					
																From 2631.2' to 2631.4': <2" Planar breaks					ITS = 1,097
-635																-2634.3': 31° Planar smooth					
																-2634.9': 30° Planar smooth					
																-2636': 0°-90° Stepped rough		C	100	38	
																-2637.1': 0° Planar smooth					
-640																From 2637.3' to 2638.4': 79° Planar smooth					
																From 2639' to 2641': Rubble					
																-2642': 40° Planar smooth					PL(A) = 929
																From 2643' to 2644': (4) 0° Planar smooth					
-645																-2644.1': 61° Undulating rough					ITS = 319
																From 2645' to 2645.5': 59° Planar smooth					
																From 2647' to 2648': 32°-30° Undulating rough		C	100	53	
-650	QTZ MONZONITE, light gray to white, phaneritic, massive															From 2648' to 2650': (3) 60°-67° Undulating rough, brittle					
-652.9																From 2650' to 2665': Decomposed					
-653.2	CORE LOSS																	C	89	0	
-655																					

BORING TYPE: HQ3

DRILLER: Crux

LOGGED BY: Chris Messenger

HOLE DEPTH (ft): 3045

WATER OBSERVATIONS: 795 ft, 826.5 ft

CASING: HW to 70 ft

REMARKS:

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type <u> </u>)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154898.691
EASTING: 6515647.859

PROJECT No: 951-20
DATE: 6/1/2023 - 7/25/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
-95																					
-2665																					
-2670																					
-2675																					
-2680																					
-2685																					
-2690																					

BORING TYPE: HQ3
HOLE DEPTH (ft): 3045
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 795 ft, 826.5 ft

LOGGED BY: Chris Messenger
CASING: HW to 70 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type ___)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

CLIENT: Lane Power & Energy Solutions

SURFACE ELEVATION (ft): 2570

PROJECT No: 951-20

PROJECT: Hydrostor Zevsar

NORTHING: 2154898.691

DATE: 6/1/2023 - 7/25/2023

PROJECT LOCATION: Rosamod, CA

EASTING: 6515647.859

DIP/AZIMUTH: -90 /

[illegible]

BORING TYPE: HQ3

DRILLER: Crux

LOGGED BY: Chris Messenger

HOLE DEPTH (ft): 3045

WATER OBSERVATIONS: 795 ft, 826.5 ft

CASING: HW to 70 ft

REMARKS:

SAMPLING & IN SITU TESTING LEGEND			
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)
	Water seep	SLK	Slake durability test (Type _____)
	Water level	PL(A)	Point load axial test (s/50) (psi)
		PL(D)	Point load diametral test (s/50) (psi)
		TRI	Triaxial stress test (psi)
		UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154898.691
EASTING: 6515647.859

PROJECT No: 951-20
DATE: 6/1/2023 - 7/25/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
-2735																					
-2740																		C	100	0	SLK = Type II
-2745																		C	100	0	
-2750																		C	100	9	
-2755	QTZ MONZONITE, light gray to white and dark gray to white, phaneritic, massive, with plagioclase, biotite, and quartz, trace muscovite, epidote, pyrite, and chlorite																				
-2760																					
-2761.8'																		C	100	39	UCS = 1,398 SLK = Type II
-2764.3'																					

BORING TYPE: HQ3
HOLE DEPTH (ft): 3045
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 795 ft, 826.5 ft

LOGGED BY: Chris Messenger
CASING: HW to 70 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type ___)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
WL	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154898.691
EASTING: 6515647.859

PROJECT No: 951-20
DATE: 6/1/2023 - 7/25/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
-200																					
-205																					
-210																					
-215																					
-220																					
-225																					
-2770																					
-2775																					
-2780																					
-2785																					
-2790																					
-2795																					
	From 2794' to 2800': Qtz feldspar pegmatite, high K feldspar																				

BORING TYPE: HQ3
HOLE DEPTH (ft): 3045
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 795 ft, 826.5 ft

LOGGED BY: Chris Messenger
CASING: HW to 70 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type ___)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154898.691
EASTING: 6515647.859

PROJECT No: 951-20
DATE: 6/1/2023 - 7/25/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
-235 -2805																From 2800' to 2806.7': Rubble, 90° fractures		C	100	10	PL(A) = 1,189
-240 -2810																-2807.9': 39° Planar rough -2808.9': 39° Planar smooth					
-245 -2815																From 2809' to 2815': Some vertical 80°-90° healed and unhealed fracturing, rubble remainder		C	100	0	
-250 -2820																From 2815' to 2817': 79°-84° Stepped rough fracture From 2817' to 2817.6': Rubble with identifiable healed and open 80°-90° undulating fracture					
-255 -2825																-2819.2': 39° K feldspar infill undulating smooth					
-260 -2830																From 2820' to 2827': Rubble partially fractured		C	100	0	
																2827': 44°-38°-44° Undulating smooth Ca+2 30° planar rough wedge From 2827.4' to 2829.2': 84° Planar rough, 77° undulating rough					
																From 2830' to 2831': Rubble From 2831' to 2833': Updating 90° smooth		C	100	24	PL(A) = 743
																From 2833.7' to 2835': Rubble					

BORING TYPE: HQ3
HOLE DEPTH (ft): 3045
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 795 ft, 826.5 ft

LOGGED BY: Chris Messenger
CASING: HW to 70 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154898.691
EASTING: 6515647.859

PROJECT No: 951-20
DATE: 6/1/2023 - 7/25/2023
DIP/AZIMUTH: -90 /

EL	DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																													
			Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																										
-2840		QTZ MONZONITE, light gray to white, phaneritic, massive, with Ca+2 plagioclase feldspar and qtz K feldspar biotite, trace muscovite and chlorite														0.05	0.25	0.50	2.50	5.00																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																												

BORING TYPE: HQ3
HOLE DEPTH (ft): 3045
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 795 ft, 826.5 ft

LOGGED BY: Chris Messenger
CASING: HW to 70 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
L	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154898.691
EASTING: 6515647.859

PROJECT No: 951-20
DATE: 6/1/2023 - 7/25/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
2875																From 2869' to 2870': Veining healed fracture deflected biotite					SLK = Type I PL(A) = 522
2880																2871.1': 38° Planar smooth					
2885																From 2873' to 2873.2': (2) 0° Planar smooth					C 100 8
2890																From 2876' to 2879': Multiple 30°-90° fractures, rubble, planar rough					
2895																From 2879' to 2887': Rubble decomposed					C 100 47
2900																2887.4': 26° Planar smooth					
																2888.2': 42°-90° Planar smooth					C 100 17
																From 2891.35' to 2891.72': 69°-71° Undulating rough					
																From 2892' to 2894': Rev angle 77°-74°-72° healed Ca+2 90° fracturing ending at 45° planar smooth					C 100 17
																2898': 0°-12° Planar smooth					
																From 2898.4' to 2895': Rubble					C 100 17
																From 2900' to 2902': (7) 42°-51° J. fractures planar smooth					
																From 2902.3' to 2905': Disc (10) 0° planar smooth					C 100 17

BORING TYPE: HQ3
HOLE DEPTH (ft): 3045
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 795 ft, 826.5 ft

LOGGED BY: Chris Messenger
CASING: HW to 70 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154898.691
EASTING: 6515647.859

PROJECT No: 951-20
DATE: 6/1/2023 - 7/25/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
-2910																-2905.6': 42° Planar smooth					UCS = 22,134
-2915																-2907': 0° Planar rough		C	100	80	PL(A) = 848
																-2907.6': 3° Planar smooth					
																-2908': 42° Planar smooth K feldspar					UCS = 15,131
																-2909.2': 41° Stepped rough					
																-2910.8': 7°-11° Planar smooth					ITS = 673
																-2913.8': 40° Planar smooth					SLK = Type I
																-2914.9': 79° Undulating rough					
																From 2915.5' to 2915.75': Wedge 32°-42° Planar smooth		C	100	30	ITS = 815
																From 2916.5' to 2917': Stepped rough 42°-42° wedge					SLK = Type I
-2920																					
-2921.0	DIABASE DIKE															-2921': 80° Planar rough					
																From 2921.8' to 2922.6': Diabase 90° dike					
-2923.0																From 2922.9' to 2923.9': 90° Planar smooth					
-2925																From 2924' to 2928': Rubble					
-2927.45	DIABASE DIKE																				
																From 2928.3' to 2930': Diabase 84° dike		C	100	20	
-2930																From 2930' to 2932': Intrusive alteration rubble					
-2930.65																					
																-2933': 39° Planar rough					
																-2933.4': Rev angle 42° rough undulating					PL(A) = 813
-2933.35	QTZ MONZONITE, light gray to white, phaneritic, massive, with plagioclase, K feldspar, biotite, and quartz, trace muscovite, pyrite, and chlorite															From 2935' to 2936.75': Stepped rough 81° and 83° J. fractures					
																From 2938.2' to 2938.5': (3) 62° J. undulating slickenside fractures		C	100	12	ITS = 893
																-2939': (3) 42° Planar					

BORING TYPE: HQ3
HOLE DEPTH (ft): 3045
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 795 ft, 826.5 ft

LOGGED BY: Chris Messenger
CASING: HW to 70 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type ☐)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
WL	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154898.691
EASTING: 6515647.859

PROJECT No: 951-20
DATE: 6/1/2023 - 7/25/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
-375 -2945																smooth J. fractures					
-380 -2950																-2943': Disc alteration 0° rough planar					UCS = 13,118
-385 -2955																-2944.9': 27° Planar smooth					PL(A) = 446
-390 -2960																-2945.7': 39° Planar smooth					ITS = 842
-395 -2965																-2949': 51° Undulating rough					SLK = Type I
-400 -2970																-2952.9': 42° Planar smooth Ca+2					UCS = 19,524 SLK = Type I
																-2956.9': 27° Planar smooth					
																From 2957' to 2964': (40) Disc alteration planar rough					PL(A) = 432
																From 2965' to 2966': 90° Stepped rough and 71° Planar rough					
																-2966.9': 9° Planar smooth K feldspar					
																From 2967' to 2970': Rubble					
																-2971.1': 31° Stepped smooth K feldspar					UCS = 9,417
																-2972.4': 0°-7° Planar smooth					PL(A) = 1,082
																-2972.6': 0°-7° Planar smooth					ITS = 1,171

BORING TYPE: HQ3
HOLE DEPTH (ft): 3045
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 795 ft, 826.5 ft

LOGGED BY: Chris Messenger
CASING: HW to 70 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type ___)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154898.691
EASTING: 6515647.859

PROJECT No: 951-20
DATE: 6/1/2023 - 7/25/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
-410 -2980																2972.9' 0°-7° Planar smooth					SLK = Type II
-415 -2985																From 2973' to 2975': (6) 39° Planar smooth J.		C	100	11	
-420 -2990																From 2977' to 2978': (3) 29°-84° J. planar rough					
-425 -2995																From 2979' to 2980': (4) 0°-9° Planar rough		C	100	7	
-430 -3000																		C	100	0	
-435 -3005																		C	100	20	
																From 3010' to 3012': Veined and Ca+2 K					

BORING TYPE: HQ3
HOLE DEPTH (ft): 3045
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 795 ft, 826.5 ft

LOGGED BY: Chris Messenger
CASING: HW to 70 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type __)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
WL	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154898.691
EASTING: 6515647.859

PROJECT No: 951-20
DATE: 6/1/2023 - 7/25/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities	Sampling & In Situ Testing																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																							
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard				B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																		

BORING TYPE: HQ3
Bottom of borehole at 3045.0 feet.

HOLE DEPTH (ft): 3045

REMARKS:

DRILLER: Crux

WATER OBSERVATIONS: 795 ft, 826.5 ft

LOGGED BY: Chris Messenger

CASING: HW to 70 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type ___)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)



CLIENT: Lane Power & Energy Solutions

SURFACE ELEVATION (ft): 2570

PROJECT No: 951-20

PROJECT: Hydrostor Zevsar

NORTHING: 2154809.152

DATE: 8/5/2023 - 10/21/2023

PROJECT LOCATION: Rosamod, CA

EASTING: 6514431.756

DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
0	Well Casing																				
5																					
10																					
15																					
20																					
25																					
30																					

BORING TYPE: HQ3

DRILLER: CruX

LOGGED BY: Chris Messenger

HOLE DEPTH (ft): 3014.7

WATER OBSERVATIONS: 711 ft

CASING: HW to 171 ft

REMARKS: _____

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type <u> </u>)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions

SURFACE ELEVATION (ft): 2570

PROJECT No: 951-20

PROJECT: Hydrostor Zevsar

NORTHING: 2154809.152

DATE: 8/5/2023 - 10/21/2023

PROJECT LOCATION: Rosamod, CA

EASTING: 6514431.756

DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
40 2530																					
45 2525																					
50 2520																					
55 2515																					
60 2510																					
65 2505																					

BORING TYPE: HQ3

DRILLER: CruX

LOGGED BY: Chris Messenger

HOLE DEPTH (ft): 3014.7

WATER OBSERVATIONS: 711 ft

CASING: HW to 171 ft

REMARKS: _____

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type <u> </u>)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions

SURFACE ELEVATION (ft): 2570

PROJECT No: 951-20

PROJECT: Hydrostor Zevsar

NORTHING: 2154809.152

DATE: 8/5/2023 - 10/21/2023

PROJECT LOCATION: Rosamod, CA

EASTING: 6514431.756

DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
75 2495																					
80 2490																					
85 2485																					
90 2480																					
95 2475																					
100 2470																					

BORING TYPE: HQ3

DRILLER: CruX

LOGGED BY: Chris Messenger

HOLE DEPTH (ft): 3014.7

WATER OBSERVATIONS: 711 ft

CASING: HW to 171 ft

REMARKS: _____

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type <u> </u>)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154809.152
EASTING: 6514431.756

PROJECT No: 951-20
DATE: 8/5/2023 - 10/21/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
110 2460																					
115 2455																					
120 2450																					
125 2445																					
130 2440																					
135 2435																					

BORING TYPE: HQ3
HOLE DEPTH (ft): 3014.7
REMARKS: _____

DRILLER: CruX
WATER OBSERVATIONS: 711 ft

LOGGED BY: Chris Messenger
CASING: HW to 171 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type __)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions

SURFACE ELEVATION (ft): 2570

PROJECT No: 951-20

PROJECT: Hydrostor Zevsar

NORTHING: 2154809.152

DATE: 8/5/2023 - 10/21/2023

PROJECT LOCATION: Rosamod, CA

EASTING: 6514431.756

DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
145 2425																					
150 2420																					
155 2415																					
160 2410																					
165 2405																					
170 2400																					
171	QTZ MONZONITE, light gray to white, phaneritic, massive, with plagioclase, K feldspar, alkali quartz, pyroxene, and biotite, trace chlorite, muscovite, and pyrite															From 171.9' to 172.7': 90° Planar smooth Ca+2 infill					
																-173.7': 32° Planar smooth		C	100	44	

BORING TYPE: HQ3

DRILLER: CruX

LOGGED BY: Chris Messenger

HOLE DEPTH (ft): 3014.7

WATER OBSERVATIONS: 711 ft

CASING: HW to 171 ft

REMARKS: _____

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type <u> </u>)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154809.152
EASTING: 6514431.756

PROJECT No: 951-20
DATE: 8/5/2023 - 10/21/2023
DIP/AZIMUTH: -90 /

EL	DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																			
			Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																

BORING TYPE: HQ3
HOLE DEPTH (ft): 3014.7
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 711 ft

LOGGED BY: Chris Messenger
CASING: HW to 171 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type ___)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154809.152
EASTING: 6514431.756

PROJECT No: 951-20
DATE: 8/5/2023 - 10/21/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
215																					
220																					
225																					
230																					
235																					
240																					

BORING TYPE: HQ3
HOLE DEPTH (ft): 3014.7
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 711 ft

LOGGED BY: Chris Messenger
CASING: HW to 171 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type ___)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154809.152
EASTING: 6514431.756

PROJECT No: 951-20
DATE: 8/5/2023 - 10/21/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
250 2320																					
255 2315																					
260 2310																					
265 2305																					
270 2300																					
275 2295																					

BORING TYPE: HQ3
HOLE DEPTH (ft): 3014.7
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 711 ft

LOGGED BY: Chris Messenger
CASING: HW to 171 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154809.152
EASTING: 6514431.756

PROJECT No: 951-20
DATE: 8/5/2023 - 10/21/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
285																		C	100	30	
290																		C	100	80	
295																293.9': 7° Planar smooth					
																295.9': Planar smooth					
300																From 298.6' to 298.9': (2) Planar irregular					
																300.75': Planar irregular					
305																From 302.4' to 303.2': 74° Planar smooth					
																From 303.7' to 304': (2) 17°-22° Planar irregular		C	100	53	
																304.7': 55° Planar irregular					
																305.4': Planar irregular					
																308': 42° Planar smooth					
310																From 310' to 311': (4) 0°-10° Planar smooth					
																312': 17° Planar irregular					
																312.9': 41° Planar irregular		C	100	69	
																314.45': Planar irregular					

BORING TYPE: HQ3
HOLE DEPTH (ft): 3014.7
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 711 ft

LOGGED BY: Chris Messenger
CASING: HW to 171 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type ___)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
WL	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154809.152
EASTING: 6514431.756

PROJECT No: 951-20
DATE: 8/5/2023 - 10/21/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
320																From 316' to 317': Rubble					
325																317.5': 42° Planar smooth					
																318.25': 17° Planar					
																318.75': 42° Undulating smooth					
330																320.2': Undulating smooth					
																From 321.2' to 321.75': 32° Planar smooth					
																From 323' to 324': Rubble	C	100	70		
335																327.1': 0° Planar smooth, 45° planar smooth					
																329': 22° Undulating smooth					
																From 331' to 332.5': (3) 16°-24° Planar irregular					
340																334.1': 49° Planar smooth	C	100	61		
																From 337' to 339': (8) 0°-4° Planar smooth					
345																342': Planar irregular	C	100	90		
																348.75': 39° Planar smooth					

BORING TYPE: HQ3
HOLE DEPTH (ft): 3014.7
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 711 ft

LOGGED BY: Chris Messenger
CASING: HW to 171 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type __)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154809.152
EASTING: 6514431.756

PROJECT No: 951-20
DATE: 8/5/2023 - 10/21/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
355 2215																351.7': Rev fracture veining, 39° undulating smooth					
																From 353' to 353.8': 32°-45° Planar smooth		C	100	78	
360 2210																360': 67° Undulating rough					
																362.3': 42° Undulating rough		C	100	80	
365 2205																363': Planar irregular					
																364.1': 52° Slickenside					
																From 365.1' to 365.45': 77° Undulating rough					
																From 366' to 366.5': Rubble					
																From 366.5' to 367': 89° Stepped rough					
370 2200																368.9': 31° Planar rough					
																369.85': 36° Planar smooth					
																370.75': 42° Undulating rough					
375 2195																From 374' to 376': (3) 22°-31° Planar smooth/rough		C	100	82	
																375.9': 31° Planar slickenside					
																From 377' to 378': 90° Rough, rubble					
																378.75': Planar smooth					
380 2190																379': Rev angle 31°-42° undulating rough					
																380': 47° Undulating rough					
																From 381' to 383': 90° S. stepped rough		C	100	61	

BORING TYPE: HQ3
HOLE DEPTH (ft): 3014.7
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 711 ft

LOGGED BY: Chris Messenger
CASING: HW to 171 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154809.152
EASTING: 6514431.756

PROJECT No: 951-20
DATE: 8/5/2023 - 10/21/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
390																					
395																					
400																					
405																					
410																					
415																					

BORING TYPE: HQ3
HOLE DEPTH (ft): 3014.7
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 711 ft

LOGGED BY: Chris Messenger
CASING: HW to 171 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type ___)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)



CLIENT: Lane Power & Energy Solutions

SURFACE ELEVATION (ft): 2570

PROJECT No: 951-20

PROJECT: Hydrostor Zevsar

NORTHING: 2154809.152

DATE: 8/5/2023 - 10/21/2023

PROJECT LOCATION: Rosamod, CA

EASTING: 6514431.756

DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
																smooth					
																-421.75': 69° Undulating slickenside					
																424.1': Undulating rough		C	100	93	
																425.1': 45° Planar slickenside					
																428.75': Planar rough					
																429.35': 0° Planar smooth					
																430.5': 0° Planar smooth					
																432': 31° Planar smooth		C	100	62	
																435': 42° Planar smooth					
																From 439' to 440': (4) 0°-4° Planar smooth					
																441.25': 37° Planar smooth					
																From 441.5' to 446': (8) 0°-7° Planar smooth		C	100	60	
																448.35': 45° Undulating rough					
																From 451' to 461': Multiple 0°-12° Planar smooth fractures throughout		C	100	30	

BORING TYPE: HQ3

DRILLER: Crux

LOGGED BY: Chris Messenger

HOLE DEPTH (ft): 3014.7

WATER OBSERVATIONS: 711 ft

CASING: HW to 171 ft

REMARKS: _____

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type ____)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154809.152
EASTING: 6514431.756

PROJECT No: 951-20
DATE: 8/5/2023 - 10/21/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
460 2110																					
465 2105																					
470 2100																					
475 2095																					
480 2090																					
485 2085																					

BORING TYPE: HQ3
HOLE DEPTH (ft): 3014.7
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 711 ft

LOGGED BY: Chris Messenger
CASING: HW to 171 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type ___)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
WL	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions

SURFACE ELEVATION (ft): 2570

PROJECT No: 951-20

PROJECT: Hydrostor Zevsar

NORTHING: 2154809.152

DATE: 8/5/2023 - 10/21/2023

PROJECT LOCATION: Rosamod, CA

EASTING: 6514431.756

DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
495																		C	90	0	
496	CORE LOSS																				
497																					
500																					
505																-502.6': Stepped slickenside/ rough From 504' to 506': (4) 32°-41° Undulating rough -506.35': 67° Planar smooth From 508' to 512': (9) 12°-21° Planar smooth		C	100	41	
510																					
515																513.2': 49° Slickenside 514': 39° Slickenside -515.7': 44°-39° Wedge rev angle, planar smooth From 517' to 520': (8) Weak fractures irregular 0°-27°		C	100	26	
520																523': 39° Irregular 524': Planar irregular		C	100	27	

BORING TYPE: HQ3

DRILLER: Crux

LOGGED BY: Chris Messenger

HOLE DEPTH (ft): 3014.7

WATER OBSERVATIONS: 711 ft

CASING: HW to 171 ft

REMARKS: _____

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type ____)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154809.152
EASTING: 6514431.756

PROJECT No: 951-20
DATE: 8/5/2023 - 10/21/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities B - Bedding S - Shear J - Joint F- Fault	Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard				Type	Core Rec. %	RQD %	Test Results & Comments
530	QTZ MONZONITE, light gray to white, phaneritic, massive, with plagioclase, K feldspar, quartz, biotite, and pyroxene, trace muscovite, chlorite, pyrite																			
531																				
535																				
540																				
545																				
550																				
555																				

BORING TYPE: HQ3
HOLE DEPTH (ft): 3014.7
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 711 ft

LOGGED BY: Chris Messenger
CASING: HW to 171 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)



CLIENT: Lane Power & Energy Solutions

SURFACE ELEVATION (ft): 2570

PROJECT No: 951-20

PROJECT: Hydrostor Zevsar

NORTHING: 2154809.152

DATE: 8/5/2023 - 10/21/2023

PROJECT LOCATION: Rosamod, CA

EASTING: 6514431.756

DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
565	QTZ MONZONITE, light gray to white, phaneritic, massive															-561.7': 61° Planar smooth					
																-563.2': 12° Planar smooth		C	100	34	
																-564': 49° Planar rough					
																-565.45': 7° Planar smooth					
																From 567' to 572': (9) 12°-27° Planar smooth					
570																570.2': J.					
575																		C	100	70	
																From 575.6' to 576': 82° S. undulating smooth					
580																					
585																From 581' to 582.25': (3) 12°-17° Undulating smooth		C	100	70	
																584.1': 7° Planar rough					
																From 585' to 585.7': 61° Planar smooth					
																586.7': Undulating smooth					
																From 587' to 590.3': (3) 22°-27° Planar smooth					
590																		C	100	20	

BORING TYPE: HQ3

DRILLER: Crux

LOGGED BY: Chris Messenger

HOLE DEPTH (ft): 3014.7

WATER OBSERVATIONS: 711 ft

CASING: HW to 171 ft

REMARKS: _____

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type ___)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
WL	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154809.152
EASTING: 6514431.756

PROJECT No: 951-20
DATE: 8/5/2023 - 10/21/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
600																					
605																		C	100	30	
610																		C	100	20	
615																					
620																					
621	QTZ MONZONITE, light gray to white, phaneritic, massive, rich in feldspar, quartz, pyroxene, and biotite, trace chlorite, muscovite, pyrite																	C	100	79	-621.5': 45° Undulating smooth along veins -623': 67° Undulating smooth along veins -624': 78° Undulating rough -From 625.7' to 626': 17° Planar smooth -629.6': 31° Planar
625																					

BORING TYPE: HQ3
HOLE DEPTH (ft): 3014.7
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 711 ft

LOGGED BY: Chris Messenger
CASING: HW to 171 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type ___)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
WL	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions

SURFACE ELEVATION (ft): 2570

PROJECT No: 951-20

PROJECT: Hydrostor Zevsar

NORTHING: 2154809.152

DATE: 8/5/2023 - 10/21/2023

PROJECT LOCATION: Rosamod, CA

EASTING: 6514431.756

DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
635																smooth					
640																From 632' to 635': (6) 7°-12° Planar smooth		C	100	70	
645																640.5': 17° Planar smooth					
650																642.9': 38° Undulating rough		C	100	40	
655																643.6': 61° Planar smooth					
660																From 646' to 648': 90° Stepped rough					
																From 651' to 654.6': (12) 0°-19° Planar smooth		C	100	73	
																655.8': 39° Undulating slickenside/smooth					
																659.3': 3° Planar rough					
																660': 2° Planar smooth					
																663.31': 21° Planar smooth		C	100	78	

BORING TYPE: HQ3

DRILLER: Crux

LOGGED BY: Chris Messenger

HOLE DEPTH (ft): 3014.7

WATER OBSERVATIONS: 711 ft

CASING: HW to 171 ft

REMARKS: _____

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type ____)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
WL	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154809.152
EASTING: 6514431.756

PROJECT No: 951-20
DATE: 8/5/2023 - 10/21/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
670																664.78': 0° Planar rough					
675																665.2': 0° Planar smooth					
																From 666' to 667': (2) 0°-12° Planar smooth					
680																From 671' to 675': (9) 0°-21° Planar smooth		C	100	77	
685																From 679.7' to 680.1': (3) 12° Planar smooth					
690																From 681.2' to 681.7': (3) 27°-38° Undulating smooth		C	100	82	
695																683': 40° Planar smooth					
																684': 30° Planar smooth					
																685.6': 39° Planar smooth					
																692.3': 21° Planar rough		C	100	96	

BORING TYPE: HQ3
HOLE DEPTH (ft): 3014.7
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 711 ft

LOGGED BY: Chris Messenger
CASING: HW to 171 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type ___)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
WL	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154809.152
EASTING: 6514431.756

PROJECT No: 951-20
DATE: 8/5/2023 - 10/21/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
705																					
710																					
715																					
720																					
725																					
730																					

BORING TYPE: HQ3
HOLE DEPTH (ft): 3014.7
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 711 ft

LOGGED BY: Chris Messenger
CASING: HW to 171 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type ___)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154809.152
EASTING: 6514431.756

PROJECT No: 951-20
DATE: 8/5/2023 - 10/21/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
740																735': 42° Undulating smooth					
																737.62': Planar rough					
																739.95': 29° Planar smooth					
745																743.2': 42° Planar smooth		C	100	90	
																749': 39° Undulating rough					
750																752': 0° Planar smooth		C	100	91	
																754.71': 41° Slickenside					
																756.2': 37° Planar smooth					
																757.1': 45° Planar smooth					
																759.3': 19° Planar smooth					
760																763': Veining, 79° slickenside		C	100	90	
																764.55': 31°-25° J. planar rough					
765																					

BORING TYPE: HQ3
HOLE DEPTH (ft): 3014.7
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 711 ft

LOGGED BY: Chris Messenger
CASING: HW to 171 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type ___)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
WL	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154809.152
EASTING: 6514431.756

PROJECT No: 951-20
DATE: 8/5/2023 - 10/21/2023
DIP/AZIMUTH: -90 /

EL	DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities	Sampling & In Situ Testing																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																				
			Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard				B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																															

BORING TYPE: HQ3
HOLE DEPTH (ft): 3014.7
REMARKS: _____

DRILLER: Crux
WATER OBSERVATIONS: 711 ft

LOGGED BY: Chris Messenger
CASING: HW to 171 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type _____)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
WL	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154809.152
EASTING: 6514431.756

PROJECT No: 951-20
DATE: 8/5/2023 - 10/21/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
810																					
815																					
820																		C	100	97	
825																					
830																					
835																					

BORING TYPE: HQ3
HOLE DEPTH (ft): 3014.7
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 711 ft

LOGGED BY: Chris Messenger
CASING: HW to 171 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type __)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)



CLIENT: Lane Power & Energy Solutions

SURFACE ELEVATION (ft): 2570

PROJECT No: 951-20

PROJECT: Hydrostor Zevsar

NORTHING: 2154809.152

DATE: 8/5/2023 - 10/21/2023

PROJECT LOCATION: Rosamod, CA

EASTING: 6514431.756

DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
845																840.2': 21° Planar smooth veins					
850																845.1': 43° Planar smooth					
855																849': 21° Planar smooth veins					
860																From 851' to 852': (2) 28° Planar smooth					
865																From 853.9' to 857.9': Stepped/undulating smooth					
870																858.6': 21° Planar smooth					
																859.9': Planar smooth					
																860.4': 32° Planar smooth					
																861.2': Planar					
																863.3': Planar					
																864.8': Planar					
																867.9': 25° S.					
																868.2': Planar					
																869': S.					
																870.9': 45° S.					
																872.7': Planar					
																873': Planar					
																874': J.					

BORING TYPE: HQ3

DRILLER: Crux

LOGGED BY: Chris Messenger

HOLE DEPTH (ft): 3014.7

WATER OBSERVATIONS: 711 ft

CASING: HW to 171 ft

REMARKS: _____

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type _____)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
WL	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154809.152
EASTING: 6514431.756

PROJECT No: 951-20
DATE: 8/5/2023 - 10/21/2023
DIP/AZIMUTH: -90 /

EL	DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																							
			Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Cone Rec. %	RQD %	Test Results & Comments																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																				

BORING TYPE: HQ3
HOLE DEPTH (ft): 3014.7
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 711 ft

LOGGED BY: Chris Messenger
CASING: HW to 171 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type ___)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154809.152
EASTING: 6514431.756

PROJECT No: 951-20
DATE: 8/5/2023 - 10/21/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
915																					
920																					
925																					
930																					
935																					
940																					

BORING TYPE: HQ3
HOLE DEPTH (ft): 3014.7
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 711 ft

LOGGED BY: Chris Messenger
CASING: HW to 171 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type ___)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154809.152
EASTING: 6514431.756

PROJECT No: 951-20
DATE: 8/5/2023 - 10/21/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
950	From 971' to 972': Qtz feldspar															From 943' to 944': J.					
																944.9': Planar					
																945.5': 75° S.					
																945.9': Planar					
																946.6': 40° S.					
																946.8': 50° S.					
																947': 40° S.					
																947.7': 45° S.					
																948': 50° S.					
																948.6': 35° S.					
																950': Planar	C	100	73		
																From 952' to 953.5': J.					
																953.6': 25° S.					
																955.4': 40° S.					
																957': Planar					
																957.6': Planar					
																957.9': 45° S.					
																959.5': Planar					
																962': Planar					
																962.9': 48° S.	C	100	40		
																963.2': 28° S.					
																964': 55° S.					
																966': 65° S.					
																From 966.1' to 971': Fractured throughout					
																971.2': 20° S.					
																973.3': 30° S.	C	100	63		
																973.5': 55° S.					
																From 974.2' to 974.9': Multiple planar S. at 40°-40°-30°-45°					
																975.9': 60° S.					
																976': 45° S.					
																977.7': 43° S.					
																978.6': Planar					

BORING TYPE: HQ3
HOLE DEPTH (ft): 3014.7
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 711 ft

LOGGED BY: Chris Messenger
CASING: HW to 171 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)

CLIENT: Lane Power & Energy Solutions

SURFACE ELEVATION (ft): 2570

PROJECT No: 951-20

PROJECT: Hydrostor Zevsar

NORTHING: 2154809.152

DATE: 8/5/2023 - 10/21/2023

PROJECT LOCATION: Rosamod, CA

EASTING: 6514431.756

DIP/AZIMUTH: -90 /

EL	DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)				Discontinuities		Sampling & In Situ Testing			
			Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard		0.05	0.25	0.50	2.50	5.00	B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %
																		980.2': 40° S.							
																		981.25': 42° Stepped slickenside							
																		982.9': 11° Planar smooth	C	100	63				
	985																	984': 90°-71° Stepped rough							
																		985': 36° Planar smooth							
																		986.1': Wedge rev angle 39°-46° planar slickenside							
																		987.9': 17° Stepped rough							
	990																	From 990' to 991': 90° S. planar smooth							
																		993.65': 16° Planar smooth	C	100	51				
	995																	995.62': 3° Planar smooth							
	1000																								
																				C	100	73			
	1005																								
	1010																								
																				C	100	89			
																		1013.75': 45° Planar smooth							

BORING TYPE: HQ3

DRILLER: Crux

LOGGED BY: Chris Messenger

HOLE DEPTH (ft): 3014.7

WATER OBSERVATIONS: 711 ft

CASING: HW to 171 ft

REMARKS:

<u>SAMPLING & IN SITU TESTING LEGEND</u>					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type _____)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154809.152
EASTING: 6514431.756

PROJECT No: 951-20
DATE: 8/5/2023 - 10/21/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
1020																1014.7': 12° Planar smooth					
1025																1017.85': 3° Planar rough					
1030																1023.9': 4° Undulating rough		C	100	62	
1035																From 1025' to 1026': (3) 3°-17° Planar smooth					
1040																1027.1': 12° Planar smooth					
1045																From 1029.35' to 1031': 90° Stepped rough					
1041	QTZ MONZONITE, light gray to white, phaneritic, massive															1031.9': 62° Planar smooth					
																1033.6': 40° Undulating rough		C	100	65	
																From 1034' to 1035': (2) 11°-19° Planar smooth					
																1042.2': Planar smooth					
																From 1043' to 1044': (2) 46° Planar smooth		C	100	41	
																1043.3': 45° S. undulating					
																1043.7': Planar undulating					
																1045': 59° Planar slickenside					
																1045.1': 45° S.					
																1046': 45° Planar					

BORING TYPE: HQ3
HOLE DEPTH (ft): 3014.7
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 711 ft

LOGGED BY: Chris Messenger
CASING: HW to 171 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type ___)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions

SURFACE ELEVATION (ft): 2570

PROJECT No: 951-20

PROJECT: Hydrostor Zevsar

NORTHING: 2154809.152

DATE: 8/5/2023 - 10/21/2023

PROJECT LOCATION: Rosamod, CA

EASTING: 6514431.756

DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
1055	QTZ MONZONITE, light gray, phaneritic, massive																				
1060																					
1065																					
1070																					
1075																					
1080																					
	From 1083' to 1086': Qtz feldspar pegmatite																				

BORING TYPE: HQ3

DRILLER: Crux

LOGGED BY: Chris Messenger

HOLE DEPTH (ft): 3014.7

WATER OBSERVATIONS: 711 ft

CASING: HW to 171 ft

REMARKS:

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
L	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154809.152
EASTING: 6514431.756

PROJECT No: 951-20
DATE: 8/5/2023 - 10/21/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
1086	QTZ MONZONITE, light gray to white, phaneritic, massive															rough					
																1061.8': 45° Undulating rough					
																1062.3': 45° Planar rough					
																1062.5': Undulating rough					
1090																From 1063.5' to 1073': Multiple fractures					
																1074.2': 35° Planar smooth					
																1075': Planar smooth					
																1075.4': Planar smooth		C	100	53	
																1075.7': Planar smooth					
1095	From 1096' to 1097': Qtz feldspar															1077': 45° Undulating rough					
																1077.3': 18° Undulating rough					
																1077.6': 45° Planar smooth					
																1077.8': 45° Undulating rough					
																1077.9': 45° Undulating rough					
1100																1078': 55° Planar smooth					
																1080.4': 40° Planar smooth		C	100	100	
																1082': 50° Planar rough					
1105																1085': Planar undulating					
																1087.2': 73° Undulating rough					
																1088': Planar rough					
																1089': Planar rough					
																1090': 55° Stepped slickenside					
1110																1090.9': Planar rough					
																1092': 35° Planar smooth					
																1094': Planar smooth					
																From 1094.5' to 1095': J.		C	100	91	
1115	From 1115' to 1117': Qtz feldspar															1095.2': 50° Undulating rough					
																1095.7': 25° Planar rough					
																From 1095.9' to 1097': Multiple J.					
																1097.3': Undulating planar					
	From 1119' to 1121': Qtz feldspar															1097.5': 45° Planar					

BORING TYPE: HQ3
HOLE DEPTH (ft): 3014.7
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 711 ft

LOGGED BY: Chris Messenger
CASING: HW to 171 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)

CLIENT: Lane Power & Energy Solutions

SURFACE ELEVATION (ft): 2570

PROJECT No: 951-20

PROJECT: Hydrostor Zevsar

NORTHING: 2154809.152

DATE: 8/5/2023 - 10/21/2023

PROJECT LOCATION: Rosamod, CA

EASTING: 6514431.756

DIP/AZIMUTH: -90 /

[illegible]

BORING TYPE: HQ3

DRILLER: Crux

LOGGED BY: Chris Messenger

HOLE DEPTH (ft): 3014.7

WATER OBSERVATIONS: 711 ft

CASING: HW to 171 ft

REMARKS:

SAMPLING & IN SITU TESTING LEGEND			
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)
		SLK	Slake durability test (Type ___)
		TRI	Triaxial stress test (psi)
		UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154809.152
EASTING: 6514431.756

PROJECT No: 951-20
DATE: 8/5/2023 - 10/21/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
1160																					
1165																					
1170																					
1175																					
1176	QTZ MONZONITE, light gray to white, phaneritic, massive																				
1180																					
1185																					

BORING TYPE: HQ3
HOLE DEPTH (ft): 3014.7
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 711 ft

LOGGED BY: Chris Messenger
CASING: HW to 171 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154809.152
EASTING: 6514431.756

PROJECT No: 951-20
DATE: 8/5/2023 - 10/21/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
1192	From 1192' to 1195': Qtz feldspar pegmatite																				
1196.95	DOLERITE																				
1197																					
1200																		C	100	86	
1203																					
1205																					
1210																		C	100	78	
1215																					
1216	DOLERITE, with intrusive pegmatite																				
1220																		C	100	63	
1221																					
1225																					
1230																					

BORING TYPE: HQ3
HOLE DEPTH (ft): 3014.7
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 711 ft

LOGGED BY: Chris Messenger
CASING: HW to 171 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
WL	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154809.152
EASTING: 6514431.756

PROJECT No: 951-20
DATE: 8/5/2023 - 10/21/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
1229																					
1230																		C	100	48	
1235																					
1240																					
1245																					
1248	DOLERITE																				
1250																					
1251																					
1255																					
1258	CORE LOSS																				

BORING TYPE: HQ3
HOLE DEPTH (ft): 3014.7
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 711 ft

LOGGED BY: Chris Messenger
CASING: HW to 171 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154809.152
EASTING: 6514431.756

PROJECT No: 951-20
DATE: 8/5/2023 - 10/21/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
1264																					
1265																					
1268.2																		C	100	89	
1269																					
1269.75																					
1270																					
1272.3																					
1275																					
1278.25																		C	100	68	
1279.9																					
1281																					
1284																					
1285.5																					
1289																		C	100	27	
1290																					

BORING TYPE: HQ3
HOLE DEPTH (ft): 3014.7
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 711 ft

LOGGED BY: Chris Messenger
CASING: HW to 171 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154809.152
EASTING: 6514431.756

PROJECT No: 951-20
DATE: 8/5/2023 - 10/21/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
1300																					
1270																					
1305																					
1265																					
1310																					
1260																					
1315																					
1255	From 1316' to 1318': Qtz feldspar																				
1320																					
1250																					
1321	DOLERITE																				
1325																					
1245																					
1328																					

BORING TYPE: HQ3
HOLE DEPTH (ft): 3014.7
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 711 ft

LOGGED BY: Chris Messenger
CASING: HW to 171 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type __)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
WL	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154809.152
EASTING: 6514431.756

PROJECT No: 951-20
DATE: 8/5/2023 - 10/21/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
1335	From 1338' to 1343': Qtz feldspar pegmatite															1328.4': 39° Planar smooth					
1340																1330.4': 45° Planar smooth					
1345	From 1345.75' to 1347': Qtz feldspar pegmatite															From 1333.9' to 1335': (2) 0°-4° Planar rough					
1350																1335': 90° Undulating rough					
1355	QTZ MONZONITE, light gray, phaneritic, massive															1342': 69° Undulating rough					
1360																1342.75': 74° Undulating rough					
																1343.8': 90° Vertical fracture					
																1345.8': Irregular					
																From 1346.5' to 1347': Rubble					
																1348.3': 21° Undulating smooth					
																1351.3': 39° Planar smooth					
																From 1353.7' to 1354': 50° Planar smooth					
																1357.8': 45° Planar smooth					
																1359.3': Planar smooth					
																1360.7': 82° S.					
																From 1361' to 1361.9': Multiple breaks, J.					
																From 1362' to 1364.7': Multiple breaks					

BORING TYPE: HQ3
HOLE DEPTH (ft): 3014.7
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 711 ft

LOGGED BY: Chris Messenger
CASING: HW to 171 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions

SURFACE ELEVATION (ft): 2570

PROJECT No: 951-20

PROJECT: Hydrostor Zevsar

NORTHING: 2154809.152

DATE: 8/5/2023 - 10/21/2023

PROJECT LOCATION: Rosamod, CA

EASTING: 6514431.756

DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																	
																		Type		Core Rec. %	RQD %	Test Results & Comments																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																													
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																		
1370															1365.5': 75° Undulating rough 1366.2': 45° Undulating smooth 1367': 65° Undulating smooth 1369.6': 7°-0° Undulating rough 1369.9': 35° Planar smooth From 1371.5' to 1375': 70° Planar rough From 1372.4' to 1373.1': J., rubble 1373.6': Planar rough 1374.4': 65° Planar rough 1375.5': 30° Planar smooth 1376': 50° Planar rough 1376.9': 60° Planar rough From 1377' to 1378': Decomposed, rubble 1378.5': 72° Planar rough From 1379' to 1380': Rubble From 1380.5' to 1381': J. From 1381' to 1383.7': Decomposed, rubble 1384.2': Planar rough 1384.7': 60° Planar rough 1385.8': Stepped rough From 1386' to 1388': Decomposed, multiple fractures 1388.1': 40° Planar rough From 1388.8' to 1389.3': 50° J. 1390.3': Planar smooth 1390.5': 78° Undulating rough From 1391' to 1392': Decomposed 1392.9': 35° Planar smooth 1393.4': 50° Planar smooth																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																				
1375																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																			

BORING TYPE: HQ3

DRILLER: Cruz

LOGGED BY: Chris Messenger

HOLE DEPTH (ft): 3014.7

WATER OBSERVATIONS: 711 ft

CASING: HW to 171 ft

REMARKS: _____

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type _____)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
WL	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)

CLIENT: Lane Power & Energy Solutions

SURFACE ELEVATION (ft): 2570

PROJECT No: 951-20

PROJECT: Hydrostor Zevsar

NORTHING: 2154809.152

DATE: 8/5/2023 - 10/21/2023

PROJECT LOCATION: Rosamod, CA

EASTING: 6514431.756

DIP/AZIMUTH: -90 /

[illegible]

BORING TYPE: HQ3

DRILLER: Crux

LOGGED BY: Chris Messenger

HOLE DEPTH (ft): 3014.7

WATER OBSERVATIONS: 711 ft

CASING: HW to 171 ft

REMARKS:

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type _____)
W	Water seep	PL(A)	Point load axial test 1s(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test 1s(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154809.152
EASTING: 6514431.756

PROJECT No: 951-20
DATE: 8/5/2023 - 10/21/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
1439.4	CORE LOSS															smooth					
1440.4																1436.3': Planar rough					
1440.4																1436.9': 30° Planar rough					
1440.4																From 1437' to 1439.4': Rubble					
1442.0																1442': Undulating rough		C	100	49	
1444.7																1444.7': J.					
1445.3																1445.3': 40° Planar smooth					
1446.0																From 1446' to 1447': Decomposed					
1447.7																1447.7': J.					
1448.6																1448.6': 40° Undulating rough					
1449.2																1449.2': 25° Undulating rough					
1449.7																From 1449.7' to 1450': Rubble					
1451.8																1451.8': Planar rough		C	100	38	
1453.4																1453.4': 30° Planar smooth					
1454.6																1454.6': 35° Planar smooth					
1456.0																From 1456' to 1461': Highly fractured, decomposed					
1461.0																From 1461' to 1462.5': Rubble					
1462.5	CORE LOSS															From 1463' to 1471.6': Multiple fractures		C	95	5	
1463.0																					
1465.0																					

BORING TYPE: HQ3
HOLE DEPTH (ft): 3014.7
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 711 ft

LOGGED BY: Chris Messenger
CASING: HW to 171 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
WL	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions

SURFACE ELEVATION (ft): 2570

PROJECT No: 951-20

PROJECT: Hydrostor Zevsar

NORTHING: 2154809.152

DATE: 8/5/2023 - 10/21/2023

PROJECT LOCATION: Rosamod, CA

EASTING: 6514431.756

DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
1474 1474.3 1475	CORE LOSS																				
1475																					
1480																					
1485																					
1490																					
1495																					
1500																					

BORING TYPE: HQ3

DRILLER: Crux

LOGGED BY: Chris Messenger

HOLE DEPTH (ft): 3014.7

WATER OBSERVATIONS: 711 ft

CASING: HW to 171 ft

REMARKS: _____

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type ____)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154809.152
EASTING: 6514431.756

PROJECT No: 951-20
DATE: 8/5/2023 - 10/21/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
1500	QTZ MONZONITE, light gray to white, phaneritic, massive, with plagioclase and K feldspar, quartz, and biotite														0.05	From 1506' to 1536': Rubble					
1510															0.25						
1515															0.50						
1520															2.50						
1525															5.00						
1530																					
1535																					

BORING TYPE: HQ3
HOLE DEPTH (ft): 3014.7
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 711 ft

LOGGED BY: Chris Messenger
CASING: HW to 171 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type ___)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions

SURFACE ELEVATION (ft): 2570

PROJECT No: 951-20

PROJECT: Hydrostor Zevsar

NORTHING: 2154809.152

DATE: 8/5/2023 - 10/21/2023

PROJECT LOCATION: Rosamod, CA

EASTING: 6514431.756

DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
1545	QTZ MONZONITE, light gray to white, phaneritic, massive, with Na-Ca-K rich feldspar, quartz, and biotite, trace muscovite, pyrite, and chlorite																				
1550																					
1551																					
1555																					
1560																					
1565																					
1570																					
																					ITS = 1,366

BORING TYPE: HQ3

DRILLER: Crux

LOGGED BY: Chris Messenger

HOLE DEPTH (ft): 3014.7

WATER OBSERVATIONS: 711 ft

CASING: HW to 171 ft

REMARKS: _____

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type _____)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
WL	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154809.152
EASTING: 6514431.756

PROJECT No: 951-20
DATE: 8/5/2023 - 10/21/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
1580																From 1575' to 1578': (5) 20°-38° Planar smooth					PL(A) = 1,288
1585																1578': 27° Undulating smooth		C	100	45	
1590																From 1578.1' to 1581': (5) 35°-45° Planar smooth					
1595																1582': 42° Planar smooth, rubble					
1600																1584.1': 31°					
1605																1587': 38° Planar smooth		C	100	70	UCS = 24,992
																1588': 61° Stepped smooth					
																1588.9': 52° Undulating rough					
																1589.9': 7° Planar smooth					
																From 1591' to 1594': (5) 27°-42° Planar smooth					
																From 1594.1' to 1596': Rubble					
																From 1596.1' to 1598.75': (8) 17° Planar smooth		C	100	50	PL(A) = 824
																1600': 38° Planar smooth					
																1602': 42° Undulating					
																1603.1': 32° Planar smooth					
																From 1604.6' to 1605': (2) 41° Planar smooth					
																From 1609' to 1611': 90° Vertical planar rough		C	100	60	

BORING TYPE: HQ3
HOLE DEPTH (ft): 3014.7
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 711 ft

LOGGED BY: Chris Messenger
CASING: HW to 171 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type ___)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions

SURFACE ELEVATION (ft): 2570

PROJECT No: 951-20

PROJECT: Hydrostor Zevsar

NORTHING: 2154809.152

DATE: 8/5/2023 - 10/21/2023

PROJECT LOCATION: Rosamod, CA

EASTING: 6514431.756

DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
1615																From 1611' to 1613': Rubble					PL(A) = 1,140 PL(A) = 1,093 PL(A) = 488
1620																-1619.2': 38° Undulating smooth		C	100	70	
1625																		C	100	80	
1630																-1631.4': 45° Planar smooth					UCS = 15,188 ITS = 1,338
1635																-1636.8': 31° Planar smooth					
1640																-1638': 41° Planar rough		C	100	50	
																From 1638.9' to 1641': (5) 40°-42° Planar smooth					
																-1641.25': 21° Planar smooth					
																-1643': 7° Planar smooth					

BORING TYPE: HQ3

DRILLER: Crux

LOGGED BY: Chris Messenger

HOLE DEPTH (ft): 3014.7

WATER OBSERVATIONS: 711 ft

CASING: HW to 171 ft

REMARKS: _____

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type ____)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
WL	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154809.152
EASTING: 6514431.756

PROJECT No: 951-20
DATE: 8/5/2023 - 10/21/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
1650	QTZ MONZONITE, light gray to white to pink, phaneritic, massive																				
1654																1648.2': 12° Planar rough		C	100	74	
1655																1648.3': 21° Planar smooth					
1660																1652.2': Planar rough					
1665																From 1654' to 1656': Highly fractured					
1670																1656.3': 55° Planar smooth		C	100	78	
																1657.4': 7° Planar smooth					
																1658.4': 72° Planar slickenside					
																1661.75': Planar irregular					
1675																1663.15': 12° Planar smooth					
																From 1666' to 1671': Rubble		C	100	18	
																From 1671' to 1681': Rubble					
																		C	100	40	

BORING TYPE: HQ3
HOLE DEPTH (ft): 3014.7
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 711 ft

LOGGED BY: Chris Messenger
CASING: HW to 171 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type ___)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
WL	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154809.152
EASTING: 6514431.756

PROJECT No: 951-20
DATE: 8/5/2023 - 10/21/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
1685																					
1690																					
1695																					
1700																					
1705																					
1710																					

BORING TYPE: HQ3
HOLE DEPTH (ft): 3014.7
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 711 ft

LOGGED BY: Chris Messenger
CASING: HW to 171 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type ___)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

CLIENT: Lane Power & Energy Solutions

SURFACE ELEVATION (ft): 2570

PROJECT No: 951-20

PROJECT: Hydrostor Zevsar

NORTHING: 2154809.152

DATE: 8/5/2023 - 10/21/2023

PROJECT LOCATION: Rosamod, CA

EASTING: 6514431.756

DIP/AZIMUTH: -90 /

EL	DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)				Discontinuities		Sampling & In Situ Testing																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																													
			Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard		0.05	0.25	0.50	2.50	5.00	B - Bedding	J - Joint	Type	Core Rec. %	RQD %	Test Results & Comments																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																									
																					S - Shear	F - Fault																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																													

BORING TYPE: HQ3

DRILLER: Crux

LOGGED BY: Chris Messenger

HOLE DEPTH (ft): 3014.7

WATER OBSERVATIONS: 711 ft

CASING: HW to 171 ft

REMARKS:

SAMPLING & IN SITU TESTING LEGEND			
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)
		SLK	Slake durability test (Type _____)
		TRI	Triaxial stress test (psi)
		UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154809.152
EASTING: 6514431.756

PROJECT No: 951-20
DATE: 8/5/2023 - 10/21/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
1755																					
1760																		C	100	20	
1765																1763.4': J.					
1770																1765.5': Planar rough 1765.8': J. 1766.4': 25° Planar rough 1766.6': 35° Planar smooth From 1767' to 1768': Rubble From 1769' to 1769.4': Multiple fractures, J. 1769.8': 35° Planar rough 1770': 40° Planar rough, J. From 1771' to 1772.4': Rubble		C	100	24	
1775																1772.6': J. 1773.2': 50° Planar smooth 1773.8': Planar rough 1773.9': 55° Undulating rough 1774.4': 65° Stepped rough From 1774.5' to 1775.4': Rubble From 1775.5' to 1776': Multiple breaks		C	90	22	PL(A) = 900
1784	CORE LOSS																				

BORING TYPE: HQ3
HOLE DEPTH (ft): 3014.7
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 711 ft

LOGGED BY: Chris Messenger
CASING: HW to 171 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154809.152
EASTING: 6514431.756

PROJECT No: 951-20
DATE: 8/5/2023 - 10/21/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
1785																From 1776.5' to 1777': Multiple fractures					
																1777.6': 10° Undulating smooth					
																1778': 30° Planar rough					
																1778.2': 25° Planar rough	C	100	17		
1790																1779.2': Planar rough					
																1779.4': 45° Planar smooth					
																From 1781.6' to 1784.9': Rubble					
																From 1785.9' to 1786.6': Rubble					
1795																1787': J.					
																1787.6': 25° Planar smooth					
																1787.7': 30° Planar smooth					
																From 1787.8' to 1788.2': Multiple breaks	C	100	12		
																1788.2': 35° Planar rough					
1800																From 1788.4' to 1785': Rubble					
																1789.3': 50° Planar rough					
																1789.9': 40° Planar rough					
1805																From 1791' to 1792.6': Rubble, multiple fractures					
																1792.9': 60° Planar rough					
																From 1793.7' to 1794': J.					
																1794.5': 50° Undulating rough	C	100	18		
1810																From 1795' to 1795.6': Multiple breaks					
																1795.9': 60° Planar rough					
																From 1796' to 1797': Multiple breaks, (1) at 53°					
1815																From 1797' to 1799': Rubble					
																From 1799' to 1799.7': Decomposed					
																From 1799.8' to 1802': Rubble, multiple fractures					
																1803': 60° Planar rough	C	100	33		
																1803.2': J.					

BORING TYPE: HQ3
HOLE DEPTH (ft): 3014.7
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 711 ft

LOGGED BY: Chris Messenger
CASING: HW to 171 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type ___)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154809.152
EASTING: 6514431.756

PROJECT No: 951-20
DATE: 8/5/2023 - 10/21/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
1825																From 1804.4' to 1806': Rubble, multiple fractures					
1830																From 1806' to 1810.4': Rubble					
1835																1810.6': Planar rough					
1840																1810.8': 20° Undulating smooth					
1845																1810.9': 30° Planar rough					
1850																1811': Planar rough					
1855																1811.5': 30° Undulating rough	C	100	47		
1860																1812': Planar smooth					
1865																1813': J.					
1870																From 1813.6' to 1821': Rubble, high K feldspar and chlorite					
1875																1821.5': J.					UCS = 14,797
1880																1824': Planar rough					
1885																1824.8': 75° Planar rough					
1890																1825.4': 90° S.					
1895																1827': 27° Planar smooth					
1900																1828': Planar rough	C	100	23		
1905																1829.5': 30° Planar rough					
1910																1830': J.					
1915																1831': Planar rough					
1920																1831.8': Stepped rough					
1925																1832': Planar smooth					
1930																From 1834' to 1836': 90° S.					
1935																1835': Planar rough					
1940																1836': 75° Planar rough					
1945																1837': 70° Planar rough					
1950																1837.8': Planar rough					
1955																From 1838.8' to 1839.2': J. at 60° and 45°-35°					
1960																1839.8': 60° J.					
1965																1840.5': 70° Undulating rough					PL(A) = 438
1970																1840.9': 60° Planar smooth					
1975																From 1841' to 1841.5': Multiple breaks	C	100	15		
1980																From 1842.5' to 1842.7':					

BORING TYPE: HQ3
HOLE DEPTH (ft): 3014.7
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 711 ft

LOGGED BY: Chris Messenger
CASING: HW to 171 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type ___)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions

SURFACE ELEVATION (ft): 2570

PROJECT No: 951-20

PROJECT: Hydrostor Zevsar

NORTHING: 2154809.152

DATE: 8/5/2023 - 10/21/2023

PROJECT LOCATION: Rosamod, CA

EASTING: 6514431.756

DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
1860																					
1865																					
1870																					
1873	CORE LOSS																				
1875																					
1880																					
1881	QTZ MONZONITE, light gray to white, massive, with plagioclase, K feldspar, quartz, and biotite, trace chlorite, pyrite, and muscovite																				
1885																					
1886	DIORITE																				

BORING TYPE: HQ3

DRILLER: Crux

LOGGED BY: Chris Messenger

HOLE DEPTH (ft): 3014.7

WATER OBSERVATIONS: 711 ft

CASING: HW to 171 ft

REMARKS: _____

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type _____)
W	Water seep	PL(A)	Point load axial test (50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test (50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)

CLIENT: Lane Power & Energy Solutions

SURFACE ELEVATION (ft): 2570

PROJECT No: 951-20

PROJECT: Hydrostor Zevsar

NORTHING: 2154809.152

DATE: 8/5/2023 - 10/21/2023

PROJECT LOCATION: Rosamod, CA

EASTING: 6514431.756

DIP/AZIMUTH: -90 /

EL	DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength					Water	Fracture Spacing (ft)				Discontinuities		Sampling & In Situ Testing			
			Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard		Ex Hard	0.05	0.25	0.50	2.50	5.00	B - Bedding S - Shear	J - Joint F- Fault	Type	Core Rec. %
1896.95	1896.95																							
1896.95	1896.95																			C	100	0		
1896.95	1896.95																							
1896.95	1896.95																							
1896.95	1896.95																							
1896.95	1896.95																							
1896.95	1896.95																							
1896.95	1896.95																							
1896.95	1896.95																							
1896.95	1896.95																							
1896.95	1896.95																							
1896.95	1896.95																							
1896.95	1896.95																							
1896.95	1896.95																							
1896.95	1896.95																							
1896.95	1896.95																							
1896.95	1896.95																							
1896.95	1896.95																							
1896.95	1896.95																							
1896.95	1896.95																							
1896.95	1896.95																							
1896.95	1896.95																							
1896.95	1896.95																							
1896.95	1896.95																							
1896.95	1896.95																							
1896.95	1896.95																							
1896.95	1896.95																							
1896.95	1896.95																							
1896.95	1896.95																							
1896.95	1896.95																							
1896.95	1896.95																							
1896.95	1896.95																							
1896.95	1896.95																							
1896.95	1896.95																							
1896.95	1896.95																							
1896.95	1896.95																							
1896.95	1896.95																							
1896.95	1896.95																							
1896.95	1896.95																							
1896.95	1896.95																							
1896.95	1896.95																							
1896.95	1896.95																							
1896.95	1896.95																							
1896.95	1896.95																							
1896.95	1896.95																							
1896.95	1896.95																							
1896.95	1896.95																							
1896.95	1896.95																							
1896.95	1896.95																							
1896.95	1896.95																							
1896.95	1896.95																							
1896.95	1896.95																							
1896.95	1896.95																							
1896.95	1896.95																							
1896.95	1896.95																							
1896.95	1896.95																							
1896.95	1896.95																							
1896.95	1896.95																							
1896.95	1896.95																							
1896.95	1896.95																							
1896.95	1896.95																							
1896.95	1896.95																							
1896.95	1896.95																							
1896.95	1896.95																							
1896.95	1896.95																							
1896.95	1896.95																							
1896.95	1896.95																							
1896.95	1896.95																							
1896.95	1896.95																							
1896.95	1896.95																							
1896.95	1896.95																							
1896.95	1896.95																							
1896.95	1896.95																							
1896.95	1896.95																							
1896.95	1896.95																							
1896.95	1896.95																							
1896.95	1896.95																							
1896.95	1896.95																							
1896.95	1896.95																							
1896.95	1896.95																							
1896.95	1896.95																							
1896.95	1896.95																							
1896.95	1896.95																							
1896.95	1896.95																							
1896.95	1896.95																							

BORING TYPE: HQ3

DRILLER: Crux

LOGGED BY: Chris Messenger

HOLE DEPTH (ft): 3014.7

WATER OBSERVATIONS: 711 ft

CASING: HW to 171 ft

REMARKS:

SAMPLING & IN SITU TESTING LEGEND			
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)
W	Water seep	SLK	Slake durability test (Type _____)
W	Water level	TRI	Triaxial stress test (psi)
		PLA(I)	Point load axial test (s(50) (psi)
		PL(D)	Point load diametral test (s(50) (psi)
		UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154809.152
EASTING: 6514431.756

PROJECT No: 951-20
DATE: 8/5/2023 - 10/21/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
1930																Undulating rough, rubble					
1935																1926': 79° Planar rough 1927': 82° Planar smooth From 1927.6' to 1931': (5) 70°-80° Short planar rough J.					
1940																From 1932.4' to 1933': (2) 51°-63° Planar smooth 1933.1': 17° Planar rough 1934.1': 0° Planar rough From 1935' to 1936': (2) 80°-90° Planar smooth From 1937.3' to 1938.2': 71° K infilled smooth		C	100	57	
1941	QTZ MONZONITE, light gray to white to pink, phaneritic, massive															From 1941' to 1956': Rubble		C	100	0	
1945																					
1950																					
1955																		C	100	0	
																1957.9': 45° Planar smooth From 1958' to 1963': Multidirectional					

BORING TYPE: HQ3
HOLE DEPTH (ft): 3014.7
REMARKS: _____

DRILLER: Crux
WATER OBSERVATIONS: 711 ft

LOGGED BY: Chris Messenger
CASING: HW to 171 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type ___)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)

CLIENT: Lane Power & Energy Solutions

SURFACE ELEVATION (ft): 2570

PROJECT No: 951-20

PROJECT: Hydrostor Zevsar











NORTHING: 2154809.152

DATE: 8/5/2023 - 10/21/2023

PROJECT LOCATION: Rosamod, CA

EASTING: 6514431.756

DIP/AZIMUTH: -90 /

EL	DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)			Discontinuities		Sampling & In Situ Testing																												
			Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard		0.05	0.25	0.50	2.50	5.00	B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments																							
605	1965	QTZ MONZONITE, light gray to white, phaneritic, massive, with Ca-Na-K rich feldspar, biotite, and quartz, trace pyrite, chlorite, and muscovite																																															
1971	fractures, rubble																									C	100	40	From 1964.1': 49° Ca+2 infill undulating smooth	1965.2': 40° Planar smooth	1966.5': 42° Planar rough	1969': 29° Planar smooth	From 1970' to 1970.3': (2) 38°-42° Undulating smooth	1972': 6° Planar rough	1975.8': 0° Planar smooth	1976.4': 17° Undulating rough	1978': 35° Planar smooth	1982.45': 4° Planar rough	1983.7': Undulating rough	From 1986' to 1987': Rubble	1987.4': 12° Planar smooth	1989.15': 61° Planar smooth	From 1990.5' to 1991.5': Rubble	From 1992' to 1992.7': 90° Undulating rough	1993.8': 38° Planar smooth				
600	1970																																																
595	1975																																																
590	1980																																																
585	1985																																																
580	1990																																																

BORING TYPE: HQ3

DRILLER: Crux

LOGGED BY: Chris Messenger

HOLE DEPTH (ft): 3014.7

WATER OBSERVATIONS: 711 ft

CASING: HW to 171 ft

REMARKS:

SAMPLING & IN SITU TESTING LEGEND			
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)
		SLK	Slake durability test (Type _____)
		TRI	Triaxial stress test (psi)
		UCS	Uniaxial stress test (psi)

(Continued Next Page)

CLIENT: Lane Power & Energy Solutions

SURFACE ELEVATION (ft): 2570

PROJECT No: 951-20

PROJECT: Hydrostor Zevsar

NORTHING: 2154809.152

DATE: 8/5/2023 - 10/21/2023

PROJECT LOCATION: Rosamod, CA

EASTING: 6514431.756

DIP/AZIMUTH: -90 /

EL	DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
									Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F- Fault	Type	Core Rec. %	RQD %	Test Results & Comments
			Fr	SA	MA	HA	CA															
570	2000																1994.6': 44° Planar smooth 1996.3': 45° Planar rough 1997.2': 61° Planar rough 1998.78': 52° Planar smooth From 1999.6' to 2011': Rubble				UCS = 20,362 ITS = 1,028 PL(A) = 1,034 SLK = Type I	
565	2005																					
560	2010																					
555	2015																					
550	2020																	From 2017.8' to 2018.4': (2) 61° Stepped rough				
545	2025																					

BORING TYPE: HQ3

DRILLER: Crux

LOGGED BY: Chris Messenger

HOLE DEPTH (ft): 3014.7

WATER OBSERVATIONS: 711 ft

CASING: HW to 171 ft

REMARKS:

SAMPLING & IN SITU TESTING LEGEND			
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)
W	Water seep	PL(A)	Point load axial test 1s(50) (psi)
W	Water level	PL(D)	Point load diametral test 1s(50) (psi)
		SLK	Slake durability test (Type _____)
		TRI	Triaxial stress test (psi)
		UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154809.152
EASTING: 6514431.756

PROJECT No: 951-20
DATE: 8/5/2023 - 10/21/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
535 -2035																					
530 -2040	QTZ MONZONITE, light gray to white to pink to green, phaneritic																	C	100	50	
525 -2045																		C	100	7	
520 -2050																		C	100	0	
515 -2055																					
510 -2060																		C	100	17	

-From 2040' to 2061':
Rubble

-2062': 67° Undulating
smooth

BORING TYPE: HQ3
HOLE DEPTH (ft): 3014.7
REMARKS: _____

DRILLER: Crux
WATER OBSERVATIONS: 711 ft

LOGGED BY: Chris Messenger
CASING: HW to 171 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type ___)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
WL	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154809.152
EASTING: 6514431.756

PROJECT No: 951-20
DATE: 8/5/2023 - 10/21/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
500 -2070																From 2066' to 2070': (10) Double angle 59° J.					
																From 2070' to 2072': Rubble					
																From 2072.9' to 2073.7': (3) Planar rough 59°-42°-71°		C	100	32	ITS = 1,127 SLK = Type I UCS = 6,646 PL(A) = 1,050
495 -2075																From 2074.2' to 2074.4': 38°-42° Planar smooth					
																2078': Planar irregular					
																2078.8': 73° Undulating rough					
490 -2080																From 2079' to 2080': 80°-90° S. stepped rough					
																From 2081' to 2092': Rubble		C	100	0	
485 -2085																					
480 -2090																					
475 -2095																From 2092.6' to 2092.8': 0°-4° Planar rough		C	100	11	ITS = 1,122 SLK = Type I
																2093.4': 21° Undulating rough					
																From 2094' to 2101.6': Rubble					

BORING TYPE: HQ3
HOLE DEPTH (ft): 3014.7
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 711 ft

LOGGED BY: Chris Messenger
CASING: HW to 171 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type ___)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154809.152
EASTING: 6514431.756

PROJECT No: 951-20
DATE: 8/5/2023 - 10/21/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
2105																		C	100	39	UCS = 1,475
2110																					
2115																		C	100	27	ITS = 1,258 PL(A) = 912 SLK = Type I UCS = 19,550
2120																					
2125																		C	100	0	
2130																					
2134	CORE LOSS																	C	90	30	

BORING TYPE: HQ3
HOLE DEPTH (ft): 3014.7
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 711 ft

LOGGED BY: Chris Messenger
CASING: HW to 171 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154809.152
EASTING: 6514431.756

PROJECT No: 951-20
DATE: 8/5/2023 - 10/21/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
2135.4																					
2140																					
2145																					
2150																					
2155																					
2160																					
2165																					

BORING TYPE: HQ3
HOLE DEPTH (ft): 3014.7
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 711 ft

LOGGED BY: Chris Messenger
CASING: HW to 171 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type __)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)

CLIENT: Lane Power & Energy Solutions

SURFACE ELEVATION (ft): 2570

PROJECT No: 951-20

PROJECT: Hydrostor Zevsar

NORTHING: 2154809.152

DATE: 8/5/2023 - 10/21/2023

PROJECT LOCATION: Rosamod, CA

EASTING: 6514431.756

DIP/AZIMUTH: -90 /

[illegible]

BORING TYPE: HQ3

DRILLER: Crux

LOGGED BY: Chris Messenger

HOLE DEPTH (ft): 3014.7

WATER OBSERVATIONS: 711 ft

CASING: HW to 171 ft

REMARKS:

SAMPLING & IN SITU TESTING LEGEND			
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)
		SLK	Slake durability test (Type _____)
		TRI	Triaxial stress test (psi)
		UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154809.152
EASTING: 6514431.756

PROJECT No: 951-20
DATE: 8/5/2023 - 10/21/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
2210																					
2215																					
2220																					
2223.3 2223.7	CORE LOSS																				
2225																					
2230																					
2235																					

BORING TYPE: HQ3
HOLE DEPTH (ft): 3014.7
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 711 ft

LOGGED BY: Chris Messenger
CASING: HW to 171 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154809.152
EASTING: 6514431.756

PROJECT No: 951-20
DATE: 8/5/2023 - 10/21/2023
DIP/AZIMUTH: -90 /

EL	DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
			Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
2241		QTZ MONZONITE, light gray to white, phaneritic, massive, with K-Na-Ca rich feldspar, quartz, hornblende, and biotite, trace muscovite, chlorite, and pyrite															2240.45': 78° Undulating rough					SLK = Type I TRI = 50,516 TRI = 47,212 TRI = 59,658
																	2241.5': 39° Planar smooth					
																	From 2242.1' to 2245': (10) 20°-22° Stress planar smooth	C	100	29		
2245																	From 2248' to 2251': 90° Planar rough					ITS = 1,172 PL(A) = 773 UCS = 16,103
																	2251.8': 17° Planar smooth					
																	From 2252.6' to 2253': 32°-43° Rev angle wedge planar rough	C	100	67		
2250																	From 2253.1' to 2253.4': 81° Undulating rough					PL(A) = 299
																	2255.8': 42° Planar smooth Ca+2					
																	2257': 49° Undulating smooth					
2255																	2258': 12° Planar smooth					PL(A) = 299
																	2258.9': 2° Planar smooth					
																	From 2260' to 2262': (3) 59°-71° Undulating rough					
2260																	From 2263' to 2264': 85°-71° J., stress fracture planar smooth	C	100	40		PL(A) = 299
																	2265': 42° Planar smooth					
																	From 2267' to 2268': 69° Undulating rough					
2265																	From 2269' to 2270': 90° S. planar smooth					PL(A) = 299
																	From 2271' to 2272': Rubble					
																	From 2273' to 2274': (6) 49°-61° Stress planar rough, (1) 80° stepped and smooth	C	100	37		
2270																						

BORING TYPE: HQ3
HOLE DEPTH (ft): 3014.7
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 711 ft

LOGGED BY: Chris Messenger
CASING: HW to 171 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154809.152
EASTING: 6514431.756

PROJECT No: 951-20
DATE: 8/5/2023 - 10/21/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)		Discontinuities		Sampling & In Situ Testing					
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard		0.05	0.25	0.50	2.50	5.00	B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %
2280																		From 2276.2' to 2277': 17°-21° Planar smooth 2279': 41° Planar smooth From 2280' to 2281': (4) 38° Planar smooth From 2281.1' to 2283': (2) 17°-32° Planar smooth 2283.1': 42° and 90° undulating smooth From 2284.4' to 2285': (2) 27° Planar smooth				ITS = 816 SLK = Type I UCS = 19,470		
2285																				C	100		32	
2290																					C		100	14
2295																								
2300	CORE LOSS																							
2305																				C	44	30		
2306.0																		From 2309.4' to 2310': 81° Planar smooth					ITS = 1,393 PL(A) = 695 SLK = Type I UCS = 15,069	

BORING TYPE: HQ3
HOLE DEPTH (ft): 3014.7
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 711 ft

LOGGED BY: Chris Messenger
CASING: HW to 171 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type I)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154809.152
EASTING: 6514431.756

PROJECT No: 951-20
DATE: 8/5/2023 - 10/21/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
2315																					
2320																					
2325																					
2330																					
2335																					
2340																					

BORING TYPE: HQ3
HOLE DEPTH (ft): 3014.7
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 711 ft

LOGGED BY: Chris Messenger
CASING: HW to 171 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type ___)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154809.152
EASTING: 6514431.756

PROJECT No: 951-20
DATE: 8/5/2023 - 10/21/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
2350	From 2369' to 2370': Qtz feldspar pegmatite															(7) Undulating rough				ITS = 1,265 PL(A) = 1,014 UCS = 18,181 SLK = Type I	
2355																	2347': 42°				
2360																	From 2349' to 2350': (3) 20°-24° Planar smooth				
2365																	From 2350' to 2359': 61°-74° Planar smooth Ca+2				
2370																	2354.3': 7° Undulating rough, K feldspar	C	100		71
																	2357': 79° S. undulating rough				
																	2361.9': 45° Planar smooth				
																	From 2362.2' to 2367.6': Stepped 38°-42° wedge	C	100		45
																	From 2363.3' to 2366': 90° Planar smooth S.				
																	2369.2': Planar smooth				
2375															2372.1': 2° Planar smooth						
															2372.9': 3° Planar smooth	C	100	62			
															From 2375' to 2375.45': 84° Undulating rough						
															2375.9': 80° Undulating rough						
															2378': 49° Undulating smooth						
															2379': 38° Planar smooth						

BORING TYPE: HQ3
HOLE DEPTH (ft): 3014.7
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 711 ft

LOGGED BY: Chris Messenger
CASING: HW to 171 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type ___)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
L	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154809.152
EASTING: 6514431.756

PROJECT No: 951-20
DATE: 8/5/2023 - 10/21/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
185 -2385																-2382': 11° Undulating rough From 2383' to 2383.7': 31° Planar smooth		C	100	77	ITS = 1,521 UCS = 17,945 PL(A) = 1,180 SLK = Type I
180 -2390																-2385.75': 49° Stepped rough From 2386' to 2387': 90° Stepped rough, Ca+2 and K From 2387.1' to 2388': (4) 67°-79° Planar rough 2390': 2° Planar rough					
175 -2395																-2392': 59° Planar smooth Ca+2 -2394.6': 7° Planar smooth From 2395' to 2396': (2) 61° Planar smooth		C	100	84	ITS = 491 UCS = 15,661
170 -2400																2400': 67° Planar rough From 2400.1' to 2407': 71° Undulating rough		C	100	67	
165 -2405																From 2408.2' to 2408.78': 82° Planar smooth From 2409' to 2411': 90° S. undulating smooth					ITS = 491 UCS = 15,661
160 -2410																		C	100	63	

BORING TYPE: HQ3
HOLE DEPTH (ft): 3014.7
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 711 ft

LOGGED BY: Chris Messenger
CASING: HW to 171 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type ___)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
WL	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



PAGE 70 OF 87

DIP/AZIMUTH: -90 /

BORING TYPE: <u>HQ3</u>	DRILLER: <u>Crux</u>	LOGGED BY: <u>Chris Messenger</u>
HOLE DEPTH (ft): <u>3014.7</u>	WATER OBSERVATIONS: <u>711 ft</u>	CASING: <u>HW to 171 ft</u>
REMARKS:		

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions

SURFACE ELEVATION (ft): 2570

PROJECT No: 951-20

PROJECT: Hydrostor Zevsar


NORTHING: 2154809.152

DATE: 8/5/2023 - 10/21/2023

PROJECT LOCATION: Rosamod, CA

EASTING: 6514431.756

DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)		Discontinuities		Sampling & In Situ Testing					
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard		0.05	0.25	0.50	2.50	5.00	B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %
115 -2455	QTZ MONZONITE, light gray to white, phaneritic, massive																			C	100	62	PL(A) = 161 SLK = Type I	
110 -2460																								-2454.9': 49° Planar smooth From 2456' to 2458': 90°-45° S. planar smooth -2458.3': 47° Undulating smooth From 2460' to 2461': Rubble, 90° stepped rough -2462.1': 71° Undulating rough From 2463' to 2463.1': 27°-49° Undulating rough From 2464' to 2466': Stepped 90° S. rough
105 -2465																								
100 -2470																								
95 -2475																								
90 -2480																						UCS = 7,179		
2473 -2475																							TRI = 30,236 TRI = 37,313 TRI = 32,387	
2473 -2475																								
2473 -2475																								
2473 -2475																								
2473 -2475																								
2473 -2475																								
2473 -2475																								
2473 -2475																								
2473 -2475																								
2473 -2475																								
2473 -2475																								
2473 -2475																								
2473 -2475																								
2473 -2475																								
2473 -2475																								
2473 -2475																								
2473 -2475																								
2473 -2475																								
2473 -2475																								
2473 -2475																								
2473 -2475																								
2473 -2475																								
2473 -2475																								
2473 -2475																								
2473 -2475																								
2473 -2475																								
2473 -2475																								
2473 -2475																								
2473 -2475																								
2473 -2475																								
2473 -2475																								
2473 -2475																								
2473 -2475																								
2473 -2475																								
2473 -2475																								
2473 -2475																								
2473 -2475																								
2473 -2475																								
2473 -2475																								
2473 -2475																								
2473 -2475																								
2473 -2475																								
2473 -2475																								

BORING TYPE: HQ3

DRILLER: Crux

LOGGED BY: Chris Messenger

HOLE DEPTH (ft): 3014.7

WATER OBSERVATIONS: 711 ft

CASING: HW to 171 ft

REMARKS: _____

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type ____)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154809.152
EASTING: 6514431.756

PROJECT No: 951-20
DATE: 8/5/2023 - 10/21/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
80 2490	DIORITE															From 2486' to 2488': (3) 39° Planar smooth					SLK = Type I
																From 2488.1' to 2489': 90° Undulating rough					
																From 2489.1' to 2491': (6) 30°-34° Planar smooth					
75 2495																From 2491.1' to 2506': Rubble		C	100	0	
2496																					
70 2500	DIORITE																				SLK = Type I
65 2505																2506.3': 42° Planar rough					
																2507': 22° Planar smooth Ca+2					
60 2510	DIORITE															From 2508' to 2511': Multiple 90°-60° vertical level fractures					SLK = Type I
55 2515																From 2511.1' to 2526': Rubble		C	100	0	

BORING TYPE: HQ3
HOLE DEPTH (ft): 3014.7
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 711 ft

LOGGED BY: Chris Messenger
CASING: HW to 171 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type ___)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
WL	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions

SURFACE ELEVATION (ft): 2570

PROJECT No: 951-20

PROJECT: Hydrostor Zevsar

NORTHING: 2154809.152

DATE: 8/5/2023 - 10/21/2023

PROJECT LOCATION: Rosamod, CA

EASTING: 6514431.756

DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
2523	CORE LOSS																	C	82	21	ITS = 1,047 UCS = 9,224
2524.8																					
2526																					SLK = Type II PL(A) = 301
2530																					
2535																					C
2540																					
2545																					C
2550																					
																					C
																					100
																					14

BORING TYPE: HQ3

DRILLER: Crux

LOGGED BY: Chris Messenger

HOLE DEPTH (ft): 3014.7

WATER OBSERVATIONS: 711 ft

CASING: HW to 171 ft

REMARKS: _____

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type <u> </u>)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154809.152
EASTING: 6514431.756

PROJECT No: 951-20
DATE: 8/5/2023 - 10/21/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
								Rock Strength										Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
-2560															From 2556.4' to 2559.4': (7) 40°-60° Stress fracture undulating rough				ITS = 1,640		
-2565															From 2561' to 2565': 90° Undulating rough	C	100	13	SLK = Type I		
-2570															From 2567' to 2570': (8) 32°-49° Undulating rough						
-2575															From 2571' to 2572': 90° Planar smooth	C	100	39	UCS = 19,333		
-2580															From 2572.6' to 2574': 90° Stepped smooth				PL(A) = 1,342		
-2585															From 2575.3' to 2577.8': 46° Planar smooth				ITS = 1,232		
															From 2577.8' to 2578.7': 32° Planar rough						
															From 2578.7' to 2579.9': 45° Stepped smooth						
															From 2579.9' to 2580.5': (2) 47° Planar smooth						
															From 2580.5' to 2581': Rubble	C	100	16			
															From 2581' to 2586': Rubble						
															From 2586' to 2587.2': 32° Planar smooth						
															From 2587.2' to 2587.5': 32° Planar smooth						
															From 2587.5' to 2587.8': 41° Planar smooth						
															From 2587.8' to 2588.1': 67° Planar smooth						

BORING TYPE: HQ3
HOLE DEPTH (ft): 3014.7
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 711 ft

LOGGED BY: Chris Messenger
CASING: HW to 171 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154809.152
EASTING: 6514431.756

PROJECT No: 951-20
DATE: 8/5/2023 - 10/21/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
-2595																smooth					
																From 2588.6' to 2592': 80°-90° Vertical S. undulating rough					
																From 2592.9' to 2593.5': 90° S. undulating planar smooth		C	100	27	
																From 2594' to 2596': 90°-78° S. undulating rough					
																From 2596' to 2597': Rubble					
-2600																2599.4': Planar irregular smooth					
																From 2600' to 2600.7': 0° Planar smooth					
																2601.5': 74° Planar smooth					
-2605																2603.6': 8° Undulating smooth		C	100	41	
																From 2606' to 2607': Rubble					
																From 2609' to 2610.8': Rubble					
-2610																2613.4': 7° Planar smooth					
																2613.7': 89° Planar smooth		C	100	52	
-2615																2617.9': Planar irregular					
																From 2618.7' to 2620': Rubble					
-2620																From 2621' to 2623': Rubble					
																From 2623.1' to 2625.6': Multiple 90° S. 42° (2) 20° smooth		C	100	8	

PL(A) = 214
UCS = 3,493
SLK = Type II

BORING TYPE: HQ3
HOLE DEPTH (ft): 3014.7
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 711 ft

LOGGED BY: Chris Messenger
CASING: HW to 171 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type ___)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154809.152
EASTING: 6514431.756

PROJECT No: 951-20
DATE: 8/5/2023 - 10/21/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
-60																From 2626.4' to 2629': Rubble					
-630																2629.35': 7° Planar smooth					
																2629.65': 13° Planar smooth					
-65																2629.85': 32° Planar smooth					
-635																2630': 22° Planar rough					
																From 2630.25' to 2631': 79° Planar smooth					
-65																2631.45': 22° Planar smooth					
-640																From 2632.9' to 2633.7': 90° Undulating rough					
																2634.1': 22° Planar smooth					
-65																From 2635' to 2636': (2) 38° Planar smooth					
																From 2636.5' to 2639': 90° Undulating rough, healed and open K					
-65																2640': 42° Planar smooth					
-645																From 2641' to 2642.2': (3) 0° Planar smooth					
																From 2644.72' to 2646': Rubble					
-65																From 2646.1' to 2648': (4) 0° Planar smooth/ rubble					
-650																From 2646.9' to 2652.2': (6) 50°-67° Planar smooth					
																From 2652.5' to 2653.7': 90° S. planar smooth, mineralized					
-655																2654': 3° Planar smooth					
																2654.9': 3° Planar smooth					
-655																From 2655' to 2656.4': Rubble					
																2657': 71° Undulating smooth					
-655																From 2658' to 2659.6': Multiple 90° undulating					

BORING TYPE: HQ3
HOLE DEPTH (ft): 3014.7
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 711 ft

LOGGED BY: Chris Messenger
CASING: HW to 171 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type ___)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154809.152
EASTING: 6514431.756

PROJECT No: 951-20
DATE: 8/5/2023 - 10/21/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
																Fractures					
																From 2660' to 2661': Rubble					
																2661.5': 67° Planar smooth					
-2665																From 2664' to 2666': (3) 50°-60° Planar smooth		C	100	55	
																2667': 57° Planar smooth					
																2668.5': 66° Undulating smooth					
-2670																2670': 69° Planar smooth/ undulating					
																From 2671' to 2690': (4) 60°-70° Planar smooth					
																From 2671.1' to 2672': (3) 38° Planar smooth		C	100	45	
-2675																From 2672.6' to 2673.8': Rubble					SLK = Type I
																2674.45': 26° Planar smooth					
																2675.9': Planar smooth					
																2677': 22° Planar smooth					ITS = 1,405
																From 2678.7' to 2679': (3) 20°-26° Planar smooth					UCS = 22,096
-2680																From 2680' to 2681': Rubble					
																From 2681.1' to 2682': 90° S. undulating smooth					
																2683': 81° Undulating smooth		C	100	60	PL(A) = 655
-2685																2684': 31° Planar smooth					TRI = 29,762
																2685.3': 38° Planar smooth					
																2686.5': 13° Planar smooth					
																2687.7': 45° Planar smooth					TRI = 38,095
-2690																2689': 31° Undulating smooth					
																From 2691' to 2696': (8) 45° Undulating, (7) 0°-10° Planar rough		C	100	20	

BORING TYPE: HQ3
HOLE DEPTH (ft): 3014.7
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 711 ft

LOGGED BY: Chris Messenger
CASING: HW to 171 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions

SURFACE ELEVATION (ft): 2570

PROJECT No: 951-20

PROJECT: Hydrostor Zevsar

NORTHING: 2154809.152

DATE: 8/5/2023 - 10/21/2023

PROJECT LOCATION: Rosamod, CA

EASTING: 6514431.756

DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
-130 -2700																From 2696.1' to 2706': Rubble					IRI = 29,827
-135 -2705																					UCS = 1,014
2707 -140 -2710	DIORITE																	C	100	23	ITS = 1,481
-145 -2715																					
2718 -150 -2720																		C	100	30	SLK = Type I
-155 -2725																		C	100	45	PL(A) = 1,170 TRI = 17,136 TRI = 24,185 UCS = 6,744

BORING TYPE: HQ3

DRILLER: Crux

LOGGED BY: Chris Messenger

HOLE DEPTH (ft): 3014.7

WATER OBSERVATIONS: 711 ft

CASING: HW to 171 ft

REMARKS: _____

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type ___)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
WL	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154809.152
EASTING: 6514431.756

PROJECT No: 951-20
DATE: 8/5/2023 - 10/21/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
-165 -2735																Rubble					
																From 2729.4' to 2736': (13) 60°-90° Undulating planar smooth J.					
																		C	100	14	
-170 -2740																From 2736.1' to 2740': 90° Vertical and 79° stepped undulating rough					
																From 2741' to 2742.7': Rubble					
																		C	100	18	ITS = 1,053 UCS = 8,318
-175 -2745	DIABASE															From 2746' to 2752': 20°-45° and 90° Undulating					
-180 -2750																2751': 69°-74° Undulating smooth					
																2753': 90° Stepped smooth					
																From 2754' to 2755': 90° Healed					
																From 2756' to 2757': Rubble					
-185 -2755																2758': 47° Undulating smooth					
																From 2759' to 2760': 90° S. planar rough					
																2760': 42° Planar smooth					
-190 -2760																From 2761' to 2763': Rubble					
																From 2763.1' to 2765': 90°-0° Stepped rough					
																		C	100	27	SLK = Type I ITS = 542

BORING TYPE: HQ3
HOLE DEPTH (ft): 3014.7
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 711 ft

LOGGED BY: Chris Messenger
CASING: HW to 171 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type ___)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
L	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



PAGE 80 OF 87

DIP/AZIMUTH: -90 /

REMARKS:

SAMPLING & IN SITU TESTING LEGEND			
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)
	Water seep	SLK	Slake durability test (Type _____)
	Water level	PL(A)	Point load axial test (s/50) (psi)
		PL(D)	Point load diametral test (s/50) (psi)
		TRI	Triaxial stress test (psi)
		UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154809.152
EASTING: 6514431.756

PROJECT No: 951-20
DATE: 8/5/2023 - 10/21/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
-235 -2805	From 2811' to 2826': Chlorite and epidote															From 2800' to 2810': Multiple fractures, veins					
-240 -2810																From 2810' to 2820': Multiple fractures, veins		C	100	71	
-245 -2815																From 2820' to 2830': Multiple fractures, veins		C	100	43	
-250 -2820																From 2830' to 2840': Multiple fractures, veins		C	100	56	
-255 -2825																					
-260 -2830																					

BORING TYPE: HQ3
HOLE DEPTH (ft): 3014.7
REMARKS: _____

DRILLER: Crux
WATER OBSERVATIONS: 711 ft

LOGGED BY: Chris Messenger
CASING: HW to 171 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type ___)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154809.152
EASTING: 6514431.756

PROJECT No: 951-20
DATE: 8/5/2023 - 10/21/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
2841	From 2841' to 2861': Calcite, chlorite, and epidote present QTZ MONZONITE, light gray to white, phaneritic, with biotite, K-Na-Ca feldspar, and quartz, trace epidote, chlorite, pyrite, and calcite																				PL(A) = 1,033
2840																		C	100	50	
2845																		C	100	15	PL(A) = 828
2850																					
2855																					
2860																		C	100	38	
2865																					SLK = Type II

BORING TYPE: HQ3
HOLE DEPTH (ft): 3014.7
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 711 ft

LOGGED BY: Chris Messenger
CASING: HW to 171 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type ___)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154809.152
EASTING: 6514431.756

PROJECT No: 951-20
DATE: 8/5/2023 - 10/21/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
2875	QTZ MONZONITE, light gray to white, porphyritic, phaneritic, massive, with biotite, rich Na-Ca K feldspar, chlorite, epidote, calcite, and quartz															rough					UCS = 1,345 PL(A) = 35 UCS = 1,426
																2868.5': J.					
																2869.9': 20° Planar smooth					
																From 2870' to 2870.5': Multiple J.		C	100	40	
																2870.8': 7° Planar smooth					
																2870.9': 10° Undulating smooth					
																From 2871' to 2871.5': J.					
																From 2872' to 2874': Multiple fractures					
																From 2874.1' to 2874.8': High K feldspar veining, healed fractures					
																2874.8': 75° Stepped rough					
																2877.8': Planar rough					
																2878.6': 35° Stepped slickenside					
																From 2880' to 2881': Multiple J.					
																2881.1': Planar smooth					
																From 2882' to 2883.6': Rubble					C 100 6
																2884': Planar rough					
																2884.6': 50° Undulating rough					
																From 2884.7' to 2884.9': Rubble					
																2885': 90° S. fracture					
																2886.6': Planar rough					
																2886.9': 70° Planar rough					
																From 2887' to 2888': Multiple fractures					
																2888.5': Planar rough					
																From 2889.4' to 2891': Multiple fractures					
																From 2891.5' to 2891.9': Rubble					
																2892.6': J.					C 100 3
																2893.4': 45° Undulating rough					
																From 2893.7' to 2901': Multiple fractures planar, S., J., rubble					
																2901.7': Planar smooth					
2901																2901.9': 90° S.					

BORING TYPE: HQ3
HOLE DEPTH (ft): 3014.7
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 711 ft

LOGGED BY: Chris Messenger
CASING: HW to 171 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154809.152
EASTING: 6514431.756

PROJECT No: 951-20
DATE: 8/5/2023 - 10/21/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
2910 -340	QTZ MONZONITE, light gray to white, porphyritic, phaneritic, massive, with biotite, rich Na-Ca K feldspar, trace chlorite, epidote, calcite, and quartz															2902.25' Planar smooth					
2915 -345																2902.4' 75° Planar rough					
2920 -350																From 2902.5' to 2906': 55°-75° Planar rough, rubble					
2925 -355																From 2906.1' to 2911': Rubble					
2930 -360																From 2911.1' to 2916.5': Rubble					
2931																2917.4': Planar rough					
2935 -365																2917.7': J.	C	100	13	SLK = Type III	
																2919.6': Planar rough					
																From 2920.8' to 2926': Rubble, high K feldspar and chlorite					
																2926.5': 70° Stepped rough					
																2927.3': Planar smooth					
																2928': J.					
																2929.3': Planar rough					
																2930': Undulating rough					
																2930.3': Planar rough					
																2930.8': 30° Undulating rough					
																2931.4': J.	C	100	15		
																2932.4': Planar rough					
																2932.7': 40° Stepped rough					
																2933': Undulating rough					
																2933.4': 50° Stepped rough					
																2933.6': 25° Undulating rough					

ITS = 822

BORING TYPE: HQ3
HOLE DEPTH (ft): 3014.7
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 711 ft

LOGGED BY: Chris Messenger
CASING: HW to 171 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type ___)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
WL	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions

SURFACE ELEVATION (ft): 2570

PROJECT No: 951-20

PROJECT: Hydrostor Zevsar

NORTHING: 2154809.152

DATE: 8/5/2023 - 10/21/2023

PROJECT LOCATION: Rosamod, CA

EASTING: 6514431.756

DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																									
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																						
-375 2945	QTZ MONZONITE, light gray to white, porphyritic, phaneritic, massive, with biotite, plagioclase feldspar, and quartz, trace chlorite, epidote, and calcite																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																										</

BORING TYPE: HQ3

DRILLER: Crux

LOGGED BY: Chris Messenger

HOLE DEPTH (ft): 3014.7

WATER OBSERVATIONS: 711 ft

CASING: HW to 171 ft

REMARKS: _____

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type _____)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
L	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)

(Continued Next Page)



CLIENT: Lane Power & Energy Solutions
PROJECT: Hydrostor Zevsar
PROJECT LOCATION: Rosamod, CA

SURFACE ELEVATION (ft): 2570
NORTHING: 2154809.152
EASTING: 6514431.756

PROJECT No: 951-20
DATE: 8/5/2023 - 10/21/2023
DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	SA	MA	HA	CA		Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
-410 -2980																2956.5': Planar rough					SLK = Type I UCS = 15,773
																2956.8': J.					
																2957.8': 60° Undulating rough					
																From 2958' to 2961': Multiple 60° fractures, 20°-30° planar smooth		C	100	8	
																From 2968.8' to 2969.1': Multiple J.					
																2969.6': 30° Undulating rough					
																2969.7': 30° Undulating rough					
																From 2970' to 2972.4': Rubble					
																2972.7': 79° S.					
																2973': Multiple fractures					
																From 2973.1' to 2974': Multiple J., 55° planar rough					SLK = Type I UCS = 15,773
																From 2974.5' to 2976': Rubble					
																From 2976.1' to 2976.8': Rubble					
																2977': 20° Planar smooth					
																From 2977.1' to 2977.5': Rubble		C	100	5	
																2977.8': 50° Undulating rough					
																2978.3': 25° Planar smooth					
																2978.7': 40° Planar smooth					
																From 2979' to 2981': Rubble					
																2981.9': 60° Planar rough					
																2982.2': Planar rough					SLK = Type I UCS = 15,773
																From 2982.5' to 2983': Rubble					
																From 2983' to 2991': Rubble					
																2983.5': 30° Planar rough					
																From 2991.1' to 2993': Rubble					
																2993.1': 40° Undulating slickenside					
																2994': J.					
																From 2994.1' to 2995': Rubble		C	100	4	

BORING TYPE: HQ3
HOLE DEPTH (ft): 3014.7
REMARKS:

DRILLER: Crux
WATER OBSERVATIONS: 711 ft

LOGGED BY: Chris Messenger
CASING: HW to 171 ft

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type ___)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)



CLIENT: Lane Power & Energy Solutions

SURFACE ELEVATION (ft): 2570

PROJECT No: 951-20

PROJECT: Hydrostor Zevsar

NORTHING: 2154809.152

DATE: 8/5/2023 - 10/21/2023

PROJECT LOCATION: Rosamod, CA

EASTING: 6514431.756

DIP/AZIMUTH: -90 /

EL DEPTH (ft)	Description of Strata	Degree of Alteration					Graphic Log	Rock Strength						Water	Fracture Spacing (ft)	Discontinuities		Sampling & In Situ Testing			
		Fr	Degree of Alteration					Very Soft	Soft	Med-Hard	Hard	Very Hard	Ex Hard			B - Bedding S - Shear	J - Joint F- Fault	Type	Core Rec. %	RQD %	Test Results & Comments
			SA	MA	HA	CA															
																2995.1': 45° Planar rough 2995.5': J. 2996.3': 55° Planar rough 2996.9': 65° S./J. 2997.1': 55° Planar rough					
-445'	Bottom of borehole at 3014.7 feet.															From 2997.6' to 2998.4': Rubble 2998.4': 45° Planar rough 2999.5': 63° Planar smooth From 3000' to 3004.7': Multiple fractures, J., planar, and S. 3006.6': 60° Undulating rough From 3006.7' to 3007.6': Rubble 3008.2': Planar rough 3008.4': 50° J. 3008.8': J. From 3009' to 3014.7': Multiple fractures, J., 50°-70°, rubble					
-450'																					
-455'																					
-460'																					
-465'																					
-470'																					

BORING TYPE: HQ3

DRILLER: Crux

LOGGED BY: Chris Messenger

HOLE DEPTH (ft): 3014.7

WATER OBSERVATIONS: 711 ft

CASING: HW to 171 ft

REMARKS: _____

SAMPLING & IN SITU TESTING LEGEND					
C	Core drilling	ITS	Indirect tensile strength (Brazilian) test (psi)	SLK	Slake durability test (Type ____)
W	Water seep	PL(A)	Point load axial test Is(50) (psi)	TRI	Triaxial stress test (psi)
W	Water level	PL(D)	Point load diametral test Is(50) (psi)	UCS	Uniaxial stress test (psi)