

DOCKETED	
Docket Number:	25-OPT-01
Project Title:	Viracocha Hill Battery Energy Storage System Project
TN #:	261774
Document Title:	Volume 2 Virococha Hill BESS Appendix 5 4A Part B Geotechnical Investigation Report
Description:	Volume 2 Virococha Hill BESS Appendix 5 4A Part B Geotechnical Investigation Report
Filer:	Sarah Madams
Organization:	Jacobs
Submitter Role:	Applicant Consultant
Submission Date:	2/14/2025 1:56:56 PM
Docketed Date:	2/14/2025

APPENDIX A

Diamond Coring Logs

PROJECT NO.: 4245-200A BORING NO.: 1 / Turbine 22
DATE INITIATED: 1-3-23
DATE COMPLETED: 1-4-23
TOTAL DEPTH OF HOLE: 90'
BOREHOLE ELEVATION: _____
GROUNDWATER ELEVATION: _____
CASING ELEVATION: _____

RUN NO.	DRILLING PRESSURE (psi)	DRILL RATE (MIN/FT)	CUT	RECOVERED	% RECOVERY	% DRILLING FLUID LOSS	RQD (%)	DEPTH	LOG	DESCRIPTION
		Rotary Wash to 15'								SPT Sample - blow count 5/11/16
								2		Silty Sandy Clay, brown-moist, medium stiff
								4		Sandstone, yellow-brown, highly weathered, medium to fine, weak
								6		SPT Sample - blow count 6/50
								8		
								10		
								12		SPT Sample - 50 Blows for 6"
								14		

Berlogar Stevens & Associates

FIELD CORE LOG

PROJECT: Rooney/ Sand Hill

PROJECT NO.: 4245.200A BORING NO.: 1/ Turbine 22

	RUN NO.	DRILLING PRESSURE (psi)	DRILL RATE (MIN/FT)	CUT	RECOVERED	% RECOVERY	% DRILLING FLUID LOSS	RQD (%)	DEPTH	LOG	DESCRIPTION
1:52pm 2:00pm	⑨		6	5'	4.3'	86%		44" 72%	59		Sandstone, olive-brown, highly weathered, medium to fine grain, moderately strong
2:18pm 2:25pm	⑩		7	5'	3'	60%		22" 36%	60		
									62		
									64		
8:08am 8:15am	⑪		7	5'	4.7'	94%		53" 93%	66		
									68		
									70		
									72		
8:36am 8:42am	⑫		6	5'	5'	100%		60" 100%	74		

Berlogar Stevens & Associates

FIELD CORE LOG

PROJECT: Rooney/ Sand Hill

PROJECT NO.: 4245.200A BORING NO.: 1/ Turbine 22

	RUN NO.	DRILLING PRESSURE (psi)	DRILL RATE (MIN/FT)	CUT	RECOVERED	% RECOVERY	% DRILLING FLUID LOSS	RQD (%)	DEPTH	LOG	DESCRIPTION
8:49am 8:55am	(13)		6	5'	4.6'	92%		55" 100%	75		Sandstone, olive-brown, highly weathered, medium to fine grain, moderately strong
									76		
									78		
											Sandstone, gray, highly weathered, medium to fine grain, very strong
									80		Sandstone, yellow-brown, highly weathered, medium to fine grain, strong
9:10am 9:17am	(14)		7	5'	4.7'	94%		56" 100%			Claystone, olive-gray, highly weathered, strong
									82		
											Sandstone, yellow-brown, highly weathered, medium to fine grain, strong
									84		
											Claystone, olive-gray, highly weathered, strong
10:32am 10:40am	(15)		8	5'	4.5'	90%		49" 91%	86		Sandstone, olive-brown, highly weathered, medium to fine grain, strong
									88		
											Claystone, olive-gray, highly weathered, strong
									90		Sandstone, olive-brown, highly weathered, medium to fine grain, strong

Sand Hill
Turbine 22

17'

18.5

20'

20.3

22.2

24.2

24.2

26.1

Sand Hill
Turbine 22

26.1

33.7

36.4

27.8

29.8

36.4

38.2

40

Sand Hill
Turbine 22

40

47

49

50.9

52.9

55

Sand Hill
Turbine 22

54.6

56.4

65.5'

58.2

63.2

65

67.2

Sand Hill
Turbine 22

67.2'

68.8'

70'

72'

73.8'

70'

68.8'

71.7'

75'

Sand Hill
Turbine 22

75.6

77'

78.8

82.5'

80'

83.2

76.8

78.8

85'

Sand Hill
Turbine 22

85.6

87.3

88.9

90'

88.9

87.3

PROJECT NO.: 4245.200A BORING NO.: 2 / Turbine 28
 DATE INITIATED: 1-6-23
 DATE COMPLETED: 1-6-23
 TOTAL DEPTH OF HOLE: 90'
 BOREHOLE ELEVATION: _____
 GROUNDWATER ELEVATION: _____
 CASING ELEVATION: _____

RUN NO.	DRILLING PRESSURE (psi)	DRILL RATE (MIN/FT)	CUT	RECOVERED	% RECOVERY	% DRILLING FLUID LOSS	RQD (%)	DEPTH	LOG	DESCRIPTION
		Hollow Stem to 10'							CL	Silty sandy clay, dark brown, moist-wet, medium-stiff
								2	Sandstone, yellow-brown, highly weathered, medium to fine grain, weak	
								4		
①		9	5'	2.6'	52%		27" 84%	6		
								8		
								10		
								12		Sandstone, olive-brown, highly weathered, medium to fine grain, friable
②		8	5'	5'	100%		60" 100%	14		
								16		

PROJECT: Rooney/San Hill
 DRILLING COMPANY: Gregg Drilling
 DRILLING METHOD: Diamond Core
 DRILL RIG: CME 850
 NUMBER OF CORE BOXES: 7
 LOGGED BY: Andres Garibay
 CASING TYPE: HQ3

PROJECT NO.: 4245.200A BORING NO.: 2 / Turbine 28
 DATE INITIATED: 1-6-23
 DATE COMPLETED: 1-6-23
 TOTAL DEPTH OF HOLE: 90'
 BOREHOLE ELEVATION: _____
 GROUNDWATER ELEVATION: _____
 CASING ELEVATION: _____

	RUN NO.	DRILLING PRESSURE (psi)	DRILL RATE (MIN/FT)	CUT	RECOVERED	% RECOVERY	% DRILLING FLUID LOSS	RQD (%)	DEPTH	LOG	DESCRIPTION
9:09am 9:17am	(2)		8	5'	5'	100%		60" 100%	16		Sandstone, olive-brown, highly weathered, medium to fine grain, friable
									18		
									20		
9:23am 9:30am	(3)		7	5'	2.6'	52%		25" 81%	20		
									22		
									24		
									26		
9:36am 9:43am	(4)		7	5'	5'	100%		60" 100%	26		
									28		
									30		
9:46am 9:52am	(5)		6	5'	5'	100%		60" 100%	30		
									32		

PROJECT: Rooney/San Hill
 DRILLING COMPANY: Gregg Drilling
 DRILLING METHOD: Diamond Core
 DRILL RIG: CME 850
 NUMBER OF CORE BOXES: 7
 LOGGED BY: Andres Garibay
 CASING TYPE: HQ3

PROJECT NO.: 4245.200A BORING NO.: 2 / Turbine 28
 DATE INITIATED: 1-6-23
 DATE COMPLETED: 1-6-23
 TOTAL DEPTH OF HOLE: 90'
 BOREHOLE ELEVATION: _____
 GROUNDWATER ELEVATION: _____
 CASING ELEVATION: _____

	RUN NO.	DRILLING PRESSURE (psi)	DRILL RATE (MIN/FT)	CUT	RECOVERED	% RECOVERY	% DRILLING FLUID LOSS	RQD (%)	DEPTH	LOG	DESCRIPTION
9:46am 9:52am	⑤		6	5'	5'	100%		60" 100%	32		Sandstone, olive-brown, highly weathered, medium to fine grain, weak
									34		
10:15am 10:21am	⑥		6	1'	.2'	20%			36		note: Core barrel plugged, resulted in 1' cut
									38		
10:37am 10:45am	⑦		8	5'	5'	100%		60" 100%	40		Sandstone, olive-brown, highly weathered, medium to fine grain, strong
									42		
									44		Sandstone, olive-gray, highly weathered, medium to fine grain, strong
									46		Sandstone, olive-brown, highly weathered, medium to fine grain, strong
10:48am 10:55am	⑧		7	5'	4.6'	92%		54" 100%	48		

PROJECT: Rooney/San Hill
 DRILLING COMPANY: Gregg Drilling
 DRILLING METHOD: Diamond Core
 DRILL RIG: CME 850
 NUMBER OF CORE BOXES: 7
 LOGGED BY: Andres Garibay
 CASING TYPE: HQ3

PROJECT NO.: 4245.200A BORING NO.: 2 / Turbine 28
 DATE INITIATED: 1-6-23
 DATE COMPLETED: 1-6-23
 TOTAL DEPTH OF HOLE: 90'
 BOREHOLE ELEVATION: _____
 GROUNDWATER ELEVATION: _____
 CASING ELEVATION: _____

	RUN NO.	DRILLING PRESSURE (psi)	DRILL RATE (MIN/FT)	CUT	RECOVERED	% RECOVERY	% DRILLING FLUID LOSS	RQD (%)	DEPTH	LOG	DESCRIPTION
10:48am 10:55am	8		7	5'	4.6'	92%		54" 100%	48		Sandstone, olive-brown, highly weathered, medium to fine grain, strong
									50		
12:40pm 12:47pm	9		7	5'	4.6'	92%		54" 100%	52		
									54		
									56		Sandstone, olive-gray, highly weathered, medium to fine grain, strong
									58		
12:49pm 12:57pm	10		8	5'	5'	100%		60" 100%	60		
									62		
1:07pm 1:13pm	11		6	5'	5'	100%		60" 100%	64		

PROJECT: Rooney/San Hill
 DRILLING COMPANY: Gregg Drilling
 DRILLING METHOD: Diamond Core
 DRILL RIG: CME 850
 NUMBER OF CORE BOXES: 7
 LOGGED BY: Andres Garibay
 CASING TYPE: HQ3

PROJECT NO.: 4245.200A BORING NO.: 2 / Turbine 28
 DATE INITIATED: 1-6-23
 DATE COMPLETED: 1-6-23
 TOTAL DEPTH OF HOLE: 90'
 BOREHOLE ELEVATION: _____
 GROUNDWATER ELEVATION: _____
 CASING ELEVATION: _____

	RUN NO.	DRILLING PRESSURE (psi)	DRILL RATE (MIN/FT)	CUT	RECOVERED	% RECOVERY	% DRILLING FLUID LOSS	RQD (%)	DEPTH	LOG	DESCRIPTION
1:07pm 1:13pm	(11)		6'	5'	5'	100%		60" 100%	64		Sandstone, olive-gray, highly weathered, medium to fine grain, strong
1:31pm 1:38pm	(12)		7	5'	5'	100%		60" 100%	66		
									68		
1:50pm 1:57pm	(13)		7	5'	4.6'	92%		55" 100%	70		
									72		
									74		
2:09pm 2:16pm	(14)		7						76		
									78		note: Sample stuck in barrel, destroyed during retrieval
									80		

PROJECT NO.: 4245.200A BORING NO.: 2 / Turbine 28
DATE INITIATED: 1-6-23
DATE COMPLETED: 1-6-23
TOTAL DEPTH OF HOLE: 90'
BOREHOLE ELEVATION: _____
GROUNDWATER ELEVATION: _____
CASING ELEVATION: _____

[illegible]

**Sand Hill
Turbine 28**

12.4'

14'

15.6'

17.4'

19.4'

20'

22.2'

15'

14'

15.6'

17.4'

19.1'

23.2'

Sand Hill
Turbine 28



COMPANY Recony / Sand Hill PROPERTY 424 S. 200
HOLE NO. 2 / T-28 BOX NO. 2
FROM 23.2 TO 32

23.2

25.3'

27'

28.7'

30.3'

25'

30'

25.3'

27'

28.7'

30.3'

32'

Sand Hill
Turbine 28

COMPANY _____
HOLE NO. _____
FROM _____ TO _____



32'

33.6'

33.5
39.7

40'

41.6

43.2

45'

45'

Sand Hill
Turbine 28

COMPANY
HOLE NO.
FROM

PROPERTY
BOX NO.
TO

45.6

51.5

50'
51'

47.3'

48.9

53.2

55'

Direct Shear Worksheet ASTM D-3080
Project Number: 4245-200



COMPANY Reiner / Sand Hill PROPERTY 4245-200
HOLE NO. 2 / T-28 BOX NO. 5
FROM 55' TO 65'

www.holeproducts.com

Sand Hill
Turbine 28

hole
PRODUCTS
holeproducts.com

COMPANY
PROPERTY
BOX NO.

55'				63.5'
56.4	58.4	60'	62'	65'

Sand Hill
Turbine 28



COMPANY Rogers / Sand Hill PROPERTY 4245 200
HOLE NO. 2/T-28 BOX NO. 6
FROM 65 TO 75

65'

68.1'

70'
71.6'

68'

66.4'

72'

73.6'

75'

Sand Hill

Turbine 28

85.3

86.7

88

89.3

90

APPENDIX B

Rotary Wash Logs

Berlogar Stevens & Associates
1220 Quarry Lane
Pleasanton, CA 94566

BORING NUMBER RB1

PAGE 1 OF 3

CLIENT Viracocha Wind PROJECT NAME Rooney/Sand Hill
PROJECT NUMBER 4245.200 PROJECT LOCATION Livermore CA
DATE STARTED 4.17.23 COMPLETED 4.17.23 LOGGED BY: AG
DRILLING CONTRACTOR Gregg GROUNDWATER: AT TIME OF DRILLING ---
DRILLING EQUIPMENT Rotary Wash SAMPLER TYPE: AT END OF DRILLING ---
HAMMER 140lb Auto Hammer - 30" Drop
NOTES Turbine 17



Modified California
Sampler



Standard
Penetration Test



Bulk Sample



Shelby
Tube

BLOWS PER HALF FOOT			BLOWS PER FOOT	SAMPLER	DEPTH (ft)	USCS CLASSIFICATION	MATERIAL DESCRIPTION	POCKET PENETROMETER	TORVANE SHEAR STRENGTH
					0				
					1	CL	Silty Sandy Clay, Brown, Dry-Moist, Med-Stiff		
					2		Sandstone, Yellow-Brown, Highly Weathered, Friable		
28	29	46	75		3				
					4				
					5				
33	50/5		50/5		6				
					7				
15	20	30	50		8		Claystone, Olive-Brown, Highly Weathered, Weak		
					9				
					10				
20	32	42	74		11				
					12				
					13				
					14				
					15				
28	45	50	95		16				
					17				
					18				
					19				
					20				

BORING NUMBER RB1
PAGE 3 OF 3

PROJECT NAME Rooney/Sand Hill

PROJECT LOCATION Livermore CA

LOGGED BY: AG

GROUNDWATER: AT TIME OF DRILLING ---

SAMPLER TYPE: AT END OF DRILLING ---

Modified California Sampler Standard Penetration Test Bulk Sample Shelby Tube

BLOWS PER HALF FOOT			BLOWS PER FOOT	SAMPLER DEPTH (ft)	USCS CLASSIFICATION	MATERIAL DESCRIPTION	POCKET PENETROMETER	TORVANE SHEAR STRENGTH
				40				
22	50/5		50/5	41		Claystone, Olive-Brown, Moderately Weathered, Weak		
				42				
				43				
				44				
50/5			50/5	45				
				46				
				47				
				48				
				49				
				50				
36	37	42	79	51				
				52				
				53				
				54				
				55				
				56				
				57				
				58				
				59				
41	50/5		50/5	60		Bottom Of Hole 60'		

Berlogar Stevens & Associates
1220 Quarry Lane
Pleasanton, CA 94566

BORING NUMBER RB2

PAGE 1 OF 3

CLIENT Viracocha Wind PROJECT NAME Rooney/Sand Hill
PROJECT NUMBER 4245.200 PROJECT LOCATION Livermore CA
DATE STARTED 4.17.23 COMPLETED 4.18.23 LOGGED BY: AG
DRILLING CONTRACTOR Gregg GROUNDWATER: AT TIME OF DRILLING ---
DRILLING EQUIPMENT Rotary Wash SAMPLER TYPE: AT END OF DRILLING ---
HAMMER 140lb Auto Hammer - 30" Drop
NOTES Turbine 18



Modified California
Sampler



Standard
Penetration Test



Bulk Sample



Shelby
Tube

BLOWS PER HALF FOOT			BLOWS PER FOOT	SAMPLER	DEPTH (ft)	USCS CLASSIFICATION	MATERIAL DESCRIPTION	POCKET PENETROMETER	TORVANE SHEAR STRENGTH
					0				
					1	CL	Silty Sandy Clay, Brown, Dry-Moist, Med-Stiff		
					2		Sandstone, Yellow-Brown, Highly Weathered, Friable		
5	41	50/4	50/4		3				
					4				
					5				
19	39	42	81		6				
					7				
27	48	50/2	50/2		8				
					9				
					10				
36	50/4		50/4		11				
					12				
					13				
					14				
					15				
25	31	42	73		16		Claystone, Olive-Brown, Moderately Weathered, Weak		
					17				
					18				
					19				
					20				

Berlogar Stevens & Associates
1220 Quarry Lane
Pleasanton, CA 94566

BORING NUMBER RB2

PAGE 2 OF 3

CLIENT Viracocha Wind

PROJECT NAME Rooney/Sand Hill

PROJECT NUMBER 4245.200

PROJECT LOCATION Livermore CA

DATE STARTED 4.17.23 COMPLETED 4.18.23

LOGGED BY: AG

DRILLING CONTRACTOR Gregg

GROUNDWATER: AT TIME OF DRILLING ---

DRILLING EQUIPMENT Rotary Wash

SAMPLER TYPE: AT END OF DRILLING ---

HAMMER 140lb Auto Hammer - 30" Drop



Modified California
Sampler



Standard
Penetration Test



Bulk Sample



Shelby
Tube

NOTES Turbine 19

BLOWS PER HALF FOOT			BLOWS PER FOOT	SAMPLER	DEPTH (ft)	USCS CLASSIFICATION	MATERIAL DESCRIPTION	POCKET PENETROMETER	TORVANE SHEAR STRENGTH
					20				
13	39	50/4	50/4		21		Sandstone, Yellow-Brown, Moderately Weathered, Weak		
					22				
					23				
					24				
					25				
45	43	50/6	50/6		26		Claystone, Olive-Brown, Moderately Weathered, Weak		
					27				
					28				
					29				
					30				
50/5			50/5		31		Sandstone, Olive-Brown, Moderately Weathered, Strong		
					32				
					33				
					34				
					35				
15	43	50/3	50/3		36				
					37				
					38				
					39				
					40				

Berlogar Stevens & Associates
1220 Quarry Lane
Pleasanton, CA 94566

BORING NUMBER RB3

PAGE 1 OF 3

CLIENT Viracocha Wind

PROJECT NAME Rooney/Sand Hill

PROJECT NUMBER 4245.200

PROJECT LOCATION Livermore CA

DATE STARTED 4.18.23 COMPLETED 4.18.23

LOGGED BY: AG

DRILLING CONTRACTOR Gregg

GROUNDWATER: AT TIME OF DRILLING ---

DRILLING EQUIPMENT Rotary Wash

SAMPLER TYPE: AT END OF DRILLING ---

HAMMER 140lb Auto Hammer - 30" Drop

 Modified California Sampler
  Standard Penetration Test
  Bulk Sample
  Shelby Tube

NOTES Turbine 19

BLOWS PER HALF FOOT			BLOWS PER FOOT	SAMPLER	DEPTH (ft)	USCS CLASSIFICATION	MATERIAL DESCRIPTION	POCKET PENETROMETER	TORVANE SHEAR STRENGTH
					0				
					1	CL	Silty Sandy Clay, Brown, Dry-Moist, Med-Stiff		
					2		Sandstone, Yellow-Brown, Highly Weathered, Friable		
2	7	25	32		3				
					4				
					5				
					6				
					7				
22	50/5		50/5		8		Claystone, Olive-Gray to Olive-Brown, Moderately Weathered, Weak		
					9				
					10				
					11				
					12				
50/1			50/1		13				
					14				
					15				
					16				
					17				
					18				
					19				
					20				

Berlogar Stevens & Associates
1220 Quarry Lane
Pleasanton, CA 94566

BORING NUMBER RB3
 PAGE 3 OF 3

CLIENT <u>Viracocha Wind</u>	PROJECT NAME <u>Rooney/Sand Hill</u>
PROJECT NUMBER <u>4245.200</u>	PROJECT LOCATION <u>Livermore CA</u>
DATE STARTED <u>4.18.23</u> COMPLETED <u>4.18.23</u>	LOGGED BY: <u>AG</u>
DRILLING CONTRACTOR <u>Gregg</u>	GROUNDWATER: <u>AT TIME OF DRILLING ---</u>
DRILLING EQUIPMENT <u>Rotary Wash</u>	SAMPLER TYPE: <u>AT END OF DRILLING ---</u>
HAMMER <u>140lb Auto Hammer - 30" Drop</u>	 Modified California Sampler  Standard Penetration Test  Bulk Sample  Shelby Tube
NOTES <u>Turbine 19</u>	

BLOWS PER HALF FOOT			BLOWS PER FOOT	SAMPLER	DEPTH (ft)	USCS CLASSIFICATION	MATERIAL DESCRIPTION	POCKET PENETROMETER	TORVANE SHEAR STRENGTH
					40				
					41				
					42				
					43		Claystone, Olive-Brown, Moderately Weathered, Weak		
20	50/5		50/5		44				
					45				
					46				
					47				
					48				
					49				
					50				
					51				
40	50/6		50/6		52				
					53				
					54				
					55				
					56				
					57				
					58				
					59				
43	50/5		50/5		60				
							Bottom Of Hole 60.5'		

Berlogar Stevens & Associates
1220 Quarry Lane
Pleasanton, CA 94566

BORING NUMBER RB4
 PAGE 1 OF 3

CLIENT <u>Viracocha Wind</u>	PROJECT NAME <u>Rooney/Sand Hill</u>
PROJECT NUMBER <u>4245.200</u>	PROJECT LOCATION <u>Livermore CA</u>
DATE STARTED <u>4.19.23</u> COMPLETED <u>4.19.23</u>	LOGGED BY: <u>AG</u>
DRILLING CONTRACTOR <u>Gregg</u>	GROUNDWATER: <u>AT TIME OF DRILLING ---</u>
DRILLING EQUIPMENT <u>Rotary Wash</u>	SAMPLER TYPE: <u>AT END OF DRILLING ---</u>
HAMMER <u>140lb Auto Hammer - 30" Drop</u>	 Modified California Sampler  Standard Penetration Test  Bulk Sample  Shelby Tube
NOTES <u>Turbine 20</u>	

BLOWS PER HALF FOOT			BLOWS PER FOOT	SAMPLER	DEPTH (ft)	USCS CLASSIFICATION	MATERIAL DESCRIPTION	POCKET PENETROMETER	TORVANE SHEAR STRENGTH
					0				
					1		Silty Sandy Clay, Brown, Dry-Moist, Med-Stiff		
					2		Sandstone, Yellow-Brown, Highly Weathered, Friable		
7	12	24	36		3				
					4				
					5				
					6				
					7				
9	22	30	52		8		Claystone, Olive-Brown, Moderately Weathered, Weak		
					9				
					10				
					11				
					12				
21	50/6		50/6		13				
					14				
					15				
					16				
					17				
					18				
					19				
					20				

Berlogar Stevens & Associates
1220 Quarry Lane
Pleasanton, CA 94566

BORING NUMBER RB4
 PAGE 2 OF 3

CLIENT <u>Viracocha Wind</u>	PROJECT NAME <u>Rooney/Sand Hill</u>
PROJECT NUMBER <u>4245.200</u>	PROJECT LOCATION <u>Livermore CA</u>
DATE STARTED <u>4.19.23</u> COMPLETED <u>4.19.23</u>	LOGGED BY: <u>AG</u>
DRILLING CONTRACTOR <u>Gregg</u>	GROUNDWATER: <u>AT TIME OF DRILLING ---</u>
DRILLING EQUIPMENT <u>Rotary Wash</u>	SAMPLER TYPE: <u>AT END OF DRILLING ---</u>
HAMMER <u>140lb Auto Hammer - 30" Drop</u>	 Modified California Sampler  Standard Penetration Test  Bulk Sample  Shelby Tube
NOTES <u>Turbine 20</u>	

BLOWS PER HALF FOOT			BLOWS PER FOOT	SAMPLER	DEPTH (ft)	USCS CLASSIFICATION	MATERIAL DESCRIPTION	POCKET PENETROMETER	TORVANE SHEAR STRENGTH
					20				
50/5			50/5		21		Claystone, Olive-Brown, Moderately Weathered, Weak		
					22				
					23				
					24				
					25				
					26				
					27				
50/4			50/4		28				
					29				
					30				
					31				
					32				
					33				
					34				
					35				
50/6			50/6		36				
					37				
					38				
					39				
					40				

Berlogar Stevens & Associates
1220 Quarry Lane
Pleasanton, CA 94566

BORING NUMBER RB4
 PAGE 3 OF 3

CLIENT <u>Viracocha Wind</u>	PROJECT NAME <u>Rooney/Sand Hill</u>
PROJECT NUMBER <u>4245.200</u>	PROJECT LOCATION <u>Livermore CA</u>
DATE STARTED <u>4.19.23</u> COMPLETED <u>4.19.23</u>	LOGGED BY: <u>AG</u>
DRILLING CONTRACTOR <u>Gregg</u>	GROUNDWATER: <u>AT TIME OF DRILLING ---</u>
DRILLING EQUIPMENT <u>Rotary Wash</u>	SAMPLER TYPE: <u>AT END OF DRILLING ---</u>
HAMMER <u>140lb Auto Hammer - 30" Drop</u>	 Modified California Sampler  Standard Penetration Test  Bulk Sample  Shelby Tube
NOTES <u>Turbine 20</u>	

BLOWS PER HALF FOOT			BLOWS PER FOOT	SAMPLER	DEPTH (ft)	USCS CLASSIFICATION	MATERIAL DESCRIPTION	POCKET PENETROMETER	TORVANE SHEAR STRENGTH
					40				
					41				
					42				
					43		Claystone, Olive-Brown, Moderately Weathered, Weak		
50/6			50/6		44				
					45				
					46				
					47				
					48				
					49				
					50				
					51				
50/4			50/4		52				
					53				
					54				
					55				
					56				
					57				
					58				
					59				
50/5			50/5		60				
							Bottom Of Hole 60.5'		

Berlogar Stevens & Associates
1220 Quarry Lane
Pleasanton, CA 94566

BORING NUMBER RB5
 PAGE 1 OF 3

CLIENT <u>Viracocha Wind</u>	PROJECT NAME <u>Rooney/Sand Hill</u>
PROJECT NUMBER <u>4245.200</u>	PROJECT LOCATION <u>Livermore CA</u>
DATE STARTED <u>4.19.23</u> COMPLETED <u>4.19.23</u>	LOGGED BY: <u>AG</u>
DRILLING CONTRACTOR <u>Gregg</u>	GROUNDWATER: <u>AT TIME OF DRILLING ---</u>
DRILLING EQUIPMENT <u>Rotary Wash</u>	SAMPLER TYPE: <u>AT END OF DRILLING ---</u>
HAMMER <u>140lb Auto Hammer - 30" Drop</u>	 Modified California Sampler  Standard Penetration Test  Bulk Sample  Shelby Tube
NOTES <u>Turbine 21</u>	

BLOWS PER HALF FOOT			BLOWS PER FOOT	SAMPLER	DEPTH (ft)	USCS CLASSIFICATION	MATERIAL DESCRIPTION	POCKET PENETROMETER	TORVANE SHEAR STRENGTH
					0				
					1	CL	Silty Sandy Clay, Brown, Dry-Moist, Med-Stiff		
					2				
3	10	28	38		3		Claystone, Olive-Brown, Highly Weathered, Friable		
					4				
					5				
					6				
					7				
13	17	27	44		8		Claystone, Olive-Brown, Moderately Weathered, Weak		
					9				
					10				
					11				
					12				
24	35	50/5	50/5		13				
					14				
					15				
					16				
					17				
					18				
					19				
					20				

Berlogar Stevens & Associates
1220 Quarry Lane
Pleasanton, CA 94566

BORING NUMBER RB5

PAGE 2 OF 3

CLIENT Viracocha Wind

PROJECT NAME Rooney/Sand Hill

PROJECT NUMBER 4245.200

PROJECT LOCATION Livermore CA

DATE STARTED 4.19.23 COMPLETED 4.19.23

LOGGED BY: AG

DRILLING CONTRACTOR Gregg

GROUNDWATER: AT TIME OF DRILLING ---

DRILLING EQUIPMENT Rotary Wash

SAMPLER TYPE: AT END OF DRILLING ---

HAMMER 140lb Auto Hammer - 30" Drop



Modified California
Sampler



Standard
Penetration Test



Bulk Sample



Shelby
Tube

NOTES Turbine 21

BLOWS PER HALF FOOT			BLOWS PER FOOT	SAMPLER	DEPTH (ft)	USCS CLASSIFICATION	MATERIAL DESCRIPTION	POCKET PENETROMETER	TORVANE SHEAR STRENGTH
					20				
22	35	50/4	50/4		21		Claystone, Olive-Brown, Moderately Weathered, Weak		
					22				
					23				
					24				
					25				
					26				
					27				
18	22	40	64		28		Claystone, Gray to Olive-Brown, Moderately Weathered, Weak		
					29				
					30				
					31				
					32				
					33				
					34				
					35				
35	34	50/5	50/5		36				
					37				
					38				
					39				
					40				

Berlogar Stevens & Associates
1220 Quarry Lane
Pleasanton, CA 94566

BORING NUMBER RB5
 PAGE 3 OF 3

CLIENT <u>Viracocha Wind</u>	PROJECT NAME <u>Rooney/Sand Hill</u>
PROJECT NUMBER <u>4245.200</u>	PROJECT LOCATION <u>Livermore CA</u>
DATE STARTED <u>4.19.23</u> COMPLETED <u>4.19.23</u>	LOGGED BY: <u>AG</u>
DRILLING CONTRACTOR <u>Gregg</u>	GROUNDWATER: <u>AT TIME OF DRILLING ---</u>
DRILLING EQUIPMENT <u>Rotary Wash</u>	SAMPLER TYPE: <u>AT END OF DRILLING ---</u>
HAMMER <u>140lb Auto Hammer - 30" Drop</u>	 Modified California Sampler  Standard Penetration Test  Bulk Sample  Shelby Tube
NOTES <u>Turbine 21</u>	

BLOWS PER HALF FOOT			BLOWS PER FOOT	SAMPLER	DEPTH (ft)	USCS CLASSIFICATION	MATERIAL DESCRIPTION	POCKET PENETROMETER	TORVANE SHEAR STRENGTH
					40				
					41		Claystone, Olive-Brown, Moderately Weathered, Weak		
					42				
					43				
26	35	50/5	50/5		44				
					45				
					46				
					47				
					48				
					49				
					50				
50/4			50/4		51				
					52				
					53				
					54				
					55				
					56				
					57				
					58				
50/6			50/6		59				
					60				
							Bottom Of Hole 60.5'		

Berlogar Stevens & Associates
1220 Quarry Lane
Pleasanton, CA 94566

BORING NUMBER RB6

PAGE 1 OF 3

CLIENT Viracocha Wind PROJECT NAME Rooney/Sand Hill
PROJECT NUMBER 4245.200 PROJECT LOCATION Livermore CA
DATE STARTED 4.20.23 COMPLETED 4.20.23 LOGGED BY: AG
DRILLING CONTRACTOR Gregg GROUNDWATER: AT TIME OF DRILLING ---
DRILLING EQUIPMENT Rotary Wash SAMPLER TYPE: AT END OF DRILLING ---
HAMMER 140lb Auto Hammer - 30" Drop
NOTES Turbine 25



Modified California
Sampler



Standard
Penetration Test



Bulk Sample



Shelby
Tube

BLOWS PER HALF FOOT			BLOWS PER FOOT	SAMPLER	DEPTH (ft)	USCS CLASSIFICATION	MATERIAL DESCRIPTION	POCKET PENETROMETER	TORVANE SHEAR STRENGTH
					0				
					1	CL	Silty Sandy Clay, Brown, Dry-Moist, Med-Stiff		
					2				
6	20	39	59		3		Sandstone, Red-Brown, Highly Weathered, Friable		
					4				
					5				
					6				
					7				
13	38	50/3	50/3		8		Claystone, Olive-Brown, Highly Weathered, Friable		
					9				
					10				
					11				
					12				
33	50/5		50/5		13				
					14				
					15				
					16				
					17				
					18				
					19				
					20				

Berlogar Stevens & Associates
1220 Quarry Lane
Pleasanton, CA 94566

BORING NUMBER RB6

PAGE 2 OF 3

CLIENT Viracocha Wind

PROJECT NAME Rooney/Sand Hill

PROJECT NUMBER 4245.200

PROJECT LOCATION Livermore CA

DATE STARTED 4.20.23 COMPLETED 4.20.23

LOGGED BY: AG

DRILLING CONTRACTOR Gregg

GROUNDWATER: AT TIME OF DRILLING ---

DRILLING EQUIPMENT Rotary Wash

SAMPLER TYPE: AT END OF DRILLING ---

HAMMER 140lb Auto Hammer - 30" Drop



Modified California
Sampler



Standard
Penetration Test



Bulk Sample



Shelby
Tube

NOTES Turbine 25

BLOWS PER HALF FOOT			BLOWS PER FOOT	SAMPLER	DEPTH (ft)	USCS CLASSIFICATION	MATERIAL DESCRIPTION	POCKET PENETROMETER	TORVANE SHEAR STRENGTH
					20				
14	19	36	55		21		Claystone, Olive-Brown, Moderately Weathered, Weak		
					22				
					23				
					24				
					25				
					26				
					27				
50/3			50/3		28		Sandstone, Yellow-Brown, Moderately Weathered, Weak		
					29				
					30				
					31				
					32				
					33				
					34				
					35				
50/5			50/5		36		Claystone, Gray, Moderately Weathered, Weak		
					37				
					38				
					39				
					40				

Berlogar Stevens & Associates
1220 Quarry Lane
Pleasanton, CA 94566

BORING NUMBER RB6

PAGE 3 OF 3

CLIENT Viracocha Wind

PROJECT NAME Rooney/Sand Hill

PROJECT NUMBER 4245.200

PROJECT LOCATION Livermore CA

DATE STARTED 4.20.23 COMPLETED 4.20.23

LOGGED BY: AG

DRILLING CONTRACTOR Gregg

GROUNDWATER: AT TIME OF DRILLING ---

DRILLING EQUIPMENT Rotary Wash

SAMPLER TYPE: AT END OF DRILLING ---

HAMMER 140lb Auto Hammer - 30" Drop

 Modified California Sampler

 Standard Penetration Test

 Bulk Sample

 Shelby Tube

NOTES Turbine 25

BLOWS PER HALF FOOT			BLOWS PER FOOT	SAMPLER	DEPTH (ft)	USCS CLASSIFICATION	MATERIAL DESCRIPTION	POCKET PENETROMETER	TORVANE SHEAR STRENGTH
					40				
					41				
					42		Claystone, Olive-Brown, Moderately Weathered, Weak		
					43				
50/2			50/2		44				
					45				
					46				
					47				
					48				
					49				
					50				
					51		Claystone, Gray, Moderately Weathered, Weak		
50/3			50/3		52				
					53				
					54				
					55				
					56				
					57				
					58				
					59		Sandstone, Gray, Highly Weathered, Friable		
50/1			50/1		60				
							Bottom Of Hole 60.5'		

Berlogar Stevens & Associates
1220 Quarry Lane
Pleasanton, CA 94566

BORING NUMBER RB7

PAGE 1 OF 3

CLIENT Viracocha Wind

PROJECT NAME Rooney/Sand Hill

PROJECT NUMBER 4245.200

PROJECT LOCATION Livermore CA

DATE STARTED 4.20.23 COMPLETED 4.20.23

LOGGED BY: AG

DRILLING CONTRACTOR Gregg

GROUNDWATER: AT TIME OF DRILLING ---

DRILLING EQUIPMENT Rotary Wash

SAMPLER TYPE: AT END OF DRILLING ---

HAMMER 140lb Auto Hammer - 30" Drop

 Modified California Sampler
  Standard Penetration Test
  Bulk Sample
  Shelby Tube

NOTES Turbine 29

BLOWS PER HALF FOOT			BLOWS PER FOOT	SAMPLER	DEPTH (ft)	USCS CLASSIFICATION	MATERIAL DESCRIPTION	POCKET PENETROMETER	TORVANE SHEAR STRENGTH
					0				
					1	CL	Silty Sandy Clay, Brown, Dry-Moist, Med-Stiff		
					2				
5	8	23	31		3				
					4				
					5				
					6				
					7				
7	10	14	24		8		Claystone, Olive-Brown, Highly Weathered, Friable		
					9				
					10				
					11				
					12				
40	50/2		50/2		13		Claystone, Olive-Brown, Moderately Weathered, Weak		
					14				
					15				
					16				
					17				
					18				
					19				
					20				

Berlogar Stevens & Associates
1220 Quarry Lane
Pleasanton, CA 94566

BORING NUMBER RB7
 PAGE 2 OF 3

CLIENT <u>Viracocha Wind</u>	PROJECT NAME <u>Rooney/Sand Hill</u>
PROJECT NUMBER <u>4245.200</u>	PROJECT LOCATION <u>Livermore CA</u>
DATE STARTED <u>4.20.23</u> COMPLETED <u>4.20.23</u>	LOGGED BY: <u>AG</u>
DRILLING CONTRACTOR <u>Gregg</u>	GROUNDWATER: <u>AT TIME OF DRILLING ---</u>
DRILLING EQUIPMENT <u>Rotary Wash</u>	SAMPLER TYPE: <u>AT END OF DRILLING ---</u>
HAMMER <u>140lb Auto Hammer - 30" Drop</u>	 Modified California Sampler  Standard Penetration Test  Bulk Sample  Shelby Tube
NOTES <u>Turbine 29</u>	

BLOWS PER HALF FOOT			BLOWS PER FOOT	SAMPLER	DEPTH (ft)	USCS CLASSIFICATION	MATERIAL DESCRIPTION	POCKET PENETROMETER	TORVANE SHEAR STRENGTH
					20				
50/5			50/5		21		Claystone, Olive-Brown, Moderately Weathered, Weak		
					22				
					23				
					24				
					25				
					26				
					27				
					28				
50/6			50/6		29				
					30				
					31				
					32				
					33				
					34				
					35				
47	50/5		50/5		36				
					37				
					38				
					39				
					40				

Berlogar Stevens & Associates
1220 Quarry Lane
Pleasanton, CA 94566

BORING NUMBER RB7
 PAGE 3 OF 3

CLIENT <u>Viracocha Wind</u>	PROJECT NAME <u>Rooney/Sand Hill</u>
PROJECT NUMBER <u>4245.200</u>	PROJECT LOCATION <u>Livermore CA</u>
DATE STARTED <u>4.20.23</u> COMPLETED <u>4.20.23</u>	LOGGED BY: <u>AG</u>
DRILLING CONTRACTOR <u>Gregg</u>	GROUNDWATER: <u>AT TIME OF DRILLING ---</u>
DRILLING EQUIPMENT <u>Rotary Wash</u>	SAMPLER TYPE: <u>AT END OF DRILLING ---</u>
HAMMER <u>140lb Auto Hammer - 30" Drop</u>	 Modified California Sampler  Standard Penetration Test  Bulk Sample  Shelby Tube
NOTES <u>Turbine 29</u>	

BLOWS PER HALF FOOT			BLOWS PER FOOT	SAMPLER	DEPTH (ft)	USCS CLASSIFICATION	MATERIAL DESCRIPTION	POCKET PENETROMETER	TORVANE SHEAR STRENGTH
					40				
					41				
					42		Claystone, Olive-Brown, Moderately Weathered, Weak		
					43				
27	50/3		50/3		44				
					45				
					46				
					47				
					48				
					49				
					50				
					51				
50/5			50/5		52				
					53				
					54				
					55				
					56				
					57				
					58				
					59				
50/6			50/6		60				
							Bottom Of Hole 60.5'		

BORING NUMBER RB8
PAGE 1 OF 3

PROJECT NAME Rooney/Sand Hill

PROJECT LOCATION Livermore CA

LOGGED BY: AG

GROUNDWATER: AT TIME OF DRILLING ---

SAMPLER TYPE: AT END OF DRILLING ---

Modified California Sampler Standard Penetration Test Bulk Sample Shelby Tube

BLOWS PER HALF FOOT			BLOWS PER FOOT	SAMPLER	DEPTH (ft)	USCS CLASSIFICATION	MATERIAL DESCRIPTION	POCKET PENETROMETER	TORVANE SHEAR STRENGTH
					0	CL			
					1		Silty Sandy Clay, Brown, Dry-Moist, Med-Stiff		
					2				
					3				
					4		Sandstone, Yellow-Brown, Highly Weathered, Friable		
24	49	50/5	50/5		5				
					6				
					7				
34	50/5		50/5		8				
					9				
					10				
					11				
					12				
41	50/5		50/5		13				
					14				
					15				
					16				
					17				
					18				
					19				
					20				

Berlogar Stevens & Associates
1220 Quarry Lane
Pleasanton, CA 94566

BORING NUMBER RB8

PAGE 2 OF 3

CLIENT Viracocha Wind

PROJECT NAME Rooney/Sand Hill

PROJECT NUMBER 4245.200

PROJECT LOCATION Livermore CA

DATE STARTED 4.21.23 COMPLETED 4.21.23

LOGGED BY: AG

DRILLING CONTRACTOR Gregg

GROUNDWATER: AT TIME OF DRILLING ---

DRILLING EQUIPMENT Rotary Wash

SAMPLER TYPE: AT END OF DRILLING ---

HAMMER 140lb Auto Hammer - 30" Drop



Modified California
Sampler



Standard
Penetration Test



Bulk Sample



Shelby
Tube

NOTES Turbine 23

BLOWS PER HALF FOOT			BLOWS PER FOOT	SAMPLER	DEPTH (ft)	USCS CLASSIFICATION	MATERIAL DESCRIPTION	POCKET PENETROMETER	TORVANE SHEAR STRENGTH
					20				
34	40	49	89		21		Sandstone, Yellow-Brown, Moderately Weathered, Weak		
					22				
					23				
					24				
					25				
					26				
					27				
					28		Claystone, Olive-Brown, Moderately Weathered, Weak		
29	33	50/4	50/4		29				
					30				
					31				
					32				
					33				
					34				
					35				
50/3			50/3		36				
					37				
					38				
					39				
					40				

Berlogar Stevens & Associates
1220 Quarry Lane
Pleasanton, CA 94566

BORING NUMBER RB8
 PAGE 3 OF 3

CLIENT <u>Viracocha Wind</u>	PROJECT NAME <u>Rooney/Sand Hill</u>
PROJECT NUMBER <u>4245.200</u>	PROJECT LOCATION <u>Livermore CA</u>
DATE STARTED <u>4.21.23</u> COMPLETED <u>4.21.23</u>	LOGGED BY: <u>AG</u>
DRILLING CONTRACTOR <u>Gregg</u>	GROUNDWATER: <u>AT TIME OF DRILLING ---</u>
DRILLING EQUIPMENT <u>Rotary Wash</u>	SAMPLER TYPE: <u>AT END OF DRILLING ---</u>
HAMMER <u>140lb Auto Hammer - 30" Drop</u>	 Modified California Sampler  Standard Penetration Test  Bulk Sample  Shelby Tube
NOTES <u>Turbine 23</u>	

BLOWS PER HALF FOOT			BLOWS PER FOOT	SAMPLER	DEPTH (ft)	USCS CLASSIFICATION	MATERIAL DESCRIPTION	POCKET PENETROMETER	TORVANE SHEAR STRENGTH
					40				
					41		Claystone, Olive-Brown, Moderately Weathered, Weak		
					42				
					43				
44	50/4		50/4		44				
					45				
					46				
					47				
					48				
					49				
					50				
					51				
50/5			50/5		52				
					53				
					54				
					55				
					56				
					57				
					58				
					59				
50/5			50/5		60				
							Bottom Of Hole 60.5'		

Berlogar Stevens & Associates
1220 Quarry Lane
Pleasanton, CA 94566

BORING NUMBER RB9

PAGE 1 OF 3

CLIENT Viracocha Wind PROJECT NAME Rooney/Sand Hill
PROJECT NUMBER 4245.200 PROJECT LOCATION Livermore CA
DATE STARTED 4.21.23 COMPLETED 4.21.23 LOGGED BY: AG
DRILLING CONTRACTOR Gregg GROUNDWATER: AT TIME OF DRILLING ---
DRILLING EQUIPMENT Rotary Wash SAMPLER TYPE: AT END OF DRILLING ---
HAMMER 140lb Auto Hammer - 30" Drop
NOTES Turbine 26



Modified California
Sampler



Standard
Penetration Test



Bulk Sample



Shelby
Tube

BLOWS PER HALF FOOT			BLOWS PER FOOT	SAMPLER	DEPTH (ft)	USCS CLASSIFICATION	MATERIAL DESCRIPTION	POCKET PENETROMETER	TORVANE SHEAR STRENGTH
					0	CL	Silty Sandy Clay, Brown, Dry, Med-Stiff		
					1				
					2				
6	39	38	77		3		Sandstone, Yellow-Brown, Highly Weathered, Friable		
					4				
					5				
					6				
					7				
26	21	29	50		8				
					9				
					10				
					11				
					12				
20	20	28	48		13		Claystone, Olive-Brown, Moderately Weathered, Weak		
					14				
					15				
					16				
					17				
					18				
					19				
					20				

Berlogar Stevens & Associates
1220 Quarry Lane
Pleasanton, CA 94566

BORING NUMBER RB9

PAGE 2 OF 3

CLIENT <u>Viracocha Wind</u>	PROJECT NAME <u>Rooney/Sand Hill</u>
PROJECT NUMBER <u>4245.200</u>	PROJECT LOCATION <u>Livermore CA</u>
DATE STARTED <u>4.21.23</u> COMPLETED <u>4.21.23</u>	LOGGED BY: <u>AG</u>
DRILLING CONTRACTOR <u>Gregg</u>	GROUNDWATER: <u>AT TIME OF DRILLING ---</u>
DRILLING EQUIPMENT <u>Rotary Wash</u>	SAMPLER TYPE: <u>AT END OF DRILLING ---</u>
HAMMER <u>140lb Auto Hammer - 30" Drop</u>	 Modified California Sampler  Standard Penetration Test  Bulk Sample  Shelby Tube
NOTES <u>Turbine 26</u>	

BLOWS PER HALF FOOT			BLOWS PER FOOT	SAMPLER	DEPTH (ft)	USCS CLASSIFICATION	MATERIAL DESCRIPTION	POCKET PENETROMETER	TORVANE SHEAR STRENGTH
					20		Claystone, Olive-Brown, Moderately Weathered, Weak		
6	4	9	13		21				
					22				
					23				
					24				
					25				
					26				
					27				
20	50/5		50/5		28				
					29				
					30				
					31				
					32				
					33				
					34				
					35				
29	50/2		50/2		36				
					37				
					38				
					39				
					40				

Berlogar Stevens & Associates
1220 Quarry Lane
Pleasanton, CA 94566

BORING NUMBER B-
 PAGE 3 OF 3

CLIENT <u>Viracocha Wind</u>	PROJECT NAME <u>Rooney/Sand Hill</u>
PROJECT NUMBER <u>4245.200</u>	PROJECT LOCATION <u>Livermore CA</u>
DATE STARTED <u>4.21.23</u> COMPLETED <u>4.21.23</u>	LOGGED BY: <u>AG</u>
DRILLING CONTRACTOR <u>Gregg</u>	GROUNDWATER: <u>AT TIME OF DRILLING ---</u>
DRILLING EQUIPMENT <u>Rotary Wash</u>	SAMPLER TYPE: <u>AT END OF DRILLING ---</u>
HAMMER <u>140lb Auto Hammer - 30" Drop</u>	 Modified California Sampler  Standard Penetration Test  Bulk Sample  Shelby Tube
NOTES <u>Turbine 26</u>	

BLOWS PER HALF FOOT			BLOWS PER FOOT	SAMPLER	DEPTH (ft)	USCS CLASSIFICATION	MATERIAL DESCRIPTION	POCKET PENETROMETER	TORVANE SHEAR STRENGTH
					40				
					41		Claystone, Olive-Brown, Moderately Weathered, Weak		
					42				
					43				
37	50/6		50/6		44				
					45				
					46				
					47				
					48				
					49				
					50				
					51				
34	50/5		50/5		52				
					53				
					54				
					55				
					56				
					57				
					58				
					59				
50/5			50/5		60				
							Bottom Of Hole 60.5'		

Berlogar Stevens & Associates
1220 Quarry Lane
Pleasanton, CA 94566

BORING NUMBER RB10

PAGE 1 OF 3

CLIENT Viracocha Wind

PROJECT NAME Rooney/Sand Hill

PROJECT NUMBER 4245.200

PROJECT LOCATION Livermore CA

DATE STARTED 4.24.23 COMPLETED 4.24.23

LOGGED BY: AG

DRILLING CONTRACTOR Gregg

GROUNDWATER: AT TIME OF DRILLING ---

DRILLING EQUIPMENT Rotary Wash

SAMPLER TYPE: AT END OF DRILLING ---

HAMMER 140lb Auto Hammer - 30" Drop

 Modified California Sampler
  Standard Penetration Test
  Bulk Sample
  Shelby Tube

NOTES Turbine 27

BLOWS PER HALF FOOT			BLOWS PER FOOT	SAMPLER	DEPTH (ft)	USCS CLASSIFICATION	MATERIAL DESCRIPTION	POCKET PENETROMETER	TORVANE SHEAR STRENGTH
					0				
					1	CL	Silty Sandy Clay, Brown, Dry, Med-Stiff		
					2				
8	8	11	19		3		Sandstone, Red-Brown, Highly Weathered, Friable		
					4				
					5				
					6				
					7				
6	15	15	30		8		Claystone, Olive-Brown, Highly Weathered, Friable to Weak		
					9				
					10				
					11				
					12				
18	32	43	75		13		Claystone, Olive-Brown to Olive-Gray, Moderately Weathered, Weak		
					14				
					15				
					16				
					17				
					18				
					19				
					20				

Berlogar Stevens & Associates
1220 Quarry Lane
Pleasanton, CA 94566

BORING NUMBER RB10

PAGE 2 OF 3

CLIENT <u>Viracocha Wind</u>	PROJECT NAME <u>Rooney/Sand Hill</u>
PROJECT NUMBER <u>4245.200</u>	PROJECT LOCATION <u>Livermore CA</u>
DATE STARTED <u>4.24.23</u> COMPLETED <u>4.24.23</u>	LOGGED BY: <u>AG</u>
DRILLING CONTRACTOR <u>Gregg</u>	GROUNDWATER: <u>AT TIME OF DRILLING ---</u>
DRILLING EQUIPMENT <u>Rotary Wash</u>	SAMPLER TYPE: <u>AT END OF DRILLING ---</u>
HAMMER <u>140lb Auto Hammer - 30" Drop</u>	 Modified California Sampler  Standard Penetration Test  Bulk Sample  Shelby Tube
NOTES <u>Turbine 27</u>	

BLOWS PER HALF FOOT			BLOWS PER FOOT	SAMPLER	DEPTH (ft)	USCS CLASSIFICATION	MATERIAL DESCRIPTION	POCKET PENETROMETER	TORVANE SHEAR STRENGTH
					20				
50/3			50/3		21		Claystone, Olive-Brown to Olive-Gray, Moderately Weathered, Weak		
					22				
					23				
					24				
					25				
					26				
					27				
50/1			50/1		28		Sandstone, Gray, Highly Weathered, Weak		
					29				
					30				
					31				
					32				
					33				
					34				
					35				
50/4			50/4		36		Claystone, Olive-Brown, Moderately Weathered, Weak		
					37				
					38				
					39				
					40				

Berlogar Stevens & Associates
1220 Quarry Lane
Pleasanton, CA 94566

BORING NUMBER RB10

PAGE 3 OF 3

CLIENT Viracocha Wind

PROJECT NAME Rooney/Sand Hill

PROJECT NUMBER 4245.200

PROJECT LOCATION Livermore CA

DATE STARTED 4.24.23 COMPLETED 4.24.23

LOGGED BY: AG

DRILLING CONTRACTOR Gregg

GROUNDWATER: AT TIME OF DRILLING ---

DRILLING EQUIPMENT Rotary Wash

SAMPLER TYPE: AT END OF DRILLING ---

HAMMER 140lb Auto Hammer - 30" Drop

 Modified California Sampler
  Standard Penetration Test
  Bulk Sample
  Shelby Tube

NOTES Turbine 27

BLOWS PER HALF FOOT			BLOWS PER FOOT	SAMPLER	DEPTH (ft)	USCS CLASSIFICATION	MATERIAL DESCRIPTION	POCKET PENETROMETER	TORVANE SHEAR STRENGTH
					40		Claystone, Olive-Brown, Moderately Weathered, Weak		
					41				
					42				
					43				
37	50/6		50/6		44				
					45				
					46				
					47				
					48				
					49				
					50				
					51		Sandstone, Gray, Highly Weathered, Moderately Strong		
34	50/5		50/5		52		Sampler bouncing off bedrock. Sample retrieved by using sifter in water coming out of the conductor casing.		
					53				
					54				
					55				
					56				
					57				
					58				
					59		Claystone, Olive-Gray, Moderately Weathered, Weak		
50/5			50/5		60				
							Bottom Of Hole 60.5'		

Berlogar Stevens & Associates
1220 Quarry Lane
Pleasanton, CA 94566

BORING NUMBER RB11
 PAGE 1 OF 3

CLIENT <u>Viracocha Wind</u>	PROJECT NAME <u>Rooney/Sand Hill</u>
PROJECT NUMBER <u>4245.200</u>	PROJECT LOCATION <u>Livermore CA</u>
DATE STARTED <u>4.24.23</u> COMPLETED <u>4.24.23</u>	LOGGED BY: <u>AG</u>
DRILLING CONTRACTOR <u>Gregg</u>	GROUNDWATER: <u>AT TIME OF DRILLING ---</u>
DRILLING EQUIPMENT <u>Rotary Wash</u>	SAMPLER TYPE: <u>AT END OF DRILLING ---</u>
HAMMER <u>140lb Auto Hammer - 30" Drop</u>	 Modified California Sampler  Standard Penetration Test  Bulk Sample  Shelby Tube
NOTES <u>Turbine 24</u>	

BLOWS PER HALF FOOT			BLOWS PER FOOT	SAMPLER	DEPTH (ft)	USCS CLASSIFICATION	MATERIAL DESCRIPTION	POCKET PENETROMETER	TORVANE SHEAR STRENGTH
					0				
					1	CL	Silty Sandy Clay, Brown, Dry-Moist, Med-Stiff		
					2		Sandstone, Red-Brown, Highly Weathered, Friable		
4	18	50/3	50/3		3				
					4				
					5				
					6				
50/2			50/2		7				
					8				
					9				
					10				
					11				
18	32	43	75		12				
					13				
					14				
					15				
					16				
					17				
					18				
					19				
					20				

BORING NUMBER RB11
PAGE 2 OF 3

PROJECT NAME Rooney/Sand Hill

PROJECT LOCATION Livermore CA

LOGGED BY: AG

GROUNDWATER: AT TIME OF DRILLING ---

SAMPLER TYPE: AT END OF DRILLING ---

BLOWS PER HALF FOOT			BLOWS PER FOOT	SAMPLER DEPTH (ft)	USCS CLASSIFICATION	MATERIAL DESCRIPTION	POCKET PENETROMETER	TORVANE SHEAR STRENGTH
				20	Claystone, Olive-Brown, Moderately Weathered, Weak			
50/3			50/3	21				
				22				
				23				
				24				
				25				
				26				
				27				
22	30	50/5	50/5	28				
				29				
				30				
				31				
				32				
				33				
				34				
				35				
42	50/3		50/3	36				
				37				
				38				
				39				
				40				

Berlogar Stevens & Associates
1220 Quarry Lane
Pleasanton, CA 94566

BORING NUMBER RB11
 PAGE 3 OF 3

CLIENT <u>Viracocha Wind</u>	PROJECT NAME <u>Rooney/Sand Hill</u>
PROJECT NUMBER <u>4245.200</u>	PROJECT LOCATION <u>Livermore CA</u>
DATE STARTED <u>4.24.23</u> COMPLETED <u>4.24.23</u>	LOGGED BY: <u>AG</u>
DRILLING CONTRACTOR <u>Gregg</u>	GROUNDWATER: <u>AT TIME OF DRILLING ---</u>
DRILLING EQUIPMENT <u>Rotary Wash</u>	SAMPLER TYPE: <u>AT END OF DRILLING ---</u>
HAMMER <u>140lb Auto Hammer - 30" Drop</u>	 Modified California Sampler  Standard Penetration Test  Bulk Sample  Shelby Tube
NOTES <u>Turbine 24</u>	

BLOWS PER HALF FOOT			BLOWS PER FOOT	SAMPLER	DEPTH (ft)	USCS CLASSIFICATION	MATERIAL DESCRIPTION	POCKET PENETROMETER	TORVANE SHEAR STRENGTH
					40				
					41		Claystone, Olive-Brown, Moderately Weathered, Weak		
					42				
					43				
26	38	50/5	50/5		44				
					45				
					46				
					47				
					48				
					49				
					50				
					51				
50/4			50/4		52				
					53				
					54				
					55				
					56				
					57				
					58				
					59				
40	50/5		50/5		60				
							Bottom Of Hole 60.5'		

Berlogar Stevens & Associates
1220 Quarry Lane
Pleasanton, CA 94566

BORING NUMBER RB12
 PAGE 1 OF 3

CLIENT <u>Viracocha Wind</u>	PROJECT NAME <u>Rooney/Sand Hill</u>
PROJECT NUMBER <u>4245.200</u>	PROJECT LOCATION <u>Livermore CA</u>
DATE STARTED <u>4.25.23</u> COMPLETED <u>4.25.23</u>	LOGGED BY: <u>AG</u>
DRILLING CONTRACTOR <u>Gregg</u>	GROUNDWATER: <u>AT TIME OF DRILLING ---</u>
DRILLING EQUIPMENT <u>Rotary Wash</u>	SAMPLER TYPE: <u>AT END OF DRILLING ---</u>
HAMMER <u>140lb Auto Hammer - 30" Drop</u>	 Modified California Sampler  Standard Penetration Test  Bulk Sample  Shelby Tube
NOTES <u>Turbine 3</u>	

BLOWS PER HALF FOOT			BLOWS PER FOOT	SAMPLER	DEPTH (ft)	USCS CLASSIFICATION	MATERIAL DESCRIPTION	POCKET PENETROMETER	TORVANE SHEAR STRENGTH
					0				
					1	CL	Silty Sandy Clay, Brown, Dry-Moist, Med-Stiff		
					2				
					3				
8	13	26	39		4				
					5		Sandstone, Yellow-Brown, Highly Weathered, Friable		
					6				
					7				
6	20	34	54		8		Claystone, Olive-Brown, Highly Weathered, Friable		
					9				
					10				
					11				
					12				
34	50/5		50/5		13				
					14				
					15				
					16				
					17				
					18				
					19				
					20				

BORING NUMBER RB12
PAGE 2 OF 3

PROJECT NAME Rooney/Sand Hill

PROJECT LOCATION Livermore CA

LOGGED BY: AG

GROUNDWATER: AT TIME OF DRILLING ---

SAMPLER TYPE: AT END OF DRILLING ---



Modified California Sampler



Standard Penetration Test



Bulk Sample



Shelby Tube

BLOWS PER HALF FOOT			BLOWS PER FOOT	SAMPLER DEPTH (ft)	USCS CLASSIFICATION	MATERIAL DESCRIPTION	POCKET PENETROMETER	TORVANE SHEAR STRENGTH
				20	Sandstone, Red-Brown, Moderately Weathered, Weak			
50/4			50/4	21				
				22				
				23				
				24				
				25				
				26				
				27				
40	50/3		50/3	28		Claystone, Olive-Brown to Olive-Gray, Moderately Weathered, Weak		
				29				
				30				
				31				
				32				
				33				
				34				
				35				
50/5			50/5	36				
				37				
				38				
				39				
				40				

Berlogar Stevens & Associates
1220 Quarry Lane
Pleasanton, CA 94566

BORING NUMBER RB12
 PAGE 3 OF 3

CLIENT <u>Viracocha Wind</u>	PROJECT NAME <u>Rooney/Sand Hill</u>
PROJECT NUMBER <u>4245.200</u>	PROJECT LOCATION <u>Livermore CA</u>
DATE STARTED <u>4.25.23</u> COMPLETED <u>4.25.23</u>	LOGGED BY: <u>AG</u>
DRILLING CONTRACTOR <u>Gregg</u>	GROUNDWATER: <u>AT TIME OF DRILLING ---</u>
DRILLING EQUIPMENT <u>Rotary Wash</u>	SAMPLER TYPE: <u>AT END OF DRILLING ---</u>
HAMMER <u>140lb Auto Hammer - 30" Drop</u>	 Modified California Sampler  Standard Penetration Test  Bulk Sample  Shelby Tube
NOTES <u>Turbine 3</u>	

BLOWS PER HALF FOOT			BLOWS PER FOOT	SAMPLER	DEPTH (ft)	USCS CLASSIFICATION	MATERIAL DESCRIPTION	POCKET PENETROMETER	TORVANE SHEAR STRENGTH
					40				
					41		Claystone, Olive-Brown to Olive-Gray, Moderately Weathered, Weak		
					42				
					43				
50/5			50/5		44				
					45				
					46				
					47				
					48				
					49				
					50				
					51				
50/5			50/5		52				
					53				
					54				
					55				
					56				
					57				
					58				
					59				
50/5			50/5		60				
							Bottom Of Hole 60.5'		

Berlogar Stevens & Associates
1220 Quarry Lane
Pleasanton, CA 94566

BORING NUMBER RB13
 PAGE 1 OF 3

CLIENT <u>Viracocha Wind</u>	PROJECT NAME <u>Rooney/Sand Hill</u>
PROJECT NUMBER <u>4245.200</u>	PROJECT LOCATION <u>Livermore CA</u>
DATE STARTED <u>4.25.23</u> COMPLETED <u>4.25.23</u>	LOGGED BY: <u>AG</u>
DRILLING CONTRACTOR <u>Gregg</u>	GROUNDWATER: <u>AT TIME OF DRILLING ---</u>
DRILLING EQUIPMENT <u>Rotary Wash</u>	SAMPLER TYPE: <u>AT END OF DRILLING ---</u>
HAMMER <u>140lb Auto Hammer - 30" Drop</u>	 Modified California Sampler  Standard Penetration Test  Bulk Sample  Shelby Tube
NOTES <u>Turbine 4</u>	

BLOWS PER HALF FOOT			BLOWS PER FOOT	SAMPLER	DEPTH (ft)	USCS CLASSIFICATION	MATERIAL DESCRIPTION	POCKET PENETROMETER	TORVANE SHEAR STRENGTH
					0				
					1	CL	Silty Sandy Clay, Brown, Dry, Med-Stiff		
					2		Claystone, Olive-Brown, Moderately Weathered, Weak		
2	3	9	12		3				
					4				
					5				
					6				
					7				
5	14	27	41		8				
					9				
					10				
					11				
					12				
13	19	24	43		13				
					14				
					15				
					16				
					17				
					18				
					19				
					20				

Berlogar Stevens & Associates
1220 Quarry Lane
Pleasanton, CA 94566

BORING NUMBER RB13
 PAGE 2 OF 3

CLIENT <u>Viracocha Wind</u>	PROJECT NAME <u>Rooney/Sand Hill</u>
PROJECT NUMBER <u>4245.200</u>	PROJECT LOCATION <u>Livermore CA</u>
DATE STARTED <u>4.25.23</u> COMPLETED <u>4.25.23</u>	LOGGED BY: <u>AG</u>
DRILLING CONTRACTOR <u>Gregg</u>	GROUNDWATER: <u>AT TIME OF DRILLING ---</u>
DRILLING EQUIPMENT <u>Rotary Wash</u>	SAMPLER TYPE: <u>AT END OF DRILLING ---</u>
HAMMER <u>140lb Auto Hammer - 30" Drop</u>	 Modified California Sampler  Standard Penetration Test  Bulk Sample  Shelby Tube
NOTES <u>Turbine 4</u>	

BLOWS PER HALF FOOT			BLOWS PER FOOT	SAMPLER	DEPTH (ft)	USCS CLASSIFICATION	MATERIAL DESCRIPTION	POCKET PENETROMETER	TORVANE SHEAR STRENGTH
					20				
23	25	25	50		21		Claystone, Olive-Brown to Olive-Gray, Moderately Weathered, Weak		
					22				
					23				
					24				
					25				
					26				
					27				
50/1			50/1		28				
					29				
					30				
					31				
					32				
					33				
					34				
					35				
17	9	30	39		36				
					37				
					38				
					39				
					40				

Berlogar Stevens & Associates
1220 Quarry Lane
Pleasanton, CA 94566

BORING NUMBER RB13
 PAGE 3 OF 3

CLIENT <u>Viracocha Wind</u>	PROJECT NAME <u>Rooney/Sand Hill</u>
PROJECT NUMBER <u>4245.200</u>	PROJECT LOCATION <u>Livermore CA</u>
DATE STARTED <u>4.25.23</u> COMPLETED <u>4.25.23</u>	LOGGED BY: <u>AG</u>
DRILLING CONTRACTOR <u>Gregg</u>	GROUNDWATER: <u>AT TIME OF DRILLING ---</u>
DRILLING EQUIPMENT <u>Rotary Wash</u>	SAMPLER TYPE: <u>AT END OF DRILLING ---</u>
HAMMER <u>140lb Auto Hammer - 30" Drop</u>	 Modified California Sampler  Standard Penetration Test  Bulk Sample  Shelby Tube
NOTES <u>Turbine 4</u>	

BLOWS PER HALF FOOT			BLOWS PER FOOT	SAMPLER	DEPTH (ft)	USCS CLASSIFICATION	MATERIAL DESCRIPTION	POCKET PENETROMETER	TORVANE SHEAR STRENGTH
					40				
					41		Claystone, Olive-Brown, Moderately Weathered, Weak		
					42				
					43				
50/3			50/3		44				
					45				
					46				
					47				
					48				
					49				
					50				
					51				
50/3			50/3		52				
					53				
					54				
					55				
					56				
					57				
					58				
					59				
50/3			50/3		60				
							Bottom Of Hole 60.5'		

Berlogar Stevens & Associates
1220 Quarry Lane
Pleasanton, CA 94566

BORING NUMBER RB14
 PAGE 1 OF 3

CLIENT <u>Viracocha Wind</u>	PROJECT NAME <u>Rooney/Sand Hill</u>
PROJECT NUMBER <u>4245.200</u>	PROJECT LOCATION <u>Livermore CA</u>
DATE STARTED <u>4.26.23</u> COMPLETED <u>4.26.23</u>	LOGGED BY: <u>AG</u>
DRILLING CONTRACTOR <u>Gregg</u>	GROUNDWATER: <u>AT TIME OF DRILLING ---</u>
DRILLING EQUIPMENT <u>Rotary Wash</u>	SAMPLER TYPE: <u>AT END OF DRILLING ---</u>
HAMMER <u>140lb Auto Hammer - 30" Drop</u>	 Modified California Sampler  Standard Penetration Test  Bulk Sample  Shelby Tube
NOTES <u>Turbine 5</u>	

BLOWS PER HALF FOOT			BLOWS PER FOOT	SAMPLER	DEPTH (ft)	USCS CLASSIFICATION	MATERIAL DESCRIPTION	POCKET PENETROMETER	TORVANE SHEAR STRENGTH
					0				
					1	CL	Silty Sandy Clay, Brown, Dry, Soft		
					2				
6	5	6	11		3				
					4				
					5				
					6				
					7				
14	28	38	66		8		Claystone, Olive-Brown, Highly Weathered, Friable		
					9				
					10				
					11				
					12				
33	46	50/5	50/5		13				
					14				
					15				
					16				
					17				
					18				
					19				
					20				

BORING NUMBER RB14
PAGE 2 OF 3

PROJECT NAME Rooney/Sand Hill

PROJECT LOCATION Livermore CA

LOGGED BY: AG

GROUNDWATER: AT TIME OF DRILLING ---

SAMPLER TYPE: AT END OF DRILLING ---



Modified California Sampler



Standard Penetration Test



Bulk Sample



Shelby
Tube

BLOWS PER HALF FOOT			BLOWS PER FOOT	SAMPLER DEPTH (ft)	USCS CLASSIFICATION	MATERIAL DESCRIPTION	POCKET PENETROMETER	TORVANE SHEAR STRENGTH
				20				
50/5			50/5	21		No recovery		
				22				
				23				
				24				
				25				
				26				
				27				
				28		Claystone, Olive-Gray to Olive-Brown, Moderately Weathered, Weak		
50/4			50/4	29				
				30				
				31				
				32				
				33				
				34				
				35				
50/4			50/4	36				
				37				
				38				
				39				
				40				

Berlogar Stevens & Associates
1220 Quarry Lane
Pleasanton, CA 94566

BORING NUMBER RB14
 PAGE 3 OF 3

CLIENT <u>Viracocha Wind</u>	PROJECT NAME <u>Rooney/Sand Hill</u>
PROJECT NUMBER <u>4245.200</u>	PROJECT LOCATION <u>Livermore CA</u>
DATE STARTED <u>4.26.23</u> COMPLETED <u>4.26.23</u>	LOGGED BY: <u>AG</u>
DRILLING CONTRACTOR <u>Gregg</u>	GROUNDWATER: <u>AT TIME OF DRILLING ---</u>
DRILLING EQUIPMENT <u>Rotary Wash</u>	SAMPLER TYPE: <u>AT END OF DRILLING ---</u>
HAMMER <u>140lb Auto Hammer - 30" Drop</u>	 Modified California Sampler  Standard Penetration Test  Bulk Sample  Shelby Tube
NOTES <u>Turbine 5</u>	

BLOWS PER HALF FOOT			BLOWS PER FOOT	SAMPLER	DEPTH (ft)	USCS CLASSIFICATION	MATERIAL DESCRIPTION	POCKET PENETROMETER	TORVANE SHEAR STRENGTH
					40				
					41				
					42				
					43				
50/4			50/4		44		Claystone, Olive-Brown, Moderately Weathered, Weak		
					45				
					46				
					47				
					48				
					49				
					50				
					51				
18	21	26	47		52				
					53				
					54				
					55				
					56				
					57				
					58				
					59				
50/1			50/1		60				
							Bottom Of Hole 60.5'		

Berlogar Stevens & Associates
1220 Quarry Lane
Pleasanton, CA 94566

BORING NUMBER RB15
 PAGE 1 OF 3

CLIENT <u>Viracocha Wind</u>	PROJECT NAME <u>Rooney/Sand Hill</u>
PROJECT NUMBER <u>4245.200</u>	PROJECT LOCATION <u>Livermore CA</u>
DATE STARTED <u>4.26.23</u> COMPLETED <u>4.26.23</u>	LOGGED BY: <u>AG</u>
DRILLING CONTRACTOR <u>Gregg</u>	GROUNDWATER: <u>AT TIME OF DRILLING ---</u>
DRILLING EQUIPMENT <u>Rotary Wash</u>	SAMPLER TYPE: <u>AT END OF DRILLING ---</u>
HAMMER <u>140lb Auto Hammer - 30" Drop</u>	 Modified California Sampler  Standard Penetration Test  Bulk Sample  Shelby Tube
NOTES <u>Turbine 6</u>	

BLOWS PER HALF FOOT			BLOWS PER FOOT	SAMPLER	DEPTH (ft)	USCS CLASSIFICATION	MATERIAL DESCRIPTION	POCKET PENETROMETER	TORVANE SHEAR STRENGTH
					0				
					1	CL	Silty Sandy Clay, Brown, Dry, Med-Stiff		
					2				
3	13	9	22		3				
					4				
					5				
					6				
					7				
9	5	13	18		8		Claystone, Olive-Brown, Highly Weathered, Friable		
					9				
					10				
					11				
					12				
34	50/4		50/4		13				
					14				
					15				
					16				
					17				
					18				
					19				
					20				

Berlogar Stevens & Associates
1220 Quarry Lane
Pleasanton, CA 94566

BORING NUMBER RB15
 PAGE 2 OF 3

CLIENT <u>Viracocha Wind</u>	PROJECT NAME <u>Rooney/Sand Hill</u>
PROJECT NUMBER <u>4245.200</u>	PROJECT LOCATION <u>Livermore CA</u>
DATE STARTED <u>4.26.23</u> COMPLETED <u>4.26.23</u>	LOGGED BY: <u>AG</u>
DRILLING CONTRACTOR <u>Gregg</u>	GROUNDWATER: <u>AT TIME OF DRILLING ---</u>
DRILLING EQUIPMENT <u>Rotary Wash</u>	SAMPLER TYPE: <u>AT END OF DRILLING ---</u>
HAMMER <u>140lb Auto Hammer - 30" Drop</u>	 Modified California Sampler  Standard Penetration Test  Bulk Sample  Shelby Tube
NOTES <u>Turbine 6</u>	

BLOWS PER HALF FOOT			BLOWS PER FOOT	SAMPLER	DEPTH (ft)	USCS CLASSIFICATION	MATERIAL DESCRIPTION	POCKET PENETROMETER	TORVANE SHEAR STRENGTH
					20				
22	50/6		50/6		21		Claystone, Olive-Brown, Moderately Weathered, Weak		
					22				
					23				
					24				
					25				
					26				
					27				
31	39	39	78		28				
					29				
					30				
					31				
					32				
					33				
					34				
					35				
50/6			50/6		36				
					37				
					38				
					39				
					40				

Berlogar Stevens & Associates
1220 Quarry Lane
Pleasanton, CA 94566

BORING NUMBER RB15
 PAGE 3 OF 3

CLIENT <u>Viracocha Wind</u>	PROJECT NAME <u>Rooney/Sand Hill</u>
PROJECT NUMBER <u>4245.200</u>	PROJECT LOCATION <u>Livermore CA</u>
DATE STARTED <u>4.26.23</u> COMPLETED <u>4.26.23</u>	LOGGED BY: <u>AG</u>
DRILLING CONTRACTOR <u>Gregg</u>	GROUNDWATER: <u>AT TIME OF DRILLING ---</u>
DRILLING EQUIPMENT <u>Rotary Wash</u>	SAMPLER TYPE: <u>AT END OF DRILLING ---</u>
HAMMER <u>140lb Auto Hammer - 30" Drop</u>	 Modified California Sampler  Standard Penetration Test  Bulk Sample  Shelby Tube
NOTES <u>Turbine 6</u>	

BLOWS PER HALF FOOT			BLOWS PER FOOT	SAMPLER	DEPTH (ft)	USCS CLASSIFICATION	MATERIAL DESCRIPTION	POCKET PENETROMETER	TORVANE SHEAR STRENGTH
					40				
					41				
					42				
46	50/3		50/3		43		Claystone, Olive-Brown, Moderately Weathered, Weak		
					44				
					45				
					46				
					47				
					48				
					49				
					50				
					51				
50/6			50/6		52				
					53				
					54				
					55				
					56				
					57				
					58				
					59				
50/5			50/5		60				
							Bottom Of Hole 60.5'		

Berlogar Stevens & Associates
1220 Quarry Lane
Pleasanton, CA 94566

BORING NUMBER RB16
 PAGE 1 OF 3

CLIENT <u>Viracocha Wind</u>	PROJECT NAME <u>Rooney/Sand Hill</u>
PROJECT NUMBER <u>4245.200</u>	PROJECT LOCATION <u>Livermore CA</u>
DATE STARTED <u>4.27.23</u> COMPLETED <u>4.27.23</u>	LOGGED BY: <u>AG</u>
DRILLING CONTRACTOR <u>Gregg</u>	GROUNDWATER: <u>AT TIME OF DRILLING ---</u>
DRILLING EQUIPMENT <u>Rotary Wash</u>	SAMPLER TYPE: <u>AT END OF DRILLING ---</u>
HAMMER <u>140lb Auto Hammer - 30" Drop</u>	 Modified California Sampler  Standard Penetration Test  Bulk Sample  Shelby Tube
NOTES <u>Turbine 7</u>	

BLOWS PER HALF FOOT			BLOWS PER FOOT	SAMPLER	DEPTH (ft)	USCS CLASSIFICATION	MATERIAL DESCRIPTION	POCKET PENETROMETER	TORVANE SHEAR STRENGTH
					0				
					1	CL	Silty Sandy Clay, Brown, Dry, Med-Stiff		
					2				
2	8	7	15		3				
					4		Claystone, Olive-Brown, Moderately Weathered, Weak		
					5				
					6				
					7				
3	10	9	19		8				
					9				
					10				
					11				
					12				
11	20	24	44		13				
					14				
					15				
					16				
					17				
					18				
					19				
					20				

Berlogar Stevens & Associates
1220 Quarry Lane
Pleasanton, CA 94566

BORING NUMBER RB16
 PAGE 2 OF 3

CLIENT <u>Viracocha Wind</u>	PROJECT NAME <u>Rooney/Sand Hill</u>
PROJECT NUMBER <u>4245.200</u>	PROJECT LOCATION <u>Livermore CA</u>
DATE STARTED <u>4.27.23</u> COMPLETED <u>4.27.23</u>	LOGGED BY: <u>AG</u>
DRILLING CONTRACTOR <u>Gregg</u>	GROUNDWATER: <u>AT TIME OF DRILLING ---</u>
DRILLING EQUIPMENT <u>Rotary Wash</u>	SAMPLER TYPE: <u>AT END OF DRILLING ---</u>
HAMMER <u>140lb Auto Hammer - 30" Drop</u>	 Modified California Sampler  Standard Penetration Test  Bulk Sample  Shelby Tube
NOTES <u>Turbine 7</u>	

BLOWS PER HALF FOOT			BLOWS PER FOOT	SAMPLER	DEPTH (ft)	USCS CLASSIFICATION	MATERIAL DESCRIPTION	POCKET PENETROMETER	TORVANE SHEAR STRENGTH
					20				
22	30	32	62		21		Claystone, Olive-Brown, Moderately Weathered, Weak		
					22				
					23				
					24				
					25				
					26				
					27				
26	47	50/5	50/5		28				
					29				
					30				
					31				
					32				
					33				
					34				
					35				
50/5			50/5		36				
					37				
					38				
					39				
					40				

Berlogar Stevens & Associates
1220 Quarry Lane
Pleasanton, CA 94566

BORING NUMBER RB16
 PAGE 3 OF 3

CLIENT <u>Viracocha Wind</u>	PROJECT NAME <u>Rooney/Sand Hill</u>
PROJECT NUMBER <u>4245.200</u>	PROJECT LOCATION <u>Livermore CA</u>
DATE STARTED <u>4.27.23</u> COMPLETED <u>4.27.23</u>	LOGGED BY: <u>AG</u>
DRILLING CONTRACTOR <u>Gregg</u>	GROUNDWATER: <u>AT TIME OF DRILLING ---</u>
DRILLING EQUIPMENT <u>Rotary Wash</u>	SAMPLER TYPE: <u>AT END OF DRILLING ---</u>
HAMMER <u>140lb Auto Hammer - 30" Drop</u>	 Modified California Sampler  Standard Penetration Test  Bulk Sample  Shelby Tube
NOTES <u>Turbine 7</u>	

BLOWS PER HALF FOOT			BLOWS PER FOOT	SAMPLER	DEPTH (ft)	USCS CLASSIFICATION	MATERIAL DESCRIPTION	POCKET PENETROMETER	TORVANE SHEAR STRENGTH
					40				
					41		Claystone, Olive-Brown, Moderately Weathered, Weak		
					42				
					43				
29	50/5		50/5		44				
					45				
					46				
					47				
					48				
					49				
					50				
					51				
31	46	50/4	50/4		52				
					53				
					54				
					55				
					56				
					57				
					58				
					59				
41	50/3		50/3		60				
							Bottom Of Hole 60.5'		

BORING NUMBER RB17
PAGE 1 OF 3

Modified California Sampler Standard Penetration Test Bulk Sample Shelby Tube

BLOWS PER HALF FOOT			BLOWS PER FOOT	SAMPLER DEPTH (ft)	USCS CLASSIFICATION	MATERIAL DESCRIPTION	POCKET PENETROMETER	TORVANE SHEAR STRENGTH	
				0	CL	Silty Sandy Clay, Brown, Dry, Soft			
				1					
				2					
5	9	15	24	3		Claystone, Olive-Brown, Highly Weathered, Friable			
				4					
				5					
				6					
				7					
15	21	27	48	8					
				9					
				10					
				11					
				12					
20	31	43	74	13					
				14					
				15					
				16					
				17					
				18					
				19					
				20					

Berlogar Stevens & Associates
1220 Quarry Lane
Pleasanton, CA 94566

BORING NUMBER RB17
 PAGE 2 OF 3

CLIENT <u>Viracocha Wind</u>	PROJECT NAME <u>Rooney/Sand Hill</u>
PROJECT NUMBER <u>4245.200</u>	PROJECT LOCATION <u>Livermore CA</u>
DATE STARTED <u>4.27.23</u> COMPLETED <u>4.27.23</u>	LOGGED BY: <u>AG</u>
DRILLING CONTRACTOR <u>Gregg</u>	GROUNDWATER: <u>AT TIME OF DRILLING ---</u>
DRILLING EQUIPMENT <u>Rotary Wash</u>	SAMPLER TYPE: <u>AT END OF DRILLING ---</u>
HAMMER <u>140lb Auto Hammer - 30" Drop</u>	 Modified California Sampler  Standard Penetration Test  Bulk Sample  Shelby Tube
NOTES <u>Turbine 9</u>	

BLOWS PER HALF FOOT			BLOWS PER FOOT	SAMPLER	DEPTH (ft)	USCS CLASSIFICATION	MATERIAL DESCRIPTION	POCKET PENETROMETER	TORVANE SHEAR STRENGTH
					20				
27	33	41	54		21		Claystone, Olive-Brown, Moderately Weathered, Weak		
					22				
					23				
					24				
					25				
					26				
					27				
28	38	50/6	50/6		28				
					29				
					30				
					31				
					32				
					33				
					34				
					35				
25	39	39	78		36				
					37				
					38				
					39				
					40				

Berlogar Stevens & Associates
1220 Quarry Lane
Pleasanton, CA 94566

BORING NUMBER RB17
 PAGE 3 OF 3

CLIENT <u>Viracocha Wind</u>	PROJECT NAME <u>Rooney/Sand Hill</u>
PROJECT NUMBER <u>4245.200</u>	PROJECT LOCATION <u>Livermore CA</u>
DATE STARTED <u>4.27.23</u> COMPLETED <u>4.27.23</u>	LOGGED BY: <u>AG</u>
DRILLING CONTRACTOR <u>Gregg</u>	GROUNDWATER: <u>AT TIME OF DRILLING ---</u>
DRILLING EQUIPMENT <u>Rotary Wash</u>	SAMPLER TYPE: <u>AT END OF DRILLING ---</u>
HAMMER <u>140lb Auto Hammer - 30" Drop</u>	 Modified California Sampler  Standard Penetration Test  Bulk Sample  Shelby Tube
NOTES <u>Turbine 9</u>	

BLOWS PER HALF FOOT			BLOWS PER FOOT	SAMPLER	DEPTH (ft)	USCS CLASSIFICATION	MATERIAL DESCRIPTION	POCKET PENETROMETER	TORVANE SHEAR STRENGTH
					40				
					41		Claystone, Olive-Brown, Moderately Weathered, Weak		
					42				
					43				
					44				
50/6			50/6		45				
					46				
					47				
					48				
					49				
					50				
					51		Claystone, Gray, Moderately Weathered, Weak		
50/5			50/5		52				
					53				
					54				
					55				
					56				
					57				
					58				
					59				
50/3			50/3		60				
							Bottom Of Hole 60.5'		

Berlogar Stevens & Associates
1220 Quarry Lane
Pleasanton, CA 94566

BORING NUMBER RB18
 PAGE 1 OF 3

CLIENT <u>Viracocha Wind</u>	PROJECT NAME <u>Rooney/Sand Hill</u>
PROJECT NUMBER <u>4245.200</u>	PROJECT LOCATION <u>Livermore CA</u>
DATE STARTED <u>4.27.23</u> COMPLETED <u>4.27.23</u>	LOGGED BY: <u>AG</u>
DRILLING CONTRACTOR <u>Gregg</u>	GROUNDWATER: <u>AT TIME OF DRILLING ---</u>
DRILLING EQUIPMENT <u>Rotary Wash</u>	SAMPLER TYPE: <u>AT END OF DRILLING ---</u>
HAMMER <u>140lb Auto Hammer - 30" Drop</u>	 Modified California Sampler  Standard Penetration Test  Bulk Sample  Shelby Tube
NOTES <u>Turbine 8</u>	

BLOWS PER HALF FOOT			BLOWS PER FOOT	SAMPLER	DEPTH (ft)	USCS CLASSIFICATION	MATERIAL DESCRIPTION	POCKET PENETROMETER	TORVANE SHEAR STRENGTH
					0				
					1	CL	Silty Sandy Clay, Dark Brown, Dry-Moist, Med-Stiff		
					2				
7	7	10	17		3				
					4				
					5				
					6				
					7				
10	24	35	59		8	CL	Claystone, Olive-Brown, Highly Weathered, Friable		
					9				
					10				
					11				
					12				
26	35	40	75		13				
					14				
					15				
					16				
					17				
					18				
					19				
					20				

Berlogar Stevens & Associates
1220 Quarry Lane
Pleasanton, CA 94566

BORING NUMBER RB18
 PAGE 2 OF 3

CLIENT <u>Viracocha Wind</u>	PROJECT NAME <u>Rooney/Sand Hill</u>
PROJECT NUMBER <u>4245.200</u>	PROJECT LOCATION <u>Livermore CA</u>
DATE STARTED <u>4.27.23</u> COMPLETED <u>4.27.23</u>	LOGGED BY: <u>AG</u>
DRILLING CONTRACTOR <u>Gregg</u>	GROUNDWATER: <u>AT TIME OF DRILLING ---</u>
DRILLING EQUIPMENT <u>Rotary Wash</u>	SAMPLER TYPE: <u>AT END OF DRILLING ---</u>
HAMMER <u>140lb Auto Hammer - 30" Drop</u>	 Modified California Sampler  Standard Penetration Test  Bulk Sample  Shelby Tube
NOTES <u>Turbine 8</u>	

BLOWS PER HALF FOOT			BLOWS PER FOOT	SAMPLER	DEPTH (ft)	USCS CLASSIFICATION	MATERIAL DESCRIPTION	POCKET PENETROMETER	TORVANE SHEAR STRENGTH
					20				
50/1			50/1		21		Sandstone, Red-Brown, Moderately Weathered, Weak		
					22				
					23				
					24				
					25				
					26				
					27				
50/5			50/5		28				
					29				
					30				
					31				
					32				
					33				
					34				
					35				
50/6			50/6		36				
					37				
					38				
					39				
					40				

Berlogar Stevens & Associates
1220 Quarry Lane
Pleasanton, CA 94566

BORING NUMBER RB18
 PAGE 3 OF 3

CLIENT <u>Viracocha Wind</u>	PROJECT NAME <u>Rooney/Sand Hill</u>
PROJECT NUMBER <u>4245.200</u>	PROJECT LOCATION <u>Livermore CA</u>
DATE STARTED <u>4.27.23</u> COMPLETED <u>4.27.23</u>	LOGGED BY: <u>AG</u>
DRILLING CONTRACTOR <u>Gregg</u>	GROUNDWATER: <u>AT TIME OF DRILLING ---</u>
DRILLING EQUIPMENT <u>Rotary Wash</u>	SAMPLER TYPE: <u>AT END OF DRILLING ---</u>
HAMMER <u>140lb Auto Hammer - 30" Drop</u>	 Modified California Sampler  Standard Penetration Test  Bulk Sample  Shelby Tube
NOTES <u>Turbine 8</u>	

BLOWS PER HALF FOOT			BLOWS PER FOOT	SAMPLER	DEPTH (ft)	USCS CLASSIFICATION	MATERIAL DESCRIPTION	POCKET PENETROMETER	TORVANE SHEAR STRENGTH
					40		Claystone, Olive-Brown, Moderately Weathered, Weak		
					41				
					42				
					43				
					44				
50/5			50/5		45				
					46				
					47				
					48				
					49				
					50				
					51		No recovery		
39	50/5		50/5		52				
					53				
					54				
					55				
					56				
					57				
					58				
					59		No recovery		
50/4			50/4		60				
							Bottom Of Hole 60.5'		

APPENDIX C

Hollow Stem Logs

Berlogar Stevens & Associates
1220 Quarry Lane
Pleasanton, CA 94566

BORING NUMBER B-1

PAGE 1 OF 1

CLIENT Viracocha Wind

PROJECT NAME Rooney/Sand Hill

PROJECT NUMBER 4245.200

PROJECT LOCATION Livermore CA

DATE STARTED 3.15.23 COMPLETED 3.15.23

LOGGED BY: AG

DRILLING CONTRACTOR Gregg

GROUNDWATER: AT TIME OF DRILLING ---

DRILLING EQUIPMENT Rhino

SAMPLER TYPE: AT END OF DRILLING ---

HAMMER DH103


 Modified California Sampler

 Standard Penetration Test

 Bulk Sample

 Shelby Tube

NOTES AML Substation

BLOWS PER HALF FOOT			BLOWS PER FOOT	SAMPLER	DEPTH (ft)	USCS CLASSIFICATION	MATERIAL DESCRIPTION	POCKET PENETROMETER	TORVANE SHEAR STRENGTH
					0				
Hand auger to 3.5'					1	CL	6" of crushed rock		
					2		Sandy Clay, Med-Brown, Dry-Moist, Med-Stiff (Fill)		
					3				
					4				
50/6			50/6		5		Claystone, Olive-Brown, Highly weathered, Weak		
					6		Sandstone, Yellow-Brown, Highly Weathered, Friable		
					7				
					8				
50/2			50/2		9				
					10				
					11				
					12				
					13				
50/6			50/6		14				
					15		Bottom of Hole 15'		
					16				
					17				
					18				
					19				
					20				

BORING NUMBER B-2
PAGE 1 OF 2

PROJECT NAME Rooney/Sand Hill

PROJECT LOCATION Livermore CA

LOGGED BY: AG

GROUNDWATER: AT TIME OF DRILLING ---

SAMPLER TYPE: AT END OF DRILLING ---

 Modified California Sampler

 Standard Penetration Test

 Bulk Sample

 Shelby Tube

BLOWS PER HALF FOOT			BLOWS PER FOOT	SAMPLER DEPTH (ft)	USCS CLASSIFICATION	MATERIAL DESCRIPTION	POCKET PENETROMETER	TORVANE SHEAR STRENGTH
				0				
Hand auger to 3.5'				1	CL	6" of crushed rock		
				2		Sandy Clay, Med-Brown, Dry-Moist, Med-Stiff (Fill)		
				3		Claystone, Olive-Brown, Highly weathered, Weak		
				4				
				5				
				6				
9	26	30	56	7				
				8				
				9				
				10				
				11				
				12		Sandstone, Yellow-Brown, Highly weathered, Friable		
				13				
				14				
				15				
				16				
				17				
				18				
				19				
				20				
				21				
				22				
				23				
				24				
				25				
				26				
				27				
				28				
				29				
				30				
				31				
				32				
				33				
				34				
				35				
				36				
				37				
				38				
				39				
				40				
				41				
				42				
				43				
				44				
				45				
				46				
				47				
				48				
				49				
				50				
				51				
				52				
				53				
				54				
				55				
				56				
				57				
				58				
				59				
				60				
				61				
				62				
				63				
				64				
				65				
				66				
				67				
				68				
				69				
				70				
				71				
				72				
				73				
				74				
				75				
				76				
				77				
				78				
				79				
				80				
				81				
				82				
				83				
				84				
				85				
				86				
				87				
				88				
				89				
				90				
				91				
				92				
				93				
				94				
				95				
				96				
				97				
				98				
				99				
				100				
				101				
				102				
				103				
				104				
				105				
				106				
				107				
				108				
				109				
				110				
				111				
				112				
				113				
				114				
				115				
				116				
				117				
				118				
				119				
				120				
				121				
				122				
				123				
				124				
				125				
				126				
				127				
				128				
				129				
				130				
				131				
				132				
				133				
				134				
				135				
				136				
				137				
				138				
				139				
				140				
				141				
				142				
				143				
				144				
				145				
				146				
				147				
				148				
				149				
				150				
				151				
				152				
				153				
				154				
				155				
				156				
				157				
				158				
				159				
				160				
				161				
				162				
				163				
				164				
				165				
				166				
				167				
				168				
				169				
				170				
				171				
				172				
				173				
				174				
				175				
				176				
				177				
				178				
				179				
				180				
				181				
				182				
				183				
				184				
				185				
				186				
				187				
				188				
				189				
				190				
				191				
				192				
				193				
				194				
				195				
				196				
				197				
				198				
				199				
				200				
				201				
				202				
				203				
				204				
				205				
				206				
				207				
				208				
				209				
				210				
				211				
				212				
				213				
				214				
				215				
				216				
				217				
				218				
				219				
				220				
				221				
				222				
				223				
				224				
				225				
				226				
				227				
				228				
				229				
				230				
				231				
				232				
				233				
				234				
				235				
				236				
				237				
				238				
				239				
				240				
				241				
				242				
				243				
				244				
				245				
				246				
				247				
				248				
				249				
				250				
				251				
				252				
				253				
				254				
				255				
				256				
				257				
				258				
				259				
				260				
				261				
				262				
				263				
				264				
				265				
				266				
				267				
				268				
				269				
				270				
				271				
				272				
				273				
				274				
				275				
				276				
				277				
				278				
				279				
				280				
				281				
				282				
				283				
				284				
				285				
				286				
				287				
				288				
				289				
				290				
				291				
				292				
				293				
				29				

BORING NUMBER B-2
PAGE 2 OF 2

PROJECT NAME Rooney/Sand Hill

PROJECT LOCATION Livermore CA

LOGGED BY: AG

GROUNDWATER: AT TIME OF DRILLING ---

SAMPLER TYPE: AT END OF DRILLING ---

 Modified California Sampler

 Standard Penetration Test

 Bulk Sample

 Shelby Tube

BLOWS PER HALF FOOT			BLOWS PER FOOT	SAMPLER DEPTH (ft)	USCS CLASSIFICATION	MATERIAL DESCRIPTION	POCKET PENETROMETER	TORVANE SHEAR STRENGTH
				20				
				21				
				22		Claystone, Gray, Highly weathered, Friable		
				23				
				24				
37	50/3		50/3	25		Claystone, Olive-Brown, Highly weathered, Weak		
				26		Bottom of Hole 25'		
				27				
				28				
				29				
				30				
				31				
				32				
				33				
				34				
				35				
				36				
				37				
				38				
				39				
				40				

Berlogar Stevens & Associates
1220 Quarry Lane
Pleasanton, CA 94566

BORING NUMBER B-3

PAGE 1 OF 1

CLIENT Viracocha Wind PROJECT NAME Rooney/Sand Hill
 PROJECT NUMBER 4245.200 PROJECT LOCATION Livermore CA
 DATE STARTED 3.15.23 COMPLETED 3.15.23 LOGGED BY: AG
 DRILLING CONTRACTOR Gregg GROUNDWATER: AT TIME OF DRILLING ---
 DRILLING EQUIPMENT Rhino SAMPLER TYPE: AT END OF DRILLING ---
 HAMMER DH103
 NOTES AML Substation



Modified California
Sampler



Standard
Penetration Test



Bulk Sample



Shelby
Tube

BLOWS PER HALF FOOT			BLOWS PER FOOT	SAMPLER	DEPTH (ft)	USCS CLASSIFICATION	MATERIAL DESCRIPTION	POCKET PENETROMETER	TORVANE SHEAR STRENGTH
					0				
Hand auger to 3.5'					1	CL	6" of crushed rock		
							Sandy Clay, Med-Brown, Dry-Moist, Med-Stiff (Fill)		
					2				
					3		Sandstone, Yellow-Brown, Highly Weathered, Friable		
12	40	50/3	50/3		4				
					5				
					6				
					7				
					8				
17	50/5		50/5		9				
					10		Bottom of Hole 10'		
					11				
					12				
					13				
					14				
					15				
					16				
					17				
					18				
					19				
					20				

Berlogar Stevens & Associates
1220 Quarry Lane
Pleasanton, CA 94566

BORING NUMBER B-4

PAGE 1 OF 2

CLIENT <u>Viracocha Wind</u>	PROJECT NAME <u>Rooney/Sand Hill</u>
PROJECT NUMBER <u>4245.200</u>	PROJECT LOCATION <u>Livermore CA</u>
DATE STARTED <u>3.15.23</u> COMPLETED <u>3.15.23</u>	LOGGED BY: <u>AG</u>
DRILLING CONTRACTOR <u>Gregg</u>	GROUNDWATER: <u>AT TIME OF DRILLING ---</u>
DRILLING EQUIPMENT <u>Rhino</u>	SAMPLER TYPE: <u>AT END OF DRILLING ---</u>
HAMMER <u>DH103</u>	 Modified California Sampler  Standard Penetration Test  Bulk Sample  Shelby Tube
NOTES <u>Zond Substation</u>	

BLOWS PER HALF FOOT			BLOWS PER FOOT	SAMPLER	DEPTH (ft)	USCS CLASSIFICATION	MATERIAL DESCRIPTION	POCKET PENETROMETER	TORVANE SHEAR STRENGTH
					0				
Hand auger to 3.5'					1	SC	6" of crushed rock		
					2		Silty Clayey Sand, Brown, Moist-Wet, Med-Dense		
					3				
					4				
8	9	13	22		5				
					6				
					7				
					8				
3	3	5	8		9				
					10				
					11				
					12				
					13				
2	2	1	3		14				
					15				
					16				
					17				
					18				
3	3	2	5		19		Claystone, Gray, Highly weathered, Friable		
					20				
							Bottom of Hole 20 Feet		

Berlogar Stevens & Associates
1220 Quarry Lane
Pleasanton, CA 94566

BORING NUMBER B-4
 PAGE 2 OF 2

CLIENT <u>Viracocha Wind</u>	PROJECT NAME <u>Rooney/Sand Hill</u>
PROJECT NUMBER <u>4245.200</u>	PROJECT LOCATION <u>Livermore CA</u>
DATE STARTED <u>3.15.23</u> COMPLETED <u>3.15.23</u>	LOGGED BY: <u>AG</u>
DRILLING CONTRACTOR <u>Gregg</u>	GROUNDWATER: <u>AT TIME OF DRILLING ---</u>
DRILLING EQUIPMENT <u>Rhino</u>	SAMPLER TYPE: <u>AT END OF DRILLING ---</u>
HAMMER <u>DH103</u>	 Modified California Sampler  Standard Penetration Test  Bulk Sample  Shelby Tube
NOTES <u>Zond Substation</u>	

BLOWS PER HALF FOOT			BLOWS PER FOOT	SAMPLER	DEPTH (ft)	USCS CLASSIFICATION	MATERIAL DESCRIPTION	POCKET PENETROMETER	TORVANE SHEAR STRENGTH
					20				
					21	SC	Silty Clayey Sand, Brown, Moist-Wet, Med-Dense		
					22				
					23				
2	3	7	10		24				
					25				
					26				
					27				
50/6			50/6		28		Claystone, Olive-Brown, Highly weathered, Weak		
					29				
					30				
					31				
					32				
50/3			50/3		33				
					34				
					35		Bottom of Hole 35'		
					36				
					37				
					38				
					39				
					40				

BORING NUMBER B-5
PAGE 1 OF 2

PROJECT NAME Rooney / Sand Hill

PROJECT LOCATION Livermore, CA

LOGGED BY: AG

GROUNDWATER: AT TIME OF DRILLING ---

SAMPLER TYPE: AT END OF DRILLING ---

 Modified California Sampler

 Standard Penetration Test

 Bulk Sample

 Shelby Tube

BLOWS PER HALF FOOT			BLOWS PER FOOT	SAMPLER DEPTH (ft)	USCS CLASSIFICATION	MATERIAL DESCRIPTION	POCKET PENETROMETER	TORVANE SHEAR STRENGTH
				0				
HAND AUGER TO 3.5'					SC	6 INCHES / CRUSHED ROCK		
				1		YELLOW-		
				2		SILTY CLAYEY SAND, BROWN, MOIST-WET, MED-DENSE		
				3				
5	8	10	18	4				
				5				
				6				
				7				
				8				
5	7	11	18	9				
				10				
				11				
				12				
				13				
7	9	9	18	14				
				15				
				16				
				17				
				18				
1	1	3	4	19				
				20				

Berlogar Stevens & Associates
1220 Quarry Lane
Pleasanton, CA 94566

BORING NUMBER B-5
 PAGE 2 OF 2

CLIENT <u>Viracocha Wind</u>	PROJECT NAME <u>Rooney / Sand Hill</u>
PROJECT NUMBER <u>4245.200</u>	PROJECT LOCATION <u>Location</u>
DATE STARTED <u>3-16-23</u> COMPLETED <u>3-16-23</u>	LOGGED BY: <u>AG</u>
DRILLING CONTRACTOR <u>Gregg</u>	GROUNDWATER: <u>AT TIME OF DRILLING ---</u>
DRILLING EQUIPMENT <u>Rhino</u>	SAMPLER TYPE: <u>AT END OF DRILLING ---</u>
HAMMER <u>DH03</u>	 Modified California Sampler  Standard Penetration Test  Bulk Sample  Shelby Tube
NOTES <u>Zond Substation</u>	

BLOWS PER HALF FOOT			BLOWS PER FOOT	SAMPLER	DEPTH (ft)	USCS CLASSIFICATION	MATERIAL DESCRIPTION	POCKET PENETROMETER	TORVANE SHEAR STRENGTH
					20				
					21	SC	SILTY CLAYEY SAND, YELLOW-BROWN, MOIST-WET, MED-DENSE		
					22				
					23				
26	35	48	83		24		CLAYSTONE, OLIVE-BROWN, MODERATELY WEATHERED, WEAK		
					25				
					26				
					27				
					28				
12	22	31	53		29				
					30		Bottom of Hole 30 Feet		
					31				
					32				
					33				
					34				
					35				
					36				
					37				
					38				
					39				
					40				

Berlogar Stevens & Associates
1220 Quarry Lane
Pleasanton, CA 94566

BORING NUMBER B-6

PAGE 1 OF 1

CLIENT Viracocha Wind PROJECT NAME Rooney / Sand Hill
PROJECT NUMBER 4245.200 PROJECT LOCATION Livermore, CA
DATE STARTED 3-16-23 COMPLETED 3-16-23 LOGGED BY: AG
DRILLING CONTRACTOR Gregg GROUNDWATER: AT TIME OF DRILLING ---
DRILLING EQUIPMENT Rhino SAMPLER TYPE: AT END OF DRILLING ---
HAMMER DH03
NOTES Zond Substation



Modified California
Sampler



Standard
Penetration Test



Bulk Sample



Shelby
Tube


BLOWS PER HALF FOOT			BLOWS PER FOOT	SAMPLER	DEPTH (ft)	USCS CLASSIFICATION	MATERIAL DESCRIPTION	POCKET PENETROMETER	TORVANE SHEAR STRENGTH
					0		6 INCHES / CRUSHED ROCK		
HAND AUGER TO 3.5'			↓		1	SC			
					2		SILTY CLAYEY SAND, YELLOW-BROWN, MOIST-WET, MED-DENSE		
					3				
8	6	7	13		4				
					5				
					6				
					7				
1	2	3	5		8				
					9				
					10				
					11				
					12				
50/3			50/3		13		SANDSTONE, LIGHT-GRAY, HIGHLY WEATHERED, WEAK		
					14		Bottom of Hole 13.3 Feet		
					15				
					16				
					17				
					18				
					19				
					20				

APPENDIX D





Trench Logs

0+00 0+10 0+20 0+30 0+40 0+50 0+60 0+70 0+80 0+90 0+100


TURBINE #3



TURBINE #4






TURBINE #8




0+00 0+10 0+20 0+30 0+40 0+50 0+60 0+70 0+80 0+90 0+100


TURBINE #9




TURBINE #18



TURBINE #19






TURBINE #20



WIND TURBINE TRENCH LOGS ROONEY SANDHILL SANTA CLARA, CALIFORNIA

Berlogar Stevens & Associates
SOIL ENGINEERS • ENGINEERING GEOLOGISTS

JOB NUMBER: 245,200
DATE: 11/09/22
DRAWN BY: ZG



WIND TURBINE TRENCH LOGS ROONEY SANDHILL SANTA CLARA, CALIFORNIA

Berlogar Stevens & Associates
SOIL ENGINEERS • ENGINEERING GEOLOGISTS

APPENDIX E

Test Pits

Test Pit Logs

TP-1

0' – 2.5' Silty Clay, dark brown, moist-wet, soft
2.5' – 6' Claystone, weathered, olive to olive-brown, weak

TP-2

0' – 2' Silty Clay, dark-brown, moist-wet, soft
2' – 6' Silty Clay, red-brown, moist-wet, medium stiff
6' – 7' Claystone, light olive-brown to tan, weathered, weak

TP-3

0' – 2.5' Silty Clay, dark brown, moist-wet, soft
2.5' – 3.5' Claystone, olive to olive-brown, highly weathered, weak
3.5' – 7' Claystone, red-brown, weathered, weak

TP-4

0' – 3' Silty Clay, dark brown, moist-wet, soft
3' – 7' Sandstone, highly weathered, yellow-brown, weak

TP-5

0' – 3' Silty Clay, dark-brown, moist-wet, soft
3' – 7' Claystone, light olive-brown to olive, weathered, weak

TP-6

0' – 4.5' Silty Clay, dark-brown, moist-wet, soft
4.5' – 8' Claystone, olive-brown, highly weathered, weak

TP-7

0' – 3' Silty Clay, brown, moist-wet, soft
3' – 6' Clayey Sand, red-brown, moist-wet, medium dense

TP-8

0' – 4.5' Silty Clay, brown, moist-wet, soft
4.5' – 7' Sandstone, light yellow-brown to tan, highly weathered, weak

TEST PITS EXCAVATED FEBRUARY 2023

Test Pit Logs

TP-9 (Turbine 23)

- 0' – 1.5' Silty Clay, dark brown, dry, medium stiff
- 1.5' – 4' Sandstone, yellow-brown, friable, highly weathered, 65° F

TP-10 (AML Substation)

- 0' – 1' Crushed Rock
- 1' – 4' Sandstone, yellow-brown, friable, highly weathered, 67° F

TP-11 (Zond Substation)

- 0' – 1.5' Crushed Rock
- 1.5' – 4.5' Silty Clayey Sand, medium brown, moist, medium dense, 60°F

TP-12 (Turbine 5)

- 0' – 2' Silty Clayey Sand, medium brown, dry, dense
- 2' – 5' Claystone, Olive-brown, moderately weathered, weak, 52° F

TEST PITS EXCAVATED 6/8/2023