

DOCKETED

Docket Number:	17-BSTD-01
Project Title:	2019 Building Energy Efficiency Standards PreRulemaking
TN #:	217911
Document Title:	6-6-17 Loading Dock Seals Presentation
Description:	Presentation made by Payam Bozorgchami at the 6-6-17 Staff Workshop.
Filer:	Adrian Ownby
Organization:	California Energy Commission
Submitter Role:	Commission Staff
Submission Date:	6/7/2017 11:31:06 AM
Docketed Date:	6/7/2017



2019 Building Energy Efficiency Standards Pre-Rulemaking Workshop

LOADING DOCK SEALS

Payam Bozorgchami, PE
Building Standards Office
June 06, 2017



Acknowledgments

California Utilities Statewide Codes and
Standards Team

CASE Authors:

John Arent, PE, NORESKO

Katie Gustafson, NORESKO



Relevant Code History

- There are no requirements in Title 24, Part 6
- Requirement for weather seals in ASHRAE Climate Zones 4-8



Dock Seal





Dock Shelter





Introduction to Dock Seal Technology

- **Dock Seals and Dock Shelters**

- Dock seals have a foam core designed to provide a sealed fit with a specific truck size

- **Pros:** Less expensive and creates a good seal
- **Cons:** Repeated impacts causes wear

- Dock shelters consist of a fiberglass curtain and are designed to accommodate a wide array of truck heights and sizes

- **Pros:** Able to adapt to a variety of truck heights and some materials have improved durability
- **Cons:** Higher first cost and varying performance in sealing

- Dock seal products have energy benefits, but are typically specified for other reasons (privacy, inhibit rain/moisture, and/or pest control)



Measure Scope

- Possible mandatory requirement for dock seals or shelters in warehouses and other buildings
- Evaluated for each California Climate Zone separately



Definition of Baseline and Proposed Conditions

Field Verification

- Energy savings depends on air leakage reduction with dock seal
 - Air Leakage rate determined through ASTM E783 field test, at two different sites, and two different dock seal conditions
- Parametric energy simulations used to estimate savings

Energy Modeling

- Warehouse Prototype (49,495 sf) minimally compliant with 2016 Title 24 Standards
- Four 70 sf loading dock doors with baseline infiltration rate of 2250 cfm and proposed infiltration rate (with seal) of 417 cfm*
- Model tested for all 16 CEC climate zones
 - Three loading frequency levels: low (2x daily), medium (5x daily) and high (11x day)
 - Tested heated only and fully conditioned warehouse options
 - Unconditioned warehouses not subject to the requirement



They Do Take a Beating






Incremental Costs

- Incremental First Cost
 - First Cost (\$1,400-\$2,400 per door installed)
 - **Total Incremental First Cost (\$9,600) for 4 loading dock doors per 49,495 sf model**
 - Assumes highest first cost for dock shelter
- Incremental Maintenance Costs over 15-year period of analysis
 - Estimated Expected Useful Life at 7.5 years
 - Total Incremental Maintenance Cost (estimated at \$7,680) – complete seal replacement at end of EUL, adjusted by discount rate



California Climate Zone Map



Coastal - 1, 3, 5, 6, 7, 8

Inland - 2, 4, 9, 10

Central Valley - 11, 12, 13

Desert - 14, 15

Mountains - 16



Annual Energy Savings and Cost Effectiveness: Low Dock Use Case

Climate Zone	Save Low (\$/sf)	NPV Low (\$/sf)	BCR Low
1	0.443	\$ 0.09	1.27
2	0.162	\$ (0.19)	0.46
3	0.304	\$ (0.05)	0.87
4	0.150	\$ (0.20)	0.43
5	0.240	\$ (0.11)	0.69
6	0.138	\$ (0.21)	0.40
7	0.109	\$ (0.24)	0.31
8	0.074	\$ (0.27)	0.21
9	0.097	\$ (0.25)	0.28
10	0.092	\$ (0.26)	0.26
11	0.310	\$ (0.04)	0.89
12	0.200	\$ (0.15)	0.57
13	0.126	\$ (0.22)	0.36
14	0.315	\$ (0.03)	0.90
15	0.075	\$ (0.27)	0.21
16	0.614	\$ 0.26	1.76



Annual Energy Savings and Cost Effectiveness: Medium Dock Use Case

Climate Zone	Sav High (\$/sf)	NPV High	BCR
1	0.995	\$ 0.65	2.85
2	0.362	\$ 0.01	1.04
3	0.692	\$ 0.34	1.98
4	0.362	\$ 0.01	1.04
5	0.579	\$ 0.23	1.66
6	0.286	\$ (0.06)	0.82
7	0.251	\$ (0.10)	0.72
8	0.174	\$ (0.18)	0.50
9	0.219	\$ (0.13)	0.63
10	0.227	\$ (0.12)	0.65
11	0.655	\$ 0.31	1.87
12	0.429	\$ 0.08	1.23
13	0.319	\$ (0.03)	0.91
14	0.683	\$ 0.33	1.96
15	0.168	\$ (0.18)	0.48
16	1.044	\$ 0.69	2.99



Annual Energy Savings and Cost Effectiveness: Higher Dock Use Case

Climate Zone	Sav High (\$/sf)	NPV High	BCR
1	0.995	\$ 0.65	2.85
2	0.362	\$ 0.01	1.04
3	0.692	\$ 0.34	1.98
4	0.362	\$ 0.01	1.04
5	0.579	\$ 0.23	1.66
6	0.286	\$ (0.06)	0.82
7	0.251	\$ (0.10)	0.72
8	0.174	\$ (0.18)	0.50
9	0.219	\$ (0.13)	0.63
10	0.227	\$ (0.12)	0.65
11	0.655	\$ 0.31	1.87
12	0.429	\$ 0.08	1.23
13	0.319	\$ (0.03)	0.91
14	0.683	\$ 0.33	1.96
15	0.168	\$ (0.18)	0.48
16	1.044	\$ 0.69	2.99



Proposed Code Change

SECTION 100.1 – DEFINITIONS AND RULES OF CONSTRUCTION

add definitions for Loading Dock Door, Dock Seal, and Dock Shelter.

SECTION 110.7 – MANDATORY REQUIREMENTS TO LIMIT AIR LEAKAGE

All joints, penetrations and other openings in the building envelope that are potential sources of air leakage shall be caulked, gasketed, weather stripped, or otherwise sealed to limit infiltration and exfiltration.

Newly Constructed Loading Dock Seal Requirement. Exterior loading dock doors that are adjacent to conditioned or indirectly conditioned spaces shall have dock seals or dock shelters installed. This requirement shall apply to newly constructed buildings in climate zones ---- and to added loading dock doors in existing buildings in climate zones ----.



KEY WEB-LINK

2019 Title 24 Utility-Sponsored Stakeholder

<http://title24stakeholders.com/>

Building Energy Efficiency Program

<http://www.energy.ca.gov/title24/>

Comments to be submitted to

<https://efiling.energy.ca.gov/EComment/EComment.aspx?docketnumber=17-BSTD-01>.



Contact Information

Payam Bozorgchami, PE

Project Manager, 2019 Building
Standards

Payam.Bozorgchami@energy.ca.gov

916-654-4618





Questions?

