
DOCKETED	
Docket Number:	21-AFC-02
Project Title:	Gem Energy Storage Center
TN #:	243019
Document Title:	Att DA53-6 Architectural History Survey Report
Description:	N/A
Filer:	Elizabeth Diaz
Organization:	Golder Associates
Submitter Role:	Applicant Consultant
Submission Date:	5/11/2022 2:41:09 PM
Docketed Date:	5/11/2022



HISTORIC RESOURCES EVALUATION REPORT:
AN ADDENDUM TO CULTURAL RESOURCES
TECHNICAL REPORT FOR THE
HYDROSTOR A-CAES PROJECT,



# HISTORIC RESOURCES EVALUATION REPORT: AN ADDENDUM TO CULTURAL RESOURCES TECHNICAL REPORT FOR THE HYDROSTOR A-CAES PROJECT, KERN COUNTY, CALIFORNIA

#### Prepared by:

Lisa Demarais, M.A. Emma Keethler, M.A. Alex Bethke, M.A. Kyle Knabb, Ph.D., RPA Caity Chandler, M.A.

#### Prepared for:

Golder, a member of WSP 1575 Treat Boulevard, #201 Walnut Creek, California 94598

**Technical Report No. 22-243** 

PaleoWest, LLC

517 South Ivy Avenue Monrovia, California 91016 (626) 408-8006

May 6, 2022

Keywords: Willow Springs; California Historic Landmark #130; Kern County; Rosamond, California; Antelope Valley; Mojave Desert; PaleoWest

# **EXECUTIVE SUMMARY**

Hydrostor, Inc. (Hydrostor) proposes to construct the Hydrostor advanced compressed air energy storage (A-CAES) Project (Project), a nominal 500-Megawatt (MW) A-CAES facility deploying proprietary A-CAES technology and associated 10.9-mile-long, 200-foot-wide easement corridor that houses a 230-kilovolt (kV) single-circuit tie-line (gen-tie lines) connecting to the Southern California Edison (SCE) Whirlwind Substation, or an approximately 3.5-mile-long 230kV single-circuit tie-line connecting to the future Los Angeles Department of Water and Power (LADWP) Rosamond Substation.

This Historic Resources Evaluation Report (HRER) evaluates the potential for the proposed action to affect buildings, objects, structures, and other built environment resources listed or eligible for listing in the California Register of Historical Resources (CRHR). The specific purpose of this HRER is to comply with applicable sections of the California Environmental Quality Act (CEQA) and California Energy Commission (CEC) guidelines. The Area of Potential Impacts (API) defined for the Project includes the Area of Direct Impacts (ADI), which consists of the Project footprint for the proposed A-CAES facility and 50-foot buffer on either side of all proposed above ground linear facilities (Project area), and the Area of Indirect Impacts (AII), which consists of a ½-mile buffer around the Project area.

To comply with these regulations, PaleoWest, LLC (PaleoWest) was contracted by Golder Associates, Inc. to conduct this HRER as an addendum to the *Cultural Resources Technical Report for the Hydrostor A-CAES Project, Kern County, California*. PaleoWest consulted the records search conducted for the Cultural Resources Technical Report, conducted extensive historical and archival research on all parcels containing historic period built environment resources, reviewed existing historic contexts and documentation relating to the Project area, and identified previously recorded historical resources within, conducted a historic architectural field survey of the API from the public right-of-way (ROW), recorded all historic period built environment resources forty-five years or older using appropriate California Department of Parks and Recreation (DPR) 523-series forms, and evaluated all historic period built environment resources for eligibility for listing in the CRHR.

There have been twenty-two prior cultural resource studies that identified, assessed, or evaluated historic period built environment resources within the API. The historic architecture field survey for the Project led to the documentation and evaluation of historic period built environment resources on 20 parcels within the API for the Project. A listed California Landmark (Willow Springs Village) and a contributor to a CRHR-listed Historic District (the Vincent 220kV Transmission Line) were also documented and evaluated. Three residential properties were unable to be accessed for evaluation and are assumed to be eligible for the purposes of assessing impacts under CEQA.

PaleoWest assessed that the proposed Project will not result in any adverse direct impacts, such as demolition or materialistic alteration to historical resources. No significant indirect and visual impacts to the Vincent 220kV Transmission Line and associated SCE Big Creek Hydroelectric System Historic District are anticipated. Visual impacts to the Willow Springs Village are expected to be less than significant with the implementation of a recommended mitigation measure, and no other significant impacts to the site are expected. Impacts to the assumed-eligible residential resources are anticipated to be less than significant. As such, the

Project as proposed will not result in a substantial adverse change or significant impact in accordance with CEQA Section 15064.5(b).

This page intentionally left blank.

# **CONTENTS**

1	INTRODUC	CTION	1
	1.1	PROJECT LOCATION AND DESCRIPTION	1
	1.2	KEY PERSONNEL	
	1.3	REPORT ORGANIZATION	2
2	REGULAT	ORY CONTEXT	7
	2.1	CALIFORNIA ENVIRONMENTAL QUALITY ACT	7
		2.1.1 Impacts Assessment Criteria	
		2.1.2 Assessing Visual Impacts	
		2.1.3 Mitigation of Adverse Impacts	9
3	METHODS	)	9
	3.1	RESEARCH	
		3.1.1 Records Search	
	3.2	FIELD SURVEY METHODS	
4	HISTORIC	CONTEXT	16
	4.1	SPANISH AND MEXICAN EXPLORATION AND SETTLEMENT IN THE	
	4.0	MOJAVE DESERT	16
	4.2	AMERICAN EXPLORATION AND SETTLEMENT IN THE MOJAVE DESERT	
		4.2.1 Industry in the Antelope Valley	
	4.3	4.2.2 Infrastructure in the Antelope Valley	
	4.3	4.3.1 Community Development (ca. 1850–1918)	
		4.3.2 Community Development (1918–1975)	
5	HISTORIC	ARCHITECTURAL FIELD SURVEY RESULTS	
5	5.1	PROPERTY DESCRIPTIONS	
	5.1	5.1.1 Willow Springs, California Landmark #130 (P-15-000129)	
		5.1.2 LADWP Owens Valley 230kV Transmission Line Easement Corridor (	
		15-018681)	
		5.1.3 Vincent 2206V Transmission Line, Big Creek #3-Springville (P-15-	
		017243) / SCE Big Creek Hydroelectric System Historic District	34
		5.1.4 General Petroleum Access Road (P-15-013833)	35
		5.1.5 14205 Irone Avenue (358-132-12)	35
		5.1.6 4040 Manly Road (315-012-01, 315-012-02, 252-341-05)	
		5.1.7 14101 Irone Avenue (358-132-10)	
		5.1.8 14070 Lodestar Avenue (358-132-07)	
		5.1.9 10145 Hamilton Road (358-052-08)	
		5.1.10 10085 Hamilton Road (358-052-07)	
		5.1.12 9714 Rosamond Boulevard (374-042-03)	.41 12
		5.1.13 9668 Rosamond Boulevard (374-042-04)	43
		5.1.14 9650 West Rosamond Boulevard (374-042-39)	44
		5.1.15 9580 Rosamond Boulevard (374-042-07)	
		5.1.16 9009 Rosamond Boulevard (252-352-33)	
		5.1.17 3045 90 <sup>th</sup> Street (252-352-32) / High Desert Cellars	47
		5.1.18 2973 95 <sup>th</sup> Street (374-042-08)	48
		5.1.19 2860 West 100 <sup>th</sup> Street (374-041-09)	49
		5.1.20 APN 358-131-02	50
6	SIGNIFICA	NCE AND ELIGIBILITY	51

6.1.1 California Register of Historical Resources		6.1	ELIGII	BILITY CRITERIA	51
6.2.1 Willow Springs Village, California Historic Landmark #130					
6.2.2 Segment of the LADWP Owens Gorge 230kV Transmission Corridor54 6.2.3 Segment of the Vincent 2206V Transmission Line, Big Creek #3-Springville (P-15-017243) / SCE Big Creek Hydroelectric System Historic District 54 6.2.4 Segment of the General Petroleum Access Road		6.2	EVAL		
6.2.3 Segment of the Vincent 2206V Transmission Line, Big Creek #3-Springville (P-15-017243) / SCE Big Creek Hydroelectric System Historic District 54 6.2.4 Segment of the General Petroleum Access Road			_		
Springville (P-15-017243) / SCE Big Creek Hydroelectric System Historic District 54					î54
6.2.4 Segment of the General Petroleum Access Road					
6.2.4 Segment of the General Petroleum Access Road 6.2.5 14205 Irone Avenue (358-132-12)			Spring	ville (P-15-017243) / SCE Big Creek Hydroelectric System Historic Di	strict
6.2.5 14205 Irone Avenue (358-132-12)					
6.2.6 4040 Manly Road (315-012-01, 315-012-02, 252-341-05)					
6.2.7 14101 Irone Avenue (358-132-10)				14205 Irone Avenue (358-132-12)	55
6.2.8 14070 Lodestar Avenue (358-132-07)				4040 Manly Road (315-012-01, 315-012-02, 252-341-05)	56
6.2.9 10145 Hamilton Road (358-052-08). 61 6.2.10 10085 Hamilton Road (358-052-07) 62 6.2.11 10057 Hamilton Road (358-052-06) 62 6.2.12 9714 Rosamond Boulevard (374-042-03) 62 6.2.13 9668 Rosamond Boulevard (374-042-04) 64 6.2.14 9650 West Rosamond Boulevard (374-042-39) 66 6.2.15 9580 Rosamond Boulevard (374-042-39) 67 6.2.16 9009 Rosamond Boulevard (252-352-33) 69 6.2.17 3045 90 <sup>th</sup> Street (252-352-32) / High Desert Cellars 70 6.2.18 2973 95 <sup>th</sup> Street (374-042-08) 71 6.2.19 2860 West 100 <sup>th</sup> Street (374-041-09) 72 6.2.20 APN 358-131-02 74 6.2.21 Historic District Eligibility 74 7 IMPACTS ASSESSMENT 74 7.1.1 Willow Springs Village, California Historic Landmark #130 75 7.1.2 Vincent 220kV Transmission Line; Big Creek Hydroelectric Historic District 75 7.1.3 10085 Hamilton Road (APN 358-052-07) 75 7.1.4 10057 Hamilton Road (APN 358-052-07) 75 7.1.5 APN 358-131-02 76 8 RESULTS AND RECOMMENDATIONS 76 8.1 SUMMARY OF RESULTS 76 8.2 RECOMMENDATIONS AND CONCLUSION 78 9 REFERENCES 79 FIGURES Figure 1-1. Project vicinity map 75 Figure 1-2. Project location map 75 Figure 3-1 Built environment Survey area 75 Figure 4-2. Standard cottages at Willow Springs (ca 1905) 24 Figure 4-3. Residence at Willow Springs (ca 1905) 24					
6.2.10 10085 Hamilton Road (358-052-07) 6.2 6.2.11 10057 Hamilton Road (358-052-06) 6.2 6.2.12 9714 Rosamond Boulevard (374-042-03) 6.2 6.2.13 9668 Rosamond Boulevard (374-042-04) 6.4 6.2.14 9650 West Rosamond Boulevard (374-042-09) 66 6.2.15 9580 Rosamond Boulevard (374-042-07) 6.7 6.2.16 9009 Rosamond Boulevard (374-042-07) 6.7 6.2.18 2973 95 <sup>th</sup> Street (252-352-32) / High Desert Cellars 70 6.2.18 2973 95 <sup>th</sup> Street (374-042-08) 71 6.2.19 2860 West 100 <sup>th</sup> Street (374-041-09) 72 6.2.20 APN 358-131-02 74 6.2.21 Historic District Eligibility 74 7 IMPACTS ASSESSMENT 74 7.1.1 Willow Springs Village, California Historic Landmark #130 75 7.1.2 Vincent 220kV Transmission Line; Big Creek Hydroelectric Historic District 75 7.1.3 10085 Hamilton Road (APN 358-052-07) 75 7.1.4 10057 Hamilton Road (APN 358-052-07) 76 8 RESULTS AND RECOMMENDATIONS 76 8.1 SUMMARY OF RESULTS 76 8.2 RECOMMENDATIONS AND CONCLUSION 78 9 REFERENCES 79 FIGURES Figure 1-1. Project vicinity map 5 Figure 1-2. Project location map 5 Figure 3-1 Built environment Survey area 5 Figure 4-1. Hotel Rosamond (ca. 1905) 23 Figure 4-2. Standard cottages at Willow Springs (ca. 1905) 24 Figure 4-3. Residence at Willow Springs (ca. 1905) 24					
6.2.11 10057 Hamilton Road (358-052-06)					
6.2.12 9714 Rosamond Boulevard (374-042-03)					
6.2.13 9668 Rosamond Boulevard (374-042-04)					
6.2.14 9650 West Rosamond Boulevard (374-042-39)					
6.2.15 9580 Rosamond Boulevard (374-042-07)					
6.2.16 9009 Rosamond Boulevard (252-352-33)					
6.2.17 3045 90 <sup>th</sup> Street (252-352-32) / High Desert Cellars					
6.2.18 2973 95th Street (374-042-08)			6 2 17	30/15 00th Street (252-352-32) / High Desert Cellars	09 70
6.2.19 2860 West 100 <sup>th</sup> Street (374-041-09)			6 2 18	2973 95th Street (374-042-08)	70 71
6.2.20 APN 358-131-02					
6.2.21 Historic District Eligibility       74         7 IMPACTS ASSESSMENT       74         7.1.1 Willow Springs Village, California Historic Landmark #130       75         7.1.2 Vincent 220kV Transmission Line; Big Creek Hydroelectric Historic District 75       7.1.3 10085 Hamilton Road (APN 358-052-07)       75         7.1.4 10057 Hamilton Road (APN 358-052-06)       76         7.1.5 APN 358-131-02       76         8 RESULTS AND RECOMMENDATIONS       76         8.1 SUMMARY OF RESULTS       76         8.2 RECOMMENDATIONS AND CONCLUSION       78         9 REFERENCES       79         FIGURES         Figure 1-1. Project vicinity map       3         Figure 1-2. Project location map       5         Figure 3-1. Built environment Survey area       5         Figure 4-1. Hotel Rosamond (ca. 1905)       23         Figure 4-2. Standard cottages at Willow Springs (ca. 1905)       23         Figure 4-3. Residence at Willow Springs (ca. 1905)       24					
7 IMPACTS ASSESSMENT					
7.1.1 Willow Springs Village, California Historic Landmark #130	7	IMPACTS			
7.1.2 Vincent 220kV Transmission Line; Big Creek Hydroelectric Historic District 75 7.1.3 10085 Hamilton Road (APN 358-052-07)	•	IIIII AOIO			
District 75					
7.1.3       10085 Hamilton Road (APN 358-052-07)       75         7.1.4       10057 Hamilton Road (APN 358-052-06)       76         7.1.5       APN 358-131-02       76         8       RESULTS AND RECOMMENDATIONS       76         8.1       SUMMARY OF RESULTS       76         8.2       RECOMMENDATIONS AND CONCLUSION       78         9       REFERENCES       79         FIGURES         Figure 1-1. Project vicinity map       3         Figure 1-2. Project location map       5         Figure 1-3. Project location map       6         Figure 3-1. Built environment Survey area       15         Figure 4-1. Hotel Rosamond (ca. 1905)       23         Figure 4-2. Standard cottages at Willow Springs (ca. 1905)       23         Figure 4-3. Residence at Willow Springs (ca. 1905)       24					
7.1.4       10057 Hamilton Road (APN 358-052-06)       76         7.1.5       APN 358-131-02       76         8       RESULTS AND RECOMMENDATIONS       76         8.1       SUMMARY OF RESULTS       76         8.2       RECOMMENDATIONS AND CONCLUSION       78         9       REFERENCES       79         Figure 1-1.       Project vicinity map       3         Figure 1-2.       Project location map       5         Figure 1-3.       Project location map       6         Figure 3-1.       Built environment Survey area       15         Figure 4-1.       Hotel Rosamond (ca. 1905)       23         Figure 4-2.       Standard cottages at Willow Springs (ca 1905)       23         Figure 4-3.       Residence at Willow Springs (ca. 1905)       24					75
7.1.5 APN 358-131-02					
8 RESULTS AND RECOMMENDATIONS       76         8.1 SUMMARY OF RESULTS       76         8.2 RECOMMENDATIONS AND CONCLUSION       78         9 REFERENCES       79         Figure 1-1. Project vicinity map.       3         Figure 1-2. Project location map.       5         Figure 1-3. Project location map.       6         Figure 3-1. Built environment Survey area.       15         Figure 4-1. Hotel Rosamond (ca. 1905).       23         Figure 4-2. Standard cottages at Willow Springs (ca. 1905).       23         Figure 4-3. Residence at Willow Springs (ca. 1905).       24			7.1.5	APN 358-131-02	76
8.1 SUMMARY OF RESULTS	8	RESULTS	AND R	FCOMMENDATIONS	76
8.2 RECOMMENDATIONS AND CONCLUSION 78  9 REFERENCES 79  FIGURES  Figure 1-1. Project vicinity map. 3  Figure 1-2. Project location map. 5  Figure 1-3. Project location map. 6  Figure 3-1. Built environment Survey area. 15  Figure 4-1. Hotel Rosamond (ca. 1905). 23  Figure 4-2. Standard cottages at Willow Springs (ca. 1905). 23  Figure 4-3. Residence at Willow Springs (ca. 1905). 24	•				_
FIGURES Figure 1-1. Project vicinity map			RECO	MMENDATIONS AND CONCLUSION	78
FIGURES Figure 1-1. Project vicinity map	a				
Figure 1-1. Project vicinity map	3	IXEI LIXLIA	OLS		1 9
Figure 1-1. Project vicinity map					
Figure 1-1. Project vicinity map					
Figure 1-2. Project location map	FI	GURES			
Figure 1-3. Project location map	Fig	gure 1-1. Pi	roject v	ricinity map	3
Figure 3-1. Built environment Survey area					
Figure 3-1. Built environment Survey area					
Figure 4-1. Hotel Rosamond (ca. 1905)					
Figure 4-2. Standard cottages at Willow Springs (ca 1905)				•	
Figure 4-3. Residence at Willow Springs (ca. 1905)24					

Figure 5-2. Partial overview of Willow Springs Village along Manly Road, facing northeast	29
Figure 5-3. Overview of the Willow Springs Segment of the Vincent 220kV Transmiss Line.	ion
Figure 5-4. Overview of the Willow Springs Segment of General Petroleum Access Road	
Figure 5-5. Property overview of 14205 Irone Avenue, facing north.	
Figure 5-6. Overview of Residences 1 and 2 on APN 252-341-05, facing southeast Figure 5-7. Property overview of 14101 Irone Avenue facing north showing the south	. 37
façade	
Figure 5-8. Property overview of 14070 Lodestar Avenue, facing southwest	
Figure 5-10. Property overview of 10145 Hamilton Road, view facing north	
Figure 5-11. Property overview of 10057 Hamilton Road, view facing north	
Figure 5-12. Overview of 9714 Rosamond Boulevard, view facing southwest from	
Rosamond Boulevard	. 43
Figure 5-13. Overview of 9668 Rosamond Boulevard facing southwest	
Figure 5-14. Property overview of 9650 W Rosamond Boulevard facing south from	
Rosamond Boulevard	. 45
Figure 5-15. Property overview of 9580 Rosamond Boulevard facing southwest from	
Rosamond Boulevard	. 46
Figure 5-16. Property overview of 9009 Rosamond Boulevard facing north from	47
Rosamond Boulevard	
Figure 5-17. Property overview of 3045 90th Street West, facing northwest	
Figure 5-19. Property overview of 2860 West 100th Street, facing east	
rigure 3-19. I Toperty overview of 2000 West Tooth Street, lacing east	. 30
TABLES	
Table 3-1. Previous Investigations of the Built Environment within the Study Area	
Table 3-2. Previously Identified Built Environment Cultural Resources in the Study Are	
T.I. 54.0	. 12
Table 5-1. Surveyed Cultural Resources in the API	
Table 8-1. Previously Identified CRHR-eligible or Listed Historical Resources within the API	
Table 8-2. Built Environment Cultural Resources Assumed CRHR-eligible within the A	
Table 6-2. Built Environment Cultural Resources Assumed CRHR-eligible within the A	
Table 8-3. Built Environment Cultural Resources within the API Recommended Not Eligible for CRHR Listing	

#### **APPENDICES**

Appendix A. Site Forms

This page intentionally left blank.

# 1 INTRODUCTION

At the request of Golder Associates, Inc., PaleoWest, LLC (PaleoWest) conducted this Historic Resources Evaluation Report (HRER) in support of the Hydrostor, Inc. (Hydrostor) advanced compressed air energy storage (A-CAES) project (Project) near Willow Springs in Kern County, California. This report was prepared as an addendum to the *Cultural Resources Technical Report for the Hydrostor A-CAES Project, Kern County, California* completed by PaleoWest in 2021. The HRER consists of extensive historical and archival research on all parcels containing historic period built environment resources, reviewed existing historic contexts and documentation relating to the Project area, and identified previously recorded historical resources within, conducted a historic architectural field survey from the public right-of-way (ROW), recorded all historic period built environment resources forty-five years or older using appropriate California Department of Parks and Recreation (DPR) 523-series forms, and evaluated all historic period built environment resources for eligibility for listing in the California Register of Historical Resources (CRHR). This report describes the goals, methods, and evaluation conducted by PaleoWest for the historic resources evaluation.

This Historical Resources Evaluation Report (HRER) was prepared following technical guidance provided by the California Office of Historic Preservation (California OHP) in *Instructions for Recording Historical Resources* and *Technical Assistance Series #7: How to Nominate a Resource to the California Register of Historical Resources*, and in conformance with California Environmental Policy Act (CEQA) regulations and definitions for historical resources. Based on CEC guidance for new transmission line construction in rural settings and guidance for assessing impacts pursuant to CEQA, PaleoWest defined the Project's Area of Potential Impacts (API) as the Area of Direct Impacts (ADI), which consists of the Project footprint for the proposed A-CAES facility and 50-foot buffer on either side of all proposed above ground linear facilities (Project area), and the Area of Indirect Impacts (AII), which consists of a ½-mile buffer around the Project area. All built environment cultural resources forty-five years old or older within this API were identified, surveyed, and recorded on the appropriate California Department of Parks and Recreation (DPR) 523 forms. The identified resources not already evaluated for CRHR-eligibility within the past five years were then evaluated for listing, as per California OHP guidance.

#### 1.1 PROJECT LOCATION AND DESCRIPTION

The Project is west of the unincorporated community of Willow Springs in the southeastern portion of Kern County (County), between 170th Street West to the west, 90th Street West to the east, Hamilton Boulevard to the north, and Rosamond Boulevard to the south (Figure 1-1 through Figure 1-3). Regionally, the site is depicted on the U.S. Geological Survey (USGS) Tylerhorse Canyon, Fairmont Butte, Willow Springs, and Little Buttes 7.5-minute topographic quadrangle maps. The Project is within Sections 13, 14, 23, and 24 in Township 9 North, Range 15 West, Sections 1–4, 8–12, and 16–18 in Township 9 North, Range 14 West, and Sections 7, 8, 17–19, and 24 in Township 9 North, Range 13 West, San Bernardino baseline and meridian.

The Project proposes the construction of a nominal 500-Megawatt (MW) A-CAES facility deploying Hydrostor proprietary A-CAES technology. Located on private land, the Project will consist of an approximately 10.9-mi-long, 200-foot- (ft-) wide easement corridor that houses

230-kilivolt (kV) single-circuit tie-line (gen-tie lines) connecting to the Southern California Edison (SCE) Whirlwind Substation, or an approximately 3.5-mi-long 230kV single-circuit tie-line connecting to the future Los Angeles Department of Water and Power (LADWP) Rosamond Substation. The Project area encompasses 400 acres.

The purpose of the Project is to construct an energy storage facility consisting of five, 100-MW (nominal) power blocks. Each power block will contain a motor-driven air compressor drivetrain, heat exchangers, and an air turbine generator and their ancillary equipment. Each power block will share a common set of thermal storage tanks (hot and cold) as well as the air storage cavern. The site will be designed to store 500 MW for up to 14 hours and deliver up to 4,000 MW hours (MWh) over an 8-hour period when discharging.

#### 1.2 KEY PERSONNEL

Senior Archaeologist Kyle Knabb, Ph.D., RPA served as Project Manager and provided technical oversight. Associate Architectural Historian Lisa Demarais, M.A. served as Technical Lead and the report was completed with Senior Technical Review from Senior Architectural Historian Alex Bethke, M.A. Under guidance from the Technical Lead, archaeologists Gena Granger, M.A., RPA and Evan Mills, M.A., RPA conducted pedestrian intensive right-of-way (ROW) and reconnaissance surveys. Associate Architectural Historian Emma Keethler, M.A. and Ms. Demarais completed the built environment resources assessments and prepared appropriate Department of Parks and Recreation (DPR) 523 forms (Appendix A) with support from Staff Architectural Historian Caity Chandler, M.A. Ms. Demarais also performed research, developed the historic context, assessed potential effects to historical resources, and authored this report. Staff Historian/Preservation Planner Caleb Gasparek, B.A. and Associate Archaeologist Cara Kubiak, M.A., RPA assisted with archival research.

Ms. Keethler and Ms. Demarais exceed the Secretary of the Interior's (SOI's) Professional Qualification Standards for Architectural History. Ms. Demarais and Mr. Bethke exceed the SOI's Professional Qualification Standards for History.

## 1.3 REPORT ORGANIZATION

This section of the report describes the proposed Project, its location, and the parameters for the historic period built environment resource study. The regulations applicable to the Project are explained in Section 2. The methods used in preparing this report is provided in Section 3. Section 4 describes the historic context relevant to the API. Section 5 describes the results of the historic architecture field survey, including property descriptions and photographs. Applicable eligibility criteria are outlined in Section 6, and Section 7 assesses the significance of the historic period built environment resources within the API. Section 8 provides a summary of results. California DPR 523 forms for surveyed properties are included as Appendix A.




Figure 1-1. Project vicinity map.

This page intentionally left blank.




Figure 1-2. Project location map.




Figure 1-3. Project location map.

# 2 REGULATORY CONTEXT

#### 2.1 CALIFORNIA ENVIRONMENTAL QUALITY ACT

CEQA Section 15064.5 *Determining the Significance of Impacts to Archeological and Historical Resources* requires that all private and public activities not specifically exempted be evaluated against the potential for environmental damage. Under CEQA, a historical resource is recognized as part of the environment. CEQA defines a historical resource as "any object, building, structure, site, area, place, record, or manuscript which a lead agency determines to be historically significant or significant in the architectural, engineering, scientific, economic, agricultural, educational, social, political, military, or cultural annals of California." This definition includes historical resources listed or identified as eligible for listing in the CRHR.

The CRHR is used in the consideration of historic resources relative to significance for purposes of CEQA. The CRHR includes resources listed in, or formally determined eligible for listing in, the National Register of Historic Places (NRHP), as well as some California State Landmarks and Points of Historical Interest. Properties of local significance that have been designated under a local preservation ordinance (local landmarks or landmark districts), or that have been identified in a local historic resources inventory, may be eligible for listing in the CRHR and are presumed to be significant resources for purposes of CEQA unless a preponderance of evidence indicates otherwise.

Generally, a resource shall be considered by the lead agency to be a "historical resource" if it:

- Is listed in or is determined to be eligible by the State Historical Resources Commission, for listing in the CRHR (Public Resources Code Section 5024.1, Title 14 CCR, Section 4850 et seq.).
- Is included in a local register of historic resources or is identified as significant in an historic resource survey meeting the requirements Section 5024.1(g) of the Public Resources Code (PRC).
- Is a building or structure determined to be historically significant or significant in the architectural, engineering, scientific, economic, agricultural, educational, social, political, military, or cultural annals of California.

# 2.1.1 Impacts Assessment Criteria

CEQA Section §21084.1 states that significant impacts may occur if "a project may cause a substantial adverse change in the significance of an historical resource." CEQA Guidelines use the terms effects and impacts interchangeably. Section §15064.5(b)(1) defines adverse impacts as a substantial adverse change to a historic resource, encompassing "demolition, destruction, relocation, or alteration of the resource or its immediate surroundings such that the significance of an historical resource would be materially impaired." As outlined in 14 CCR §15064.5(b)(2), the significance of a historical resource is materially impaired when a project:

A. Demolishes or materially alters in an adverse manner those physical characteristics of a historical resource that convey its historical significance and that justify its inclusion in, or eligibility for, inclusion in the CRHR; or

- B. Demolishes or materially alters in an adverse manner those physical characteristics that account for its inclusion in a local register of historical resources pursuant to Section 5020.1(k) of the Public Resources Code or its identification in a historical resources survey meeting the requirements of Section 5024.1(g) of the Public Resources Code, unless the public agency reviewing the effects of the project establishes by a preponderance of evidence that the resource is not historically or culturally significant; or
- C. Demolishes or materially alters in an adverse manner those physical characteristics of a historical resource that convey its historical significance and that justify its eligibility for inclusion in the CRHR as determined by a lead agency for purposes of CEQA.

#### CEQA defines three types of effects:

- 1. **Direct** or primary effects that are caused by a project and occur at the same time and place.
- 2. **Indirect** or secondary effects that are reasonably foreseeable and caused by a project but occur at a different time or place.
- 3. **Cumulative** impacts that are two or more individual effects which, when considered together, are considerable or which compound or increase other environmental impacts.

# 2.1.2 Assessing Visual Impacts

The process to determine significant impacts includes not only direct impacts, but potential indirect visual impacts. The CEQA definition of a substantial adverse change includes "alteration such that the significance of an historical resource *or its immediate surroundings* would be materially impaired." Although demolition and destruction are fairly obvious significant impacts, it is more difficult to assess when change, alteration, or relocation crosses the threshold of substantial adverse change. For an alteration to be considered a substantial adverse change, therefore, it must be shown that the integrity and/or significance of the historical resource would be materially impaired by the change in views towards or from a historic resource.

Adverse visual impacts may be created when an undertaking is visible within the viewshed of the historical resource, when it blocks a view toward the historical resource, or when it introduces an element that is incompatible with the criteria under which the resource is eligible. Simply because a project will be visible from a historical resource does not mean it automatically will create a significant impact. Therefore, it is necessary to evaluate the visual changes and alterations a proposed project may introduce to the resource.

An adverse impact may be obstructive, which is to say it may block the view to or from a historical resource; it may also not be obstructive and still create an adverse impact in that it introduces elements so incompatible with the criterion or criteria under which a historical resource is eligible for listing that it diminishes the resource's significance to a substantial degree.

#### 2.1.3 Mitigation of Adverse Impacts

Mitigation of adverse impacts is required if a proposed project will cause substantial adverse change to a historical resource (14 CCR §15064.5[b]). Mitigation measures must be enforceable through permit conditions, agreements, or other legal means and are proportional to the expected impacts. The measures seek to reduce impacts entirely or to a level considered not significant (14 CCR §15126.4). As such, the examples of mitigation measures provided may not satisfy CEQA requirements in every circumstance. Mitigation measures for historical resources may include but are not limited to:

- 1. Altering a proposed project to avoid damaging effects on any historical resource in a significant manner, such as by not taking a certain action or parts of an action.
- 2. Rectifying impacts through maintenance, repair, stabilization, rehabilitation, restoration, preservation, conservation, or reconstruction of the historical resource in a manner consistent with the SOI's Standards for the Treatment of Historic Properties.
- 3. Documentation of the historical resource, by way of historic narrative and photographs or architectural drawings meeting California OHP recommendations prior to demolition.
- 4. Deeding the site into a permanent conservation easement.
- 5. Abandonment of the proposed project.

CEQA Section 15064.5(b)(3) states that a project that follows the *Secretary of the Interior's Standards for the Treatment of Historic Properties* (*SOI Standards*) shall be considered as mitigated to a level of less than a significant impact on the historical resource.

# 3 METHODS

The following sections detail the methods used for background research and the built environment field survey.

#### 3.1 RESEARCH

PaleoWest conducted original secondary and archival research to establish an appropriate historic context from which to evaluate historic architectural resources within the API for CRHR-eligibility in compliance with CEQA. Specifically, research was conducted to develop an overview of the history of early settlement and exploration, development of agriculture and mining, founding of the community of Willow Springs, twentieth century commercial and residential development, and the evolution of energy infrastructure in and near the Project area.

Site-specific archival research using newspaper and genealogical databases was conducted to determine whether any owners of the identified properties were historically significant for contributions to broad patterns of history. Historical maps and aerial photographs were reviewed to establish the property's connection to the development of the Antelope Valley and the immediate surrounding area of Willow Springs. Building permits, when publicly available, also provided construction history of the properties.

Historical maps consulted include Elizabeth Lake, CA (1915, 1917) 30-minute; Willow Springs, CA (1943, 1965) 15-minute; Los Angeles, CA (1949, 1955, 1959) 1-degree; Little Buttes, CA (1965) 7.5-minute; Fairmont Butte, CA (1965) 7.5 minute; and Tylerhorse Canyon, CA (1965) 7.5-minute USGS quadrangles. Historical aerial images from NETROnline and the University of Santa Barbara (UCSB) dated 1948, 1959, 1963, 1974, and 1994 were also reviewed. The archival research indicates that by the early 1940s, portions of Hamilton Road and Rosamond Boulevard were present, with a few dirt roads connecting sparse structures to these relatively more major routes. The area remained relatively undeveloped until the 1960s, when a series of grid-oriented dirt roads were established throughout the Project area and the general vicinity. These road grids were presumably built for planned communities that were never established. Most of the roads visited during the survey exhibit some degree of use by residents. The most significant development in the area has been wind and solar energy development, with the Project vicinity remaining relatively undeveloped and retaining its rural character.

#### 3.1.1 Records Search

A records search was conducted at the SSJVIC, housed at California State University, Bakersfield, on November 5, 2020, and again on August 18, 2021. This inventory effort included the Project area and a 1/2-mi radius around all above ground linear routes and a 1-mi radius around the A-CAES facility, collectively termed the Study area. The objective of this records search was to identify prehistoric or historical period resources that have been previously recorded within the Study area during prior cultural resource investigations. Comprehensive lists of previous cultural resource investigations and cultural resources identified within the search radius were included in the original Cultural Resources Technical Report completed in 2021 (Knabb et al. 2021). Previously conducted cultural resource investigations that included built environment studies are listed in Table 3-1. Previously identified historic period built environment resources are listed in Table 3-2.

Table 3-1. Previous Investigations of the Built Environment within the Study Area

Report Number	Date	Author(s)	Title
KE-00101	1996	Kimball, Marcia (Bureau of Land Management [BLM], Barstow Resource Area)	Cultural Resource Testing and Evaluation Report for the Cory and Minn Parcels of the Loomis Land Exchange
KE-00355	1994	Clift, Gregory R. and Mark Q. Sutton (California State University, Bakersfield)	An Archaeological Assessment of Tentative Tract No. 5612, Rosamond, Kern County, California
KE-00634	1985	Mack, Michael E. and Jill Wiesbord (Applied Conservation Technology, Inc.)	Sylmar Expansion Project: Cultural Resources Inventory and Significant Evaluation Addendum to Final Report
KE-00634A	1985	Mack, Michael E. and Jill Wiesbord (Applied Conservation Technology, Inc.)	Sylmar Expansion Project Cultural Resources Inventory and Significance Evaluation Final Report Volume II
KE-01993	1995	Hayden, William E., Michael E. Macko, and David D. Earle (Macko. Inc.)	A Class III Intensive Survey of Five Land Exchange Sites for Hughes Land Company in the Rosamond and Palmdale Areas, Los Angeles and Kern Counties, California

Report Number	Date	Author(s)	Title
KE-02059	1997	Love, Bruce (CRM TECH)	Cultural Resources Survey Report: Bakersfield-Rialto Fiberoptic Line Project, Kern, Los Angeles, and San Bernardino Counties, California
KE-03546	2006	Ahmet, Koral, Roger Mason, and Sara Bholat (Aspen Environmental Group)	Cultural Resources Survey Report for Antelope Transmission Project: Segments 2 & 3 Los Angeles and Kern Counties
KE-03793	2008	Romani, John F. and Alan P. Gold (Garfinkel) (Compass Rose Archaeological, Inc.)	Archaeological Survey Report Tehachapi Willow Springs Road from Rosamond Boulevard to 10 Miles North, Willow Springs Area, Kern County, California
KE-03889	2009	DeCarlo, Matthew and Rebecca Orfila (Center for Archaeological Research)	A Cultural Resources Assessment of Three Proposed Deteriorated Pole Replacement Projects (WO 4703- 0455) Near Rosamond, Kern County, California
KE-03941	2009	Price, Barry A., Mary Clark Baloian, Robert Lichtenstein, and Marc Linder (Aspen Environmental Group)	Confidential Specialist Report: Cultural Resources Inventory for the Tehachapi Renewable Transmission Project Kern, Los Angeles, and San Bernardino Counties, California
KE-04057	2011	Hudlow, Scott M. (Hudlow Cultural Resource Associates)	Phase I Cultural Resources Survey for PV3, Willow Springs, Kern County, California
KE-04058	2011	Hudlow, Scott M. (Hudlow Cultural Resource Associates)	Phase I Cultural Resources Survey for PV-11, (Rosamond Solar Array) Rosamond, Kern County, California
KE-04080	2010	Wilson, Stacie and Stacey C. Jordan (AECOM)	Draft Cultural Resources Report for the Proposed RRG Antelope Valley Solar Project Kern and Los Angeles Counties, California
KE-04224	2010	Pacific Legacy, Inc. with Urbana Preservation and Planning, LLC	Supplemental Archaeological Investigation and National Register of Historic Places and California Register of Historical Resources Eligibility Evaluation of Archaeological Site CA-KER-7214H Southern California Edison Tehachapi Renewable Transmission Project, Segment 9, Kern County, California
KE-04226	2010	Schneider, Tsim D. and John Holson (Pacific Legacy, Inc.)	Supplemental Archaeological Survey Report #2, Tehachapi Renewable Transmission project Segment 4, Kern and Los Angeles Counties, California
KE-04227	2010	Schneider, Tsim D. and John Holson (Pacific Legacy, Inc.)	Supplemental Archaeological Survey Report #2, Tehachapi Renewable Transmission Project Segment 10, Kern County, California
KE-04435	2010	Meyer, Jack, D. Craig Young, and Jeffrey S. Rosenthal (Far Western Anthropological Research Group, Inc.)	Volume I: A Geoarchaeological Overview and Assessment of Caltrans Districts 6 and 9, Cultural Resources Inventory of Caltrans District 6/9 Rural Conventional Highways
KE-04435A	2010	Meyer, Jack, D. Craig Young, and Jeffrey S. Rosenthal (Far Western	Volume II: Appendices A Geoarchaeological Overview and Assessment of Caltrans District 6 and 9 - Cultural

Report Number	Date	Author(s)	Title
		Anthropological Research Group, Inc.)	Resources Inventory of Caltrans District 6/9 Rural Conventional Highways - EA 06-0A7408 TEA Grant
KE-04833	2016	Foglia, Shannon and Theodore Cooley (AECOM)	Cultural Resources Survey Report for the Proposed Southern California Edison Company's Antelope- Magunden No. 1 Transmission Line Rating Remediation Project, Kern County, California
KE-04887	2009	Way, K. Ross, Thomas L. Jackson, and Kari Jones (Pacific Legacy, Inc.)	Results of the Evaluation of Eligibility of Archaeological Site CA-KER-2821/H (Bean Spring) for Listing in the California Register of Historical Resources and Data Recovery Program for Mitigating Unavoidable Impacts to the Site That May Result from Activities Associated with Construction of Segment 3 of the Tehachapi Renewable Transmission Project
KE-04953	2017	Whitley, David, Peter Carey, and Robert Azpitarte (ASM Affiliates)	Phase I Survey/Class III Inventory, AVEP Solar Project, Kern County, California
KE-05043	2016	Whitley, David S. and Peter A. Carey (ASM Affiliates)	Phase I Survey/Class III Inventory, Rosamond 5 and 6 Solar Project Areas, Kern County, California

Table 3-2. Previously Identified Built Environment Cultural Resources in the Study Area

Primary Number	Survey No.	Name	Parcel Number(s)	Build Date	Resource Type	Previous Status Code
P-15-000129	1	Willow Springs; California Landmark #130	315-012-01, 252-341-05	ca. 1900– 1915	Site, District	7L
P-15-018681	2	LADWP Owens Gorge 230kV Transmission Line (contributing resource within the SCE Big Creek Hydroelectric System Historic District	-	1952– 1955	Structure	6Z-Segment previously evaluated is outside of Study area
P-54-005027	_	SCE Big Creek Hydroelectric System Historic District	_	1911– 1987	District	1S
P-15-017243	3	Vincent 220kV Transmission Line; Big Creek #3-Springville	315-230-10; 315-012-07	1925– 1927	Structure	1D
P-15-013833	4	General Petroleum Access Road	-	ca. 1915	Site	6Z-Segment previously evaluated is outside of Study area
P-15-020596	_	Access Road to SCE Big Creek Hydroelectric System Vincent 220kV Transmission Line	-	1927	Site	6Z

## 3.2 FIELD SURVEY METHODS

Intensive-level pedestrian survey of the API (Figure 3-1) from the public ROW was conducted on August 30, 2021 and March 29, 2022 by Ms. Granger and Mr. Mills. During the survey, high resolution photographs were taken of the properties determined to have extant buildings or structures at least 45 years old based on the records search results and desktop reconnaissance of the API. To thoroughly document the built environment resources and their settings, field notes were also taken. To determine whether the properties might be associated with a historic district, attention was paid to the setting, level of architectural cohesion, and historic integrity of the area. All field survey materials were reviewed by Ms. Demarais and Ms. Keethler as part of the evaluations of eligibility against CRHR eligibility criteria, assessment of potential impacts, and in the preparation of this report.

This page intentionally left blank.




Figure 3-1. Built environment Survey area.

# **4 HISTORIC CONTEXT**

# 4.1 SPANISH AND MEXICAN EXPLORATION AND SETTI EMENT IN THE MOJAVE DESERT

The earliest known European exploration of the Mojave Desert began during the sixteenth century at the time Spanish explorers first entered California and claimed it for Spain; however, sustained and widespread Euro-American settlement of the region did not occur until the late eighteenth and nineteenth centuries. Thus, exploration and settlement of the Mojave Desert by non-indigenous peoples can be best divided into three major categories defined by separate periods of Spanish (1769–1822), Mexican (1822–1848), and American (1848–Present) control.

The Spanish Period of exploration and settlement in the Mojave Desert began during the late eighteenth century when missionaries and explorers entered the region. Pedro Fages, who led an expedition into the western Mojave in 1772, was among the first Europeans in the area (Pourade 1960). In 1776, Franciscan missionary Francisco Garcés entered the area from New Mexico to explore overland routes between Santa Fe and Southern California (Coues 1900; Sutton 1991). The route used by Garcés became part of the Old Spanish Trail, a frequented historical pack mule trade route that passed through much of the Southwest and was first traversed by indigenous Mojave peoples. The Old Spanish Trail passes to the east and south of the Project area, leading south into the San Gabriel Valley. These portions of the trail are known as the Mojave Road and Mojave River Route (National Park Service [NPS] 2020:6).

During the eighteenth century, the establishment of Spanish missions and trade routes throughout the Mojave Desert region was difficult due to contention with indigenous Mojave peoples who hindered Spanish expansion into Mojave lands. Permanent settlement of non-indigenous populations in California during this era was also largely limited to lands near the Pacific coast by the rugged topography and weather of the High Desert region (Bean and Bourgeault 1989). Ongoing use and development of the Old Spanish Trail eventually made travel in the area much easier; however, the route was not firmly established until the 1830s (Norris and Carrico 1978).

After Mexico gained independence from Spain as a result of the Mexican War of Independence (1810–1821), Mexican Governor Pío Pico established a series of land grants, known as ranchos, throughout Southern California, or Alta California, as it was known at the time. The ranchos were granted as part of a movement to secularize former Spanish mission lands. Governor Pico granted many of these ranchos during the beginning of the Mexican American War (1846–1848), quickly dividing up Alta California to ensure Mexican land titles survived if the region were to come under U.S. control. The Antelope Valley is between two ranchos and remained public land. The Mexican American War officially ended in 1848 with the Treaty of Guadalupe Hidalgo and victory of the U.S. In 1850, California was officially admitted to the Union as a state (Los Angeles Cultural Heritage Masterplan 2000:15).

# 4.2 AMERICAN EXPLORATION AND SETTLEMENT IN THE MOJAVE DESERT

Euro-Americans migrated westward into California during the eighteenth and nineteenth century prior to California statehood through various roads and mountain passes such as the California Trail, Butterfield Overland Route, Donner Pass, Tejon Pass, and the Old Spanish Trail. American exploration into the Mojave Desert began with the entry of explorer and pioneer Jedediah Smith in 1826, and American migration and exploration into the region continued during the early nineteenth century (Pourade 1961). Smith and his party were the first Americans of European ancestry to enter the Mojave Desert, following the Old Spanish Trail, which runs south and east of the Project area (Beck and Haase 1974; Norris and Carrico 1978).

In 1843, American pioneer and explorer Joseph Walker and the Booneville Expedition traveled southward through the Sierra Nevada Mountains from Northern California along a Native American route. The party reached the Mojave Desert by way of a mountain pass in the southern Sierra Nevada Range that later became known as Walker Pass. The pass is approximately 55 mi north-northeast of the Project area. In 1844, explorer John C. Frémont also traveled to the Mojave Desert (Beck and Haase 1974; Frémont 1845). In 1845, Walker led Frémont through Walker Pass. After traveling to the area, Frémont named Kern County and Kern River for the topographer on the journey, Edward Kern (Barnard 1977). After 1860, Walker's Pass became a mining freight route to Owen's Valley and the Tehachapi Pass, to the southwest of Walker's Pass, became the most used travel route through the Sierra Nevada range to and from the Mojave Desert (California OHP 2021).

The Antelope Valley of the Mojave Desert remained sparsely populated throughout the nineteenth century, but the Homestead Act of 1862 and the Desert Land Act of 1877 generated some American settlement. Individuals could apply for land grants and would receive land in exchange for an agreement to improve the land. For example, under the Desert Land Act, settlers were required to irrigate and cultivate arid and semi-arid public lands to gain ownership. As a result, settlement in the Antelope Valley primarily followed agriculture, gas, and mining endeavors (Environmental Science Associates 2008:3.4–6). In 1866, Kern County was formed from portions of Los Angeles and Tulare counties.

## 4.2.1 Industry in the Antelope Valley

#### Mining

With the discovery of gold in the Sierra Nevada Mountains in 1848, an increase in American settlement in the California region began. The population of California continued to increase throughout the mid- and late nineteenth century, especially after the completion of the Transcontinental Railroad in 1869, even as the mining industry slowed in the later part of the century. Most early mining of gold, silver, and other minerals in California took place in the north, near Sacramento, but some mines were established as far south and east as the Mojave Desert and San Gabriel Mountains as miners became discouraged with unsuccessful attempts and an abundance of competition in Northern California.

In Kern County, gold and silver were discovered in the early 1850s. In addition to gold and silver mining, the western Mojave Desert became a major source of boron, the element for which Boron, California in eastern Kern County was named. The discovery of these resources led to

population growth and the formation of new wagon routes and stagecoach stops throughout the Antelope Valley. Various stagecoach companies, postal routes, and telegraph routes were created in areas that were formerly largely isolated using existing common travel routes to support mining operations and the communities spurred by the industry. Notable freight stagecoach companies that began operating in the western Mojave region included Wells, Fargo & Co. and Alexander & Banning. Overland Mail Company, a federally subsidized overland mail service founded in 1857, began serving the Antelope Valley. Subsequent railroads closely followed the alignment of many of these nineteenth century wagon routes and mining roads. One of the first major outposts supporting increased travel in the area was Fort Tejon, established in 1854 on the west end of the valley (Barnard 1977; California Department of Transportation [Caltrans] et al. 2010:36-37; Sherer 1994). Despite these commercial developments, the Mojave Desert remained sparsely populated until the twentieth century due to its hot and arid conditions as well as the absence of widespread water conveyance systems. Towns primarily grew between key areas of mining operations and along popular wagon routes, acting as stopovers for travelers and goods. The largest mining operations were in the eastern Mojave Desert while the most trafficked stagecoach routes ran through the western portion of the desert near the Project area (Rincon Consultants, Inc. 2021:37; Sherer 1994; Struglia et al. 2003:174-176).

#### Agriculture

Agriculture, to include both ranching and farming, has been an important part of California history. Although the Central Valley is the epicenter of California agriculture, agriculture was the main industry in the High Desert region from the late nineteenth to the late twentieth centuries. It continues to be an important industry into the twenty-first century, especially for smaller communities like Willow Springs, Little Rock, and Barstow, albeit not as prominently as it once occurred (University of California Cooperative Extension [UCCE] 2022).

One of the earliest forms of the agriculture practiced by Americans in the Antelope Valley was cattle ranching. This business originated before statehood and became the dominant industry of the region throughout the nineteenth century. The need for ranching greatly increased as the demand for meat and animal by-products boomed along with the state's population after the Gold Rush. Settlers mostly used cattle, sheep, and hogs for meat consumption, but sheep and cattle also provided a variety of other commodities such as wool, hides, and dairy for butter, cheese, and milk. American ranchers emigrating to California from the U.S. interior drove large herds of cattle to chase rising demand and prices. Drought and disease were two major challenges faced by ranchers as they met the imposing environments of the Mojave Desert, Death Valley, and the Sierra Nevada. Those that survived the journey established a variety of ranches that ranged from large corporate enterprises of hundreds of acres to mid-size ranches of about 40–160 acres or small "ranchettes" of 40 acres or less. During the 1920s, widespread economic issues and the severely decreased value of cattle made ranching less profitable, although it has remained in practice throughout the twentieth and twenty-first centuries (Caltrans 2007:82–84; LACountyLibrary.com 2021; NPS 2020).

Desert farming by American settlers was a crucial development in California during the nineteenth and twentieth centuries. Farming is still widely practiced in California, which boasts some of the largest irrigation districts in the U.S. and provides the country with over a third of its vegetables and two-thirds of its fruits and nuts. Most of the state's farming historically occurred and continues to be focused within the San Joaquin Valley, the southernmost part of

the Central Valley region, which includes parts of Fresno, Tulare, Imperial, and Kern counties. Land in the Central Valley and South Desert regions is fertile, but its lack of natural water was a major roadblock to both American company and family farms. The construction of water conveyance systems in the mid- to late nineteenth century allowed desert farming to become a reality. Between the 1910s and 1960s, large-scale water conveyance systems like the Central Valley Project, California State Water Project, and Los Angeles Aqueduct System were constructed throughout much of the state to consistently bring water to areas like the Central Valley and the Los Angeles Basin that lacked natural supplies of water. The Los Angeles Aqueduct system, completed in 1913, runs from Owners River in Central California to Los Angeles and crosses the westernmost portion of the Mojave Desert. The most common high desert crops include alfalfa, hay, onions, carrots, potatoes, peaches, pears, and nectarines. Agriculture continued to be practiced in the Antelope Valley throughout the twentieth century, though to a lesser extent after World War II (Caltrans 2007:25, 30, 63; Los Angeles County Agricultural Commissioner 2012:4–5).

#### 4.2.2 Infrastructure in the Antelope Valley

#### Railroads

Like the development of overland freight and travel routes, railroad construction was extremely influential to the character and development of desert towns in the Mojave Desert. The construction of railroads throughout the Antelope Valley coincided with the establishment of railroad lines throughout the state to support growing communities and industry. In 1854, an expedition led by Lieutenant Amiel Weeks Whipple sought to survey a railroad route leading from Arkansas to Los Angeles along the 35th parallel, near the Antelope and Fremont Valleys of the western Mojave Desert (Barnard 1977; Caltrans et al. 2010:36–37). Whipple's expedition included scientists who recorded information about the geology, climatology, and biology of the western Mojave Desert (Sherer 1994). Construction of the Southern Pacific Railroad (SPRR) through the Antelope Valley near the Project area was completed in 1876 as part of a connecting route between San Francisco and Los Angeles. Completion of the SPRR was a major development in the valley that provided foundation for new development.

The alignment of the SPRR in the valley passed through the newly established railroad towns of Rosamond and Lancaster, approximately 9 mi east and 15 mi southeast from the Project area, respectively (LACountyLibrary.com 2021; Lien 2021). The town of Mojave, approximately 10 mi north of the Project area, became a key stopover for travelers in the Antelope Valley during this period. The growth of the settlement was also connected to its proximity to the Santa Fe Railroad which could provide the town with various necessities more easily and affordably than other desert communities without their own major railroad stations. The other large town to develop in part due to railroad access was Bakersfield, which continued to grow during the twentieth and twenty-first centuries. Smaller towns and camps further from railroad lines throughout the valley also grew during the mid- to late nineteenth century, but this growth was limited in comparison to the communities with direct railroad access. There were upwards of 80 towns founded in the Antelope Valley by 1920, supported by traffic to nearby mines and routes to the Central Valley and Northern California. Although railroad development often led to the founding of new towns and population growth in others, in many instances new railroad lines were responsible for the demise of towns when the railroad entirely bypassed a community that was once a travel and trading center, like Willow Springs. Short lines and spurs

could be constructed to connect these isolated communities to a main railroad line, but not all towns could afford this development (Caltrans et al. 2010:13, 38–39, 46; Greene and Knight 1992).

#### Utilities

Implementing utility systems is an important part of community and regional development. Utility systems include resources for water storage and distribution, waste disposal, electric power distribution, and hydroelectric power distribution created by municipal or private entities (Caltrans et al. 2010:68, 118). Efforts to create utility systems in Californian towns began during the 1850s, beginning primarily with gas plants to provide indoor and outdoor lighting in place of oil lamps. Between 1840 and 1880, many gas companies were established in the state, and the use of gas lighting remained in widespread use through World War I. Electrical lighting was first introduced to California during the early 1880s; however, many rural communities did not acquire electricity until the twentieth century. Gas companies continued to form during the early twentieth century, during which time the first electric companies were established. Later in the twentieth century, many of these utility companies would be combined into large conglomerates, some of which still exist today. Progressive federal and state legislation and planning efforts aimed toward improving infrastructure also contributed to the fast development of transmission lines and other utilities in California during the twentieth century (Caltrans et al. 2010:68–69, 138).

In 1891, Southern California received its first long-distance electricity transmission line, the San Bernardino Light and Power Company's 5kV 28 mi transmission line between Pomona and San Bernardino. The first hydroelectric facility in the state opened in 1895 in Folsom, providing electricity to Sacramento 22 mi away. Transmission technology improved rapidly after the 1890s. One of the most significant advancements was the invention of the suspension insulator in 1907, which permitted long-distance transmission capacity to reach 100,000kV. This improvement led to the rapid construction of many transmission lines across the state between 1907-1920 (Caltrans et al. 2010:68-69). During the 1910s, California's first hydroelectric power project that used the suspension insulator was undertaken (Big Creek Hydroelectric System). The Big Creek Hydroelectric System, when paired with the Los Angeles Aqueduct System, would harness water from the Owens River in the Sierra Nevada to provide electric power to Los Angeles. The Big Creek Hydroelectric System was first put in service in 1912–1913 and quickly became central to Southern California's energy transmission advancement. (Caltrans et al. 2010:138, Tinsley Becker and Chiang 2016:1-2). A segment of the Vincent 220kV Transmission Line (constructed 1925–1927) of the Big Creek Hydroelectric System runs through the eastern portion of the Project area, less than a mile west of the Willow Springs townsite (Dice 2014).

The first wind power project in the Antelope Valley was constructed at the base of the Tehachapi Mountains, north of the Project area in the early 1980s. The windy Tehachapi Pass in the Mojave Desert proved to be a valuable resource on the barren landscape. More wind and eventually solar farms were built in Tehachapi Pass and Antelope Valley over the following decades. In 2011, Avangrid Renewables broke ground west of the Project area on the 80-mi² Manzana Wind Power Project for 126 1.5-MW wind turbines that came online in December 2012. The company sells electrical output to San Diego Gas and Electric, Silicon Valley Power, and LADWP. The SCE Whirlwind Substation at the southwest corner of the Project area was constructed in 2011 as part of a long-range SCE wind farm plan that connects a series of

substations through 500kV transmission lines and brings wind power to the Los Angeles Basin. Between 2013 and 2015, several large solar farms have been installed in the vicinity of the Project area, south of Rosamond Boulevard (AvangridRenewables.com 2021; Edison International 2021; Google Earth Pro 2013, 2015; Palm Desert Post 1982).

#### 4.3 HISTORY OF WILLOW SPRINGS

The opportunistic founding of towns by both individuals and large developers is a key characteristic of frontier colonization in California. Many communities in California, therefore, have a shared history in the evolution of transportation networks, natural water features, water conveyance projects, agriculture, mining, and development of energy resources. Although Willow Springs is a very small community, it too reflects many of California's, and particularly its High Desert, developmental trends of the nineteenth and twentieth centuries. Specifically, the evolution of Willow Springs reflects the ad-hoc development approach typical of rural Californian townsites. Willow Springs, like most small California towns founded during the nineteenth century, would also grow and decline based on factors like industry conditions and railroad access, or lack thereof (Caltrans et al. 2010:142–143). In 1934, Willow Springs became California Historic Landmark #130 (California OHP 2021).

#### 4.3.1 Community Development (ca. 1850–1918)

The springs at Willow Springs were a natural water feature that was first depicted next to "Tehicipi Road" [sic] between Elizabeth Lake and Oak Creek in an 1856 General Land Office (GLO) map of Township 9 North, Range 13 East within the San Bernardino Meridian (GLO 1856). Willow Springs was one of three natural oases in the Antelope Valley and thus made an ideal stopping point in the Mojave Desert, which resulted in the founding of a community and construction of a stagecoach station near the springs. Without the springs, early travelers through the Mojave Desert would have faced even more grueling and deadly conditions. Even before the first stagecoach station was built, the springs provided respite to a variety of travelers from different cultures using local overland trails.

The first recorded mention of Willow Springs dates to 1776, when Friar Garcés stopped at the springs. Explorer and pioneer John C. Frémont also stopped there in 1844. The discovery of gold along the Kern River in the 1850s led to an influx of visitors to the springs looking for water during their pursuit of gold and other valuable minerals. In 1862, Willow Springs was transferred from public to private land when it was awarded to General Edward Fitzgerald Beale. The Willow Springs stagecoach station and the springs themselves remained a sought-after stopping point throughout the 1860s, providing clean water to an increasing number of miners and cattle ranchers moving across the region during the late nineteenth century. (Bostwick 2010; Lien 2021). Due to right of way disputes with Beale, the SPRR planned to bypass Willow Springs and instead route through Rosamond to the east as it traversed the Antelope Valley. Completion of the SPRR in 1876 would have a profound effect upon the community (Lien 2021).

Willow Springs soon attracted Nelson and Adelia Ward, who are the next known owners of the land. The Wards purchased Willow Springs and endeavored to capitalize on the popularity of the natural waters by further developing the area. The Wards built an adobe boarding house next to the springs in support of the stagecoach station, which they used to host freighters, travelers, and temporarily house horse and mule teams making their way across the region

along the Los-Angeles-Havilah and Inyo Stage Lines. The accommodations were small compared to the rate of local traffic across the two routes, which were primarily in use from 1864 to 1872, earning the boarding house the unofficial name "Hotel de Rush." In 1875, two years after the death of Nelson Ward, the silver freighting company, Cerro Gordo Freighting Company, chose a new route that bypassed Willow Springs, which resulted in less traffic to the Wards' boarding house and the stagecoach station. The loss of income prompted Adelia Ward to sell the land and move elsewhere with her surviving family. The new owners, a couple only documented by the surname Riley, operated the station for one year until completion of the SPRR through Rosamond in 1876 made stagecoach travel through Willow Springs effectively obsolete (Bostwick 2010; GLO 1856; Lien 2021). By the 1880s, the adobe boarding house was in ruins (Bostwick 2010).

After completion of the SPRR through the Antelope Valley, Willow Springs was essentially abandoned until 1900 when pioneer and stonemason Ezra Hamilton purchased the springs and the surrounding 160 acres. Hamilton struck gold a few miles east of Willow Springs four years earlier and wanted a set up his own gold mill. However, enamored with the oasis in the desert landscape, Hamilton sold his mine and used the proceeds to settle there with his family and built a resort, beginning with a hotel for up to 30 guests. The resort thrived and served as a gathering place for long-range travelers and settlers within the surrounding 15 mi. The hotel was named Hotel Rosamond and was equipped with fresh ice and flush toilets (Lien 2021; Orr 2021a). Historical photos of the hotel (Figure 4-1) show that, like most original buildings built in Willow Springs, Hotel Rosamond was of stone construction. The hotel is no longer extant.

Hamilton desired to make Willow Springs a true town, and thus invested further to build necessary amenities such as a school, restaurant, general store, an auditorium, water reservoirs, and a swimming pool. He also built greenhouses to stock the restaurant and store with fresh produce, and he experimented with silkworms for silk production. Believing the springs and desert air should be accessible to anyone needing healing, Hamilton built homes and cottages that could be rented for a modest fee. From 1900-1915, other families also settled near the resort, populating the burgeoning town. In total, during this time Hamilton invested approximately \$40,000 and built 27 stone buildings including cottages, a hotel, a stone schoolhouse, a sanitorium, an opera house, and a concrete-lined swimming pool (Bostwick 2010; Lien 2021). Like the Hotel Rosamond, historical photos indicate that most, if not all, of these structures were stone with wood roofs. The swimming pool is depicted as a round structure adjacent to a stone well. The cabins and homes in surviving photos appear nearly identical with modest single-story rectangular plans, stone chimneys, and wood doors and roofs (Figure 4-2 and Figure 4-3). By July 1904, Willow Springs had upwards of 50 residents including Hamilton, his new bride Eliza Galloway, and his adult children from a previous marriage (Bakersfield Morning Echo 1904:4). Willow Springs also gained a post office in 1909, and as Ezra Hamilton was the first person in Antelope Valley to own an automobile, he built a garage and gas pump in the community. Hamilton died in 1915, and his heirs closed and sold the resort village three years later. Willow Springs and the immediately surrounding area where other families had settled would eventually be incorporated into the town of Rosamond, which the SPRR founded in 1877 (The Bakersfield Californian 1938:5; Lien 2021; Orr 2021b).



Figure 4-1. Hotel Rosamond (ca. 1905).



Figure 4-2. Standard cottages at Willow Springs (ca 1905).



Figure 4-3. Residence at Willow Springs (ca. 1905).

# 4.3.2 Community Development (1918–1975)

The village of Willow Springs was sold multiple times between 1918 and 1947, but people continued living there under leases regardless of ownership or economic circumstances. The growing accessibility of automobile travel and improvements in water conveyance meant that stopping at Willow Springs, one of the few natural springs in the western Mojave Desert, was no longer a necessary part of travel through the region. Additionally, since World War II, the springs have been severely depleted due to drought; the most recent previous survey of Willow Springs indicated that the smaller springs had gone entirely dry by 1992 and the others were at risk of depletion. Due to these changes, development and population growth in Willow Springs and its immediate surrounding area was slow throughout much of the twentieth century (California OHP 2021; Tipton 1988). Agriculture remained a primary industry in Kern County, but the growth of the aerospace industry has been a major change to the economic landscape of the region in the twentieth century. Agriculture in Willow Springs and its immediate surrounding area has remained a steady, yet small contributor to the industry of the region. Pears were once one of the major crops grown in Willow Springs (Caltrans 2008:17–18; Dunne 2016; Greene and Knight 1992; Tipton 1988).

The early twentieth century saw a new wave of mining in California, although not to the extent of the Gold Rush. Although many mines had closed by 1910, some remained in the Mojave Desert, including the Tropico Mine near Willow Springs (formerly named the Lida Mine named by Ezra Hamilton for his wife) that continued to be mined well into the 1930s. The Tropico mine was sold to various owners since it was first purchased in 1882. It continued in operation until

1956 despite a brief closure during World War II (Environmental Science Associates 2008:3.4–7). U.S. involvement in World War II during the 1940s created a need for more raw ore materials, a demand that benefited the mining industry across California (Caltrans 2008:17–18; Dunne 2016; Tipton 1988).

The Willow Springs Company began mining operations in 1932 from its headquarters in the community. Stockholders in the Willow Springs Company, Robert and Mary Nelson, purchased the Willow Springs property in 1947 and moved into one of the existing stone houses. Over the years they leased out many of the buildings on the property, including the restaurant. Most of the land that once comprised Willow Springs is still owned by the Nelson family, and much of the information known about the history of the settlement has come from accounts of the Nelson family and their time among Ezra Hamilton's children. Some of the original stone buildings in the community were destroyed by the Tehachapi earthquake of 1952, but sixteen remain in good physical condition including the Old Meeting Hall and a community gathering space (California OHP 2021; Tipton 1988).

Although Willow Springs remained predominantly unchanged during much of the twentieth century, two new nearby developments during this period affected the settlement. Muroc Army Air Field was established approximately 15 mi east of Willow Springs and Rosamond. The base, which would later become Edwards Air Force Base (EAFB), opened in 1932 and helped to bring more traffic to the Willow Springs area despite the loss of its main draws for long-range travelers and local visitors. In subsequent years, EAFB attracted settlers and investment in infrastructure, providing an economic boon to the region; however, central Rosamond and Lancaster saw the greatest economic benefits and population growth (California OHP 2021; Tipton 1988). This population boom sparked the demand for reliable infrastructure like electricity, a need that occurred nationwide. To meet this need, President Roosevelt signed the Rural Electrification Act (REA) into law in 1936 and the Willow Springs area received electricity shortly after the legislation was enacted (Barnes 2007).

In 1953, the Willow Springs International Raceway opened approximately 1.25 mi west of Willow Springs. At the time, there was little residential or commercial development around Willow Springs except for a few small desert homesteaders and other farms with newly installed irrigation equipment. During the 1960s, a series of new grided streets were cut in the area around Willow Spring and the raceway, apparently in anticipation for increased residential growth. Ultimately, few residences were built and the majority of constructed between 1960 and 1965 were centered in a small area in the Project area bound by Irone Avenue, Melody Lane, 145th Street West, and 140th Street West. New residences built during this period were primarily single-story, single-family vernacular buildings on parcels of five acres or less. Although most of these residences are devoid of a particular recognizable architectural style, they reflect common materials and basic forms used throughout Southern California, giving many a distinct rural vernacular Californian appearance commonly identified in similar communities (HistoricAerials.com 1959, 1963; Kern County Recorder 1960; UCSB Library 1952a, 1952b).

# 5 HISTORIC ARCHITECTURAL FIELD SURVEY RESULTS

Results from the field survey of the of the historic architectural resources in the API provided details for the property descriptions and evaluations of eligibility under CRHR criteria. A total of 23 properties with extant built environment resources 45 years old or older are within, or intersect portions of, the API (Table 5-1). The locations of all surveyed properties are indicated in Figure 5-1 by the map numbers indicated in Table 5-1. Of these 23 resources, four have been previously recorded and evaluated for CRHR-eligibility, though these evaluations did not include segments within the API except for Willow Springs Village and the Vincent 220kV Transmission Line (Big Creek #3-Springville) of the SCE Big Creek Hydroelectric System Historic District. Three properties were inaccessible from the ROW due to obstructions or safety concerns and are thus indicated in Table 5-1 as surveyed only at the reconnaissance level. To comply with CEQA and ensure due diligence was performed to the extent mandated, the inaccessible properties were assumed to be CRHR-eligible. Thus, these three inaccessible properties are included in the assessment of potential impacts to historical resources.

Table 5-1. Surveyed Cultural Resources in the API

Survey Map No.	Name	Parcel Number(s)	Build Date	Resource Type	Survey Type
1	Willow Springs; California Landmark #130	315-012-01, 252-341-05, 315-012-02	ca. 1900– 1915	Site, District	Intensive
2	Segment of the LADWP Easement Corridor (LADWP Owens Gorge 230kV Transmission Line; Owens Gorge Access Road)	_	1952–1955	Structure, Site	Intensive
3	Segment of the Vincent 220kV Transmission Line, Big Creek #3- Springville; SCE Big Creek Hydroelectric System Historic District	315-230-10; 315-012-07	1925–1927	Structure; District	Intensive
4	General Petroleum Access Road	_	ca. 1915	Site	Intensive
5	14205 Irone Avenue	358-132-12	1957	Building	Intensive
6	4040 Manly Road	315-012-01, 252-341-05	ca. 1970	Building	Intensive
7	14101 Irone Avenue	358-132-10	ca. 1970	Building	Intensive
8	14070 Lodestar Avenue	358-132-07	1946	Building	Intensive
9	10145 Hamilton Road	358-052-08	ca. 1960	Building	Intensive
10	10085 Hamilton Road	358-052-07	1940	Building	Reconnaissance
11	10057 Hamilton Road	358-052-06	1951	Building	Reconnaissance
12	9714 Rosamond Boulevard	374-042-03	1919	Building	Intensive

Survey Map No.	Name	Parcel Number(s)	Build Date	Resource Type	Survey Type
13	9668 Rosamond Boulevard	374-042-04	1921	Building	Intensive
14	9650 West Rosamond Boulevard	374-042-39	1950	Building	Intensive
15	9580 Rosamond Boulevard	374-042-07	1955	Building	Intensive
16	9009 Rosamond Boulevard	252-352-33	1959	Building	Intensive
17	3045 90th Street West/High Desert Cellars	252-352-32	1956	Building	Intensive
18	2973 95th Street	374-042-08	1942	Building	Intensive
19	2860 West 100th Street	374-041-09	1940	Building	Intensive
20	Unknown	358-131-02	1949	Building	Reconnaissance

# 5.1 PROPERTY DESCRIPTIONS

Descriptions of all surveyed properties with extant built environment resources 45 years old or older are included in the following sections. See Appendix A for additional photographs of the surveyed properties.

# 5.1.1 Willow Springs, California Landmark #130 (P-15-000129)

Willow Springs Village is a historic period American rural residential settlement in the vicinity of natural springs in the western Mojave Desert, identified as a California Historical Landmark (#130) in 1934, prior to the creation of the CRHR. The site was subsequently documented in 1959, 1965, 1980, and 1992. The springs were also known by the name Willow Springs, but no evidence of remaining springs was found during field survey. Water of the springs originated in the Tehachapi Mountains and flowed through Oak Creek to the village. The center of the village is approximately 0.25-mi north of Truman Road. The land surrounding the springs was first settled sparsely by Euro-Americans during the late nineteenth century, and the area developed into a small village at the beginning on the twentieth century. At the time of survey, there were 23 remaining buildings and structures built during the original settlement period (ca. 1860–1900). The identified architectural resources included 16 standing unreinforced masonry buildings (one of which is in a state of substantial disrepair), two architectural ruins, four stone wells, one round concrete-lined pool, and a stone fence with a wooden gate. There is also a known cemetery attributed to the village (P-15-003560), but no headstones remain.




Figure 5-1. Built environment survey results.

The setting is rural and agricultural with a mixture of open undeveloped land, farmland, residences, ancillary buildings, and various buildings no longer in use but are believed to have been additional residences and community buildings (Figure 5-2). There are various dirt roads as well as one paved road (Manly Road) throughout the site. Most of the roads are lined with planted trees. The landscape is defined by gentle hills and winding roads that provide a rustic and picturesque feeling. Vegetation includes a mixture of native grasses, shrubs, and trees as well as designed rows of shrubs flanking roadways. The vegetation is consistent with designed landscaping and permaculture in Southern Californian deserts, using predominantly low-water plants such as Oleander, Eucalyptus, and Joshua Trees. Vegetation includes freely growing native grasses, trees, and shrubs; limited decorative plantings of low-water and drought-resistant plants; and plantings of shrubs and trees along roads, property boundaries, and residences to serve as windbreaks and prevent flash-flooding of sandy soils in the event of rain. Overall, the district has a high level of cohesion, tied together by the rural desert landscape, density of development, the use of masonry construction materials, and the shared scale and massing of the buildings.



Figure 5-2. Partial overview of Willow Springs Village along Manly Road, facing northeast.

The extent of the village during its formal years of early development (ca. 1900–1915) is believed to have been approximately ¼ mi² based on previous documentation by archaeologists and historians; however, no primary source maps or descriptions of the village's original boundary have been uncovered. Remains of a school and a known burial site indicate areas of the village beyond the primary grouping of buildings flanking Manly Road and a possibly larger boundary than previously recorded. The boundary was drawn in consideration of both this recorded 0.25-mi² boundary estimate and the locations of known cultural resources. As to not

include speculation, the boundary drawn possibly excludes land that may have once been within the Willow Springs Village but cannot be proven to or presumed as such. Additional areas that could be reasonably believed to have been part of the village but are excluded from the boundary are APNs 252-012-02, 252-341-07, 252-341-04, 315-152-01 through 315-152-08, and the full extent of 252-351-48. The boundary of Willow Springs Village is depicted on the Survey Results Map (Figure 5-1). The boundary includes all of Assessor Parcel Number (APN) 315-012-01 (73.85 acres) and APN 315-012-02 (0.79 acres) as well as portions of APN 252-341-06 and APN 252-351-48 where extant original site elements were identified.

#### Residence A (Building 1)

Residence A is a one-story single-family residence at the southern boundary of APN 315-012-01. There are nine ancillary buildings adjacent to Residence A, seven of which are original village masonry buildings dating to circa 1900–1915. The residence has a t-shaped plan. Architectural features include a corrugated metal cross-gable roof and fieldstone masonry exterior walls. The north (primary) façade features a concrete slab front porch covered by a front-gable roof projection with closed wooden eaves. The porch roof is supported by simple wood Y-shaped columns. The east façade of the east-west wing has a stone exterior chimney. The visible windows are a mixture of double-hung and horizontal slider types composed of white aluminum frames and wood surrounds. The north side of the residence is set behind 3-ft-tall fiberglass fencing. Landscaping includes native trees and shrubs as well as a palm tree. Ancillary stone buildings are to the east and south of Residence A.

#### Old Meeting Hall (Building 3)

The Old Meeting Hall is a one and one-half story rectangular plan building with a side gable roof. It is immediately north of Manly Road and northeast of Residence A. The Old Meeting Hall is of fieldstone construction and has a wood framed roof with exposed wood rafter tails and corrugated metal sheets for roof cladding. The south (primary) façade features concrete steps that lead to a full porch constructed of open poured concrete block and wooden double batwing doors that serve as the primary entrance. The batwing doors are inset into a small stone projection covered by a shed-shaped roof extension. Historical photos indicate the entrance originally featured a front gable while the main roof was hipped. The concrete steps are flanked by metal tube railings. There are two additional entrances on the south façade, a glass inset divided-light wood door and a faux-paneled fiberglass door. Each door is topped with a singlelite transom. The south façade also features a small horizontal-oriented fixed window and a tall double-hung window. The windows of the east and west façades are all tall double-hung wood frame types. The east façade has a wooden exterior stairway that leads to a flat wood door. A window insert air-conditioning unit is above the door, blocking off what was likely a single-lite transom. The wood paneling and wood-frame windows beneath the side gables on the east and west façades are not original.

#### **Building 2**

Building 2 is a long rectangular plan one-story utilitarian structure with a corrugated metal side gable roof. The name "Willow Springs" is emblazoned across the southern slant of the roof, though the signage is faded. Circulation vents are below each gable end. The exterior of the building is composed of white limestone block. The south (primary) façade features two single personnel entrance doors and four metal double doors with iron strap hinges. One personnel

door is flat metal and the other is wooden with a square glass insert. The building is approximately 115 ft wide by 25 ft deep. Windows are double-hung with wooden frames.

#### Building 4

Building 4 is a rectangular plan one-story utilitarian structure with a corrugated metal side gable roof. The exterior of the building is composed of white limestone block. The wood paneling on the front (south) gable is not original. The south façade features a single personnel entrance door with a single fixed window on the gable. The west façade features a single fixed window, and the east façade features two single personnel entrance doors. The building is approximately 45 ft wide by 18 ft deep.

#### **Building 5**

Building 5 is a rectangular plan one-story utilitarian structure identical to Building 4 except for altered dimensions: approximately 29 ft wide by 19 ft deep.

#### Pool

The concrete-lined pool is in an orchard between Manly Road and Tehachapi-Willow Springs Road. The extant structure is 50 ft in diameter and is believed to be original to the resort built by Ezra Hamilton circa 1900–1915 based on historical photos. It is not possible to see if the bottom interior of the pool is concrete lined because it is filled with dirt and vegetation.

#### Wells

The four extant wells are above ground fieldstone structures within orchards on the east and west sides of Manly Road. Two wells are 20 ft in diameter, one well is 30 ft in diameter, and one is 5 ft in diameter. The wells stand approximately 4 ft above the ground. Historical aerial photographs indicate the wells have been present since at least the 1930s and were most likely constructed at the time the other fieldstone structures at the site. Historical photos show at least one well had been constructed in the village by 1903.

#### School Ruin

The school ruin consists of a partial collapsed fieldstone masonry building that served as the local school building during the early twentieth century. The ruin is east of Tehachapi-Willow Springs Road at the eastern end of APN 315-012-01. Small portions of the east, west, and south façades remain, and the roof and north wall are entirely collapsed. A doorway-sized opening with wood framing is present on the remaining portion of the south façade, which is believed to have been the primary façade. Two steps lead up to the entrance.

# Unidentified masonry ruin

An unidentified masonry ruin is west of Manly Road. The ruin is difficult to see from the ROW but appears to be of fieldstone construction with at least half of two walls, the north and east façades, remaining. The original use of the structure is unknown based on available data.

#### Buildings 6-12

Buildings 6–12 are south of Manly Road across the street from the Old Meeting Hall. The buildings are all one-story utilitarian structures with a corrugated metal side gable roof. The exterior of the buildings is composed of white limestone block. They are rectangular in shape, except for Building 6, Building 7, and Building 11. Building 6 has a recent addition, rectangular in shape, added to the south façade and is constructed of concrete stone masonry. Building 7 is L-shaped and appears to be in its original form. Building 11 has a recent addition to the west façade that converted the original rectangular shaped building to a T-shaped structure. A fieldstone chimney is found on the west façade of Building 6, while building 11 has a chimney on the north and south façade. The windows are a mixture of double-hung, horizontal slider, and fixed types. Doors are single personnel entry doors of wood or metal.

#### **Building 13**

Building 13 is a dilapidated one-story building of stone construction between Manly Road and Tehachapi-Willow Springs Road. The building has a rectangular plan and a hipped wood shingle roof that extends over an open porch supported by wood columns; though many shingles are missing, the wooden roof framing remains. The porch spans the south façade, which also likely housed the primary entrance. All windows and doors are missing, but fenestration openings and some wood framing remain. There are wood lintels above the window openings and the openings are not boarded over. Architectural features include fieldstone masonry and a wood single roof. The north façade features a large wood-framed opening for a door, but no door is present.

#### Residence B (Building 14)

Building 14 is a one-story building of stone construction west of Manly Road. The building has a rectangular plan and a corrugated metal side gable roof that extends over an open porch supported by wood columns. The porch spans the east façade, which also contains the single personnel entry door and two double hung windows. Architectural features include fieldstone masonry and fieldstone chimney on the south façade. An extension has been added to the rear (west) façade of the building. It is constructed of brick and not original.

#### Residence C (Building 16)

Building 16 is a one-story building of stone construction west of Manly Road. The building has a rectangular plan and a corrugated metal side gable roof. The south (primary) and north façades appear to be recent extensions, are wood paneled, and likely enclosed open porches present in other houses in Willow Springs. A single wood personnel entry door is present on the south façade. The windows are a mixture of double hung, horizontal slider, and fixed types.

#### Residence D

Residence D is a rustic one-story single-family residence with a roughly L-shaped plan and a cross-gable metal panel roof. Kern County aerials indicate that the metal roof is a recent alteration made some time after January 2020. The residence lies west of Manly Road can be accessed from the north or south via dirt roads lined with planted trees. A porch on the north (primary) façade of the house is covered by a roof extension supported by simple wood columns. Only the north façade was clearly visible at the time of survey. Additional features

noted included closed slightly overhanging wood eaves, double-hung windows (likely either aluminum or vinyl but unclear due to distance from ROW), decorative plantings, and loose stone landscaping. The original portion of the residence is of fieldstone construction, but additions with pale brick cladding have been added over the lifetime of the building to both the west and north façades. In the absence of historic photographs and due to the tree coverage of historic aerials, a specific date(s) of these alterations is unclear; however, no additions are present on an aerial from 1972 where there is a clear view of the residence, indicating these were relatively recent alterations.

Additional materials, window types, and other architectural features may be present on façades not observed from the ROW.

#### Stone Fence

The fieldstone fence at Manly Road extends from Buildings 4 and 5, enclosing a square-shaped field with both buildings contributing to the southern boundary of the enclosure. There are two extant wood gates along the southern boundary and a break in the fence along the western wall where another gate likely was.

#### Cemetery (P-15-003560)

A historic cemetery on a low ridge east of Willow Springs is associated with the village. Though no headstones remain, records from previous surveys indicate several individuals were buried there, including at least one local resident, Ray Conary (Feb. 1, 1890–Jan. 28, 1906), a 17-year-old sign painter who died of tuberculosis. The site remains unchanged since its previous documentation in 2017 by ASM Affiliates.

#### Historical Marker (1937)

The historical marker from 1937 honors the stage station and town of Willow Springs. The monument is constructed of concrete with an inset bronze plaque.

#### Historical Marker (1951)

The historical marker from 1951 recognizes the town of Willow Springs as a California Historic Landmark. The monument is constructed of fieldstone masonry with an inset bronze plaque.

# 5.1.2 LADWP Owens Valley 230kV Transmission Line Easement Corridor (P-15-018681)

PaleoWest surveyed approximately 2.16 mi of the LADWP Owens Gorge Transmission Line that is between Rosamond Boulevard and Hamilton Road in Rosamond, California (segment). The segment appears similar to portions of the line previously recorded, consisting of utilitarian deadend type towers. The Owens Gorge 230kV Transmission Line, otherwise known as OGRIN and most recently known as BAR-RIN, was built between 1950 and 1952. This transmission line originally connected three LADWP powerplants in the Owens River Gorge. These powerplants were northwest of Bishop, California and were connected to Receiving Station E in Whitnall and Cahuenga in Toluca Lake. Some modifications were made to the line during the mid-1950s and 1960s to accommodate the increase in suburban development (Dice 2014). Roadway sediments consist of light gray-tan sandy gravely loam. No artifacts were

found in association with the access road. The road consists of an actively used and maintained graded dirt road that averages 10 ft wide. Roadway sediments consist of light gray-tan sandy gravely loam. No artifacts were found in association with the access road.

# 5.1.3 Vincent 2206V Transmission Line, Big Creek #3-Springville (P-15-017243) / SCE Big Creek Hydroelectric System Historic District

The Vincent 220kV Transmission Line is a steel lattice tower transmission line constructed in 1925–1927 near present-day La Canada in Los Angeles, California. The transmission line is part of the SCE Big Creek Hydroelectric System which is a NRHP/CRHR Historic District, and the line was deemed eligible as a contributor to the district. PaleoWest surveyed a segment of the transmission line within the API near the community of Willow Springs. The transmission line originally included approximately 879 steel lattice transmission towers, of which 866 were extant in 2012. The design of the towers, depicted at the center of Figure 5-3, became known as the Vincent Type during the twentieth century. The transmission towers span 224 mi and is larger than the earlier Big Creek No. 1 and No. 2 lines that were installed between 1913 and 1922. Only about 0.55 mi of the Vincent transmission line runs through the API near the Whirlwind Substation in the southwestern corner of the Project area. The transmission line runs from the southeast to the northwest through the western edge of the Project area.



Figure 5-3. Overview of the Willow Springs Segment of the Vincent 220kV Transmission Line.

# 5.1.4 General Petroleum Access Road (P-15-013833)

PaleoWest documented a 1.56-mi-long section of the General Petroleum Access Road (CA-KER-7747H) on 4/26/2022 that ran from the SCE Whirlwind Substation south of Rosamond Boulevard in a northeast direction to 160th Street West. Although portions of the road have been previously recorded by ICF International and SWCA Environmental Consultants, the segment that is within Sections 13 and 23, Township 9 N, Range 15 W, had not been documented. The newly recorded segment consists of an actively used and maintained graded dirt road that averages 10 ft wide (Figure 5-4). Portions of the road in the vicinity of the Whirlwind Substation have been graveled (see photographs on Continuation Form). The road is adjacent to a Southern California Edison transmission line. Roadway sediments consist of light gray-tan sandy gravely loam. No artifacts were found in association with the access road.



Figure 5-4. Overview of the Willow Springs Segment of General Petroleum Access Road.

#### 5.1.5 14205 Irone Avenue (358-132-12)

The subject property (14205 Irone Avenue) is composed of a vernacular one-story, 567-ft² single-family residence on a 5-acre parcel constructed in 1957 (Figure 5-5). Landscaping consists of grasses and shrubs growing freely as well as trees planted around the residence and ancillary buildings. There is also a planting of windbreak trees around the residence. The residence has a rectangular plan, a composite shingle cross-gable roof, frame sliding and casement windows, and concrete block exterior walls. Other features include exposed rafter tails, wooden eaves, horizontal decorative wood paneling beneath the gables, square wood vents beneath the gables, and a wood inset-panel entry door. There was a travel trailer visible directly to the west of the residence at the time of survey. A single bay detached garage is the

west of the trailer. The garage has a single lift-up garage door clad in horizontal wood planks, a side gable composite shingle roof, wooden eaves, and exposed rafter tails. There are horizontal wood planks and wood vents beneath the gables of the garage, and the façades are clad with corrugated metal panels. A 2020 aerial from Kern County shows several outbuildings extent on the property; however, no additional ancillary buildings are clearly visible from the ROW.



Figure 5-5. Property overview of 14205 Irone Avenue, facing north.

# 5.1.6 4040 Manly Road (315-012-01, 315-012-02, 252-341-05)

The subject property (4040 Manly Road) consists of three single-family residences on two parcels shared with buildings of the Willow Springs Village (P-15-000129). These buildings were constructed after the decline of the village and are not directly associated with the village historically and were thus recorded separately (Figure 5-19). The three residences lie east of Manly Road and west of Tehachapi-Willow Springs Road. Residences 1 and 2 are within APN 252-341-05 and Residence 3 is within APN 315-012-01. Visibility was limited due to the topography and vegetation. All three buildings are vernacular in nature and lacking a distinct architectural style.



Figure 5-6. Overview of Residences 1 and 2 on APN 252-341-05, facing southeast.

#### 5.1.7 14101 Irone Avenue (358-132-10)

The subject property at 14101 Irone Avenue is composed of two buildings, a single-family residence and an adjacent detached garage on concrete slab foundations, on a flat rectangular five-acre parcel (Figure 5-6). Both buildings and a water tank are on the southern half of the property, which is enclosed in chain-link fencing. The northern half of the parcel is open and undeveloped. The property is accessible via a dirt driveway from Irone Avenue. The residence and garage are partially enclosed by wood and chain-link fencing within the chain-link fence of the southern half of the parcel. The residence is a roughly L-shaped single-story California bungalow of 1,069 ft<sup>2</sup>. The bungalow features a cross-gable gray composite shingle roof, smooth white stucco cladding, aluminum horizontal slider windows, and a primary (southern) entry food with a half-moon fixed inset window. There is also an entry door on the north facade. Photos from 2012 show wood ornamental shutters flanking each window, but no extant shutters were visible during survey. The detached garage has been converted into occupiable space and is immediately northwest of the residence. Photos from 2012 indicate the garage's two-bay opening had been altered to a single standard wood entry door and white wood siding. The garage features a medium-pitch side gable roof of composite gray shingle, exposed rafter tails, and smooth white stucco cladding.



Figure 5-7. Property overview of 14101 Irone Avenue facing north showing the south façade.

# 5.1.8 14070 Lodestar Avenue (358-132-07)

The subject property (14070 Lodestar Avenue) consists of a one-story 2,295-ft² single-family residence on a 5-acre parcel. The vernacular Ranch style was constructed in 1946 (Figure 5-7). Landscaping consists of grasses and shrubs growing freely throughout the property and a small grouping of trees and shrubs planted around the residence. The residence features an L-shaped plan, a cross-gable asphalt shingle roof with rectangular attic vents beneath each gable, a recessed carport with wood support columns, a shed roof extension entry porch with Y-beam wood support columns, one-over-one metal frame double hung windows, decorative shutters, one-over-one metal frame sliding windows, and stucco exterior walls. The main entryway is on the north and consists of a single entry-door covered with an additional screen exterior door. The east façade features a recessed carport/side porch with wood support columns and two windows. There is a one-by-one vinyl horizontal sliding window beneath the gable on the east façade which may indicate a finished attic or additional living space. The south (rear) façade features a wing extension, a secondary entrance with concrete steps, and at least one window. There are two outbuildings attributed to this property based on 2020 aerial photographs, but no ancillary buildings were visible from the ROW.



Figure 5-8. Property overview of 14070 Lodestar Avenue, facing southwest.

#### 5.1.9 10145 Hamilton Road (358-052-08)

The subject property (10145 Hamilton Road) is composed of a vernacular California Bungalow one-story single-family residence with a single ancillary outbuilding (Figure 5-8). The property is currently vacant and is accessible from Hamilton Road to the south and from 90th Avenue to the east. Landscaping consists of natural landscaping with native trees, shrubs, and grasses growing freely across the property. The residence has a rectangular plan, a metal front-gable roof with rectangular attic vents and exposed rafter tails in the roof eaves, a front-gable roof enclosed entry extension, two-over-two double-hung wooden windows with missing glass, and a large entry bay with an opening which is missing a door (or doors). The exterior walls of the main house are primarily clad in flat stucco, except for the enclosed porch entry which has horizontal wood plank siding. The south façade is the only elevation visible from the ROW and appears to serve as the primary entrance. The ancillary barn, directly to the west of the single-family residence features a rectangular-shaped plan, a tin front-gable roof, wood siding, and a window wall on the east and west façades.



Figure 5-9. Property overview of 10145 Hamilton Road facing north.

#### 5.1.10 10085 Hamilton Road (358-052-07)

The subject property (10085 Hamilton Road) is composed of a one-story vernacular single-family residence on a 9.78-acre parcel (Figure 5-9). The residence was constructed in 1940 and consists of 1,408 ft². The property is accessible from Hamilton Road to the south and from 90th Avenue to the west. Landscaping consists of natural landscaping with native trees, shrubs and grasses growing freely across the property. The residence has an irregular rectangular plan with additions, a side-gable roof, two brick masonry chimneys, and exterior walls clad in stucco. This residence is set back a distance on the parcel and very difficult to visually assess from the ROW. It is unclear whether the primary entrance on the east or west façade. The south façade is features two windows of unknown type with stucco sills below and a stucco lintel above. Aerials from 2020 indicate that there are at least two ancillary outbuildings on the property; however, none of the ancillary buildings are visible from the ROW to visually assess and none are listed in the Kern County Property Appraiser records. Additional details are indiscernible from the public ROW due to the setback.



Figure 5-10. Property overview of 10085 Hamilton Road, view facing north.

#### 5.1.11 10057 Hamilton Road (358-052-06)

The subject property (10057 Hamilton Road) is composed of a one-story 868-ft² single-family residence constructed in 1951 on a 9.78-acre parcel. The single-family residence is set back approximately 425 ft from the road and is not visible from the ROW (Figure 5-10). Aerials show that there are multiple structures on the property, but the Kern County Tax Assessor public record only references one residential building. The property is enclosed in chain-link fencing. Real estate records indicate that the residence is a ranch of concrete construction with a composite shingle roof and concrete slab foundation. Real estate photos from 2017 show the residence has rough stucco exterior cladding, wood eaves, and aluminum horizontal sliding windows. The 2017 photos also show a detached stucco two-bay garage, at least two ancillary buildings, and livestock corrals. None of the buildings are visible from the ROW to visually assess and none are listed in the Kern County Property Appraiser records. Additional details are indiscernible from the public ROW due to the setback.



Figure 5-11. Property overview of 10057 Hamilton Road, view facing north.

# 5.1.12 9714 Rosamond Boulevard (374-042-03)

The subject property (9714 Rosamond Boulevard) is composed of a one-story vernacular California ranch single-family residence of 828 ft² (Figure 5-11). The residence was constructed in 1919 and is on a 2.26-acre parcel. The property is accessible from the south via Rosamond Boulevard and east from an unnamed adjacent dirt road. Landscaping consists of native trees, shrubs, and grasses growing freely across the property. The residence has a rectangular plan oriented north-south with a front-gable composite shingle roof, rectangular attic vents beneath the gables, horizontal sliding vinyl windows covered with exterior screens, and tan stucco exterior walls. The entryway is on the south façade and consists of a single fiberglass entry-door behind an exterior screen door. The entrance is accessed via concrete steps and a ramp. The west façade features two windows and a side-entry door covered by an additional exterior screen door. The east façade features two windows. The residence also has a rear addition with shed pent roof extension.



Figure 5-12. Overview of 9714 Rosamond Boulevard, view facing southwest from Rosamond Boulevard.

#### 5.1.13 9668 Rosamond Boulevard (374-042-04)

The subject property (9668 Rosamond Boulevard) is composed of a one-story vernacular California bungalow of 744 ft² (Figure 5-12). The single-family residence was constructed in 1921 and sits within a 0.49-acre parcel. The property is accessible from the south via Rosamond Boulevard. Landscaping is informal and consists of native trees, shrubs, and grasses growing freely throughout the property. The residence has a rectangular plan and front gable roof with a small rear addition and enclosed entry porch addition. The rear addition has a shed roof, and the enclosed porch has a hipped roof. Other features include a composite shingle roofing, rectangular attic vents, one-by-one vinyl horizontal sliding windows of varying size, and exterior walls which are clad in stucco and modular metal. The primary entrance is on the north façade and consists of a single vinyl entry door with concrete steps. The west and east façades each have two windows. There are multiple ancillary buildings south of the main residence. At least three ancillary buildings in varying states of disrepair are visible from the ROW.



Figure 5-13. Overview of 9668 Rosamond Boulevard facing southwest.

#### 5.1.14 9650 West Rosamond Boulevard (374-042-39)

The subject property (9650 W Rosamond Boulevard) is composed of a one-story vernacular California Ranch of 1,176 ft² on a 1.47-acre parcel (Figure 5-13). The single-family residence was constructed in 1952. The property is accessible from the south via Rosamond Boulevard. Landscaping consists of a planted row of shrubs along the chain-link fence facing Rosamond Boulevard along with a large Oak tree within the front yard near the northern property boundary. Other smaller trees and shrubs grow freely across the property. The residence has a rectangular plan, a composite shingle jerkinhead roof with rectangular attic vents below the eaves on the east and west façades, faux-divided lite vinyl sliding windows, a small metal chimney stack extending from the central peak of the roof, and exterior stucco walls. The primary entrance is on the north façade and consists of a single entry-door beneath a roof overhang, concrete steps, and a metal exterior security door. The north façade features five windows and rectangular foundation vents. The east façade features two windows, and the west façade features a window and a single secondary entry door with concrete steps.



Figure 5-14. Property overview of 9650 W Rosamond Boulevard facing south from Rosamond Boulevard.

# 5.1.15 9580 Rosamond Boulevard (374-042-07)

The subject property (9580 Rosamond Boulevard) is composed of 1.94 acres and features a one-story vernacular Minimal Traditional style single-family residence constructed in 1955 (Figure 5-14). The property is accessible from Rosamond Boulevard to the south. Landscaping is minimal. Much of the landscape is open loose sandy soil with an area of hardscaping and intermittent grasses. There are small trees planted adjacent to the residence on each side. The residence has a rectangular plan, a composite shingle hipped roof, a carport with a flat roof extension on the east façade, a tall metal chimney pipe extending from the north-facing roof slope, windows of an unknown type covered in dark screen, and exterior stucco walls. The parcel is surrounded by tall privacy fencing with intermittent plastic paneling to obscure the property from view from the ROW, making documentation and assessment difficult. There is a wooden lattice projection which obscures much of the north façade.



Figure 5-15. Property overview of 9580 Rosamond Boulevard facing southwest from Rosamond Boulevard.

# 5.1.16 9009 Rosamond Boulevard (252-352-33)

The subject property at 9009 Rosamond Boulevard is comprised a 9.02-acre parcel featuring a one-story vernacular Ranch type single-family residence (primary residence) constructed in 1959, two concrete block ancillary buildings of unknown use, a one-story commercial building that is not in use, and a secondary residence constructed circa 2005 (Figure 5-15). The property is accessible from Rosamond Boulevard to the south and 90th Avenue to the east. Landscaping consists of native trees, shrubs, and grasses growing freely across the property with windbreak plantings of trees along the southern property border and to the east of the residence. The 1,237-ft<sup>2</sup> main residence has an L-shaped plan, a cross-gable composite shingle roof, an exterior masonry chimney on the west façade, faux divided-lite vinyl sliding windows with decorative wood shutters, and yellow-painted concrete block exterior walls. The south façade features the main entrance and an open porch with vinyl-clad support columns. There are two ancillary concrete block outbuildings with low-pitch side-gable metal roofs near the main residence. A rectangular plan one-story commercial building, that once operated as a gas station, is at the southeast corner of the parcel. The gas station has stucco and brick veneer cladding, metal security screen covered doors and windows, and an irregular form roof of gray asphalt shingle and wood plank. An asphalt parking lot surrounds the gas station.



Figure 5-16. Property overview of 9009 Rosamond Boulevard facing north from Rosamond Boulevard.

# 5.1.17 3045 90th Street (252-352-32) / High Desert Cellars

The subject property (3045 90th Street West) is composed of a one-story vernacular Spanish Revival commercial building (subject building) on a 9.68-acre parcel accessible from the east via 90th Street West (Figure 5-16). The building was constructed in 1956, is 3,050 ft², and is surrounded by an asphalt parking lot to the east and south. Other landscape features include a grass fenced-in lawn area north and west of the building partially lined with trees. Grasses, trees, and shrubs grow freely throughout the parcel, which is surrounded by separate chain-link fencing, excluding the eastern commercially developed portion of the property. The subject building has a rectangular plan, a flat built-up roof, stucco cladding, and a wall of steel-framed fixed windows and two steel-frame glass entrance doors on the east (primary) façade. A narrow flat roofed blind arcade projection extends from the east façade, giving the window wall and glass doors a recessed appearance. The windows and doors of the east façade are barred with steel exterior security bars. The south and north façades are absent of windows or secondary entry doors. Aerial photos from 2020 show at least two small ancillary buildings along the north property boundary and set back approximately 800 ft from 90th Street West. The use of the ancillary buildings is unclear, but they appear to be small rectangular stucco structures.



Figure 5-17. Property overview of 3045 90th Street West, facing northwest.

# 5.1.18 2973 95th Street (374-042-08)

The subject property (2973 95th Street) is a 1.94-acre parcel featuring a one-story 1,020-ft<sup>2</sup> vernacular California Bungalow built in 1942 (Figure 5-17). The property is accessible from Rosamond Boulevard to the south and from the west via 95th Street. Landscaping consists of a predominantly cleared lawn with varieties of planted grasses, trees along the western facade of the residence, and native trees growing freely. The residence has a rectangular plan, a clay tile side-gable roof with shed extension at the south (rear), and rectangular attic vents beneath the gable peaks. There is an addition along the west façade which has a low pitch side-gable roof, faux divided-lite vinyl sliding windows, and stucco exterior walls. The primary entrance of the residence is on the north facade, recessed below a roof overhang and within a partially enclosed porch. This north façade is partially obscured from the ROW by vegetation, vehicles, and debris but appears to feature at least four windows. The west façade features an addition with a single window. An adjacent structure is adjoined to the main residence by a roof extension from the western addition. The east façade includes one window and a set of glass vinyl-framed sliding doors. A detached two-door garage is northeast of the main residence and features a composite shingle front-gable roof, concrete block exterior walls, a horizontal-sliding vinyl window, and exposed rafter tails.



Figure 5-18. Property overview of 2973 95th Street, facing south.

# 5.1.19 2860 West 100<sup>th</sup> Street (374-041-09)

The subject property (2860 West 100th Street) is composed of a one-story vernacular California ranch single-family residence on a 2.41-acre parcel (Figure 5-18). The 960-ft<sup>2</sup> residence was constructed in 1940, and the property is accessible from the west via West 100th Street. Landscaping consists of naturally occurring grasses and shrubs with a planting of trees along the east of the residential structure as well as along another windbreak planting of trees along the western border of the parcel. The residence features a rectangular plan, a side-gable asphalt shingle roof with rectangular attic vents beneath each gable, a shed-pent roof extension covered entry porch with simple support columns, one-by-one vinyl sliding windows and faux divided-lite vinyl sliding windows, and stucco exterior walls. The primary entrance is a single entry-door on the north façade accessed via the covered entry porch and concrete steps leading to the door. The entrance is flanked by two windows on each side. The south façade features a single secondary entrance door with concrete steps and five windows. The west facade is not visible from the right of way. A gazebo with an asphalt shingle pyramidal roof is immediately south of the main residence and an ancillary building is southeast of the main residence. Southeast of the gazebo is a freestanding flat-roofed shelter and an accessory dwelling unit it near the northeast corner of the property.



Figure 5-19. Property overview of 2860 West 100th Street, facing east.

#### 5.1.20 APN 358-131-02

The subject property (APN 358-131-02) was identified through reconnaissance survey but was not accessible for intensive survey on-site or from the ROW due to safety hazards. The rectangular 3-acre property is bounded on the north Melody Lane (a dirt road also known as Avenue of the Stars) and to the south, west, and east by single-family properties. The property is accessible from the north via a dirt driveway. The eastern and western parcel boundaries are each lined with a row of trees forming privacy screens and windbreaks. The Kern County Tax Assessor lists one building on the property, a 1,342-ft² residence with one bedroom and one and a half bathrooms. The extant residence is approximately 2,500 ft², including a large addition to the south façade of the building performed at an unknown date between 1989 and 2003 (HistoricAerials.com 1963, 1974, 1989, 2003, 2018). The alteration transformed the residence from an L-shaped plan to an irregular plan with a vaguely rectangular form. The residence is setback approximately 210 ft from the road. A rectangular ancillary building is west of the residence. No address for the property could be identified.

# 6 SIGNIFICANCE AND ELIGIBILITY

# 6.1 ELIGIBILITY CRITERIA

#### 6.1.1 California Register of Historical Resources

The CRHR program encourages public recognition and protection of resources of architectural, historical, archaeological, and cultural significance; identifies historical resources for state and local planning purposes; determines eligibility for state historic preservation grant funding; and affords certain protections under CEQA. The criteria established for eligibility for the CRHR are directly comparable to the national criteria established for the NRHP.

To be eligible for listing in the CRHR, a building, object, or structure must satisfy at least one of the following four criteria:

- 1. It is associated with events that have made a significant contribution to the broad patterns of local or regional history or the cultural heritage of California or the United States.
- 2. It is associated with the lives of persons important to local, California, or national history.
- 3. It embodies the distinctive characteristics of a type, period, region, or method of construction, or represents the work of a master or possesses high artistic values.
- 4. It has yielded, or has the potential to yield, information important to the prehistory or history of the local area, California, or the nation.

California properties listed in or formally determined eligible for listing in the NRHP are automatically listed in the CRHR.

#### Integrity

Historical resources eligible for listing in the CRHR must also retain enough of their historic character or appearance (integrity) to be recognizable as historical resources and to convey the reasons for their significance. For the purposes of eligibility for the CRHR, integrity is defined as "the authenticity of a historical resource's physical identity evidenced by the survival of characteristics that existed during the resource's period of significance" (California OHP 2001). The evaluation of integrity must be grounded in an understanding of a resource's physical features and how they relate to the concept of integrity. Determining which of these aspects are most important to a resource requires knowing why, where, and when a resource is significant. To retain historic integrity, a resource must possess several, and usually most, aspects of integrity:

- 1. **Location** is the place where the historical resource was constructed or the place where the historic event occurred.
- 2. **Design** is the combination of elements that create the form, plan, space, structure, and style of a resource.
- 3. **Setting** is the physical environment of a historical resource and refers to the character of the site and the relationship to surrounding features and open space.

Setting often refers to the basic physical conditions under which a resource was built and the functions it was intended to serve. These features can be either natural or manmade, including vegetation, paths, fences, and relationships between other features or open space.

- 4. **Materials** are the physical elements that were combined or deposited during a particular period or time, and in a particular pattern or configuration to form a historical resource.
- 5. **Workmanship** is the physical evidence of crafts of a particular culture or people during any given period of history or prehistory and can be applied to the resource, or to individual components.
- 6. **Feeling** is a resource's expression of the aesthetic or historic sense of a particular period. It results from the presence of physical features that, when taken together, convey the resource's historic character.
- 7. **Association** is the direct link between the important historic event or person and a historical resource.

#### 6.2 EVALUATIONS OF ELIGIBILITY

To fully comply with CEQA regulations, PaleoWest followed California OHP guidelines for recording and evaluating historic period built environment resources for CRHR eligibility. PaleoWest re-evaluated all historic architectural resources previously identified that had not been documented and evaluated within the past five years. PaleoWest also completed evaluations of all built environment resources at least 45 years old. These evaluations are included in the following sections.

# 6.2.1 Willow Springs Village, California Historic Landmark #130

Willow Springs was first formally identified as historically significant in the 1930s. As a California Historical Landmark, the site was documented multiple times over the twentieth century, most recently in 1992. Because Willow Springs became a state landmark prior to January 1998 and the establishment of the CRHR, the site must be reevaluated using current standards. Willow Springs Village (15-000129) was thus evaluated for historical significance under CRHR Criteria 1–4 as follows.

Willow Springs serves as a vivid and physical manifestation of the theme of American settlement and exploration in the Mojave Desert and is a good representative of a small agricultural community. From this site, Ezra Hamilton founded a resort that catered to residents of the region and travelers emigrating from the interior of the U.S. Pears were grown and exported in the area, and the discovery of gold in the Lida Mine spurred further development in the Antelope Valley. Thus, Willow Springs was a significant community integral to various community, commercial, and industrial developments in the region. For these significant historical associations, PaleoWest recommends Willow Springs Village eligible for the CRHR under Criterion 1.

Ezra Hamilton, the founder of Willow Springs Village, was a distinguished pioneer in the history of the Antelope Valley and he was the first American recorded to have discovered gold in the Antelope Valley. He also served in the local government in Los Angeles and patented the peat-

pressing machine in 1867 before finally settling in Willow Springs. Willow Springs Village is the only known physical representation of Hamilton's significance as a pioneer, inventor, and prospector in Southern California. He is also significant as the founder of Willow Springs, one of the most distinguished settlements in the western Mojave Desert in the late nineteenth to early twentieth centuries. For its direct and strong connection to Ezra Hamilton, a historically important person who contributed to broad patterns of history in Southern California, Willow Springs Village is considered significant. The site clearly represents its period and its original function as a small settlement engrained in agriculture. As such, PaleoWest recommends Willow Springs Village eligible for the CRHR under Criterion 2.

The extant buildings and structures of the site were constructed circa 1900–1915 with locally sourced fieldstone. They are the last remaining buildings of this once prominent village in the western Mojave Desert and the last known buildings dating to that period and constructed of local stones The buildings are also significant for their unique masonry-based rustic style that is rarely seen in Southern California outside of forests, parks, and mountain communities. They are also the oldest buildings in the surrounding unincorporated area of Kern County. The buildings are also a testament to quality construction, likely designed by stonemason and founder Ezra Hamilton himself. Despite not being specially altered and reinforced to survive earthquakes, they have mostly withstood various earthquakes throughout the twentieth century. As such, PaleoWest recommends Willow Springs Village eligible under Criterion 3 for its significant unique and rare architecture.

The Willow Springs Village is a historically significant site in American history of California, and it was also once the site of a Kitanemuk village. The site has been documented through archaeological and architectural survey, and it is our professional opinion that the resource is unlikely to yield additional vital information about the history or prehistory of these two former settlements that is not readily available through research or provided in the previous recordings of the site. As such, the resource is recommended not eligible under CRHR Criterion 4.

#### Integrity Assessment

Although some elements such as the original stagecoach center, the schoolhouse, and the cemetery gravestones are no longer extant or in a ruinous condition, the Willow Springs site overall retains its integrity to adequately conveys its historical significance. Specifically, the site's location, workmanship, feeling, and associations are retained. A few buildings have been altered with additions, new roofing, and new windows where necessitated by deterioration; however, the majority of the extant site elements clearly represent their period of significance and historical connections to important events and persons as well as their unique architecture. Most original materials throughout the village, most notably the abundance of character-defining fieldstone, are retained. The alterations to the standing structures also appear to be easily reversible without the destruction of historical materials. Willow Springs Village remains as a distinguished example of an early twentieth century American settlement in the western Mojave Desert.

In summary, PaleoWest's professional opinion is that the site retains sufficient integrity to convey its historical significance under the CRHR Criteria and guidelines. Therefore, the assessment of integrity does not change PaleoWest's recommendation that the Willow Springs Village is eligible for listing in the CRHR under Criteria 1–4.

# 6.2.2 Segment of the LADWP Owens Gorge 230kV Transmission Corridor

In its evaluation of the Owens Gorge 230kV Transmission Line segment in Rosamond, California near Rosamond Boulevard and Hamilton Road, PaleoWest carefully considered whether it is eligible for the CRHR under each criterion and considered previous evaluations of other segments of the transmission line. The line is of historic age, as the towers date from the early to mid-1950s. The segment remains generally unchanged since the recording in 2014 by Power Engineers, Inc.

Under Criterion 1, a resource must constitute an association with significant events in history. Despite the proximity of Willow Springs to the resource, the Owens Gorge 230kV Transmission Line is not associated with a significant event in history. PaleoWest recommends the transmission line segment not eligible for listing in the CRHP under Criterion 1.

Under Criterion 2, a resource must have association with a significant historical figure. The Owens Gorge 230kV Transmission Line is not associated with a significant historical figure. The transmission line segment is not recommended eligible for listing in the CRHR under Criterion 2.

Under Criterion 3, a resource must embody distinctive characteristics of a type, period, method of construction, or represent the work of a master that possess high artistic values. was not representative of that of a master, nor does possess high artistic value. Additionally, it is not in association with any important persons of history. Therefore, Owens Gorge 230kV Transmission Line segment is not recommended eligible for listing in the CRHR under Criterion 3.

Owens Gorge 230kV Transmission Line segment is not recommended to be considered eligible for the listing in the CRHR under Criterion 4.

# 6.2.3 Segment of the Vincent 2206V Transmission Line, Big Creek #3-Springville (P-15-017243) / SCE Big Creek Hydroelectric System Historic District

The transmission line is part of the SCE Big Creek Hydroelectric System which is a NRHP/CRHR Historic District, and the line was deemed eligible as a contributor to the district. There have been no discernable changes since it was surveyed and evaluated in 2019. As such, PaleoWest concurs with the previous evaluation of NRHP/CRHR eligibility as a contributor to SCE Big Creek Hydroelectric System Historic District.

# 6.2.4 Segment of the General Petroleum Access Road

The segments of CA-KER-007747H are of historic age without any associated artifacts or features. The resource consists of an unpaved toad that shows evidence of periodic grading and regular use.

Site CA-KER-7747H does not appear to be associated with any important events in history with a lack of historic artifacts and features. CA-KER-7747H is recommended to be considered not eligible for listing in the CRHP under Criterion 1. The road segments of CA-KER-7747H do not indicate that the construction is representative of that of a master or is in association with any important persons of history. Therefore, CA-KER-7747H is recommended to be considered not

eligible for listing in the CRHP under Criterion 2 or 3. Site CA-KER-7747H does not contain any diagnostic artifacts or features that can warrant information of the site's history. The lack of subsurface potential does not likely yield any information as well. CA-KER-7747H is recommended to be considered not eligible for listing in the CRHP under criterion 4.

#### 6.2.5 14205 Irone Avenue (358-132-12)

Under Criterion 1, the subject property was evaluated for an association with significant historical events or broad patterns of history at the local, regional, state, or national level. The property is within an unincorporated area of the Antelope Valley, a region of the Mojave Desert that has a rich history of American exploration, migration, and settlement unique to the California and the high desert region during the nineteenth and early twentieth centuries. According to the Kern County Property Appraiser records the single-family residence was built in 1957, which is well past settlement at the regional (Antelope Valley), state (California), or local level. PaleoWest also considered whether 14205 Irone Avenue may be significant for an association with the theme of Community Development of the Antelope Valley, 1918-1975 and the sub-theme of Rural Residential Development of the valley. Although the residence and outbuilding may date to the period of significance for the theme and sub-theme, the subject property is not a rare, unique, or exemplary example of a property associated with twentieth century community development and rural residential development of the Antelope Valley. It does provide a recognizable representation of broad patterns of residential development in the valley. Additionally, the property is within an unincorporated area of Kern County and the Antelope Valley that does not have a strong cohesive pattern of community history that would include the property's period of construction for which it might be considered historically significant. The property is near the communities of Willow Springs and Rosamond but lacks an immediate connection with the development of these communities. In summary, no direct associations between 14205 Irone Avenue and historically significant events or broad patterns of history at the local, region, state, or national level could be established. As such, the subject property is recommended not eligible under CRHR Criterion 1.

Research was conducted to determine if the subject property is significant under Criterion 2 for associations with the lives of historically important persons who have made contributions to local, state, or national history. No direct connection to historically important individuals could be identified through historical and archival research of 14205 Irone Avenue. Individuals found to be associated with the property through archival research include Lonnie Sebelita, Janet Sebelita. No information was uncovered to confirm these individuals resided at 14205 Irone Avenue during its historic period and research did not suggest the identified individuals made important contributions to history. Historically important persons such as explorers Pedro Fages, Joseph Walker, and John C. Frémont are known to have traveled through the area and to have stopped at nearby Willow Springs, but these events happened well before the construction of the extant buildings on the subject property. Therefore, there is no direct correlation between known significant historical figures and the property. As 14205 Irone Avenue does not appear to be illustrative of the accomplishments of historically important persons within a local, state, or national historic context, the property is recommended not eligible under Criterion 2.

To evaluate the subject property under Criterion 3, PaleoWest considered whether it embodies distinctive characteristics of a type, period, or method of construction and whether it represents the work of a master architect or possesses high artistic value. The residence and

detached garage building at 14205 Irone Avenue are vernacular renditions of the California Ranch style which is very common to rural areas of Southern California. As an unadorned example of the California Ranch style, the property residence does not embody enough of the distinctive characteristics of this style to be considered an exemplary or unique iteration of a California Ranch. Although vernacular architecture can be considered historically significant, the residence at 14205 Irone Avenue is also not a distinctive, rare, or exemplary vernacular California Ranch which is a common type and style throughout rural areas of Southern California. PaleoWest also considered whether the subject property may be significant for an association with a master builder or architect; however, no record of a builder or architect was found through property and document search engines of the Kern County Tax Assessor's Office nor through archival research. In summary, the residence of the subject property is not a distinctive or rare example of a vernacular California Ranch residence in rural Southern California and the detached garage building is also not a unique or rare example of a rural utilitarian building or farm building. Additionally, neither building clearly represents or a specific period or method of construction, are they associated with a significant master architect or builder. As such, 14205 Irone Avenue is recommended not eligible under Criterion 3.

The subject property is a common property type that is unlikely to provide vital information about history or prehistory that is not readily available through historical and archival research. As such, the property is recommended not eligible under CRHR Criterion 4.

The subject property is not within a designated or previously identified historic district. As a very sparsely developed and unincorporated area, the immediate vicinity of the property also lacks architectural cohesion and a defined shared historical narrative to be considered a historic district. Thus, 14205 Irone Avenue is not recommended eligible as a contributor to a CRHR-eligible or listed historic district.

# 6.2.6 4040 Manly Road (315-012-01, 315-012-02, 252-341-05)

Under Criterion 1, the subject property was evaluated for an association with significant historical events or broad patterns of history at the local, regional, state, or national level. The property is within an unincorporated area of the Antelope Valley, a region of the Mojave Desert that has a rich history of American exploration, migration, and settlement unique to the California and the High Desert region during the nineteenth and early twentieth centuries. According to aerial photographs, the residences on the property were built well past the period of significance for American settlement at the regional (Antelope Valley), state (California), or local level. PaleoWest also considered whether the subject property may be significant for an association with the theme of Community Development of the Antelope Valley, 1918–1975 and the sub-theme of Rural Residential Development of the valley. Although the residence and outbuilding may date to the period of significance for development theme and sub-theme, the subject property is not a rare, unique, or exemplary example of a property associated with twentieth century community development and rural residential development of the Antelope Valley. It does provide a recognizable representation of broad patterns of residential development in the valley. Additionally, the property is within an unincorporated area of Kern County and the Antelope Valley that does not have a strong cohesive pattern of community history that would include the property's period of construction for which it might be considered historically significant. The property is near the communities of Willow Springs and Rosamond but lacks an immediate connection with the development of these communities. In summary, no direct associations between the subject property and historically significant

events or broad patterns of history at the local, region, state, or national level could be established. As such, the subject property is recommended not eligible under CRHR Criterion 1.

Research was conducted to determine if the subject property is significant under Criterion 2 for associations with the lives of historically important persons who have made contributions to local, state, or national history. No direct connection to historically important individuals could be identified through historical and archival research of the subject property. Individuals found to be associated with the property through archival research included various members of the Nelson family since the construction of the three extant residences. No information was uncovered to confirm these individuals have made important contributions to history. Historically important persons such as explorers Pedro Fages, Joseph Walker, and John C. Frémont are known to have traveled through the area and to have stopped at nearby Willow Springs, but these events happened well before the construction of the extant buildings on the subject property. Therefore, there is no direct correlation between known significant historical figures and the property. As 4040 Manly Road does not appear to be illustrative of the accomplishments of historically important persons within a local, state, or national historical context, the property is recommended not eligible under Criterion 2.

To evaluate the subject property under Criterion 3, PaleoWest considered whether it embodies distinctive characteristics of a type, period, or method of construction and whether it represents the work of a master architect or possesses high artistic value. The residences at 4040 Manly Road are vernacular renditions of a variety of architectural styles that are common to Southern California. As unadorned examples of the American Rustic, Minimal Traditional, and Californian styles, the residences do not embody enough of the distinctive characteristics of a particular style to be considered an exemplary or unique iteration of that style. Although vernacular architecture can be considered historically significant, the residences are not distinctive, rare, or exemplary examples of vernacular architecture in the Antelope Valley or other rural areas of Southern California. PaleoWest also considered whether the subject property may be significant for associations with master builders or architects; however, no record of builders or architects for the residences were uncovered through property and document search engines of the Kern County Tax Assessor's Office nor through archival research. In summary, the buildings of the subject property are not distinctive or rare examples of vernacular residential architecture in rural Southern California. Additionally, none of the buildings building clearly represent a specific period or method of construction, nor are they associated with a significant master architect or builder. As such, 4040 Manly Road is recommended not eligible under Criterion 3.

The subject property is a common property type, unlikely to provide additional information about residential development in the area that is not already available through research. The property is adjacent to the Willow Springs Village site which is a California Historical Landmark and was once the site of a Kitanemuk village. The area has been documented through archaeological survey, and it is our professional opinion that the property is unlikely to yield additional vital information about the history or prehistory of these two former settlements that is not readily available through research or provided in the previous recordings of the site. As such, the property is recommended not eligible under CRHR Criterion 4.

The subject property is not within a designated or previously identified historic district. It is on land believed to have been formerly part of an early twentieth century American settlement (a

CRHR listed site) and a Kitanemuk village; however, the extant resources known to be on the property and documented in this form are not associated directly with either settlement based on their periods of significance and construction. Thus, the subject property is not recommended eligible as a contributor to a CRHR-eligible or listed historic district.

#### 6.2.7 14101 Irone Avenue (358-132-10)

Under Criterion 1, the subject property was evaluated for an association with significant historical events or broad patterns of history at the local, regional, state, or national level. The property is within an unincorporated area of the Antelope Valley, a region of the Mojave Desert that has a rich history of American exploration, migration, and settlement unique to the California and the high desert region during the nineteenth and early twentieth centuries; however, based on a review of historical aerial photographs, the buildings on the property were constructed circa 1970, well after the period of significance for this theme of American Settlement in the Antelope Valley and the broader exploration and settlement of California. As such, the subject property cannot be directly associated with significance of exploration and settlement at the regional (Antelope Valley), state (California), or local level. PaleoWest also considered whether 14101 Irone Avenue may be significant for an association with the theme of Community Development of the Antelope Valley, 1918–1975 and the sub-theme of Rural Residential Development of the valley. Although the residence and garage date to the period of significance for the theme and sub-theme, the subject property is not a rare, unique, or exemplary example of a property associated with twentieth century community development and rural residential development of the Antelope Valley. It does provide a recognizable representation of broad patterns of residential development in the valley. Additionally, the property is within an unincorporated area of Kern County and the Antelope Valley that does not have a strong cohesive pattern of community history that would include the property's period of construction for which it might be considered historically significant. The property is near the communities of Willow Springs and Rosamond but lacks an immediate connection with the development of these communities. In summary, no direct associations between 14101 Irone Avenue and historically significant events or broad patterns of history at the local, region, state, or national level could be established. As such, the subject property is recommended not eligible under CRHR Criterion 1.

Research was conducted to determine if the subject property is significant under Criterion 2 for associations with the lives of historically important persons who have made contributions to local, state, or national history. No direct connection to historically important individuals could be identified through historical and archival research of 14101 Irone Avenue. Individuals found to be associated with the property through archival research include Jeffrey R. Williams, Caleb C. Porter, Steven Joel Cooper, Seaneen Tara McArdle, Ricard A. Valenzuela, and Melissa D. Porter. No information was uncovered to confirm these individuals resided at 14101 Irone Avenue during its historic period and research did not suggest the identified individuals made important contributions to history. Historically important persons such as explorers Pedro Fages, Joseph Walker, and John C. Frémont are known to have traveled through the area and to have stopped at nearby Willow Springs, but these events happened well before the construction of the extant buildings on the subject property. Therefore, there is no direct correlation between known significant historical figures and the property. As 14101 Irone Avenue does not appear to be illustrative of the accomplishments of historically important

persons within a local, state, or national historical context, the property is recommended not eligible under Criterion 2.

To evaluate the subject property under Criterion 3, PaleoWest considered whether it embodies distinctive characteristics of a type, period, or method of construction and whether it represents the work of a master architect or possesses high artistic value. The residence and converted garage building at 14101 Irone Avenue are vernacular renditions of the California Bungalow stye which is very common to rural areas of Southern California. As an unadorned example of the California Bungalow style, the property does not embody enough of the distinctive characteristics of this style to be considered an exemplary or unique iteration of a California Bungalow. Although vernacular architecture can be considered historically significant, 14101 Irone Avenue is not a distinctive, rare, or exemplary vernacular California Bungalow which is a common type and style throughout rural areas of Southern California. PaleoWest also considered whether the subject property may be significant for an association with a master builder or architect; however, no record of a builder or architect was found through property and document search engines of the Kern County Tax Assessor's Office nor through archival research. In summary, the subject property is not a distinctive or rare example of a vernacular California Bungalow residence in rural Southern California or a specific period or method of construction, nor is it associated with a significant master architect or builder. As such, 14101 Irone Avenue is recommended not eligible under Criterion 3.

The subject property is a common property type that is unlikely to provide vital information about history or prehistory that is not readily available through historical and archival research. As such, the property is recommended not eligible under CRHR Criterion 4.

The subject property is not within a designated or previously identified historic district. As a very sparsely developed and unincorporated area, the immediate vicinity of the property also lacks architectural cohesion and a defined shared historical narrative to be considered a historic district. Thus, 14101 Irone Avenue is not recommended eligible as a contributor to a CRHR-eligible or listed historic district.

#### 6.2.8 14070 Lodestar Avenue (358-132-07)

Under Criterion 1, the subject property was evaluated for an association with significant historical events or broad patterns of history at the local, regional, state, or national level. The property is within an unincorporated area of the Antelope Valley, a region of the Mojave Desert that has a rich history of American exploration, migration, and settlement unique to the California and the high desert region during the nineteenth and early twentieth centuries. According to the Kern County Property Appraiser records the single-family residence was built in 1946, which is well past settlement at the regional (Antelope Valley), state (California), or local level. PaleoWest also considered whether 14070 Lodestar Avenue may be significant for an association with the theme of Community Development of the Antelope Valley, 1918-1975 and the sub-theme of Rural Residential Development of the valley. Although the residence and outbuilding may date to the period of significance for the theme and sub-theme, the subject property is not a rare, unique, or exemplary example of a property associated with twentieth century community development and rural residential development of the Antelope Valley. It does provide a recognizable representation of broad patterns of residential development in the valley. Additionally, the property is within an unincorporated area of Kern County and the Antelope Valley that does not have a strong cohesive pattern of community history that would

include the property's period of construction for which it might be considered historically significant. The property is near the communities of Willow Springs and Rosamond but lacks an immediate connection with the development of these communities. In summary, no direct associations between 14070 Lodestar Avenue and historically significant events or broad patterns of history at the local, region, state, or national level could be established. As such, the subject property is recommended not eligible under CRHR Criterion 1.

Research was conducted to determine if the subject property is significant under Criterion 2 for associations with the lives of historically important persons who have made contributions to local, state, or national history. No direct connection to historically important individuals could be identified through historical and archival research of 14070 Lodestar Avenue. Individuals found to be associated with the property through archival research include Veterans Affairs, Jacob Daniels, 360 Mortgage Group, Zeive Brodnax and Steel LLP, Steven Jermaine Lowrey, and Feliciano Garcia. No information was uncovered to confirm these individuals or organizations resided at 14070 Lodestar Avenue during its historic period and research did not suggest the identified individuals made important contributions to history. Historically important persons such as explorers Pedro Fages, Joseph Walker, and John C. Frémont are known to have traveled through the area and to have stopped at nearby Willow Springs, but these events happened well before the construction of the extant buildings on the subject property. Therefore, there is no direct correlation between known significant historical figures and the property. As 14070 Lodestar Avenue does not appear to be illustrative of the accomplishments of historically important persons within a local, state, or national historical context, the property is recommended not eligible under Criterion 2.

To evaluate the subject property under Criterion 3, PaleoWest considered whether it embodies distinctive characteristics of a type, period, or method of construction and whether it represents the work of a master architect or possesses high artistic value. The residence at 14070 Lodestar Avenue are vernacular renditions of the California Ranch style which is very common to rural areas of Southern California. As an unadorned example of the California Ranch style, the property residence does not embody enough of the distinctive characteristics of this style to be considered an exemplary or unique iteration of a California Ranch. Although vernacular architecture can be considered historically significant, the residence at 14070 Lodestar Avenue is also not a distinctive, rare, or exemplary vernacular California Ranch which is a common type and style throughout rural areas of Southern California. PaleoWest also considered whether the subject property may be significant for an association with a master builder or architect; however, no record of a builder or architect was found through property and document search engines of the Kern County Tax Assessor's Office nor through archival research. In summary, the residence of the subject property is not a distinctive or rare example of a vernacular California Ranch residence in rural Southern California. Additionally, this building does not represent a specific period or method of construction, are they associated with a significant master architect or builder. As such, 14070 Lodestar Avenue is recommended not eligible under Criterion 3.

The subject property is a common property type that is unlikely to provide vital information about history or prehistory that is not readily available through historical and archival research. As such, the property is recommended not eligible under CRHR Criterion 4.

The subject property is not within a designated or previously identified historic district. As a very sparsely developed and unincorporated area, the immediate vicinity of the property also

lacks architectural cohesion and a defined shared historical narrative to be considered a historic district. Thus, 14070 Lodestar Avenue is not recommended eligible as a contributor to a CRHR-eligible or listed historic district.

## 6.2.9 10145 Hamilton Road (358-052-08)

Under Criterion 1, the subject property was evaluated for an association with significant historical events or broad patterns of history at the local, regional, state, or national level. The property is within an unincorporated area of the Antelope Valley, a region of the Mojave Desert that has a rich history of American exploration, migration, and settlement unique to California and the high desert region during the nineteenth and early twentieth centuries; however, there is no build date provided by the Kern County Assessor's Office records, and the earliest available aerial photography is 1963, which is well past settlement at the regional (Antelope Valley), state (California), or local level. As such, the subject property cannot be directly associated with significance of exploration. PaleoWest also considered whether 10145 Hamilton Road may be significant for an association with the theme of Community Development of the Antelope Valley, 1918–1975 and the sub-theme of Rural Residential Development of the valley. Although the residence and outbuilding may date to the period of significance for the theme and sub-theme, the subject property is not a rare, unique, or exemplary example of a property associated with twentieth century community development and rural residential development of the Antelope Valley. It does provide a recognizable representation of broad patterns of residential development in the valley. Additionally, the property is within an unincorporated area of Kern County and the Antelope Valley that does not have a strong cohesive pattern of community history that would include the property's period of construction for which it might be considered historically significant. The property is near the communities of Willow Springs and Rosamond but lacks an immediate connection with the development of these communities. In summary, no direct associations between 10145 Hamilton Road and historically significant events or broad patterns of history at the local, region, state, or national level could be established. As such, the subject property is recommended not eligible under CRHR Criterion 1.

Research was conducted to determine if the subject property is significant under Criterion 2 for associations with the lives of historically important persons who have made contributions to local, state, or national history. No direct connection to historically important individuals could be identified through historical and archival research of 10145 Hamilton Road. Individuals found to be associated with the property through archival research include Josephina Padilla and Luzviminda Padilla. No information was uncovered to confirm these individuals resided at 10145 Hamilton Road during its historic period and research did not suggest the identified individuals made important contributions to history. Historically important persons such as explorers Pedro Fages, Joseph Walker, and John C. Frémont are known to have traveled through the area and to have stopped at nearby Willow Springs, but these events happened well before the construction of the extant buildings on the subject property. Therefore, there is no direct correlation between known significant historical figures and the property. As 10145 Hamilton Road does not appear to be illustrative of the accomplishments of historically important persons within a local, state, or national historical context, the property is recommended not eligible under Criterion 2.

To evaluate the subject property under Criterion 3, PaleoWest considered whether it embodies distinctive characteristics of a type, period, or method of construction and whether it

represents the work of a master architect or possesses high artistic value. The residence at 10145 Hamilton Road is a vernacular rendition of the California Bungalow stye which is very common to rural areas of Southern California. As an unadorned example of the California Bungalow style, the residence does not embody enough of the distinctive characteristics of this style to be considered an exemplary or unique iteration of a California Bungalow. Although vernacular architecture can be considered historically significant, the residence at 10145 Hamilton Road is also not a distinctive, rare, or exemplary vernacular California Bungalow. The ancillary barn is a typical wooden utilitarian barn that does not embody a specific style, nor is it a rare, distinct, or excellent iteration of a rural farm building warranting historical significance for its architecture. PaleoWest also considered whether the subject property may be significant for an association with a master builder or architect; however, no record of a builder or architect was found through property and document search engines of the Kern County Tax Assessor's Office nor through archival research. In summary, the residence of the subject property is not a distinctive or rare example of a vernacular California Bungalow residence in rural Southern California and the ancillary barn is also not a unique or rare example of a rural utilitarian barn or farm building. Additionally, neither building clearly represents a specific period or method of construction, nor are they associated with a significant master architect or builder. As such, 10145 Hamilton Road is recommended not eligible under Criterion 3.

The subject property is a common property type that is unlikely to provide vital information about history or prehistory that is not readily available through historical and archival research. As such, the property is recommended not eligible under CRHR Criterion 4.

The subject property is not within a designated or previously identified historic district. As a very sparsely developed and unincorporated area, the immediate vicinity of the property also lacks architectural cohesion and a defined shared historical narrative to be considered a historic district. Thus, 10145 Hamilton Road is not recommended eligible as a contributor to a CRHReligible or listed historic district.

#### 6.2.10 10085 Hamilton Road (358-052-07)

The subject property at 10085 Hamilton Road (358-052-07) could not be evaluated for historical significance because none of the buildings are visible from the ROW to visually assess and none are listed in the Kern County Property Appraiser records. Additional details are indiscernible from the public ROW due to the setback. PaleoWest recommends that the resource be assumed eligible for the CRHR for the current Project.

#### 6.2.11 10057 Hamilton Road (358-052-06)

The subject property at 10057 Hamilton Road (358-052-06) could not be evaluated for historical significance because none of the buildings are visible from the ROW to visually assess and none are listed in the Kern County Property Appraiser records. Additional details are indiscernible from the public ROW due to the setback. PaleoWest recommends that the resource be assumed eligible for the CRHR for the current Project.

#### 6.2.12 9714 Rosamond Boulevard (374-042-03)

Under Criterion 1, the subject property was evaluated for an association with significant historical events or broad patterns of history at the local, regional, state, or national level. The

property is within an unincorporated area of the Antelope Valley, a region of the Mojave Desert that has a rich history of American exploration, migration, and settlement unique to the California and the high desert region during the nineteenth and early twentieth centuries. According to the Kern County Property Appraiser records 9714 Rosamond Boulevard was constructed circa 1919, which suggests the residence may be significant for an association with the theme of Community Development of the Antelope Valley, 1918-1975 and the subtheme of Rural Residential Development of the valley. Although the residence and outbuilding may date to the period of significance for the theme and sub-theme, the subject property is not a rare, unique, or exemplary example of a property associated with twentieth century community development and rural residential development of the Antelope Valley. It does not provide a recognizable representation of broad patterns of residential development in the valley. Additionally, the property is within an unincorporated area of Kern County and the Antelope Valley that does not have a strong cohesive pattern of community history that would include the property's period of construction for which it might be considered historically significant. The property is near the communities of Willow Springs and Rosamond but lacks an immediate connection with the development of these communities. In summary, no direct associations between 9714 Rosamond Boulevard and historically significant events or broad patterns of history at the local, region, state, or national level could be established. As such, the subject property is recommended not eligible under CRHR Criterion 1.

Research was conducted to determine if the subject property is significant under Criterion 2 for associations with the lives of historically important persons who have made contributions to local, state, or national history. No direct connection to historically important individuals could be identified through historical and archival research of 9714 Rosamond Boulevard. Individuals found to be associated with the property through archival research include Dixie Lee Noel and Roy Leo Noel. No information was uncovered to confirm these individuals resided at 9714 Rosamond Boulevard during its historic period and research did not suggest the identified individuals made important contributions to history. Historically important persons such as explorers Pedro Fages, Joseph Walker, and John C. Frémont are known to have traveled through the area and to have stopped at nearby Willow Springs, but these events happened well before the construction of the extant buildings on the subject property. Therefore, there is no direct correlation between known significant historical figures and the property. As 10145 Hamilton Road does not appear to be illustrative of the accomplishments of historically important persons within a local, state, or national historical context, the property is recommended not eligible under Criterion 2.

To evaluate the subject property under Criterion 3, PaleoWest considered whether it embodies distinctive characteristics of a type, period, or method of construction and whether it represents the work of a master architect or possesses high artistic value. The residence, not including the modern utilitarian shed type outbuilding, at 9714 Rosamond Boulevard is a vernacular rendition of the California Ranch type which is very common to rural areas of Southern California. As an unadorned example of the California Ranch type, the property residence does not embody enough of the distinctive characteristics of this style to be considered an exemplary or unique iteration of a California Ranch. Although vernacular architecture can be considered historically significant, the residence at 9714 Rosamond Boulevard is also not a distinctive, rare, or exemplary vernacular California Ranch which is a common type and style throughout rural areas of Southern California. The ancillary barn is a typical wooden utilitarian barn that does not embody a specific style, nor is it a rare, distinct, or

excellent iteration of a rural farm building warranting historical significance for its architecture. PaleoWest also considered whether the subject property may be significant for an association with a master builder or architect; however, no record of a builder or architect was found through property and document search engines of the Kern County Tax Assessor's Office nor through archival research. In summary, the residence of the subject property is not a distinctive or rare example of a vernacular California Ranch residence in rural Southern California and the ancillary modern shed is also not a unique or rare example of a rural utilitarian farm building. Additionally, neither building clearly represents or a specific period or method of construction, nor are they associated with a significant master architect or builder. As such, 9714 Rosamond Boulevard is recommended not eligible under Criterion 3.

The subject property is a common property type that is unlikely to provide vital information about history or prehistory that is not readily available through historical and archival research. As such, the property is recommended not eligible under CRHR Criterion 4.

The subject property is not within a designated or previously identified historic district. As a very sparsely developed and unincorporated area, the immediate vicinity of the property also lacks architectural cohesion and a defined shared historical narrative to be considered a historic district. Thus, 9714 Rosamond Boulevard is not recommended eligible as a contributor to a CRHR-eligible or listed historic district.

## 6.2.13 9668 Rosamond Boulevard (374-042-04)

Under Criterion 1, the subject property was evaluated for an association with significant historical events or broad patterns of history at the local, regional, state, or national level. The property is within an unincorporated area of the Antelope Valley, a region of the Mojave Desert that has a rich history of American exploration, migration, and settlement unique to the California and the high desert region during the nineteenth and early twentieth centuries. According to the Kern County Assessor's Office records, the residence was constructed circa 1921, which is past the period for settlement at the regional (Antelope Valley), state (California), or local level. PaleoWest also considered whether 9668 Rosamond Boulevard may be significant for an association with the theme of Community Development of the Antelope Valley, 1918–1975 and the sub-theme of Rural Residential Development of the valley. Although the residence may date to the period of significance for the theme and sub-theme, the subject property is not a rare, unique, or exemplary example of a property associated with twentieth century community development and rural residential development of the Antelope Valley. It does provide a recognizable representation of broad patterns of residential development in the valley. Additionally, the property is within an unincorporated area of Kern County and the Antelope Valley that does not have a strong cohesive pattern of community history that would include the property's period of construction for which it might be considered historically significant. The property is near the communities of Willow Springs and Rosamond but lacks an immediate connection with the development of these communities. In summary, no direct associations between 9668 Rosamond Boulevard and historically significant events or broad patterns of history at the local, region, state, or national level could be established. As such, the subject property is recommended not eligible under CRHR Criterion 1.

Research was conducted to determine if the subject property is significant under Criterion 2 for associations with the lives of historically important persons who have made contributions to local, state, or national history. No direct connection to historically important individuals could

be identified through historical and archival research of 9668 Rosamond Boulevard. Individuals found to be associated with the property through archival research include Ronald Smillie, Gilberto Navarez, Vicky Gale Carrer, Dixie Noel, and Douglas Arnold Middleton. No information was uncovered to confirm these individuals resided at 9668 Rosamond Boulevard during its historic period and research did not suggest the identified individuals made important contributions to history. Historically important persons such as explorers Pedro Fages, Joseph Walker, and John C. Frémont are known to have traveled through the area and to have stopped at nearby Willow Springs, but these events happened well before the construction of the extant buildings on the subject property. Therefore, there is no direct correlation between known significant historical figures and the property. As 9668 Rosamond Boulevard does not appear to be illustrative of the accomplishments of historically important persons within a local, state, or national historical context, the property is recommended not eligible under Criterion 2.

To evaluate the subject property under Criterion 3, PaleoWest considered whether it embodies distinctive characteristics of a type, period, or method of construction and whether it represents the work of a master architect or possesses high artistic value. The residence at 9668 Rosamond Boulevard is a vernacular rendition of the California Bungalow stye which is very common to rural areas of Southern California. As an unadorned example of the California Bungalow style, the property residence does not embody enough of the distinctive characteristics of this style to be considered an exemplary or unique iteration of a California Bungalow. Although vernacular architecture can be considered historically significant, the residence at 9668 Rosamond Boulevard is also not a distinctive, rare, or exemplary vernacular California Bungalow which is a common type and style throughout rural areas of Southern California. The utilitarian outbuildings are typical wooden utilitarian buildings that do not embody a specific style, nor are they a rare, distinct, or excellent iteration of a rural farm building warranting historical significance for its architecture. PaleoWest also considered whether the subject property may be significant for an association with a master builder or architect; however, no record of a builder or architect was found through property and document search engines of the Kern County Tax Assessor's Office nor through archival research. In summary, the residence of the subject property is not a distinctive or rare example of a vernacular California Bungalow residence in rural Southern California and the ancillary barn is also not a unique or rare example of a rural utilitarian barn or farm building. Additionally, neither building clearly represents or a specific period or method of construction, nor is are they associated with a significant master architect or builder. As such, 9668 Rosamond Boulevard is recommended not eligible under Criterion 3.

The subject property is a common property type that is unlikely to provide vital information about history or prehistory that is not readily available through historical and archival research. As such, the property is recommended not eligible under CRHR Criterion 4.

The subject property is not within a designated or previously identified historic district. As a very sparsely developed and unincorporated area, the immediate vicinity of the property also lacks architectural cohesion and a defined shared historical narrative to be considered a historic district. Thus, 9668 Rosamond Boulevard is not recommended eligible as a contributor to a CRHR-eligible or listed historic district.

## 6.2.14 9650 West Rosamond Boulevard (374-042-39)

Under Criterion 1, the subject property was evaluated for an association with significant historical events or broad patterns of history at the local, regional, state, or national level. The property is within an unincorporated area of the Antelope Valley, a region of the Mojave Desert that has a rich history of American exploration, migration, and settlement unique to the California and the high desert region during the nineteenth and early twentieth centuries. According to the Kern County Assessor's Office records, the residence was constructed circa 1952, which is well past the period for settlement at the regional (Antelope Valley), state (California), or local level. PaleoWest also considered whether 9650 Rosamond Boulevard may be significant for an association with the theme of Community Development of the Antelope Valley, 1918–1975 and the sub-theme of Rural Residential Development of the valley. Although the residence may date to the period of significance for the theme and sub-theme, the subject property is not a rare, unique, or exemplary example of a property associated with twentieth century community development and rural residential development of the Antelope Valley. It does provide a recognizable representation of broad patterns of residential development in the valley. Additionally, the property is within an unincorporated area of Kern County and the Antelope Valley that does not have a strong cohesive pattern of community history that would include the property's period of construction for which it might be considered historically significant. The property is near the communities of Willow Springs and Rosamond but lacks an immediate connection with the development of these communities. In summary, no direct associations between 9650 Rosamond Boulevard and historically significant events or broad patterns of history at the local, region, state, or national level could be established. As such, the subject property is recommended not eligible under CRHR Criterion 1.

Research was conducted to determine if the subject property is significant under Criterion 2 for associations with the lives of historically important persons who have made contributions to local, state, or national history. No direct connection to historically important individuals could be identified through historical and archival research of 9650 Rosamond Boulevard. Individuals found to be associated with the property through archival research include Dominga Moreno, Lydia Holton, and Michael Moreno. No information was uncovered to confirm these individuals resided at 9650 Rosamond Boulevard during its historic period and research did not suggest the identified individuals made important contributions to history. Historically important persons such as explorers Pedro Fages, Joseph Walker, and John C. Frémont are known to have traveled through the area and to have stopped at nearby Willow Springs, but these events happened well before the construction of the extant buildings on the subject property. Therefore, there is no direct correlation between known significant historical figures and the property. As 9650 Rosamond Boulevard does not appear to be illustrative of the accomplishments of historically important persons within a local, state, or national historical context, the property is recommended not eligible under Criterion 2.

To evaluate the subject property under Criterion 3, PaleoWest considered whether it embodies distinctive characteristics of a type, period, or method of construction and whether it represents the work of a master architect or possesses high artistic value. The residence at 9650 Rosamond Boulevard is a vernacular rendition of the California Ranch style which is very common to rural areas of Southern California. As an unadorned example of the California Ranch style, the property residence does not embody enough of the distinctive characteristics of this style to be considered an exemplary or unique iteration of a California Ranch. Although

vernacular architecture can be considered historically significant, the residence at 9650 Rosamond Boulevard is also not a distinctive, rare, or exemplary vernacular California Ranch which is a common type and style throughout rural areas of Southern California. PaleoWest also considered whether the subject property may be significant for an association with a master builder or architect; however, no record of a builder or architect was found through property and document search engines of the Kern County Tax Assessor's Office nor through archival research. In summary, the residence of the subject property is not a distinctive or rare example of a vernacular California Ranch residence in rural Southern California and the ancillary barn is also not a unique or rare example of a rural utilitarian barn or farm building. Additionally, neither building clearly represents or a specific period or method of construction, nor is it associated with a significant master architect or builder. As such, 9650 Rosamond Boulevard is recommended not eligible under Criterion 3.

The subject property is a common property type that is unlikely to provide vital information about history or prehistory that is not readily available through historical and archival research. As such, the property is recommended not eligible under CRHR Criterion 4.

The subject property is not within a designated or previously identified historic district. As a very sparsely developed and unincorporated area, the immediate vicinity of the property also lacks architectural cohesion and a defined shared historical narrative to be considered a historic district. Thus, 9650 Rosamond Boulevard is not recommended eligible as a contributor to a CRHR-eligible or listed historic district.

#### 6.2.15 9580 Rosamond Boulevard (374-042-07)

Under Criterion 1, the subject property was evaluated for an association with significant historical events or broad patterns of history at the local, regional, state, or national level. The property is within an unincorporated area of the Antelope Valley, a region of the Mojave Desert that has a rich history of American exploration, migration, and settlement unique to the California and the high desert region during the nineteenth and early twentieth centuries. According to the Kern County Assessor's Office records, the residence was constructed circa 1955, which is well past the period for settlement at the regional (Antelope Valley), state (California), or local level. PaleoWest also considered whether 9580 Rosamond Boulevard may be significant for an association with the theme of Community Development of the Antelope Valley, 1918–1975 and the sub-theme of Rural Residential Development of the valley. Although the residence may date to the period of significance for the theme and sub-theme, the subject property is not a rare, unique, or exemplary example of a property associated with twentieth century community development and rural residential development of the Antelope Valley. It does provide a recognizable representation of broad patterns of residential development in the valley. Additionally, the property is within an unincorporated area of Kern County and the Antelope Valley that does not have a strong cohesive pattern of community history that would include the property's period of construction for which it might be considered historically significant. The property is near the communities of Willow Springs and Rosamond but lacks an immediate connection with the development of these communities. In summary, no direct associations between 9580 Rosamond Boulevard and historically significant events or broad patterns of history at the local, region, state, or national level could be established. As such, the subject property is recommended not eligible under CRHR Criterion 1.

Research was conducted to determine if the subject property is significant under Criterion 2 for associations with the lives of historically important persons who have made contributions to local, state, or national history. No direct connection to historically important individuals could be identified through historical and archival research of 9580 Rosamond Boulevard. Individuals found to be associated with the property through archival research includes Reinaldo De La Rosa. No information was uncovered to confirm this individual resided at 9580 Rosamond Boulevard during its historic period and research did not suggest the identified individuals made important contributions to history. Historically important persons such as explorers Pedro Fages, Joseph Walker, and John C. Frémont are known to have traveled through the area and to have stopped at nearby Willow Springs, but these events happened well before the construction of the extant buildings on the subject property. Therefore, there is no direct correlation between known significant historical figures and the property. As 9580 Rosamond Boulevard does not appear to be illustrative of the accomplishments of historically important persons within a local, state, or national historical context, the property is recommended not eligible under Criterion 2.

To evaluate the subject property under Criterion 3, PaleoWest considered whether it embodies distinctive characteristics of a type, period, or method of construction and whether it represents the work of a master architect or possesses high artistic value. The residence at 9580 Rosamond Boulevard is a vernacular rendition of a California Ranch residence. As an unadorned example of a vernacular California Ranch, the property's residence does not embody enough of the distinctive characteristics of this style to be considered an exemplary or unique iteration of a vernacular California Ranch. Although vernacular architecture can be considered historically significant, the residence at 9580 Rosamond Boulevard is also not a distinctive, rare, or exemplary vernacular California Ranch which is a common type and style throughout rural areas of Southern California. The utilitarian outbuildings are typical wooden utilitarian buildings that do not embody a specific style, nor are they a rare, distinct, or excellent iteration of a rural farm building warranting historical significance for its architecture. PaleoWest also considered whether the subject property may be significant for an association with a master builder or architect; however, no record of a builder or architect was found through property and document search engines of the Kern County Tax Assessor's Office nor through archival research. In summary, the residence of the subject property is not a distinctive or rare example of a vernacular California Ranch residence in rural Southern California and the ancillary barn is also not a unique or rare example of a rural utilitarian barn or farm building. Additionally, neither building clearly represents or a specific period or method of construction, nor are they associated with a significant master architect or builder. As such, 9580 Rosamond Boulevard is recommended not eligible under Criterion 3.

The subject property is a common property type that is unlikely to provide vital information about history or prehistory that is not readily available through historical and archival research. As such, the property is recommended not eligible under CRHR Criterion 4.

The subject property is not within a designated or previously identified historic district. As a very sparsely developed and unincorporated area, the immediate vicinity of the property also lacks architectural cohesion and a defined shared historical narrative to be considered a historic district. Thus, 9580 Rosamond Boulevard is not recommended eligible as a contributor to a CRHR-eligible or listed historic district.

## 6.2.16 9009 Rosamond Boulevard (252-352-33)

Under Criterion 1, the subject property was evaluated for an association with significant historical events or broad patterns of history at the local, regional, state, or national level. The property is within an unincorporated area of the Antelope Valley, a region of the Mojave Desert that has a rich history of American exploration, migration, and settlement unique to the California and the high desert region during the nineteenth and early twentieth centuries. According to the Kern County Assessor's Office records, the residence was constructed circa 1959, which is well past the period for settlement at the regional (Antelope Valley), state (California), or local level. PaleoWest also considered whether 9009 Rosamond Boulevard may be significant for an association with the theme of Community Development of the Antelope Valley, 1918–1975 and the sub-theme of Rural Residential Development of the valley. Although the residence may date to the period of significance for the theme and sub-theme, the subject property is not a rare, unique, or exemplary example of a property associated with twentieth century community development and rural residential development of the Antelope Valley. It does provide a recognizable representation of broad patterns of residential development in the valley. Additionally, the property is within an unincorporated area of Kern County and the Antelope Valley that does not have a strong cohesive pattern of community history that would include the property's period of construction for which it might be considered historically significant. The property is near the communities of Willow Springs and Rosamond but lacks an immediate connection with the development of these communities. In summary, no direct associations between 9009 Rosamond Boulevard and historically significant events or broad patterns of history at the local, region, state, or national level could be established. As such, the subject property is recommended not eligible under CRHR Criterion 1.

Research was conducted to determine if the subject property is significant under Criterion 2 for associations with the lives of historically important persons who have made contributions to local, state, or national history. No direct connection to historically important individuals could be identified through historical and archival research of 9668 Rosamond Boulevard. Individuals found to be associated with the property through archival research include Ronald Smillie, Gilberto Navarez, Vicky Gale Carrer, Dixie Noel, and Douglas Arnold Middleton. No information was uncovered to confirm these individuals resided at 9009 Rosamond Boulevard during its historic period and research did not suggest the identified individuals made important contributions to history. Historically important persons such as explorers Pedro Fages, Joseph Walker, and John C. Frémont are known to have traveled through the area and to have stopped at nearby Willow Springs, but these events happened well before the construction of the extant buildings on the subject property. Therefore, there is no direct correlation between known significant historical figures and the property. As 9009 Rosamond Boulevard does not appear to be illustrative of the accomplishments of historically important persons within a local, state, or national historical context, the property is recommended not eligible under Criterion 2.

To evaluate the subject property under Criterion 3, PaleoWest considered whether it embodies distinctive characteristics of a type, period, or method of construction and whether it represents the work of a master architect or possesses high artistic value. The residence at 9009 Rosamond Boulevard is a vernacular rendition of the California Ranch style which is very common to rural areas of Southern California. As an unadorned example of the California Ranch style, the property residence does not embody enough of the distinctive characteristics of this style to be considered an exemplary or unique iteration of a California Ranch. Although

vernacular architecture can be considered historically significant, the residence at 9009 Rosamond Boulevard is also not a distinctive, rare, or exemplary vernacular California Ranch which is a common type and style throughout rural areas of Southern California. The utilitarian outbuildings are typical wooden utilitarian buildings that do not embody a specific style, nor are they a rare, distinct, or excellent iteration of a rural farm building warranting historical significance for its architecture. PaleoWest also considered whether the subject property may be significant for an association with a master builder or architect; however, no record of a builder or architect was found through property and document search engines of the Kern County Tax Assessor's Office nor through archival research. In summary, the residence of the subject property is not a distinctive or rare example of a vernacular California Ranch residence in rural Southern California and the modern commercial building (gas station) on the property is not an exemplary sample of commercial design or construction. It should also be noted that there are two additional age eligible utilitarian outbuildings on the property which are of a vernacular masonry design which are not exemplary samples of vernacular ancillary building design. Additionally, none of the buildings clearly represents or a specific period or method of construction, nor are they associated with a significant master architect or builder. As such, 9009 Rosamond Boulevard is recommended not eligible under Criterion 3.

The subject property is a common property type that is unlikely to provide vital information about history or prehistory that is not readily available through historical and archival research. As such, the property is recommended not eligible under CRHR Criterion 4.

The subject property is not within a designated or previously identified historic district. As a very sparsely developed and unincorporated area, the immediate vicinity of the property also lacks architectural cohesion and a defined shared historical narrative to be considered a historic district. Thus, 9009 Rosamond Boulevard is not recommended eligible as a contributor to a CRHR-eligible or listed historic district.

## 6.2.17 3045 90th Street (252-352-32) / High Desert Cellars

Under Criterion 1, the subject property was evaluated for an association with significant historical events or broad patterns of history at the local, regional, state, or national level. The property is just outside of Willow Springs a former resort community in Southern California. PaleoWest also considered whether 3025 90th Street West may be significant for an association with the theme of Community Development. Although this commercial property may date to the period of significance for the theme, the subject property is not a rare, unique, or exemplary example of a property associated with twentieth century community development. The property is near the communities of Willow Springs and Rosamond but lacks an immediate connection with the development of these communities. Thus, there is no direct association between 3045 90th Street West and historically significant events or broad patterns of history at the local, region, state, or national level could be established. As such, the subject property is recommended not eligible under CRHR Criterion 1.

Under Criterion 2, the subject property was evaluated for associations with the lives of historically important persons who have made contributions to local, state, or national history. No direct connection to historically important individuals could be identified. Therefore, there is no direct correlation between any known significant historical figures and the property. 3045 90th Street West is recommended not eligible under Criterion 2.

To evaluate the subject property under Criterion 3, PaleoWest considered whether it embodies distinctive characteristics of a type, period, or method of construction and whether it represents the work of a master architect or possesses high artistic value. The building at 3045 90th Street West is a one-story vernacular Spanish Revival commercial building, which is very common to Southern California. As an unadorned example of the Spanish Revival style, this commercial property does not embody enough of the distinctive characteristics of this style to be considered exemplary or unique. Although vernacular architecture can be considered historically significant, the commercial building at 3045 90th Street West is not a distinctive, rare, or exemplary vernacular Spanish Revival. The building does not clearly represent a specific period or method of construction, nor is it associated with a significant master architect or builder. As such, 3045 90th Street West is recommended not eligible under Criterion 3.

The subject property at 3045 90th Street West is a common property type that is unlikely to provide vital information about history or prehistory that is not readily available through historical and archival research. As such, the property is recommended not eligible under CRHR Criterion 4.

### 6.2.18 2973 95th Street (374-042-08)

Under Criterion 1, the subject property was evaluated for an association with significant historical events or broad patterns of history at the local, regional, state, or national level. The property is within an unincorporated area of the Antelope Valley, a region of the Mojave Desert that has a rich history of American exploration, migration, and settlement unique to the California and the high desert region during the nineteenth and early twentieth centuries. According to the Kern County Assessor's Office records, the residence was constructed circa 1942, which is well past the period for settlement at the regional (Antelope Valley), state (California), or local level. PaleoWest also considered whether 2973 95th Street may be significant for an association with the theme of Community Development of the Antelope Valley, 1918–1975 and the sub-theme of Rural Residential Development of the valley. Although the residence may date to the period of significance for the theme and sub-theme, the subject property is not a rare, unique, or exemplary example of a property associated with twentieth century community development and rural residential development of the Antelope Valley. It does provide a recognizable representation of broad patterns of residential development in the valley. Additionally, the property is within an unincorporated area of Kern County and the Antelope Valley that does not have a strong cohesive pattern of community history that would include the property's period of construction for which it might be considered historically significant. The property is near the communities of Willow Springs and Rosamond but lacks an immediate connection with the development of these communities. In summary, no direct associations between 2973 95th Street and historically significant events or broad patterns of history at the local, region, state, or national level could be established. As such, the subject property is recommended not eligible under CRHR Criterion 1.

Research was conducted to determine if the subject property is significant under Criterion 2 for associations with the lives of historically important persons who have made contributions to local, state, or national history. No direct connection to historically important individuals could be identified through historical and archival research of 2973 95th Street. Individuals found to be associated with the property through archival research include Ronald Smillie, Gilberto Navarez, Vicky Gale Carrer, Dixie Noel, and Douglas Arnold Middleton. No information was uncovered to confirm these individuals resided at 2973 95th Street during its historic period and

research did not suggest the identified individuals made important contributions to history. Historically important persons such as explorers Pedro Fages, Joseph Walker, and John C. Frémont are known to have traveled through the area and to have stopped at nearby Willow Springs, but these events happened well before the construction of the extant buildings on the subject property. Therefore, there is no direct correlation between known significant historical figures and the property. As 2973 95th Street does not appear to be illustrative of the accomplishments of historically important persons within a local, state, or national historical context, the property is recommended not eligible under Criterion 2.

To evaluate the subject property under Criterion 3, PaleoWest considered whether it embodies distinctive characteristics of a type, period, or method of construction and whether it represents the work of a master architect or possesses high artistic value. The residence and detached garage building at 2973 95th Street are a vernacular rendition of the California Ranch stye which is very common to rural areas of Southern California. As an unadorned example of the California Ranch style, the property residence does not embody enough of the distinctive characteristics of this style to be considered an exemplary or unique iteration of a California Ranch. Although vernacular architecture can be considered historically significant, the residence at 2973 95th Street is also not a distinctive, rare, or exemplary vernacular California Ranch which is a common type and style throughout rural areas of Southern California. The detached garage and utilitarian outbuilding are typical wooden utilitarian buildings that do not embody a specific style, nor are they a rare, distinct, or excellent iteration of a rural farm building warranting historical significance for its architecture. PaleoWest also considered whether the subject property may be significant for an association with a master builder or architect; however, no record of a builder or architect was found through property and document search engines of the Kern County Tax Assessor's Office nor through archival research. In summary, the residence of the subject property is not a distinctive or rare example of a vernacular California Ranch residence in rural Southern California and the ancillary barn is also not a unique or rare example of a rural utilitarian barn or farm building. Additionally, neither building clearly represents or a specific period or method of construction, nor are they associated with a significant master architect or builder. As such, 2973 95th Street is recommended not eligible under Criterion 3.

The subject property is a common property type that is unlikely to provide vital information about history or prehistory that is not readily available through historical and archival research. As such, the property is recommended not eligible under CRHR Criterion 4.

The subject property is not within a designated or previously identified historic district. As a very sparsely developed and unincorporated area, the immediate vicinity of the property also lacks architectural cohesion and a defined shared historical narrative to be considered a historic district. Thus, 2973 95th Street is not recommended eligible as a contributor to a CRHR-eligible or listed historic district.

## 6.2.19 2860 West 100<sup>th</sup> Street (374-041-09)

Under Criterion 1, the subject property was evaluated for an association with significant historical events or broad patterns of history at the local, regional, state, or national level. The property is within an unincorporated area of the Antelope Valley, a region of the Mojave Desert that has a rich history of American exploration, migration, and settlement unique to the California and the high desert region during the nineteenth and early twentieth centuries.

According to the Kern County Assessor's Office records, the residence was constructed circa 1940, which is well past the period for settlement at the regional (Antelope Valley), state (California), or local level. PaleoWest also considered whether 2860 West 100th Street may be significant for an association with the theme of Community Development of the Antelope Valley, 1918–1975 and the sub-theme of Rural Residential Development of the valley. Although the residence may date to the period of significance for the theme and sub-theme, the subject property is not a rare, unique, or exemplary example of a property associated with twentieth century community development and rural residential development of the Antelope Valley. It does provide a recognizable representation of broad patterns of residential development in the valley. Additionally, the property is within an unincorporated area of Kern County and the Antelope Valley that does not have a strong cohesive pattern of community history that would include the property's period of construction for which it might be considered historically significant. The property is near the communities of Willow Springs and Rosamond but lacks an immediate connection with the development of these communities. In summary, no direct associations between 2860 West 100th Street and historically significant events or broad patterns of history at the local, region, state, or national level could be established. As such, the subject property is recommended not eligible under CRHR Criterion 1.

Research was conducted to determine if the subject property is significant under Criterion 2 for associations with the lives of historically important persons who have made contributions to local, state, or national history. No direct connection to historically important individuals could be identified through historical and archival research of 2860 West 100th Street. Individuals found to be associated with the property through archival research include Patrick Ladd, Knollwood Inv Capital LLC, John Rehlkau, Ralph De Leon, Old Canal Financial. No information was uncovered to confirm these individuals or organizations resided at 9668 Rosamond Boulevard during its historic period and research did not suggest the identified individuals made important contributions to history. Historically important persons such as explorers Pedro Fages, Joseph Walker, and John C. Frémont are known to have traveled through the area and to have stopped at nearby Willow Springs, but these events happened well before the construction of the extant buildings on the subject property. Therefore, there is no direct correlation between known significant historical figures and the property. As 2860 West 100th Street does not appear to be illustrative of the accomplishments of historically important persons within a local, state, or national historical context, the property is recommended not eligible under Criterion 2.

To evaluate the subject property under Criterion 3, PaleoWest considered whether it embodies distinctive characteristics of a type, period, or method of construction and whether it represents the work of a master architect or possesses high artistic value. The residence and ancillary buildings at 2860 West 100th Street are vernacular renditions of the California Ranch stye which is very common to rural areas of Southern California. As an unadorned example of the California Ranch style, the residence does not embody enough of the distinctive characteristics of this style to be considered an exemplary or unique iteration of a California Ranch. Although vernacular architecture can be considered historically significant, the residence at 2860 West 100th Street is also not a distinctive, rare, or exemplary vernacular California Ranch which is a common type and style throughout rural areas of Southern California. The utilitarian ancillary outbuildings are typical wooden utilitarian buildings that do not embody a specific style, nor are they a rare, distinct, or excellent iteration of a rural farm building warranting historical significance for its architecture. It should also be noted that there appears

to be a secondary residential structure on this parcel, also a California Ranch style; however, there is no record of this secondary residential on the Kern County Property Appraiser records and it is not clearly visible from the right of way for assessment. PaleoWest also considered whether the subject property may be significant for an association with a master builder or architect; however, no record of a builder or architect was found through property and document search engines of the Kern County Tax Assessor's Office nor through archival research. In summary, the residence of the subject property is not a distinctive or rare example of a vernacular California Ranch residence in rural Southern California and the ancillary outbuildings are also not a unique or rare example of a rural utilitarian or farm building. Additionally, neither building clearly represents or a specific period or method of construction, nor are they associated with a significant master architect or builder. As such, 2860 West 100th Street is recommended not eligible under Criterion 3.

The subject property is a common property type that is unlikely to provide vital information about history or prehistory that is not readily available through historical and archival research. As such, the property is recommended not eligible under CRHR Criterion 4.

The subject property is not within a designated or previously identified historic district. As a very sparsely developed and unincorporated area, the immediate vicinity of the property also lacks architectural cohesion and a defined shared historical narrative to be considered a historic district. Thus, 2860 West 100th Street is not recommended eligible as a contributor to a CRHR-eligible or listed historic district.

#### 6.2.20 APN 358-131-02

The subject property at 10085 Hamilton Road (358-052-07) could not be evaluated for historical significance because none of the buildings are visible from the ROW to visually assess and none are listed in the Kern County Property Appraiser records. Additional details are indiscernible from the public ROW due to the setback and safety concerns during the survey. PaleoWest recommends that the resource be assumed eligible for the CRHR for the current Project.

## 6.2.21 Historic District Eligibility

No eligible districts were identified. As a very sparsely developed and unincorporated area, the immediate vicinity of the properties in the survey area lack architectural cohesion and a defined shared historical narrative to be considered a historic district. In addition, there is a lack of cohesion between resources in the survey area.

## 7 IMPACTS ASSESSMENT

PaleoWest determined that there are two historic period built environment resources within the Project API that are eligible or listed on the CRHR: Willow Springs Village and a segment of the Vincent 220kV Transmission Line / Big Creek Hydroelectric Historic District. The Willow Springs Village is a California Landmark and is individually eligible for listing in the CRHR. The Vincent Transmission Line is listed in the NRHP and CRHR as a contributing resource to the NRHP/CRHR-listed Big Creek Hydroelectric Historic District. Additionally, three resources, 10085 Hamilton Road, 10057 Hamilton Road, and APN 358-131-02, could not be evaluated and

are assumed eligible for the purposes of this Project. Potential impacts to these historical resources were considered in accordance with CEQA with guidance from the SOI Standards for the Treatment of Historic Properties. PaleoWest also considered potential impacts to three resources within the API that were inaccessible and thus could not be evaluated. To comply with CEQA, these three resources were assumed eligible for listing in the CRHR.

Pursuant to CEQA, potential direct, indirect, and culminative effects to historical resources were considered. To adequately assess potential impacts, PaleoWest referred to CEQA Appendix G to establish appropriate thresholds of significance. Potential factors that might affect historical resources include noise, vibration, visual obstructions, and aesthetics. Loss of a major scenic view, damage to structural integrity of historical resources through vibration or other physical damage, and loss of feeling, setting, or association would be considered significant impacts.

## 7.1.1 Willow Springs Village, California Historic Landmark #130

The proposed Project will have no direct impact on the Willow Springs Village. As no direct impacts are anticipated, the location, materials, and workmanship of the elements of the site should remain unaffected by the Project. Hydrostor has proposed multiple alternative routes of the proposed transmission lines. Although the site currently includes viewsheds of distant transmission lines, to prevent potential cumulative impacts to the historical resource, PaleoWest recommends that new construction be setback at least 1,000 ft from the contributing resources of the site. The new construction would thus not block historical resources from view nor significantly alter views to or from historical resources. Implementation of this mitigation measure will also ensure potential adverse cumulative impacts are less than significant, as defined by CEQA. The impact from the introduction of new transmission lines would thus be naturally mitigated by their distance from the village, the natural topography, and would constitute only a minor change. Specifically, the distance also ensures the setting, feeling, and associations of the historical resource will be unaffected.

Conversely, one of the proposed transmission line options, the easternmost corridor running north to south, is within the ADI of the resource boundary and would be approximately 300 ft from the site's contributing resources. Thus, it would constitute an indirect visual impact to the site's integrity, namely feeling and setting. Therefore, this option should be avoided.

## 7.1.2 Vincent 220kV Transmission Line; Big Creek Hydroelectric Historic District

A 1.75-mi segment of the Vincent 220kV Transmission Line, a contributor to the Big Creek Hydroelectric Historic District, transects the API along the Project's southwest corner but does not intersect the ADI. The Project will not directly impact the existing Transmission Line. Indirectly, additional towers and lines would visibly intrude on this segment of the Vincent Line, but given it is a 224-mi long contributor to the District, this would not constitute a significant impact to the contributor or the District as a whole.

## 7.1.3 10085 Hamilton Road (APN 358-052-07)

PaleoWest was unable to access the property associated with APN 358-052-07 and thus could not properly evaluate it under the CRHR criteria for significance. For this reason, PaleoWest

assumed that the property is CRHR-eligible for purposes of assessing impacts under CEQA. The resource is 600 ft from the nearest proposed Project transmission line, which would be along Hamilton Road to the immediate south. Any Project transmission line would be away from the primary view of the property such as not significantly impact any integrity to convey the resource's potential significance, namely setting or feeling. Additionally, the proposed Project will not significantly impact 10085 Hamilton Road from any vibration that would damage the structure due to distance.

#### 7.1.4 10057 Hamilton Road (APN 358-052-06)

PaleoWest was unable to access the property associated with APN 358-052-06and thus could not properly evaluate it under the CRHR criteria for significance. For this reason, PaleoWest assumed that the property is CRHR-eligible for purposes of assessing impacts under CEQA. The resource is 600 ft from the nearest proposed Project transmission line, which would be along Hamilton Road to the immediate south. Any Project transmission line would be away from the primary view of the property such as not significantly impact any integrity to convey the resource's potential significance, namely setting or feeling. Additionally, the proposed Project will not significantly impact 10057 Hamilton Road from any vibration that would damage the structure due to distance.

#### 7.1.5 APN 358-131-02

PaleoWest was unable to access the property associated with APN 358-131-02 and thus could not properly evaluate it under the CRHR criteria for significance. For this reason, PaleoWest assumed that the property is CRHR-eligible for purposes of assessing impacts under CEQA. The resource is 0.47-mi from the nearest proposed Project transmission line. Due to this distance, the proposed Project will not significantly impact APN 358-131-02 directly or indirectly, whether from view or any vibration that would damage the structure.

## 8 RESULTS AND RECOMMENDATIONS

## 8.1 SUMMARY OF RESULTS

PaleoWest identified and evaluated all resources within the API that are forty-five years or older for eligibility to the CRHR. Two eligible resources were previously identified and are listed in Table 8-1.

Table 8-1. Previously Identified CRHR-eligible or Listed Historical Resources within the API

Map Number	Name	Primary Number	Previous Evaluation Date	Previous CRHR Determination	Updated Eligibility Recommendation	Finding of Effect
1	Willow Springs	15-000129 (also associated with 15- 003560)	1934	N/A-Evaluation for landmark status pre-dates the CRHR	CRHR-eligible	Less than Significant with Implemented Mitigation

Map Number	Name	Primary Number	Previous Evaluation Date	Previous CRHR Determination	Updated Eligibility Recommendation	Finding of Effect
3	Vincent 220kV Transmission Line	15-017243	2019	Eligible/Listed as a contributing resource to the SCE Big Creek Hydroelectric System Historic District	_	No Impact

A further twenty resources were newly identified and evaluated. Of these, access to three properties limited PaleoWest's ability to properly evaluate the resources' historical significance and integrity for CRHR listing. As visibility to three properties was limited from the ROW, these cultural resources (Table 8-2) were assumed to be CRHR-eligible for the purposes of this study and the impacts assessment for regulatory compliance.

Table 8-2. Built Environment Cultural Resources Assumed CRHR-eligible within the API

Map Number	Name/Address	APN(s)	Build Date	Finding of Effect
10	10085 Hamilton Road	358-052-07	1940	Less than Significant
11	10057 Hamilton Road	358-052-06	1951	Less than Significant
20	Unknown	358-131-02	ca. 1970	Less than Significant

Sixteen resources within the API were evaluated for CRHR-eligibility and not recommended eligible as a historical resource pursuant to CEQA (Table 8-3).

Table 8-3. Built Environment Cultural Resources within the API Recommended Not Eligible for CRHR Listing

Map Number	Name/Address	APN(s)
2	Segment of the LADWP Easement Corridor (LADWP Owens Gorge 230kV Transmission Line; Owens Gorge Access Road)	_
4	General Petroleum Access Road	_
5	14205 Irone Avenue	358-132-12
6	4040 Manly Road	315-012-01, 252-341-05
7	14101 Irone Avenue	358-132-10
8	14070 Lodestar Avenue	358-132-07
9	10145 Hamilton Road	358-052-08
12	9714 Rosamond Blvd	374-042-03
13	9668 Rosamond Blvd	374-042-04
14	9650 W Rosamond Blvd	374-042-39
15	9580 Rosamond Blvd	374-042-07

Map Number	Name/Address	APN(s)
16	9009 Rosamond Blvd	252-352-33
17	3045 90th Street West / High Desert Cellars	252-352-32
18	2973 95th Street	374-042-08
19	2860 W 100th Street	374-041-09

#### 8.2 RECOMMENDATIONS AND CONCLUSION

PaleoWest performed an architectural history survey, evaluation, and analysis of impacts to identify and document historic period built environment resources that are listed, eligible, or potentially eligible for listing in the CRHR for the purposes of compliance with CEQA. As a result of the architectural history field survey of the API, PaleoWest identified and documented five historical resources—two previously listed in the CRHR (Willow Springs Village and the Vincent 220kV Transmission Line) and three assumed CRHR-eligible for the purposes of assessing impacts under CEQA.

The Project will not result in any adverse direct impacts such as demolition or materialistic alteration to historical resources. No significant indirect and visual impacts to the Vincent 220kV Transmission Line and the SCE Big Creek Hydroelectric System Historic District are anticipated. For the Willow Springs Village, PaleoWest recommends that new construction be setback at least 1,000 ft from the contributing resources. Visual impacts to the Willow Springs Village are expected to be less than significant with implantation of the recommended mitigation measure, and no other significant impacts to the site are expected. Impacts to 10085 Hamilton Road, 10057 Hamilton Road, and APN 358-131-02 from the Project, as proposed, are anticipated to be less than significant. As such, the Project as proposed will not result in a substantial adverse change or significant impact in accordance with CEQA Section 15064.5(b).

## 9 REFERENCES

#### AvangridRenewables.com

2021 "Manzana Wind Power Project," Avangrid Renewables, https://www.avangridrenewables.com/wps/wcm/connect/www.avangridrenewables.com/5590/54fcacf6-cb62-4b95-a026-8bef3a041068/manzana-project-factsheet.pdf?MOD=AJPERES&amp, accessed September 2021.

#### The Bakersfield Californian

"Murphy Leases Hamilton Claim, Mine Which Once Produced Unusually Rich Ore to Be Operated Again," January 25, page 5. Bakersfield, California. Available at: https://www.newspapers.com/, accessed April 2022.

#### Bakersfield Morning Echo

"Gala Day at Willow Springs: Ezra M. Hamilton and Mrs. Galloway Wed," Thursday July 7, page 4. Bakersfield, California. Available at: https://www.newspapers.com/, accessed April 2022.

#### Barnard, Edward S. (editor)

1977 Story of the Great American West. Pleasanton, New York: The Reader's Digest Association.

#### Barnes, D.F.

2007 The Challenge of Rural Electrification: Strategies for Developing Countries. RFF Press, Washington D.C.

#### Bean, Lowell John, and Lisa Bourgeault

1989 The Cahuilla. In *Indians of North America*. Frank W. Porter III, general editor. Chelsea House Publishers.

#### Beck, Warren A., and Ynez D. Haase

1974 Historical Atlas of California. Norman, Oklahoma: University of Oklahoma Press.

#### Bostwick, Charles F.

2010 "Local History - Willow Springs," Rosamond, CA 93560: The Unofficial Website.
Rosamond, California: *Antelope Valley Press*,
http://www.rosamondca.us/history/WillowSprings.htm, accessed September 2021.

California Department of Transportation (Caltrans), Anthropological Studies Center (ASC), and JRP Historical Consulting Services, LLC.

2010 A Historical Context and Archaeological Research Design for Townsite Properties in California. Division of Environmental Analysis, Sacramento, California.

#### California Department of Transportation (Caltrans)

2007 A Historical Context and Archaeological Research Design for Agricultural Properties in California. Division of Environmental Analysis, Sacramento, California.

2008 A Historical Context and Archaeological Research Design for Mining Properties in California. Division of Environmental Analysis, Sacramento, California.

#### California Office of Historic Preservation (California OHP)

- 2001 "How to Nominate a Resource to the California Register of Historical Resources."
  California State Parks, Office of Historic Preservation. Technical Assistance Series
  #7
- 2021 "Willow Springs Historical Landmark." California State Parks, Office of Historic Preservation. Available: https://ohp.parks.ca.gov/ListedResources/Detail/130. Accessed September 2021.

#### Coues, Elliot (editor)

1900 On the Trail of a Spanish Pioneer, the Diary and Itinerary of Francisco Garces in His Travels Through Sonora, Arizona, and California. New York: Francis P. Harper Company.

#### Dice, Michael H.

2014 California Department of Parks and Recreation 528 Forms for LADWP Owens Gorge 230kV Transmission Line (P-15-018681), in *Cultural Resource Survey for the Barren Ridge-Haskell Canyon 230k V Transmission Line, Los Angeles and Kern counties, California.* Submitted to LADWP and the Angeles National Forest by POWER Engineers.

#### Dunne, Kerry

2016 "Boomtimes Again: Twentieth-Century Mining in the Mojave Desert," Primary Source Sets, Digital Public Library of America, Massachusetts. https://dp.la/primary-source-sets/boomtimes-again-twentieth-century-mining-in-the-mojave-desert, accessed April 2022.

#### Edison International

2021 "Spotlight: The Tehachapi Project." Edison International. Available: https://energized.edison.com/harnessing-faraway-winds-to-power-southern-california. Accessed September 2021.

#### **Environmental Science Associates**

2008 North Los Angeles / Kern County Recycled Water Project Final Program
Environmental Impact Report SCH No. 2007101125 (ESA / 206359). Prepared for
Los Angeles County Waterworks District 40 - Antelope Valley,
https://pw.lacounty.gov/wwd/web/Forms/peir.aspx, accessed April 2022.

#### Frémont, John C.

1845 Report of the Exploring Expedition to the Rocky Mountains in the Year 1842 and to Oregon and North California in the Years 1843–1844. Washington: Gales and Seaton.

## General Land Office (GLO)

1856 "Township 9 North, Range 13 East, San Bernardino Meridian" [map]. Survey approved February 19.

#### Google Earth Pro

2013 Willow Springs, CA. Aerial imagery. May.

2015 Willow Springs, CA. Aerial imagery. April.

#### Greene, Andry and Albert Knight

1992 "P-15-000129 Supplement, Trinomial CA\_KER-129), California Landmark #130 Willow Springs," Western Mojave Survey Association, North Hollywood, California.

#### HistoricAerials.com

1948 Willow Springs, CA. Aerial imagery.

1959 Willow Springs, CA. Aerial imagery.

1963 Willow Springs, CA. Aerial imagery.

1974 Willow Springs, CA. Aerial imagery.

1989 Willow Springs, CA. Aerial imagery

2003 Willow Springs, CA. Aerial imagery

2018 Willow Springs, CA. Aerial imagery

#### Kern County Recorder

1960 Tract No. 2355 [map]. Record of Survey Book 7, Page 191.

#### LACountyLibrary.com

2021 "Antelope Valley, Community History," Los Angeles County Library. https://lacountylibrary.org/antelope-valley-local-history/, accessed September 2021.

#### Lien, Lauren

2021 "The History of Willow Springs." Lancaster Museum of Art & History. Available: https://www.lancastermoah.org/single-post/the-history-of-willow-springs. July 7. Accessed September 2021.

#### Los Angeles County Agricultural Commissioner

2012 Crop & Livestock Report, Antelope Valley: Agricultural Vistas, County of Los Angeles, Department of Agricultural Commissioner/Weights and Measures. Arcadia, California. Available at https://acwm.lacounty.gov/.

#### Los Angeles Cultural Heritage Masterplan

2000 "Preservation in Context," in Cultural Heritage Masterplan Final Draft: Chapter II.

#### National Park Service (NPS)

2020 "Ranching in Mojave National Preserve," Mojave National Preserve, Barstow, California, https://www.nps.gov/moja/learn/historyculture/ranching.htm, accessed April 2022.

#### Norris, Frank, and Richard Carrico

1978 A History of Land Use in the California Desert. Prepared for U.S. Department of the Interior Bureau of Land Management. On file at AECOM San Diego.

#### Orr, Patti

- 2021a "History of Willow Springs, Gold Town and Fleta Calif.," July 6, *Mojave Desert News*, http://www.desertnews.com/news/article\_687a0e14-ddc6-11eb-af2b-fb7dedd9aa72.html, accessed April 2022.
- 2021b "History of Rosamond, California," May 19, *Mojave Desert News*, https://www.desertnews.com/news/article\_42a5537c-b8b6-11eb-9dbc-f725f80f9128.html, accessed April 2022.

#### Palm Desert Post

1982 "Edison Joins with Private Firm to Start Tehachapi 'Wind Farm.'" January 13: A-7.

#### Pourade, Richard F.

- 1960 *The History of San Diego: The Explorers*. San Diego: Union-Tribune Publishing Company.
- 1961 *The History of San Diego: The Time of the Bells.* San Diego: Union-Tribune Publishing Company.

#### Rincon Consultants, Inc.

2021 Rosamond A-CAES Facility Project Cultural Resources Assessment Report. Prepared for Hydrostor, Inc. Los Angeles, California.

#### Sherer, Lorraine M.

1994 Bitterness Road: The Mojave 1604 to 1860. Menlo Park, California: Ballena Press.

#### Struglia, Rachel; Patricia L. Winter; Andrea Meyer

2003 Southern California Socioeconomic Assessment: Sociodemographic Conditions, Projections, and Quality of Life Indices, General Technical Report PSW-GTR-187, Pacific Southwest Research Station, United States Forest Service, United States Department of Agriculture: Berkeley, California.

#### Sutton, Mark Q.

1991 Archaeological Investigations at Cantil, Fremont Valley, Western Mojave Desert, California. Museum of Anthropology, California State University, Bakersfield, Occasional Papers in Anthropology 1.

#### Tinsley Becker, Wendy L., and Christina Chiang

2016 Historic American Engineering Record Big Creek Hydroelectric System, Vincent 220kV Transmission Line, HAER No. CA-167-O, Urbana Preservation & Planning, LLC.

#### Tipton, Karla

1988 "Willow Springs: An Oasis in Antelope Valley" from *Antelope Valley Press* in *The Gold Ledge.* Available: https://www.karlatipton.com/portfolio/Antelope-Valley-Press-Willow-Springs-May-1988.pdf. Accessed September 2021.

University of California Cooperative Extension (UCCE)

"High Desert," University of California Agriculture and Natural Resources (ANR), https://celosangeles.ucanr.edu/Agriculture/High\_Desert/, accessed April 2022.

University of Santa Barbara (UCSB) Library

1952a Flight ID ABL-1952, Frame 3K-89. October 12.

1952b Flight ID ABL-1952, Frame 4K-39. October 12.

This page intentionally left blank.

# Appendix A. Site Forms

State of California — The Resources Agency DEPARTMENT OF PARKS AND RECREATION

## PRIMARY RECORD

**Primary #** 15-000129

HRI# **Trinomial** 

**NRHP Status Code** 

Other Listings

	Review Code	Revie	wer		L	Jate		
Page 1 of 20	*Resource Name	or #:	Willow	Springs V	illage	☐ Cont	tinuatio	n 🛛 Update
P1. Other Identifier:	Willow Springs Townsite, Calif	_			-			· Mobauto
*P2. Location:	Not for Publication ⊠ Unrestric							
*a. County: Kern	<del></del>		. P2e. and	P2b or P2d.	Attach a Location Map as	s necessarv	.)	
	Villow Springs <b>Date</b> 1965			13W	SE ¼ of SW ¼ of	-	07	S.B.B.M.
c. Address Manly Road		City	Rosan				Zip	93560
d. UTM: (give more than one for	large and/or linear resources) Zone	11N		381518 m	nE/ 3860375 mN		_	
e. Other Locational Data: (e	.g. parcel#, directions to resource, elevation				SW 1/4 of SW 1/4 Se	<u>-</u> c 07, nort	h of Tru	uman Road
*P3a. Description: (Description)	pe resource and its major elements. In	clude de	sian. mat	erials, cond	dition, alterations, size,	setting, a	nd boun	daries)
Desert, identified as a Calif 1992. The springs were als Water of the springs origin approximately 0.25-mile no the late nineteenth century survey, there were 23 remidentified architectural resolutions of the control	historic-era American rural reside ornia Historical Landmark (#130) in o known by the name Willow Spriated in the Tehachapi Mountains of Truman Road. The land surty, and the area developed into a naining buildings and structures bources included 16 standing unrequins, four stone wells, one rounced to the village (P-15-003560), but	n 1934. ings, bu and flov rounding small v built duri einforce I concre	The site to no evid wed through the spillage at ng the od masor te-lined	was subsidence of rough Oak rings was the begin original sentry buildingool, and	sequently document remaining springs w Creek to the village of first settled sparse nning on the twent ettlement period, cangs (one of which	ted in 195 as found The cer by by Eur ieth cent 1860-19 is in a s	59, 1969 during nter of to-Amer ury. At 900, ide state of	5, 1980, and field survey. the village is ricans during the time of entified. The f substantial
·	-					•	ntinue	d on page 3)
P3b. Resource Attributes	· ——				, HP32. Rural Open		<u></u>	
	☐ Building ☐ Structure ☐ Objec			strict	Element of District		(Isolate	s, etc.)
P5a. Photograph or Drawin	g (Photograph required for buildings, structu	ures, and o	objects.)	] per p	and the second second			
					<b>Pescription of Photo</b> 1. Westerly view fro			
					Manly Road (March 2		ic villag	<u> </u>
The state of the s					Date Constructed/A toric Prehistori 00-1915 us DPR records	_		
				*P7. O\	wner and Address:			
			是 國籍 1	Kathy a	and James Nelson			
		- Alexandria	and the state of	4040 N	Manly Road, Rosamo	nd, CA 9	3560	,
				Lisa C.	ecorded by: (Name, Demarais, M.A.	affiliation,	and add	dress)
	A. T. Shared St.			Evan N	Mills, M.A., RPA			
			Mary Control		Vest, LLC.			
				571 S.	Ivy Avenue, Monrov	∕ia, CA 91	016	
				* <b>P</b> 9. I	Date Recorded:	April 26, :	2022	
*P10. Survey Type: (Descri	· ·							
2022 PaleoWest, LLC. A A-CAES Project, K	survey report and other sources, or endistoric Resources Evaluation Reportern County, California (2021). Prep	<i>ort, Add</i> ared for	<i>endum t</i> Golder	Associate	es			
	□ Location Map    □ Sketcl Record    □ District Record    □ ograph Record    □ Other (List):			Continuation Record				, and Object k Art Record

State of California — The Resources Agency DEPARTMENT OF PARKS AND RECREATION

**Primary #** 15-000129

HRI#

## **BUILDING, STRUCTURE, AND OBJECT RECORD**

Page 2 of 20	*NRHP Status Code 3C	.5 (previously /L)
	*Resource Name or # (Assigned by recorder)	) _ Willow Springs Village
B1. Historic Name:	Willow Springs, Willow Springs Village	
B2. Common Name:	Willow Springs	
B3. Original Use:	Residential, recreation, agriculture, lodging/hotel	
B4. Present Use:	Residential, agriculture	
*B5. Architectural Styl		1000 1015 D
		ktant buildings were constructed ca. 1900-1915. Records
	nree extant residences have all been altered with addi	206. An earlier stagecoach building built ca. 1865 is no
*B7. Moved? ⊠ No ☐		iginal Location: N/A
*B8. Related Features:		H-L
B9a. Architect: Unknows		Unknown  Area: Townsite Development in the Majava Desert
*B10. Significance: Th		Area: Townsite Development in the Mojave Desert
Period of Significance		Townsite Applicable Criteria: A, B, C, D
	n terms of historical or architectural context as defined by the	me, period, and geographic scope. Also address integrity.) orer and pioneer Jedediah Smith in 1826, and Americal
Act of 1877 generated agreement to improve that agreement to improve that agreement to improve that agreement to improve that agreement to generate agreement and the agreement and twentieth centuries. Videoline based on factors	some American settlement. Individuals could apply for the land; under the Desert Land Act, settlers specific b. In the Antelope Valley, settlement primarily followers: 8: 3.4-6). In 1866, Kern County was formed from portioning of towns by both individuals and large developers california have a shared history in the evolution of griculture, mining, and development of energy resour of the developmental trends throughout California as. Specifically, the evolution of Willow Springs reflyvillow Springs, like most small California towns foun	is a key characteristic of frontier colonization in California transportation networks, natural water features, water irces. While a very small community, the Willow Spring and particularly in the South Desert during the nineteentlects the ad hoc development approach typical of ruranded during the nineteenth century, would also grow and of access (Caltrans, et al. 2010: 142-143). In 1934, Willow
- <del> </del>		(continued on page 8
R11 Additional Passure	ce Attributes: (List attributes and codes)	
DTT. Additional Nesouli	ce Attributes. (List attributes and codes)	(Sketch Map with north arrow required.)
HP11. Engineering Stru	icture, AH12. Graves/cemetery, HP45. Unreinforced	(Sketch Map with Horth arrow required.)
	46. Walls/gates/fences, HP39. Other: Architectural	
ruins		
*B12. References: See	e page 11	
*B14. Evaluator:	Lisa Demarais, PaleoWest	
*Date of Evaluation:	April 26, 2022	
(This en	ace reserved for official comments.)	
(11113 35)	ace reserved for official confinients.	

State of California — The Resources Agency DEPARTMENT OF PARKS AND RECREATION CONTINUATION SHEET			Primary # 15-000129 HRI# Trinomial		
		Tri			
Page 3 of 20	*Resource Name or # (Assigned by reco	order) Wi	llow Springs Village		
Recorded by:	Lisa Demarais Da	ate: Ap	ril 26, 2022		
				☐ Continuation ☐Update	

#### \*P3a. Description: (continued)

The setting is rural and agricultural with a mixture of open undeveloped land, farmland, residences, ancillary buildings, and various buildings no longer in use but are believed to have been additional residences and community buildings. There are various dirt roads as well as one paved road (Manly Road) throughout the site. Most of the roads are lined with planted trees. The landscape is defined by gentle hills and winding roads that provide a rustic and picturesque feeling. Vegetation includes a mixture of native grasses, shrubs, and trees as well as designed rows of shrubs flanking roadways. The vegetation is consistent with designed landscaping and permaculture in Southern Californian deserts, using predominantly low-water plants such as Oleander, Eucalyptus, and Joshua Trees. Vegetation includes freely growing native grasses, trees, and shrubs; limited decorative plantings of low-water and drought-resistant plants; and plantings of shrubs and trees along roads, property boundaries, and residences to serve as windbreaks and prevent flash-flooding of sandy soils in the event of rain. Overall, the district has a high level of cohesion, tied together by the rural desert landscape, density of development, the use of masonry construction materials, and the shared scale and massing of the buildings.

The extent of the village during its formal years of early development, ca. 1900-1915, is believed to have been approximately ¼ square-mile based on previous documentation by archaeologists and historians; however, no primary source maps or descriptions of the village's original boundary have been uncovered. Remains of a school and a known burial site indicate areas of the village beyond the primary grouping of buildings flanking Manly Road and a possibly larger boundary than previously recorded. The boundary was drawn in consideration of both this recorded 0.25-square-mile boundary estimating and the locations of known cultural resources. As to not include speculation, the boundary drawn possibly excludes land that may have once been within the Willow Springs Village but cannot be proven to or presumed as such. Additional areas that could be reasonably believed to have been part of the village but are excluded from the boundary are APNs 252-012-02, 252-341-07, 252-341-04, 315-152-01 through 315-152-08, and the full extent of 252-351-48. The boundary of Willow Springs Village is depicted on the Location Map. The boundary includes all of Assessor Parcel Number (APN) 315-012-01 (73.85 acres) and APN 315-012-02 (.79 acres) as well as portions of APN 252-341-06 and APN 252-351-48 where extant original site elements were identified.

#### Residence A (Building 1)

Residence A is a one-story single-family residence at the southern boundary of APN 315-012-01. There are nine (9) ancillary buildings adjacent to Residence A, seven (7) of which are original village masonry buildings dating to ca. 1900-1915. The residence has a t-shaped plan. Architectural features include a corrugated metal cross-gable roof and fieldstone masonry exterior walls. The north (primary) façade features a concrete slab front porch covered by a front-gable roof projection with closed wooden eaves. The porch roof is supported by simple wood Y-shaped columns. The east façade of the east-west wing has a stone exterior chimney. The visible windows are a mixture of double-hung and horizontal slider types comprised of white aluminum frames and wood surrounds. The north side of the residence is set behind 3-foot-tall fiberglass fencing. Landscaping includes native trees and shrubs as well as a palm tree. Ancillary stone buildings are situated to the east and south of Residence A.

#### Old Meeting Hall (Building 3)

The Old Meeting Hall is a one and one-half story rectangular plan building with a side gable roof. It is immediately north of Manly Road and northeast of Residence A. The Old Meeting Hall is of fieldstone construction and has a wood framed roof with exposed wood rafter tails and corrugated metal sheets for roof cladding. The south (primary) façade features concrete steps that lead to a full porch constructed of open poured concrete block and wooden double batwing doors that serve as the primary entrance. The batwing doors are inset into a small stone projection covered by a shed-shaped roof extension. Historical photos indicate the entrance originally featured a front gable while the main roof was hipped. The concrete steps are flanked by metal tube railings. There are two additional entrances on the south façade, a glass inset divided-light wood door and a faux-paneled fiberglass door. Each door is topped with a single-lite transom. The south façade also features a small horizontal-oriented fixed window and a tall double-hung window. The windows of the east and west façades are all tall double-hung wood frame types. The east façade has a wooden exterior stairway that leads to a flat wood door. A window insert air-conditioning unit is above the door, blocking off what was likely a single-lite transom. The wood paneling and wood-frame windows beneath the side gables on the east and west façades are not original.

State of California — The Resources Agency DEPARTMENT OF PARKS AND RECREATION CONTINUATION SHEET

Page 4 of 20

**Primary #** 15-000129 **HRI#** 

Willow Springs Village

Trinomial

\*Resource Name or # (Assigned by recorder)

Recorded by: Lisa Demarais Date: April 26, 2022

☐ Continuation ☐ Update



Figure 1. Old Meeting Hall (left) and two ancillary buildings ca. 1900 (California Historical Society CHS-7665).

State of California — The Resources Agency DEPARTMENT OF PARKS AND RECREATION CONTINUATION SHEET			Primary # 15-000129 HRI#	
			Trinomial	
Page 5 of 20	*Resource Name or # (Assigned by red	corder)	Willow Springs Village	
Recorded by: L	Lisa Demarais D	Date:	April 26, 2022	
		·		☐ Continuation ☐Update

#### Building 2

Building 2 is a long rectangular plan one-story utilitarian structure with a corrugated metal side gable roof. The name "Willow Springs" is emblazoned across the southern slant of the roof, though the signage is faded. Circulation vents lie below each gable end. The exterior of the building is comprised of white limestone block. The south (primary) façade features two single personnel entrance doors and four metal double doors with iron strap hinges. One personnel door is flat metal and the other is wooden with a square glass insert. The building measures approximately 115 feet wide by 25 feet deep. Windows are double-hung with wooden frames.

#### Building 4

Building 4 (Image 23) is a rectangular plan one-story utilitarian structure with a corrugated metal side gable roof. The exterior of the building is comprised of white limestone block. The wood paneling on the front (south) gable is not original. The south façade features a single personnel entrance door with a single fixed window on the gable. The west façade features a single fixed window and the east facade features two single personnel entrance doors. The building measures approximately 45 feet wide by 18 feet deep.

#### **Building 5**

Building 5 (Image 24) is a rectangular plan one-story utilitarian structure identical to Building 4 with the exception of altered dimensions: measuring approximately 29 feet wide by 19 feet deep.

#### Pool

The cement-lined pool is in an orchard between Manly Road and Tehachapi-Willow Springs Road. The extant structure is 50 feet in diameter and is believed to be original to the resort built by Ezra Hamilton ca. 1900-1915 based on historic photos (Figure 2). It is not possible to see if the bottom interior of the pool is cement lined because it is filled with dirt and vegetation.

#### Wells

The four extant wells are above ground fieldstone structures located within orchards on the east and west sides of Manly Road. Two wells are 20 feet in diameter (Image 14 and 16), one well is 30 feet in diameter, and one is 5 feet in diameter. The wells stand approximately 4 feet above the ground. Historic aerial photographs indicate the wells have been present since at least the 1930s, and were most likely constructed at the time the other fieldstone structures at the site. Historical photos show at least one well had been constructed in the village by 1903 (Figure 2).

#### School Ruin

The school ruin (Image 17) consists of a partial collapsed fieldstone masonry building that served as the local school building during the early twentieth century. The ruin is situated east of Tehachapi-Willow Springs Road at the eastern end of APN 315-012-01. Small portions of the east, west, and south façades remain, and the roof and north wall are entirely collapsed. A doorway-sized opening with wood framing is present on the remaining portion of the south façade, which is believed to have been the primary façade. Two steps lead up to the entrance.

#### Unidentified masonry ruin

An unidentified masonry ruin is west of Manly Road. The ruin is difficult to see from the right-of-way but appears to be of fieldstone construction with at least half of two walls, the north and east façades, remaining. The original use of the structure is unknown based on available data.

#### Buildings 6-12

Buildings 6-12 (Images 2, 3, and 9-12) are located south of Manly Road across the street from the Old Meeting Hall. The buildings are all one-story utilitarian structures with a corrugated metal side gable roof. The exterior of the buildings are comprised of white limestone block. They are rectangular in shape, except for Building 6, Building 7, and Building 11. Building 6 has a recent addition, rectangular in shape, added to the south façade and is constructed of cement stone masonry. Building 7 is L-shaped and appears to be

State of Califo	ornia — The Resources Agency Prima	ary # 15-00	00129	
DEPARTMEN	T OF PARKS AND RECREATION		HRI#	
CONTINU	JATION SHEET		Trinomial	
Page 6 of 20	*Resource Name or # (Assigned by	y recorder)	Willow Springs Village	
Recorded by:	Lisa Demarais	Date:	April 26, 2022	
				☐ Continuation ⊠Update

in its original form. Building 11 has a recent addition to the west façade that converted the original rectangular shaped building to a T-shaped structure. A fieldstone chimney is found on the west façade of Building 6, while building 11 has a chimney on the north and south façade. The windows are a mixture of double-hung, horizontal slider, and fixed types. Doors are single personnel entry doors of wood or metal.

#### Building 13

Building 13 (Images 5-6) is a dilapidated one-story building of stone construction situated between Manly Road and Tehachapi-Willow Springs Road. The building has a rectangular plan and a hipped wood shingle roof that extends over an open porch supported by wood columns; though many shingles are missing, the wooden roof framing remains. The porch spans the south façade, which also likely housed the primary entrance. All windows and doors are missing, but fenestration openings and some wood framing remain. There are wood lintels above the window openings and the openings are not boarded over. Architectural features include fieldstone masonry and a wood single roof. The north façade features a large wood-framed opening for a door, but no door is present.

#### Residence B (Building 14)

Building 14 is a one-story building of stone construction situated west of Manly Road. The building has a rectangular plan and a corrugated metal side gable roof that extends over an open porch supported by wood columns. The porch spans the east façade, which also contains the single personnel entry door and two double hung windows. Architectural features include fieldstone masonry and fieldstone chimney on the south façade. An extension has been added to the rear (west) façade of the building. It is constructed of brick and not original.

#### Residence C (Building 16)

Building 16 (Image 21) is a one-story building of stone construction situated west of Manly Road. The building has a rectangular plan and a corrugated metal side gable roof. The south (primary) and north façades appear to be recent extensions, are wood paneled, and likely enclosed open porches present in other houses in Willow Springs. A single wood personnel entry door is present on the south façade. The windows are a mixture of double hung, horizontal slider, and fixed types.

#### Residence D

Residence D (Images 19-20) is a rustic one-story single-family residence with a roughly L-shaped plan and a cross-gable metal panel roof. Kern County aerials indicate that the metal roof is a recent alteration made some time after January 2020. The residence lies west of Manly Road can be accessed from the north or south via dirt roads lined with planted trees. A porch on the north (primary) façade of the house is covered by a roof extension supported by simple wood columns. Only the north façade was clearly visible at the time of survey. Additional features noted included closed slightly overhanging wood eaves, double-hung windows (likely either aluminum or vinyl but unclear due to distance from ROW), decorative plantings, and loose stone landscaping. The original portion of the residence is of fieldstone construction, but additions with pale brick cladding have been added over the lifetime of the building to both the west and north façades. In the absence of historic photographs and due to the tree coverage of historic aerials, a specific date(s) of these alterations is unclear; however, no additions are present on an aerial from 1972 where there is a clear view of the residence, indicating these were relatively recent alterations. Additional materials, window types, and other architectural features may be present on façades not observed from the ROW.

#### Stone Fence

The fieldstone fence at Manly Road (Image 15) extends from Buildings 4 and 5, enclosing a square-shaped field with both buildings contributing to the southern boundary of the enclosure. There are two extant wood gates along the southern boundary and a break in the fence along the western wall where another gate was likely located.

#### Cemetery (P-15-003560)

A historic cemetery on a low ridge east of Willow Springs is associated with the village. Though no headstones remain, records from previous surveys indicate several individuals were buried there, including at least one local resident, Ray Conary (Feb. 1, 1890 - Jan. 28, 1906), a 17-year-old sign painter who died of tuberculosis. The site remains unchanged since its previous recordation in 2017 by ASM Affiliates.

CONTINUATION SHEET		Trinomial		
Page 7 of 20	*Resource Name or # (Assigned by	recorder)	Willow Springs Village	
Recorded by:	Lisa Demarais	Date:	April 26, 2022	
	·			☐ Continuation ☒I Indate

#### Historical Marker (1937)

The historical marker from 1937 honors the stage station and town of Willow Springs. The monument is constructed of cement with an inset bronze plaque.

#### Historical Marker (1951)

The historical marker from 1951 recognizes the town of Willow Springs as a California Historic Landmark. The monument is constructed of fieldstone masonry with an inset bronze plaque.



Figure 2. Pool and a well at Willow Springs ca. 1903 (Lancaster Museum of Art and History)

State of Calif	ornia — The Resources Agency Prii	mary # 15-00	00129	
<b>DEPARTMEN</b>	T OF PARKS AND RECREATION		HRI#	
CONTINU	JATION SHEET		Trinomial	
Page 8 of 20	*Resource Name or # (Assigned	by recorder)	Willow Springs Village	
Recorded by:	Lisa Demarais	Date:	April 26, 2022	
				☐ Continuation ⊠Update

#### \*B10. Significance: (continued)

Willow Springs is a natural water feature in the Antelope Valley that was first depicted next to "Tehicipi Road" [sic] between Elizabeth Lake and Oak Cree an 1856 General Land Office (GLO) map of Township 9 North, Range 13 East within the San Bernardino Meridian (GLO 1856). Willow Springs was one of three natural oases in the Antelope Valley and thus made an ideal stopping point in the Mojave Desert, which resulted in the founding of a community and construction of a stagecoach station near the springs. Without the springs, early American travelers through the Mojave Desert would have faced even more grueling and deadly conditions. Even before a stagecoach station was built, the springs provided respite to a variety of travelers from different cultures using local overland trails.

The first recorded mention of Willow Springs dates to 1776 when Friar Garcés stopped at the springs. Explorer and pioneer John C. Frémont also stopped there in 1844. The discovery of gold along the Kern River in the 1850s led to an influx of visitors to the springs looking to quench themselves of thirst during their pursuit of gold and other valuable minerals. In 1862, Willow Springs was transferred from public domain to private land when it was awarded to General Edward Fitzgerald Beale. The Willow Springs stagecoach station and the springs themselves remained a sought-after stopping point throughout the 1860s, providing clean water to an increasing number of miners and cattle ranchers moving across the region during the late nineteenth century. (Bostwick 2010, Lien 2021). Due to right of way disputes with Beale, construction of the SPRR in the Antelope Valley was planned to bypass Willow Springs and instead route through Rosamond to the east. Completion of the SPRR in 1876 would have a profound effect upon the community (Lien 2021).

Willow Springs soon attracted Nelson and Adelia Ward, who are the next known owners of the land. The Wards purchased Willow Springs and endeavored to capitalize on the popularity of the natural waters by further developing the area. The Wards built an adobe boarding house next to the springs and in support of the stagecoach station, which they used to host freighters, travelers, and temporarily house horse and mule teams making their way across the region along the Los-Angeles-Havilah and Inyo Stage Lines. The accommodations were small compared to the rate of local traffic across the two routes, which were primarily in use 1864 to 1872, earning the boarding house the unofficial name "Hotel de Rush." In 1875, two years after the death of Nelson Ward, the silver freighting company, Cerro Gordo Freighting Company, chose a new route that bypassed Willow Springs, which resulted in less traffic to the Wards' boarding house and the stagecoach station. The loss of income prompted Adelia Ward to sell the land and move elsewhere with her five children. The new owners, a couple only documented by the surname Riley, operated the station for a year until completion of the SPRR through Rosamond in 1876 made stagecoach travel through Willow Springs effectively obsolete (GLO 1856; Lien 2021 July 7; Bostwick 2010). By the 1880s, the adobe boarding house was in ruins (Bostwick 2010).

After completion of the SPRR through the Antelope Valley, Willow Springs was essentially abandoned until 1900 when pioneer and stonemason Ezra Hamilton purchased the springs and the surrounding 160-acres. Hamilton struck gold a few miles east of Willow Springs four years earlier and wanted a set up his own gold mill. However, enamored with the oasis in the desert landscape, Hamilton sold his mine and used the proceeds to settle there with his family and built a resort, beginning with a hotel for up to 30 guests. The resort thrived and served as a gathering place for long-range travelers and settlers within the surrounding 15 miles. The hotel was named Hotel Rosamond and was equipped with fresh ice, flush toilets, and electricity (Lien 2021, Orr 2021a). Historical photos of the hotel show that like most original buildings built in Willow Springs, Hotel Rosamond was of stone construction. The hotel is no longer extant.

Hamilton desired to make Willow Springs a true town, and thus invested further to build necessary amenities such as a school, restaurant, general store, an auditorium, water reservoirs, and a swimming pool. He also built greenhouses to stock the restaurant and store with fresh produce, and he experimented with silkworms for silk production. Believing the springs and desert air should be accessible to anyone needing healing, Hamilton built homes and cottages that could be rented for a modest fee. From 1900-1915, other families besides the Hamiltons also settled near the resort, populating the burgeoning town. In total, during this time Hamilton invested approximately \$40,000 and built 27 stone buildings including cottages, a hotel, a stone schoolhouse, a sanitorium, an opera house, and a concrete-lined swimming pool (Bostwick 2010, Lien 2021, Morgan 1914: 999). Like the Hotel Rosamond, historical photos indicate that most, if not all, of these structures were stone with wood roofs. The swimming pool is depicted as a round structure adjacent to a stone well. The cabins and homes in surviving photos appear nearly identical with modest single-story rectangular plans, stone chimneys, and wood doors and roofs. By July 1904, Willow Springs had upwards of 50 residents including Hamilton, his new bride Eliza Galloway, and his adult children from a previous marriage (Bakersfield Morning Echo 1904: 4). Willow Springs also gained a post office in 1909, and as Ezra Hamilton was the first person in Antelope Valley to own an automobile, he built garage and gas pump in the community. Hamilton died in 1915, and the resort village was closed and sold three years later by his heirs. Willow Springs and the immediately surrounding area where other families had settled would eventually be incorporated into the town of Rosamond which was founded in 1877 by the SPRR (The Bakersfield Californian 1938: 5, Lien 2021, Orr 2021b).

State of California — The Resources Agency DEPARTMENT OF PARKS AND RECREATION			Primary # 15-000129 HRI#
CONTINUATION SHEET			Trinomial
Page 9 of 20	*Resource Name or # (Assigned by re	ecorder)	Willow Springs Village
Recorded by:	Lisa Demarais	Date:	April 26, 2022

☐ Continuation ☐ Update

The village of Willow Springs was sold multiple times between 1918 and 1947, but people continued living there under leases regardless of ownership, the decline in travelers, and closing of Hamilton's resort. The growing accessibility of automobile travel and improvements in water conveyance meant that stopping at Willow Springs, one of the few natural springs in the western Mojave Desert, was no longer a necessary part of travel through the region. Additionally, since WWII, the springs have been severely depleted due to drought. The most recent previous survey of Willow Springs indicated that the smaller springs had gone entirely dry by 1992 and the others were at risk of running dry. Due to these changes, development and population growth in Willow Springs and its immediate surrounding area was slow throughout much of the twentieth century (Tipton 1988; OHP 2021). Agriculture remained a primary industry in Kern County, but the growth of the aerospace industry has been a major change to the economic landscape of the region in the twentieth century. Agriculture in Willow Springs and its immediate surrounding area has remained a steady yet small contributor to the industry of the region (Caltrans 2008: 17-18, Dunne 2016, Tipton 1988, Greene and Knight 1992).

#### California Register of Historical Resources Eligibility

Willow Springs was first formally identified as historically significant in the 1930s. As a California Historical Landmark, the site was documented multiple times over the twentieth century, most recently in 1992. Because Willow Springs became a state landmark prior to January 1998 and the establishment of the California Register of Historical Resources (CRHR), the site must be reevaluated using current standards. Willow Springs Village (15-000129) was thus evaluated for historical significance under CRHR Criteria 1-4 as follows.

Willow Springs serves as a vivid and physical manifestation of the theme of American settlement and exploration in the Mojave Desert and is a good representative of a small agricultural community. From this site, Ezra Hamilton founded a resort that catered to residents of the region and travelers emigrating from the interior of the U.S. Pears were grown and exported in the area, and the discovery of gold in the Lida Mine spurred further development in the Antelope Valley. Thus, Willow Springs was a significant community integral to various community, commercial, and industrial developments in the region. For these significant historical associations, PaleoWest recommends Willow Springs Village eligible for the CRHR under Criterion 1.

Ezra Hamilton, the founder of Willow Springs Village, was a distinguished pioneer in the history of the Antelope Valley and he was the first American recorded to have discovered gold in the Antelope Valley. He also served in the local government in Los Angeles and patented the peat-pressing machine in 1867 before finally settling in Willow Springs. Willow Springs Village is the only known physical representation of Hamilton's significance as a pioneer, inventor, and prospector in Southern California. He is also significant as the founder of Willow Springs, one of the most distinguished settlements in the western Mojave Desert in the late nineteenth to early twentieth centuries. For its direct and strong connection to Ezra Hamilton, a historically important person who contributed to broad patterns of history in Southern California, Willow Springs Village is considered significant. The site clearly represents its time period and its original function as a small settlement engrained in agriculture. As such, PaleoWest recommends Willow Springs Village eligible for the CRHR under Criterion 2.

The extant buildings and structures of the site were constructed ca. 1900-1915 with locally sourced fieldstone. They are the last remaining buildings of this once prominent village in the western Mojave Desert and the last known buildings dating to that period and constructed of local stones The buildings are also significant for their unique masonry-based rustic style that is rarely seen in Southern California outside of forests, parks, and mountain communities. They are also the oldest buildings in the surrounding unincorporated area of Kern County. The buildings are also a testament to quality construction, likely designed by stonemason and founder Ezra Hamilton himself. Despite not being specially altered and reinforced to survive earthquakes, they have mostly withstood various earthquakes throughout the twentieth century. As such, PaleoWest recommends Willow Springs Village eligible under Criterion 3 for its significant unique and rare architecture.

The Willow Springs Village is a historically significant site in American history of California, and it was also once the site of a Kitanemuk village. The site has been documented through archaeological and architectural survey, and it is our professional opinion that the property is unlikely to yield additional vital information about the history or prehistory of these two former settlements that is not readily available through research or provided in the previous recordings of the site. As such, the property is recommended not eligible under CRHR Criterion 4.

State of California — The Resources Agency DEPARTMENT OF PARKS AND RECREATION			Primary # 15-000129 HRI#	
CONTINUATION SHEET		Trinomial		
Page 10 of 20	*Resource Name or # (Assigned by red	corder)	Willow Springs Village	
Recorded by:	Lisa Demarais	Date:	April 26, 2022	
				☐ Continuation ☑Update

#### Integrity

Although some elements such as the original stagecoach center, the schoolhouse, and the cemetery gravestones are no longer extant or in a ruinous condition, the Willow Springs site overall retains its integrity to adequately conveys its historical significance. Specifically, the site's location, workmanship, feeling, and associations are retained. A few buildings have been altered with additions, new roofing, and new windows where necessitated by deterioration; however, the majority of the extant site elements clearly represent their period of significance and historical connections to important events and persons as well as their unique architecture. Most original materials throughout the village, most notably the abundance of character-defining fieldstone, are retained. The alterations to the standing structures also appear to be easily reversible without the destruction of historical materials. Willow Springs Village remains as a distinguished example of an early twentieth century American settlement in the western Mojave Desert.

In summary, PaleoWest's professional opinion is that the site retain sufficient integrity to convey its historical significance under the CRHR Criteria and guidelines. Therefore, the assessment of integrity does not change PaleoWest's recommendation that the Willow Springs Village is eligible for listing in the CRHR under Criteria 1-4.

State of California — The Resources Agency DEPARTMENT OF PARKS AND RECREATION CONTINUATION SHEET

Primary # 15-000129 HRI# Trinomial

Page 11 of 20

\*Resource Name or # (Assigned by recorder)

Recorded by: Lisa Demarais Date:

April 26, 2022

Willow Springs Village

☐ Continuation ☐Update

#### \*B12. References: (continued)

#### Borge, Alyssa

2017 "Ezra Hamilton," Lancaster Museum of Art & History, www.lancastermoah.org/single-post/ezra-hamilton, accessed May 2022.

#### Bostwick, Charles F.

2010 "Local History - Willow Springs," Rosamond, CA 93560: The Unofficial Website. Rosamond, California: Antelope Valley Press, http://www.rosamondca.us/history/WillowSprings.htm, accessed September 2021.

#### California Department of Transportation (Caltrans)

2007 A Historical Context and Archaeological Research Design for Agricultural Properties in California. Division of Environmental Analysis, Sacramento, California.

2008 A Historical Context and Archaeological Research Design for Mining Properties in California. Division of Environmental Analysis, Sacramento, California.

California Department of Transportation (Caltrans), Anthropological Studies Center (ASC), and JRP Historical Consulting Services, LLC.

2010 A Historical Context and Archaeological Research Design for Townsite Properties in California. Division of Environmental Analysis, Sacramento, California.

#### California Office of Historic Preservation (OHP)

2021 "Willow Springs – Historical Landmark." California State Parks, Office of Historic Preservation. Available: https://ohp.parks.ca.gov/ListedResources/Detail/130. Accessed September 2021.

#### Dunne, Kerry

2016 "Boomtimes Again: Twentieth-Century Mining in the Mojave Desert," Primary Source Sets, Digital Public Library of America, Massachusetts. https://dp.la/primary-source-sets/boomtimes-again-twentieth-century-mining-in-the-mojave-desert, accessed April 2022.

#### Environmental Science Associates

2008 North Los Angeles / Kern County Recycled Water Project Final Program Environmental Impact Report SCH No. 2007101125 (ESA / 206359). Prepared for Los Angeles County Waterworks District 40 - Antelope Valley, https://pw.lacounty.gov/wwd/web/Forms/peir.aspx, accessed April 2022.

#### General Land Office (GLO)

1856 "Township 9 North, Range 13 East, San Bernardino Meridian" [map]. Survey approved February 19.

#### Greene, Andry and Albert Knight

1992 "P-15-000129 Supplement, Trinomial CA\_KER-129), California Landmark #130 Willow Springs," Western Mojave Survey Association, North Hollywood, California.

#### Lien, Lauren

"The History of Willow Springs." Lancaster Museum of Art & History. Available: https://www.lancastermoah.org/single-post/the-history-of-willow-springs. July 7. Accessed September 2021.

#### Orr, Patti

2021a "History of Willow Springs, Gold Town and Fleta Calif.," July 6, *Mojave Desert News*, http://www.desertnews.com/news/article\_687a0e14-ddc6-11eb-af2b-fb7dedd9aa72.html, accessed April 2022.

2021b "History of Rosamond, California," May 19, *Mojave Desert News,* https://www.desertnews.com/news/article\_42a5537c-b8b6-11eb-9dbc-f725f80f9128.html, accessed April 2022.

#### Pourade, Richard F.

1960 The History of San Diego: The Explorers. San Diego: Union-Tribune Publishing Company.

1961 The History of San Diego: The Time of the Bells. San Diego: Union-Tribune Publishing Company.

State of California — The Resources Agency DEPARTMENT OF PARKS AND RECREATION CONTINUATION SHEET			Primary # 15-000129 HRI# Trinomial		
Recorded by:	Lisa Demarais Date	e:	April 26, 2022		
				☐ Continuation ☐Update	
Tipton, Karla 1988	"Willow Springs: An Oasis in Antelope Valley" from https://www.karlatipton.com/portfolio/Antelope-Valle			_	

# The Bakersfield Californian

"Murphy Leases Hamilton Claim, Mine Which Once Produced Unusually Rich Ore to Be Operated Again," January 25, page 5. Bakersfield, California. Available at: https://www.newspapers.com/, accessed April 2022.

# Bakersfield Morning Echo

"Gala Day at Willow Springs: Ezra M. Hamilton and Mrs. Galloway Wed," Thursday July 7, page 4. Bakersfield, California. Available at: https://www.newspapers.com/, accessed April 2022.

# **CONTINUATION SHEET**

**Primary #** 15-000129 **HRI#** 

**Trinomial** 

Page 13 of 20 \*Resource Name or # (Assigned by recorder)

Recorded by: Lisa Demarais Dat

Willow Springs Village April 26, 2022

☐ Continuation ☐Update



Image 1. Residence A facing southeast.



Image 2. Building 6, facing southeast.



Image 3. Overview of Building 7, facing south.



Image 4. View of Building 2 facing northeast.

# **CONTINUATION SHEET**

HRI#

**Trinomial** 

Page 14 of 20 \*Resource Name or # (Assigned by recorder)

Recorded by: Lisa Demarais Date

Willow Springs Village April 26, 2022

Primary # 15-000129

☐ Continuation ☐Update



Image 5. View of Building 13 facing east.



Image 6. View of Building 13 facing northeast.



**Image 7.** View of 1951 historical marker facing east-southeast.



Image 8. View of Residence B facing west-northwest.

HRI#
Trinomial

Primary # 15-000129

Willow Springs Village

# **CONTINUATION SHEET**

Page 15 of 20 \*Resource Name or # (Assigned by recorder)

April 26, 2022

☐ Continuation ☑Update

Recorded by: Lisa Demarais



Image 9. View of Building 10 facing northeast



Image 10. View of Building 10 facing northeast




Image 11. Partial view of Buildings 10 (left) and 11 (right) facing northeast



Image 12. View of Building 12 facing northeast.

# **CONTINUATION SHEET**

\*Resource Name or # (Assigned by recorder)

Page 16 of 20 Recorded by: Lisa Demarais Primary # 15-000129 HRI#

**Trinomial** 

Willow Springs Village

April 26, 2022

☐ Continuation ☐ Update



Image 13. View of

looking



Image 14. Well east of Manly Road facing east-northeast.



Image 15. View of stone fencing at Manly Road facing eastnortheast.



Image 16. View of well facing northeast

# **CONTINUATION SHEET**

Page 17 of 20 \*Resource Name or # (Assigned by recorder)

Recorded by: Lisa Demarais Da

**Primary #** 15-000129 **HRI#** 

**Trinomial** 

Willow Springs Village

April 26, 2022

☐ Continuation ☐ Update



Image 17. View of school ruins facing east-northeast.



Image 18. View of 1937 historical marker facing southwest.



Image 19. Overview of Residence D facing west.



Image 20. Residence D facing southwest.

State of California — The Resources Agency RECREATION

# **CONTINUATION SHEET**

Primary # 15-000129DEPARTMENT OF PARKS AND HRI#

**Trinomial** 

Willow Springs Village

Page 18 of 20 \*Resource Name or # (Assigned by recorder)

Recorded by: Lisa Demarais Date: April 26, 2022

☐ Continuation ☐ Update




Image 21. Overview of Residence C facing southeast.



Image 22. Overview of Old Meeting Hall facing north.



Image 23. Building 4 facing north.



Image 24. Building 5 facing northeast.

State of California — The Resources Agency
DEPARTMENT OF PARKS AND RECREATION
I OCATION MAP


Primary HRI Trinomial

Page 19 of 20 Resource Name or #: California Landmark #130 "Willow Springs"

Map Name: Willow Springs, Ca (1977) 7.5' USGS Quad.

**Date:** 2022

**Scale:** 1:24,000




Primary # HRI# Trinomial

Page 20 of 20 \*Drawn by: B. Spelts

\*Resource Name or #: California Landmark #130 "Willow Springs"

\*Scale: 1:6,000 \*Date of map: April 2022



# PRIMARY RECORD

**Primary #** P-15-018681 HRI#

**Trinomial** 

**NRHP Status Code** 

Other Listings

	Revie	w Code		R	eviewer			Date		
Page 1 of 5	*Resc	ource Nan	ne or a	#:	LADWP	Owen	s Gorge Transmission Li	ine	UPDA	ATE
P1. Other Identifier:							Villow Springs Segment)			
*P2. Location:	☐ Not for Publicat						1 0 0			
*a. County: Kern	l			and (P	2c, P2e, and	P2b or F	P2d. Attach a Location Map as	necessar	y.)	
*b. USGS 7.5' Quad	Willow Springs; Little Buttes	Date	2022	Т	9N <b>R</b>	14W	SW ¼ of SW ¼ of	Sec	24	S.B.B.M.
c. Address None.		<u> </u>		City	Rosamo	ond	<del></del>		Zip	93560
d. UTM: (give more than o	ne for large and/or linear	resources)								
Line sartes 2	Zone 11N 382012 m	E/ 386272	20 mN	; Line	<b>ends</b> Zone	11N	379339 mE/ 3857944 m	N		
e. Other Locational Da	ta: (e.g. parcel#, directio	ns to resourc	e, eleva	ition, etc.	APNs	315-2	230-10; 315-012-07			
*P3a. Description: (D	escribe resource and	its major ele	ements	. Includ	e design, m	aterial	s, condition, alterations, size	e, settin	g, and I	ooundaries)
and Hamilton Road in consisting of utilitarian recently known as BA in the Owens River Go	n Rosamond, Califo n deadend type tov R-RIN, was built bet orge. These powerp and Cahuenga in To	rnia (segn vers. The tween 195 Ilants were oluca Lake	nent). Owen 50 and e locat e). Sor	The solutions Gorgens 1952. Ited normal modern contractions are modern contractions.	egment are 230kV This transithwest of	opears Transr missio Bisho <sub>l</sub>	smission Line that lies be similar to portions of nission Line, otherwise in line originally connected, California and were commade to the line during	the lin knowr ed thre onnecte	e prev n as O e LAD ed to F	riously recorded, G-RIN and most WP powerplants Receiving Station
accommodate the men		3 TO 10 PITTO	10 (010)	2011	•				(conti	inued on page 3)
*P3b. Resource Attrib							ture; HP37. Highway/trai			
				• –		Distric	t  Element of District	☐ Ot	her (Is	olates, etc.)
P5a. Photograph or Dr	awing (Photograph requ	uired for build	dings, st	ructures,	and objects.)	2-	<b>P5b. Description of P</b> Photo 1. Overview of t			
					1		Segment facing norther			
		1		_/-			*P6. Date Constructe	d/Age	and S	ource:
		/_				-			□Во	th
			4				1952-1955 (Dice 2014)			
							*P7. Owner and Addre	.ee.		
			#				Los Angeles Departme		Vater a	and Power
		W. I V. V.	A				111 N Hope St. Los Ar			
				50/44	_		*P8. Recorded by: (Na Caity Chandler, M.A.; I Clark	ame, aff	filiation,	and address)
The state of the s	A STATE OF THE PARTY OF		1	132		3	PaleoWest, LLC.			
			15. 36	a contra			571 S. Ivy Avenue, Mo	nrovia,	CA 91	016
	- 100 m		-							
			A STATE OF THE STA		N. C.		*P9. Date Recorded:	April 2	29, 202	22
* <b>P10. Survey Type</b> : (D	escribe) Intensi	ve pedest	rian							
*P11. Report Citation:	· -			or enter	"none ")					
2022 PaleoWest, L		ces Evalua	ation F	Report,	Addendun		Cultural Resources Technociates.	ical Re	port fo	or the Hydrostor
*Attachments: NC Record Archaeolog Artifact Record	gical Record 🔲 D	istrict Rec	ord				nuation Sheet			ture, and Object Rock Art Record

LINEAR FEATURE RECORD

Primary # P-15-018681 HRI #

Trinomial

Page 2 of 5 \*Resource Name or #: LADWP Access Road

L1. Historic and/or Common Name: LADWP Access Road

**L2a. Portion Described:** ☐ Entire Resource ☐ Segment ☐ Point Observation **Designation:** 

**b. Location of point or segment:** (Provide UTM coordinates, legal description, and any other useful locational data. Show the area that has been field inspected on a Location Map)

West end: Zone 11N 379339mE 3857944mN East end: Zone 11N 382012 mE 3862720mN

L3. Description: (Describe construction details, materials, and artifacts found at this segment/point. Provide plans/sections as appropriate.)

The recorded segment of resource consists of an actively used and maintained graded dirt road that averages 10 feet wide (see Photograph on Continuation Form). Roadway sediments consist of light gray-tan sandy gravely loam. No artifacts were found in association with the access road.

**L4. Dimensions:** (In feet for historic features and meters for prehistoric features)

a. Top Width: 10 ft b. Bottom Width: 10 ft c. Height or Depth: 0 ft

d. Length of Segment: 2.16 miles

L5. Associated Resources: N/A

**L4e. Sketch of Cross-Section** (include scale) **Facing:** See Photographs on Continuation Form

**L6. Setting:** (Describe natural features, landscape characteristics, slope, etc., as appropriate.)

Below the transmission towers is an actively used and maintained graded dirt road. The roadway sediments consist of light gray-tan sandy gravely loam.



# L7. Integrity Considerations:

The road is currently in use and shows signs of periodic grading.

L8b. Description of Photo, Map, or Drawing (View, scale, etc.)

Overview of access road, facing northeast

# L10. Form Prepared by:

Tiffany Clark PaleoWest LLC 517 South Ivy Avenue Monrovia, CA 91016

**L11. Date:** 4/29/2022

State of California — The Resources Agency DEPARTMENT OF PARKS AND RECREATION CONTINUATION SHEFT

Primary # P-15-018681 HRI#	
Trinomial	

001111107111011 011221			Timoma		
Page 3 of 5	*Resource Name or # (Assigne	ed by recorder)	LADWP Owens Gorge Transmission Line		
Recorded by:	Caity Chandler and Evan Mills	Date:	April 28, 2022		
			☐ Continuation ☐Update		

## \*P3a. Description (Cont):

PaleoWest documented a 2.16-mile section of the Los Angeles Department of Water and Power Access Road on 4/26/2022 that runs from the north (at Zone 11N 382012 mE 3862720mN) to the southwedt, ending at Zone 11N 379339mE 3857944mN. Roadway sediments consist of light gray-tan sandy gravely loam. No artifacts were found in association with the access road. The road consists of an actively used and maintained graded dirt road that averages 10 feet in width. Roadway sediments consist of light gray-tan sandy gravely loam. No artifacts were found in association with the access road.

#### \*B10. Significance:

Implementing utility systems was and still is an important part of community and regional development. Utility systems may include resources for water storage and distribution, waste disposal, electric power distribution, and hydroelectric power distribution created by municipal or private entities (Caltrans, et al. 2010: 68, 118). Efforts to create utility systems in Californian towns began during the 1850s, beginning primarily with gas plants to provide indoor and outdoor lighting in place of oil lamps. Between 1840 and 1880, many gas companies were established in the state, and the use of gas lighting remained in widespread use through World War I. Electrical lighting was first introduced to California during the early 1880s; however, many rural communities did not acquire electricity until the twentieth century. Gas companies continued to be formed during the early twentieth century, during which time the first electric companies were established. Later in the twentieth century, many of these utility companies would be combined into large conglomerates, some of which still exist today. Progressive federal and state legislation and planning efforts aimed toward improving infrastructure also contributed to the fast development of transmission lines and other utilities in California during the twentieth century (Caltrans, et al. 2010: 68-69, 138).

In 1891, Southern California received its first long-distance electricity transmission line, the San Bernardino Light & Power Company's 5 kV 28-mile transmission line between Pomona and San Bernardino. The first hydroelectric facility in the state opened in 1895 in Folsom, providing electricity to Sacramento 22 miles away. Transmission technology improved rapidly after the 1890s. One of the most significant advancements was the invention of the suspension insulator in 1907, which permitted long-distance transmission capacity to reach 100,000 kV. This improvement led to the rapid construction of many transmission lines across the state between 1907-1920 (Caltrans, et al. 2010: 68-69; ICF 2018: 3-1-3-2). During the 1910s, California's first hydroelectric power project, Big Creek Hydroelectric System, utilizing the suspension insulator was undertaken. The Big Creek Hydroelectric System, when paired with the Los Angeles Aqueduct System, would harness water from the Owens River in the Sierra Nevada to provide electric power to Los Angeles. The Big Creek Hydroelectric System was first put in service in 1912-1913 and quickly became central to Southern California's energy transmission advancement. (Tinsley Becker and Crane 2012: 1-2; Caltrans, et al. 2010: 138). A segment of the Vincent 220kV Transmission Line (constructed 1925-1927) of the Big Creek Hydroelectric System runs through the eastern portion of the Project area. less than a mile west of the Willow Springs townsite (Dice 2014). Another portion of runs through the project area. The Owens Gorge 230kV Transmission Line, otherwise known as OG-RIN and most recently known as BAR-RIN, was built between 1950 and 1952. This type of transmission line is known as a "deadend" tower. This transmission line originally connected three LADWP powerplants in the Owens River Gorge. These powerplants were located northwest of Bishop, California and were connected to Receiving Station E (located in Whitnall and Cahuenga in Toluca Lake). Some modifications were made to the line during the mid-1950s and 1960s to accommodate the increase in suburban development.

#### California Register of Historical Resources Eligibility

In its evaluation of the Owens Gorge 230kV Transmission Line segment in Rosamond, California near Rosamond Boulevard and Hamilton Road, Paleowest carefully considered whether it is eligible for the CRHR under each criteria and considered previous evaluations of other segments of the transmission line. The line is of historic age, as the towers date from the early to mid-1950s. The segment remains generally unchanged since the recording in 2014 by Power Engineers, Inc.

Under Criterion 1, a resource must constitute an association with significant events in history. Despite the proximity of Willow Springs to the resource, the Owens Gorge 230kV Transmission Line is not associated with a significant event in history. Paleowest recommends the transmission line segment not eligible for listing in the CRHP under Criterion 1.

Under Criterion 2, a resource must have association with a significant historical figure. The Owens Gorge 230kV Transmission Line is not associated with a significant historical figure. The transmission line segment is not recommended eligible for listing in the CRHR under Criterion 2.

Under Criterion 3, a resource must embody distinctive characteristics of a type, period, method of construction, or represent the work of a master that possess high artistic values. was not representative of that of a master, nor does possess high artistic value. Additionally, it is not in association with any important persons of history. Therefore, Owens Gorge 230kV Transmission Line segment is not recommended eliqible for listing in the CRHR under Criterion 3.

Under Criterion 4, a site must yield or can subsequently yield, important information regarding the prehistory or history of the site. The Owens Gorge 230kV Transmission Line does not yield or have the potential to yield features that can be useful to the site's history. The

State of California — The Resources Agency
DEPARTMENT OF PARKS AND RECREATION
CONTINUATION SHEET

\*Resource Name or # (Assigned by recorder)
Recorded by:
Caity Chandler and Evan Mills

Primary # P-15-018681
HRI#

Trinomial

LADWP Owens Gorge Transmission Line
April 28, 2022

Owens Gorge 230kV Transmission Line segment is not recommended to be considered eligible for the listing in the CRHR under Criterion 4.

☐ Continuation ☐ Update



Photo 2. Northern end of Segment north of Avenue of the Stars facing southwest.

# References:

Dice, Michael H.

2014 California Department of Parks and Recreation 528 Forms for LADWP Owens Gorge 230kV Transmission Line (P-15-018681), in *Cultural Resource Survey for the Barren Ridge-Haskell Canyon 230k V Transmission Line, Los Angeles and Kern counties, California.* Submitted to LADWP and the Angeles National Forest by POWER Engineers.

State of California — The Resources Agency
DEPARTMENT OF PARKS AND RECREATION
LOCATION MAP


Primary P-15-018681 HRI

**Trinomial** 

Page: 5 of 5 Resource Name or #: LADWP Owens Gorge Transmission Line

Map Name: Willow Springs, Ca (1977) & Little Buttes, Ca (1975) 7.5' USGS Quad.

**Scale:** 1:24,000 **Date:** 2022



PRIMARY RECORD

**Primary #** 15-017243 HRI#

**Trinomial** 

**NRHP Status Code** 

Other Listings

	Review Code	R	Reviewer			Date		
Page 1 of 5	*Resourc	e Name or #·	Vincent	220k\/ Tr	ansmission Line	UPDΔTF		
P1. Other Identifier:								
	☐ Not for Publication ☒ U		·στι σρι	<u>.gc ccg</u>				
*a. County: Kern	<del>_</del>		P2c P2e and	P2h or P2d	. Attach a Location Ma	n as necessa	iry )	
*b. USGS 7.5' Quad		2022 <b>T</b>		15W		Sec	14	S.B.B.M.
c. Address None		City	Rosam				Zip	93560
d. UTM:(give more than on	ne for large and/or linear resources)							
	.9 mE / 3857680 mN ; <b>west</b>	end: 11N 368	097 mE / 3	858416 r	nN			
	ta: (e.g. parcel#, directions to resou							
	ransmission Line was cons			oar proco	nt day La Canada	n in Loc /	\naoloc	California The
transmission line orig transmission towers s and 1922. Only about southwestern corner of the project area. The t the line was deemed	inally included approximatel pan 224 miles and is larger 0.55 miles of the Vincent to the project area. The trans ransmission line is part of the eligible as a contributor to the ere have been no discernable.	y 879 steel lithan the earlie ransmission li mission line ru e SCE Big Cre ne district. The	attice tran er Big Cree ne runs th uns from tl eek Hydroe e design o	smission  k No. 1 a  rough the  he Southe  electric Sy  f the towe	towers, of which and No. 2 lines when target area near east to the Northwastem which is a least became know	h 866 we nich were r the Whir vest throu NRHP/CRI vn as the \	re exta installe Iwind S gh the IR Hist	ant in 2012. The d between 1913 Substation in the western edge of coric District, and
		<u> </u>		/				
*P3b. Resource Attrib	outes: (List attributes and codes	s) <u>HP11. E</u>	ngineering	structure	Э			
*P4. Resources Prese	ent: 🗌 Building 🛛 Structure	e 🗌 Object 🛭	☐ Site ☐	District [	Element of Dis	trict 🗌 O	ther (Iso	olates, etc.)
P5a. Photograph or Dr	awing (Photograph required for bu	ildings, structures	, and objects.	)				
					5b. Description			
Section 1997				200	iew of transmission			
A STATE OF THE PARTY OF					etroleum Road int		with ac	cess road north
and the same				01	f the road looking	NE.		
The state of the s				**	De Data Canatri	.otod/Aaa	and C	
		-			P6. Date Constru	_		
					Historic  Pr	rehistoric	□ 800	.n
	7	V		19	927; SCE Enginee	ering Data		
A MANA	A A A A SOV	A						
	The second second		1					
				1	7. Owner and Ad			
					outhern California		<u> </u>	·
				22	244 Walnut Grove	e Avenue,	Rosam	ond, CA 91770
				Sec. 37 (1997)	8. Recorded by:	,		,
	ne de la companya de				isa Demarais, M.A		in Gash	Dalek, D.A.
					van Mills, M.A., R	IFA		_
	2000年的推荐(1965年)			_	aleoWest, LLC.	Managaria	CA 01	010
				5	71 S. Ivy Avenue,	ivionrovia	, CA 91	016
				* <del></del>	9. Date Recorded	<b>d•</b> April	26 201	22
*P10. Survey Type: (D	escribe) Intensive, pede	atrian		• •	J. Date Necordet	Aprii	26, 202	<u>′′∠</u>
			: "nono ")					
<u>-</u>	: (Cite survey report and other s		,	on tou Cult	ural Bassurasa To	andriaal Di	on ort fo	or the Unidenator
A-CAES Proje	.LC. <i>Historic Resources Eval</i> ect, Kern County, California (2 —	2021). Prepare	ed for Gold	er Associa	ates.			
	DNE ⊠ Location Map gical Record □ District Re Photograph Record □ Otl		lap ⊠ ear Featur					ture, and Object Rock Art Record

State of California — The Resources Agency
<b>DEPARTMENT OF PARKS AND RECREATION</b>
CONTINUIATION SHEET

**Primary #** 15-017243 **HRI#** 

Vincent 220kV Transmission Line UPDATE

# **Trinomial**


Page 2 of 5\*Resource Name or # (Assigned by recorder)Recorded by:E. MillsDate:

April 26, 2022.

☐ Continuation ☐ Update



Photo 2. South end transmission tower looking NNW from outside the built environment area near the Whirlwind Substation.



**Photo 3.** View of base of south line transmission tower ¾ mile north of the built environment area looking NW.

State of California — The Resources Agency
DEPARTMENT OF PARKS AND RECREATION
CONTINUATION SHEET

**Primary #** 15-017243 **HRI#** 

Vincent 220kV Transmission Line **UPDATE** 

**Trinomial** 

Page 3 of 5 \*Re Recorded by: \_\_\_\_\_ E.

\*Resource Name or # (Assigned by recorder)

E. Mills Date:

April 26, 2022.

☐ Continuation ☐ Update



**Photo 4.** View of transmission towers facing NW from outside of the built environment area.



**Photo 5.** View of transmission towers facing SW from near Rosamond Blvd near the Whirlwind Substation.

State of California — The Resources Agency DEPARTMENT OF PARKS AND RECREATION **CONTINUATION SHEET** 

**Primary #** 15-017243 HRI#

**Trinomial** 

Page 4 of 5 \*Resource Name or # (Assigned by recorder) Recorded by: E. Mills

Vincent 220kV Transmission Line UPDATE April 26, 2022.

☐ Continuation ☐ Update



Photo 6. View of transmission towers from General Petroleum Road intersection with access road north of the road looking NE.



Photo 7. View of transmission towers facing SW from General Petroleum Road intersection with access road north of the first tower looking SW.

State of California — The Resources Agency
DEPARTMENT OF PARKS AND RECREATION
I OCATION MAP


Primary 15-017243 HRI

Kilometers

**Trinomial** 

**Scale:** 1:24,000 Page 5 of 5 Resource Name or #: Vincent 220kV Transmission Line, Big Creek #3

Map Name: Fairmont Butte, Ca (1975) 7.5' USGS Quad.



	— The Resources Agency PARKS AND RECREATION		Primary # P-15-013883H Update HRI#
<b>CONTINUA</b>	TION SHEET		Trinomial CA-KER-7747H Update
age 1 of 6	*Resource Name or # (Assigne	d by recorder)	General Petroleum Access Road UPDATE
Recorded by:	T. Clark	_ Date:	April 29, 2022
			☐ Continuation ☐Updat
P1. Other Identifie	r: General Petroleum Access	Road (Willow S	Springs Segment)
*P2. Location:	■ Not for Publication  Unres		-1 55 - /
*a. County: K	ern	<b>and</b> (P2c, P2e	2e, and P2b or P2d. Attach a Location Map as necessary.)
* <b>b. USGS 7.5' Qua</b> c. Address <u>N/A</u>	d Fairmount Butte Date 197	75 <b>T</b> 9N City N/	I/A Zip N/A
,,	in one for large and/or linear resources) Zone	115	South end: 368870 South end: 3858550  North end: 370725 mE/ North end: 3860228 mN  Southern end terminates at the SCE Whirlwind Substation
e. Other Locational	Data: (e.g. parcel#, directions to resource, ele	votion oto \	southwest of Rosamond Blvd and 170 <sup>th</sup> Street intersection.
*P3a. Description	: (Describe resource and its major elemer	nts. Include desi	sign, materials, condition, alterations, size, setting, and boundaries)
Roadway sediments  P3b. Resource Att  P4. Resources Pre	consist of light gray-tan sandy grave	ly loam. No ar HP37. Highwa Dbject ☐ Site	e District Element of District Other (Isolates, etc.)
7 3340			P5b. Description of Photo: (view, date, accession #) Overview of NE Segment of General Petroleum
Marie Committee			Access Road segment, April 26, 2022
		fine.	*P6. Date Constructed/Age and Source:  Historic Prehistoric Both ca. 1915  Historic aerials (GLO 1881 and 1935)
			*P7. Owner and Address:
			*P8. Recorded by: (Name, affiliation, and address) Tiffany Clark, PaleoWest LLC 517 South Ivy Avenue
7			
AND DESCRIPTION OF THE PARTY OF			Monrovia, CA 91016
of What he			

A-CAES Project, Kern County, California (2021). Prepared for Golder Associates.

\*Attachments: ☐ NONE ☐ Location Map ☐ Sketch Map ☐ Continuation Sheet ☐ Building, Structure, and Object

PaleoWest, LLC. Historic Resources Evaluation Report, Addendum to: Cultural Resources Technical Report for the Hydrostor

Intensive pedestrian survey

\*P11. Report Citation: (Cite survey report and other sources, or enter "none.")

\*P10. Survey Type: (Describe)

2022

Record Archaeological Record District Record Linear Feature Record Milling Station Record Rock Art Record Artifact Record Photograph Record Other (List):

State of California — The Resources Agency DEPARTMENT OF PARKS AND RECREATION LINEAR FEATURE RECORD

Primary # P-15-013883H Update

HRI#

Trinomial CA-KER-7747H Update

Page 2 of 6

\*Resource Name or #: General Petroleum Access Road

L1. Historic and/or Common Name:

**L2a. Portion Described:** ☐ Entire Resource ☐ Segment ☐ Point Observation **Designation:** 

**b. Location of point or segment:** (Provide UTM coordinates, legal description, and any other useful locational data. Show the area that has been field inspected on a Location Map) Segment is located between SCE Whirlwind Substation and 160<sup>th</sup> Street.

UTM: Zone 11 N; Southwest end: 368870 mE / 3858550 mN; Northeast end: 370725 mE / 3860228 mN

**L3. Description:** (Describe construction details, materials, and artifacts found at this segment/point. Provide plans/sections as appropriate.) The recorded segment of CA-KER-007747H consists of an actively used and maintained graded dirt road that averages 10 feet in width. Although most of the road consists of an unprepared surface, the portion near the Whirlwind Substation has been graveled (see Photographs on Continuation Form). The road is located adjacent to a Southern California Edison transmission line. Roadway sediments consist of light gray-tan sandy gravely loam. No artifacts were found in association with the access road.

L4. Dimensions: (In feet for historic features and meters

for prehistoric features)

a. Top Width: 10 ft

b. Bottom Width: 10 ft

c. Height or Depth: 0 ft

d. Length of Segment: 1.56 miles

L5. Associated Resources: None

L4e. Sketch of Cross-Section (include scale) Facing:

See Photographs on Continuation Form

**L6. Setting:** (Describe natural features, landscape characteristics, slope, etc., as appropriate.)

The road runs across the lower alluvial fans that emanate from unnamed hills located to the northwest. The area slopes slightly to the southeast.

L7. Integrity Considerations: The road is currently in use and shows signs of periodic grading.



L8b. Description of Photo, Map, or Drawing (View, scale, etc.) View of northeastern end of access road, facing southwest.

L9. Remarks:

**L10. Form Prepared by:** Tiffany Clark

PaleoWest LLC 517 South Ivy Avenue Monrovia, CA 91016

**L11. Date:** 4/29/2022

State of California — The Resources Agency DEPARTMENT OF PARKS AND RECREATION			Primary # P-15-013883H Update HRI#		
CONTINUATION	ON SHEET		Trinomial CA-KER-7747H Update		
Page 3 of 6	*Resource Name or # (Assigned by	recorder)	General Petroleum Access Road		
Recorded by:	T. Clark	Date:	April 29, 2022		
				☐ Continuation ☐Update	
*B10. Significance:	Theme: Indust	ry		Area:	

Period of Significance: Property Type: Road Applicable Criteria: N/A

The portion of what is now referred to as the General Petroleum Access Road located north of Rosamond Blvd was present on a historic topographic map from 1915 (USGS 1915). The road segment lying south of Rosamond Blvd is first depicted on the 1943 Willow Springs, CA topographic map (USGS 1943). On the 1943 topographic quadrangle map, the road is shown as running between the Willow Springs Pumping Station and Antelope Valley Pumping Station. Archaeological investigations of associated refuse deposits found along other sections of the CA-KER-7747H indicate that the road was in use throughout much of the 20<sup>th</sup> century.

## California Register of Historical Resources Eligibility:

The segments of CA-KER-007747H are of historic age without any associated artifacts or features. The resource consists of an unpaved toad that shows evidence of periodic grading and regular use.

Under Criterion 1, a site must constitute an association with significant events in history. Site CA-KER-7747H does not appear to be associated with any important events in history with a lack of historic artifacts and features. CA-KER-7747H is recommended to be considered not eligible for listing in the CRHP under Criterion 1.

Under criteria 2 and 3, a site must have association with a significant historical figure, and embody distinctive characteristics of a type, period, method of construction, or represent the work of a master that possess high artistic values. The road segments of CA-KER-7747H do not indicate that the construction is representative of that of a master or is in association with any important persons of history. Therefore, CA-KER-7747H is recommended to be considered not eligible for listing in the CRHP under Criterion 2 or 3.

Under criterion 4, a site must yield or can subsequently yield, important information regarding the prehistory or history of the site. Site CA-KER-7747H does not contain any diagnostic artifacts or features that can warrant information of the site's history. The lack of subsurface potential does not likely yield any information as well. CA-KER-7747H is recommended to be considered not eligible for the listing in the CRHP under criterion 4.

#### \*B12. References:

United States Geological Survey (USGS)

1915 Elizabeth Lake, California, 30-minute topographic quadrangle map. Department of Interior, Washington, D.C. 1943 Willow Springs, California 7.5-minute topographic quadrangle map. Department of Interior, Washington, D.C.

\*B14. Evaluator: Lisa Demarais, PaleoWest LLC

\*Date of Evaluation: April 28, 2022


State of California — The Resources Agency
DEPARTMENT OF PARKS AND RECREATION
LOCATION MAP

Primary HRI **Trinomial** 

**Scale:** 1:24,000

Page 4 of 6Resource Name or #: General Petroleum Access Road

Map Name: Fairmont Butte, Ca (1975) & Tylerhorse Canyon, Ca (1966)



State of California — The Resources Agency DEPARTMENT OF PARKS AND RECREATION	Primary HRI
LOCATION MAP	Trinomial

**Page** 5 **of** 6 **Scale:** 1:24,000 Resource Name or #: General Petroleum Access Road

Map Name: Fairmont Butte, Ca (1975) & Tylerhorse Canyon, Ca (1966)



# **CONTINUATION SHEET**

Page 6 of 6

Recorded by:

\*Resource Name or # (Assigned by recorder) T. Clark

Primary # P-15-013883H Update HRI#

Trinomial CA-KER-7747H Update

General Petroleum Access Road April 29, 2022

□ Continuation □ Update



Photo 1. View of southeastern end of recorded segment of access road, facing southwest.



Photo 2. View of northeastern end of recorded segment of access road, facing northeast.



Photo 3. View of access road that intersects with Rosamond Blvd. near Whirlwind Substation, facing northeast.

# **PRIMARY RECORD**

Primary # HRI # Trinomial

**NRHP Status Code** 

Other Listings Review Code

istings
Code Reviewer Date

Page 1 of 5 P1. Other Ide	entifier:	*Res	source	Name o	r #:	_14	205 Irc	one A	venue	е			
*P2. Location		☐ Not for Publication	n 🕅 Un	restricte	d								
*a. County:	Ker		- 🗀 🕶			2c. P2	e. and P	2b or I	P2d. Att	tach a Location Map as	s necessar	/.)	
-	' Quad	Tylerhorse Canyon Irone Avenue	Date	1965		9N		14\		SE ¼ of SE of		08 Zip	<b>S.B.B.M.</b> 93560
		one for large and/or linear reso	urces) 7	one		_			04	mE/	206		
		ata: (e.g. parcel#, directions t			11		APN 3	3736 858-1		mE/	386	209	mN;
		Describe resource and its r				_					ze, settinç	g, and b	ooundaries)
parcel constriand ancillary composite shexposed rafte and a wood in bay detached composite shof the garage	ucted in building ingle crop tails, very tails, very tails, very tails, very tails and the content of the content ingle roce, and the building tails are the content ingle roce, and the content in the	(14205 Irone Avenue) is 1957. Landscaping cor is. There is also a plar oss-gable roof, frame s vooden eaves, horizont iel entry door. There wa is the west of the traile of, wooden eaves, and one façades are clad with try; however, no additional	nsists of nting of sliding a al deco as a trav r. The g exposed th corru	grasses windbreand case rative wo rel trailer parage had d rafter tagated m	and ak to men visi as a ails. etal	d shr rees at wir pane ble d sing Ther pane	ubs greated around arou	owing d the and eneat to the p gai norize 2020	g freele residence conciuments of the western contal version aerial version of the contal version of the conta	ly as well as trees lence. The reside rete block exterio gables, square w t of the residence door clad in horizo vood planks and v il from Kern Cour	s planted ence has r walls. rood ven at the ti ontal woo wood vei	I arour a rec Other ts ben me of od plan	nd the residence tangular plan, a features include eath the gables, survey. A single lks, a side gable neath the gables
P4. Resourc	es Pres	butes: (List attributes and ent: ⊠ Building □ Str	ucture	Objec	ct [	Site	e 🔲 🛭			Element of Distric	t 🗌 Oth	ner (Iso	plates, etc.)
							35. WH	-		. Description of			
		No. of the last of		. 4	2			No.		to 1. Property ove	erview fa	cing no	orth
			19 3						* <b>P6</b> . ⊠ H		nistoric		
			V 600000				CX 50.00	000	Kerr	n County Tax Ass	essor		
				4					*P7.	Owner and Add	ress:		
		Time // Margar						(4×1)	Lon	nie and Janet Seb	oellita		
1. Marie	- W			·	4				142	05 Irone Ave, Ros	samond,	CA 63	560
						54.83		NO		Recorded by: (No. 10 Demarais, M.		liation,	and address)
ENNOVAL							ALC: SA	TOP S	Gen	a Granger, M.A.,	RPA		
					1			/原	Pale	eoWest, LLC.			
		*							571	S. Ivy Avenue, M	onrovia,	CA 91	016
				Marie Land		4		-	*P9. I	Date Recorded:	April 2	23, 202	2
*P10. Survey	Type: (F	Describe) Intensive,	pedest	rian riaht	-0f-\	vav							
-	• • •	: (Cite survey report and o	•				e.")						
2022 Pale	oWest, I	LLC. Historic Resources ject, Kern County, Calif	s Evalua	ation Rep	ort,	Add	endum				nnical Re	port fo	or the Hydrostor
*Attachment	s: No	·	ap [ ict Reco	☐ Sketc	h M	ар	$\boxtimes$ (	Conti	inuatio				ture, and Object Rock Art Record

State of California — The Resources Agency Primary # DEPARTMENT OF PARKS AND RECREATION HRI# BUILDING, STRUCTURE, AND OBJECT RECORD Page 2 of 5 \*NRHP Status Code \*Resource Name or # (Assigned by recorder) 14205 Irone Avenue B1. Historic Name: N/A B2. Common Name: N/A B3. Original Use: Residential B4. Present Use: Residential \*B5. Architectural Style: Vernacular bungalow \*B6. Construction History: (Construction date, alterations, and date of alterations) The residence was constructed in 1957. There were no building permits associated with the property publicly available through the Kern County Assessor that indicate specific alterations. The garage is of wood frame construction overlaid with corrugated metal panel. Based on similarities between the two buildings, it is likely that the residence is, or was originally, wood frame with wood siding and the concrete block exterior is an alteration. No record of such an alteration could be confirmed. \*B7. Moved? ⊠ No ☐ Yes ☐ Unknown N/A Date: Original Location: N/A \*B8. Related Features: Detached garage

The village of Willow Springs was sold multiple times between 1918 and 1947. The growing accessibility of automobile travel and improvements in water conveyance meant that stopping at Willow Springs, one of the few natural springs in the western Mojave Desert, was no longer a necessary part of travel through the region. Additionally, since WWII, the springs have been severely depleted due to drought. The most recent survey of Willow Springs indicated that the smaller springs had gone entirely dry by 1992 and the others were at risk of running dry. Due to these changes, development and population growth in Willow Springs and its immediate surrounding area was slow throughout much of the twentieth century (Tipton 1988; OHP 2021). Agriculture remained a primary industry in Kern County, but the growth of the aerospace industry has been a major change to the economic landscape of the region in the twentieth century. Agriculture in Willow Springs and its immediate surrounding area has remained a steady yet small contributor to the industry of the region (Caltrans 2007: 17-18, Dunne 2016, Tipton 1988, Greene and Knight 1992).

b. Builder:

**Property Type:** 

(Discuss importance in terms of historical or architectural context as defined by theme, period, and geographic scope. Also address integrity.)

(continued on page 3)

Applicable Criteria: N/A

B11. Additional Resource Attributes: (List attributes and codes)

HP4. Ancillary building

Unknown

Area:

Residential

\*B12. References:

B9a. Architect: Unknown

\*B10. Significance: Theme


Period of Significance:

See page 3

\*B14. Evaluator: Lisa Demarais, M.A.

\*Date of Evaluation: April 23, 2022

(This space reserved for official comments.)



State of California — The Resources Agency
DEPARTMENT OF PARKS AND RECREATION
CONTINUATION SHEET

Primary # HRI#			
Trinomial			

CONTIN	DATION OFFEET	Timomai			
Page 3 of 5	*Resource Name or # (Assigned by	y recorder)	14205 Irone Avenue		
Recorded by:	Lisa Demarais	Date:	April 23, 2022		
				☐ Continuation ☐ Update	

#### \*B10. Significance: (continued)

Although Willow Springs remained predominantly unchanged during much of the twentieth century, two new developments were completed nearby during this period that affected the settlement. Muroc Army Air Field was established approximately 15 miles east of Willow Springs and Rosamond. The base, which would later become Edwards Air Force Base (EAFB), opened in 1932 and helped to bring more traffic to the Willow Springs area despite the loss of its main draws for long-range travelers and local visitors. In subsequent years EAFB attracted settlers and investment in infrastructure, providing an economic boon to the region; however, central Rosamond and Lancaster saw the greatest economic benefits and population growth (Tipton 1988; OHP 2021). Due to the population boom during the 1930s, the demand for reliable infrastructure increased. Much like other parts of the United States, the Willow Springs area needed electricity in order to grow and thrive. Due to this country-wide demand, President Roosevelt signed the Rural Electrification Act (REA) into law in 1936 (Barnes 2007). The Willow Springs area received electricity shortly after the REA was enacted.

In 1953, the Willow Springs International Raceway opened approximately 1.25 miles west of Willow Springs. At the time, there was little residential or commercial development around Willow Springs or the racetrack, save for a few farms that had installed irrigation equipment and a few small desert homesteaders. During the 1960s, a series of new grided streets were cut in the area around Willow Spring and the raceway, apparently in anticipation for increased residential growth. Ultimately, very few residences were built, the majority of which are centered in a small area in the Project area bound by Irone Avenue, Melody Lane, 145<sup>th</sup> Street W and 140<sup>th</sup> Street West and were constructed between 1960 and 1965. New residences built during this period were primarily single-story single-family vernacular residences on parcels of five acres or less. Although most of these residences are devoid of a particular recognizable architectural style, they reflect common materials and basic forms used throughout Southern California, giving many a distinct rural vernacular Californian appearance commonly identified in similar communities (UCSB 1952a, 1952b; HistoricAerials.com 1959, 1963; Kern County Recorder 1960).

#### \*B12. References:

Barnes, D.F.

2007. The Challenge of Rural Electrification: Strategies for Developing Countries. RFF Press, Washington D.C.

California Department of Transportation (Caltrans)

2007 A Historical Context and Archaeological Research Design for Agricultural Properties in California. Division of Environmental Analysis, Sacramento, California.

Dunne, Kerry

2016 "Boomtimes Again: Twentieth-Century Mining in the Mojave Desert," Primary Source Sets, Digital Public Library of America, Massachusetts. https://dp.la/primary-source-sets/boomtimes-again-twentieth-century-mining-in-the-mojave-desert, accessed April 2022.

Greene, Andry and Albert Knight

1992 "P-15-000129 Supplement, Trinomial CA\_KER-129), California Landmark #130 Willow Springs," Western Mojave Survey Association, North Hollywood, California.

HistoricAerials.com

1959 Willow Springs, CA. Aerial imagery.1963 Willow Springs, CA. Aerial imagery.

Kern County Recorder

1960 Tract No. 2355 [map]. Record of Survey Book 7, Page 191.

Office of Historic Preservation (OHP)

2021 "Willow Springs – Historical Landmark." California State Parks, Office of Historic Preservation. Available: https://ohp.parks.ca.gov/ListedResources/Detail/130. Accessed September 2021.

Tipton, Karla 1988

"Willow Springs: An Oasis in Antelope Valley" from Antelope Valley Press in The Gold Ledge. Available: <a href="https://www.karlatipton.com/portfolio/Antelope-Valley-Press-Willow-Springs-May-1988.pdf">https://www.karlatipton.com/portfolio/Antelope-Valley-Press-Willow-Springs-May-1988.pdf</a>. Accessed September 2021.

University of Santa Barbara (UCSB) Library

1952a Flight ID ABL-1952, Frame 3K-89. October 12.1952b Flight ID ABL-1952, Frame 4K-39. October 12.

State of California — The Resources Agency
DEPARTMENT OF PARKS AND RECREATION
CONTINUATION SHEET

Primary # HRI#	
Trinomial	
4.4005.1	_

Page 4 of 5	*Resource Name or # (Assigned by	recorder)	14205 Irone Avenue	
Recorded by:	Lisa Demarais	Date:	April 23, 2022	
				□ Continuation □ Update

#### California Register of Historical Resources Eligibility

The subject property at 14205 Irone Avenue (358-132-12) was evaluated for historical significance under California Register of Historical Resources (CRHR) Criteria 1-4.

Under Criterion 1, the subject property was evaluated for an association with significant historical events or broad patterns of history at the local, regional, state, or national level. The property lies within an unincorporated area of the Antelope Valley, a region of the Mojave Desert that has a rich history of American exploration, migration, and settlement unique to the California and the high desert region during the nineteenth and early twentieth centuries. According to the Kern County Property Appraiser records the single-family residence was built in 1957, which is well past settlement at the regional (Antelope Valley), state (California), or local level. PaleoWest also considered whether 14205 Irone Avenue may be significant for an association with the theme of Community Development of the Antelope Valley, 1918-1975 and the sub-theme of Rural Residential Development of the valley. Although the residence and outbuilding may date to the period of significance for the theme and sub-theme, the subject property is not a rare, unique, or exemplary example of a property associated with twentieth century community development and rural residential development of the Antelope Valley. It does provide a recognizable representation of broad patterns of residential development in the valley. Additionally, the property is within an unincorporated area of Kern County and the Antelope Valley that does not have a strong cohesive pattern of community history that would include the property's period of construction for which it might be considered historically significant. The property is near the communities of Willow Springs and Rosamond but lacks an immediate connection with the development of these communities. In summary, no direct associations between 14205 Irone Avenue and historically significant events or broad patterns of history at the local, region, state, or national level could be established. As such, the subject property is recommended not eligible under CRHR Criterion 1.

Research was conducted to determine if the subject property is significant under Criterion 2 for associations with the lives of historically important persons who have made contributions to local, state, or national history. No direct connection to historically important individuals could be identified through historical and archival research of 14205 Irone Avenue. Individuals found to be associated with the property through archival research include Lonnie Sebelita, Janet Sebelita. No information was uncovered to confirm these individuals resided at 14205 Irone Avenue during its historic period and research did not suggest the identified individuals made important contributions to history. Historically important persons such as explorers Pedro Fages, Joseph Walker, and John C. Frémont are known to have traveled through the area and to have stopped at nearby Willow Springs, but these events happened well before the construction of the extant buildings on the subject property. Therefore, there is no direct correlation between known significant historical figures and the property. As 14205 Irone Avenue does not appear to be illustrative of the accomplishments of historically important persons within a local, state, or national historical context, the property is recommended not eligible under Criterion 2.

To evaluate the subject property under Criterion 3, PaleoWest considered whether it embodies distinctive characteristics of a type, period, or method of construction and whether it represents the work of a master architect or possesses high artistic value. The residence and detached garage building at 14205 Irone Avenue are vernacular renditions of the California Ranch style which is very common to rural areas of Southern California. As an unadorned example of the California Ranch style, the property residence does not embody enough of the distinctive characteristics of this style to be considered an exemplary or unique iteration of a California Ranch. While vernacular architecture can be considered historically significant, the residence at 14205 Irone Avenue is also not a distinctive, rare, or exemplary vernacular California Ranch which is a common type and style throughout rural areas of Southern California. PaleoWest also considered whether the subject property may be significant for an association with a master builder or architect; however, no record of a builder or architect was found through property and document search engines of the Kern County Tax Assessor's Office nor through archival research. In summary, the residence of the subject property is not a distinctive or rare example of a vernacular California Ranch residence in rural Southern California and the detached garage building is also not a unique or rare example of a rural utilitarian building or farm building. Additionally, neither building clearly represents or a specific period or method of construction, are they associated with a significant master architect or builder. As such, 14205 Irone Avenue is recommended not eligible under Criterion 3.

The subject property is a common property type that is unlikely to provide vital information about history or prehistory that is not readily available through historical and archival research. As such, the property is recommended not eligible under CRHR Criterion 4.

The subject property is not within a designated or previously identified historic district. As a very sparsely developed and unincorporated area, the immediate vicinity of the property also lacks architectural cohesion and a defined shared historical narrative to be considered a historic district. Thus, 14205 Irone Avenue is not recommended eligible as a contributor to a CRHR-eligible or listed historic district.

State of California — The Resources Agency
DEPARTMENT OF PARKS AND RECREATION
LOCATION MAP


Primary HRI Trinomial

Page 5 of 5 **Resource Name or #:** 358-132-12

Map Name: Tylerhorse Canyon, Ca (1966) 7.5' USGS Quad.

**Date:** 2022

**Scale:** 1:24,000



State of California — The Resources Agency Primary # DEPARTMENT OF PARKS AND RECREATION HRI# PRIMARY RECORD **Trinomial NRHP Status Code Other Listings Review Code** Reviewer Date \*Resource Name or #: Page 1 of 10 4040 Manly Road P1. Other Identifier: 4050 Manly Road, 4105 Manly Road ☐ Not for Publication ☐ Unrestricted \*P2. Location: \*a. County: Kern and (P2c, P2e, and P2b or P2d. Attach a Location Map as necessary.) \*b. USGS 7.5' Quad Willow Springs Date Т 9N R 13W Sec 07: 18 S.B.B.M. c. Address 4040 Manly Road City Rosamond Zip 93560 381663 mE/ 381699 mE/ d. UTM: (give more than one for large and/or linear resources) Zone 3860405 mN 11N 3860292 mN and e. Other Locational Data: (e.g. parcel#, directions to resource, elevation, etc.) NW 1/4 of NE 1/4 of S18; SW 1/4 of SE 1/4 of S07 APN 252-341-05; 315-012-01 \*P3a. Description: (Describe resource and its major elements. Include design, materials, condition, alterations, size, setting, and boundaries) The subject property at 4040 Manly Road consists of three single-family residences on two parcels shared with buildings of the Willow Springs Village (P-15-000129). These buildings were constructed after the decline of the village and are not directly associated with the village historically and were thus recorded separately. The three residences lie east of Manly Road and west of Tehachapi-Willow Springs Road. Residences 1 and 2 are within APN 252-341-05 and Residence 3 is within APN 315-012-01. Visibility was limited due to the topography and vegetation. All three buildings are vernacular in nature and lacking a distinct architectural style. (continued on page 3) \*P3b. Resource Attributes: (List attributes and codes) HP2. Multi-family property \*P4. Resources Present: ☐ Building ☐ Structure ☐ Object ☐ Site ☐ District ☐ Element of District ☐ Other (Isolates, etc.) P5a. Photograph or Drawing (Photograph required for buildings, structures, and objects.) P5b. Description of Photo: (view, date, accession #) Photo 1. Overview facing southeast from Manly Road toward Residences 1 and 2 on APN 252-341-05. March 28, 2022 \*P6. Date Constructed/Age and Source: ca. 1948-1975 Historic aerials, NETROnline \*P7. Owner and Address: Kathy and Robert Nelson 4040 Manly Road \*P8. Recorded by: (Name, affiliation, and address) Lisa C. Demarais, M.A. Evan Mills, M.A., RPA PaleoWest, LLC. 571 S. Ivy Avenue, Monrovia, CA 91016 \*P9. Date Recorded: May 3, 2022 \*P10. Survey Type: (Describe) Intensive pedestrian

\*P11. Report Citation: (Cite survey report and other sources, or enter "none.")

2022 PaleoWest, LLC. Historic Resources Evaluation Report, Addendum to: Cultural Resources Technical Report for the Hydrostor A-CAES Project, Kern County, California (2021). Prepared for Golder Associates.

\*Attachments: ☐ NONE ☐ Location Map ☐ Sketch Map ☐ Continuation Sheet ☐ Building, Structure, and Object Record ☐ Archaeological Record ☐ District Record ☐ Linear Feature Record ☐ Milling Station Record ☐ Rock Art Record ☐ Artifact Record ☐ Photograph Record ☐ Other (List):

DEF	PARTMENT OF PA	The Resources Agency RKS AND RECREATION RUCTURE, AND OBJECT	HRI#			
	e 2 of 10	*NRHP Status C	67			
		*Resource Name or # (Assigned	by recorder	·) 404	10 Manly Road	
B1.	Historic Name:	N/A	.,	,	,	
B2.	Common Name:	N/A				
B3.	Original Use:	Residential, agricultural				
B4.	Present Use:	Residential, agricultural				
*B5	. Architectural Styl	le: Vernacular American Rustic, vernacu	ılar Californ	ia ranch, verna	cular Minimal Trad	itional
*B6	. Construction Hist	tory: (Construction date, alterations, and date of alter	rations) Ba	ased on histori	c aerial photograph	ns, all three residences
		ear to have been constructed ca. 1970-19				
_		ial, and Residence 1 was constructed ca. 1				
	Residence 1 someti	ime after 1974 and prior to 1977. A large a	ddition was	also added to	Residence 3 ca. 20	)10. Building permits
_	and aerials do not ir	ndicate any other significant alterations.				
*B7.	. Moved? ⊠ No □	Yes Unknown Date: N/A	Or	iginal Locatio	n: N/A	
*B8	. Related Features	: Ancillary buildings, swimming pool				
В9а	. Architect: Unkn	own b	. Builder:	Unknown		
*B1	0. Significance: Th	eme Community Development		Area: Rur	al Residential Deve	elopment
Peri	iod of Significance	e: N/A Propert	ty Type:	Residential	Applicable C	Criteria: N/A
	(Discuss importance in	n terms of historical or architectural context as d	defined by the	me, period, and	geographic scope. A	Ilso address integrity.)
gas,		arid public lands to gain ownership. As a rovors (Environmental Science Associates 2 nties.				,
						(continued on page 3)
B11	. Additional Resour	ce Attributes: (List attributes and codes)	HP33. F	Farm/ranch		
	<b>2. References:</b> page 6					
*B1	4. Evaluator:	Lisa Demarais		(Ske	etch Map with north	arrow required.)
	te of Evaluation:	May 3, 2022			See sketch map of	on Page 10
^ Da	te of Evaluation:	Muy 3, 2022			oo attoon map o	mr ago io
	(This	space reserved for official comments.)				

	ornia — The Resources Agency T OF PARKS AND RECREATION		Primary # HRI#	
CONTINU	JATION SHEET		Trinomial	
Page 3 of 10	*Resource Name or # (Assigned by	recorder)	4040 Manly Road	
Recorded by:	Lisa Demarais	Date:	May 3, 2022	
	-			□ Continuation □ Update

\*P3a. Description: (continued)

# Residence 1

Residence 1 (Photo 2) is a one and one-half story vernacular residence that first appears on aerial photos with a rectangular plan. A large front addition to the north façade was added ca. 1974-1977, giving the residence an L-shaped plan. The original portion of the building was constructed in the Minimal Traditional style with a Craftsman-inspired horizontal dormer protruding from a side gable roof. The roof has brown composite shingles. Windows on this portion of the building are aluminum sliders, and a full open porch extends its north façade. The porch is covered by an extension of the side gable roof which is supported by simple wood columns. The addition portion of the residence features a front gable and faux divided-lite double-hung and fixed vinyl windows. There is a single simple wood bracket beneath the apex of the gable. Double fiberglass French-style doors are on the west façade of the addition. The eaves of both the original and addition are closed wood. The residence can be accessed via a dirt drive from Manly Road to the west.

## Residence 2

Residence 2 (Photo 3) lies west of Residence 1 and can be accessed via a dirt drive from Manly Road to the west. The residence is a one-story rectangular plan rustic cottage featuring a wood shingle side-gable roof, stucco exterior cladding, decorative wood board and vents beneath the gabled roof ends, and double-hung windows. There are a mixture of wood and vinyl framed windows. Based on aerial photographs, the residence appears to have a full porch with a shed roof along the south (rear) façade. There is a swimming pool immediately southeast of the residence and a Quonset hut of recent construction to its west.

## Residence 3

Residence 3 lies north of Residences 1 and 2. While it is on a separate parcel, it has the same owners and address as Residences 1 and 2. Residence 3 is comprised of two sections, an original vernacular California ranch and a Rustic style addition. It is unclear from the exterior whether the two sections share interior space or act as separate units. The original portion of the building features a crossgable wood shingle roof, stucco cladding, a porch with a shed roof extension and simple wood columns, and double-hung replacement vinyl windows and original fixed divided-lite wood windows with stucco sills and inset wood lintels. The addition portion of the building features a mixture of board-and-batten and brick cladding, a corrugated metal side-gable roof with a shed shaped extension supported by simple wood columns, and a brick chimney. The wooden eaves are wide and closed. There is an ancillary building of recent construction northeast of the residence.

# \*B10. Significance: (continued)

With the discovery of gold in the Sierra Nevada Mountains in 1848, an increase in American settlement in the California region began. The population of California continued to increase throughout the mid- and late nineteenth century, especially after completion of the Transcontinental Railroad in 1869, even as the mining industry slowed in the later part of the century. Most early mining of gold, silver, and other minerals in California took place in the north, near Sacramento, but some mines were established as far south and east as the Mojave Desert and San Gabriel Mountains as miners became discouraged with unsuccessful attempts and an abundance of competition in Northern California. In Kern County, gold and silver were discovered in the early 1850s. In addition to gold and silver mining, the western Mojave Desert became a major source of boron, the element for which Boron, California in eastern Kern County was named. The discovery of these resources led to population growth and the formation of new wagon routes and stagecoach stops throughout the Antelope Valley. Various stagecoach companies, postal routes, and telegraph routes were created in areas that were formerly largely isolated using existing common travel routes to support mining operations and the communities spurred by the industry. Despite these commercial developments, the Mojave Desert remained sparsely populated until the twentieth century due to its hot and arid conditions as well as the absence of widespread water conveyance systems. Towns primarily grew between key areas of mining operations and along popular wagon routes, acting as stopovers for travelers and goods. The largest mining operations were in the eastern Mojave Desert while the most trafficked stagecoach routes ran through the western portion of the desert near the Project area (Sherer 1994; Rincon Consultants, Inc. 2021: 37; Struglia, et al. 2003: 174-176).

Desert farming by American settlers was a crucial development in California during the nineteenth and twentieth centuries. Farming is still widely practiced in California, which boasts some of the largest irrigation districts in the U.S. and provides the country with over a third of its vegetables and two-thirds of its fruits and nuts. The majority of the state's farming historically occurred and continues to be focused within the San Joaquin Valley, the southernmost part of the Central Valley region, which includes parts of Fresno, Tulare, Imperial, and Kern counties. Land in the Central Valley and South Desert regions is fertile, but its lack of natural water was a major roadblock to both American company and family farms. The construction of water conveyance systems in the mid- to late nineteenth

	ornia — The Resources Agency FOF PARKS AND RECREATION		Primary # HRI#	
CONTINU	JATION SHEET		Trinomial	
Page 4 of 10	*Resource Name or # (Assigned by reco	order)	4040 Manly Road	
Recorded by:	Lisa Demarais Da	ate:	May 3, 2022	
		-		□ Continuation □ Update

century allowed desert farming to become a reality. Between the 1910s and 1960s, large-scale water conveyance systems like the Central Valley Project, California State Water Project, and Los Angeles Aqueduct System were constructed throughout much of the state to consistently bring water to areas like the Central Valley and the Los Angeles Basin that lacked natural supplies of water. The Los Angeles Aqueduct system, completed in 1913, runs from Owners River in Central California to Los Angeles and crosses the westernmost portion of the Mojave Desert. The most common high desert crops include alfalfa, hay, onions, carrots, potatoes, peaches, pears, and nectarines. Agriculture continued to be practiced in the Antelope Valley throughout the twentieth century, though to a lesser extent after World War II (Caltrans 2007: 25, 30, 63).

There were upwards of 80 towns founded in the Antelope Valley by 1920, supported by traffic to nearby mines and routes to the Central Valley and Northern California. Although railroad development often led to the founding of new towns and population growth in others, in many instances new railroad lines were responsible for the demise of towns when the railroad entirely bypassed a community that was once a travel and trading center, like Willow Springs. Short lines and spurs could be constructed to connect these isolated communities to a main railroad line, but not all towns could afford this development (Caltrans, et al. 2010: 13, 38-39, 46; Greene and Knight 1992).

The growing accessibility of automobile travel and improvements in water conveyance meant that stopping at Willow Springs, one of the few natural springs in the western Mojave Desert, was no longer a necessary part of travel through the region. Additionally, since World War II, the springs have been severely depleted due to drought; the most recent previous survey of Willow Springs indicated that the smaller springs had gone entirely dry by 1992 and the others were at risk of depletion. Due to these changes, development and population growth in Willow Springs and its immediate surrounding area was slow throughout much of the twentieth century (Tipton 1988; OHP 2021). Agriculture remained a primary industry in Kern County, but the growth of the aerospace industry has been a major change to the economic landscape of the region in the twentieth century. Agriculture in Willow Springs and its immediate surrounding area has remained a steady, yet small contributor to the industry of the region. Pears were once one of the major crops grown in Willow Springs (Caltrans 2007: 17-18, Dunne 2016, Tipton 1988, Greene and Knight 1992). President Roosevelt signed the Rural Electrification Act (REA) into law in 1936 and the Willow Springs area received electricity shortly after the legislation was enacted (Barnes 2007).

In 1953, the Willow Springs International Raceway opened approximately 1.25 miles west of Willow Springs. At the time, there was little residential or commercial development around Willow Springs except for a few small desert homesteaders and other farms with newly installed irrigation equipment. During the 1960s, a series of new grided streets were cut in the area around Willow Spring and the raceway, apparently in anticipation for increased residential growth. Ultimately, few residences were built and the majority of constructed between 1960 and 1965 were centered in a small area in the Project area bound by Irone Avenue, Melody Lane, 145th Street West, and 140th Street West. New residences built during this period were primarily single-story, single-family vernacular buildings on parcels of five acres or less. Although most of these residences are devoid of a particular recognizable architectural style, they reflect common materials and basic forms used throughout Southern California, giving many a distinct rural vernacular Californian appearance commonly identified in similar communities (UCSB 1952a, 1952b; HistoricAerials.com 1959, 1963; Kern County Recorder 1960).

# California Register of Historical Resources Eligibility

The subject property (4040 Manly Road) was evaluated for historical significance under California Register of Historical Resources (CRHR) Criteria 1-4.

Under Criterion 1, the subject property was evaluated for an association with significant historical events or broad patterns of history at the local, regional, state, or national level. The property lies within an unincorporated area of the Antelope Valley, a region of the Mojave Desert that has a rich history of American exploration, migration, and settlement unique to the California and the High Desert region during the nineteenth and early twentieth centuries. According to aerial photographs, the residences on the property were built well past the period of significance for American settlement at the regional (Antelope Valley), state (California), or local level. PaleoWest also considered whether the subject property may be significant for an association with the theme of Community Development of the Antelope Valley, 1918-1975 and the sub-theme of Rural Residential Development of the valley. Although the residence and outbuilding may date to the period of significance for development theme and sub-theme, the subject property is not a rare, unique, or exemplary example of a property associated with twentieth century community development and rural residential development of the Antelope Valley. It does provide a recognizable representation of broad patterns of residential development in the valley. Additionally, the property is within an unincorporated area of Kern County and the Antelope Valley that does not have a strong cohesive pattern of community history that would include the property's period of construction for which it might be considered

State of California — The Resources Agency DEPARTMENT OF PARKS AND RECREATION CONTINUATION SHEET			Primary # HRI#	
			Trinomial	
Page 5 of 10	*Resource Name or # (Assigned by re	ecorder)	4040 Manly Road	
Recorded by:	Lisa Demarais	Date:	May 3, 2022	
				☐ Continuation ☐ Indate

historically significant. The property is near the communities of Willow Springs and Rosamond but lacks an immediate connection with the development of these communities. In summary, no direct associations between the subject property and historically significant events or broad patterns of history at the local, region, state, or national level could be established. As such, the subject property is recommended not eligible under CRHR Criterion 1.

Research was conducted to determine if the subject property is significant under Criterion 2 for associations with the lives of historically important persons who have made contributions to local, state, or national history. No direct connection to historically important individuals could be identified through historical and archival research of the subject property. Individuals found to be associated with the property through archival research included various members of the Nelson family since the construction of the three extant residences. No information was uncovered to confirm these individuals have made important contributions to history. Historically important persons such as explorers Pedro Fages, Joseph Walker, and John C. Frémont are known to have traveled through the area and to have stopped at nearby Willow Springs, but these events happened well before the construction of the extant buildings on the subject property. Therefore, there is no direct correlation between known significant historical figures and the property. As 4040 Manly Road does not appear to be illustrative of the accomplishments of historically important persons within a local, state, or national historical context, the property is recommended not eligible under Criterion 2.

To evaluate the subject property under Criterion 3, PaleoWest considered whether it embodies distinctive characteristics of a type, period, or method of construction and whether it represents the work of a master architect or possesses high artistic value. The residences at 4040 Manly Road are vernacular reditions of a variety of architectural styles that are common to Southern California. As unadorned examples of the American Rustic, Minimal Traditional, and Californian styles, the residences do not embody enough of the distinctive characteristics of a particular style to be considered an exemplary or unique iteration of that style. While vernacular architecture can be considered historically significant, the residences are not distinctive, rare, or exemplary examples of vernacular architecture in the Antelope Valley or other rural areas of Southern California. PaleoWest also considered whether the subject property may be significant for associations with master builders or architects; however, no record of builders or architects for the residences were uncovered through property and document search engines of the Kern County Tax Assessor's Office nor through archival research. In summary, the buildings of the subject property are not distinctive or rare examples of vernacular residential architecture in rural Southern California. Additionally, none of the buildings building clearly represent a specific period or method of construction, nor are they associated with a significant master architect or builder. As such, 4040 Manly Road is recommended not eligible under Criterion 3.

The subject property is a common property type, unlikely to provide additional information about residential development in the area that is not already available through research. The property is adjacent to the Willow Springs Village site which is a California Historical Landmark and was once the site of a Kitanemuk village. The area has been documented through archaeological survey, and it is our professional opinion that the property is unlikely to yield additional vital information about the history or prehistory of these two former settlements that is not readily available through research or provided in the previous recordings of the site. As such, the property is recommended not eligible under CRHR Criterion 4.

The subject property is not within a designated or previously identified historic district. It is on land believed to have been formerly part of an early twentieth century American settlement (a CRHR listed site) and a Kitanemuk village; however, the extant resources known to be on the property and documented in this form are not associated directly with either settlement based on their periods of significance and construction. Thus, the subject property is not recommended eligible as a contributor to a CRHR-eligible or listed historic district.

# State of California — The Resources Agency DEPARTMENT OF PARKS AND RECREATION CONTINUE ATION SHEET

Primary # HRI# Trinomial

4040 Manly Road

ك	Or	111	NU	ΑΙ	IOI	N St	1EE I

Page 6 of 10 \*Resource Name or # (Assigned by recorder)

Recorded by: Lisa Demarais Date: May 3, 2022

☐ Continuation ☐ Update

\*B12. References: (continued)

Barnes, D.F.

2007. The Challenge of Rural Electrification: Strategies for Developing Countries. RFF Press, Washington D.C.

California Department of Transportation (Caltrans)

2007 A Historical Context and Archaeological Research Design for Agricultural Properties in California. Division of Environmental Analysis, Sacramento, California.

A Historical Context and Archaeological Research Design for Townsite Properties in California. Division of Environmental Analysis, Sacramento, California.

Dunne, Kerry

2016 "Boomtimes Again: Twentieth-Century Mining in the Mojave Desert," Primary Source Sets, Digital Public Library of America, Massachusetts. https://dp.la/primary-source-sets/boomtimes-again-twentieth-century-mining-in-the-mojave-desert, accessed April 2022.

**Environmental Science Associates** 

2008 North Los Angeles/Kern County Recycled Water Project Final Program Environmental Impact Report. SCH No. 2007101125. Prepared for Los Angeles County Waterworks District 40 - Antelope Valley, https://pw.lacounty.gov/wwd/web/Forms/peir.aspx, accessed April 2022.

Greene, Andry and Albert Knight

1992 "P-15-000129 Supplement, Trinomial CA\_KER-129), California Landmark #130 Willow Springs," Western Mojave Survey Association, North Hollywood, California.

HistoricAerials.com

1959 Willow Springs, CA. Aerial imagery.1963 Willow Springs, CA. Aerial imagery.

Kern County Recorder

1960 Tract No. 2355 [map]. Record of Survey Book 7, Page 191.

Office of Historic Preservation (OHP)

2021 "Willow Springs – Historical Landmark." California State Parks, Office of Historic Preservation. Available: https://ohp.parks.ca.gov/ListedResources/Detail/130. Accessed September 2021.

Rincon Consultants, Inc.

2021 Rosamond A-CAES Facility Project Cultural Resources Assessment Report. Prepared for Hydrostor, Inc. Los Angeles, California.

Sherer, Lorraine M.

1994 Bitterness Road: The Mojave 1604 to 1860. Menlo Park, California: Ballena Press.

Struglia, Rachel; Patricia L. Winter; Andrea Meyer

2003 Southern California Socioeconomic Assessment: Sociodemographic Conditions, Projections, and Quality of Life Indices, General Technical Report PSW-GTR-187, Pacific Southwest Research Station, United States Forest Service, United States Department of Agriculture: Berkeley, California.

Tipton, Karla

1988 "Willow Springs: An Oasis in Antelope Valley" from Antelope Valley Press in The Gold Ledge. Available: https://www.karlatipton.com/portfolio/Antelope-Valley-Press-Willow-Springs-May-1988.pdf. Accessed September 2021.

University of Santa Barbara (UCSB) Library

1952a Flight ID ABL-1952, Frame 3K-89. October 12.1952b Flight ID ABL-1952, Frame 4K-39. October 12.

## **CONTINUATION SHEET**

**Trinomial** 

HRI#

Page 7 of 10

\*Resource Name or # (Assigned by recorder)

Recorded by: Lisa Demarais

4040 Manly Road May 3, 2022

□ Continuation □ Update



Photo 2. Residence 1, view facing south



Photo 3. Residence 2, view facing south.

## **CONTINUATION SHEET**

Lisa Demarais

Page 8 of 10

Recorded by:

Primary # HRI# **Trinomial** 4040 Manly Road

\*Resource Name or # (Assigned by recorder)

May 3, 2022

□ Continuation □ Update



Photo 4. Residence 3, view facing southeast.



Photo 5. Easterly view from Manly Road toward Residence 3.

State of California — The Resources Agency
DEPARTMENT OF PARKS AND RECREATION
LOCATION MAP

Primary HRI


Trinomial

Page 9 of 10 Resource Name or #: 4040 Manly Rd

Map Name: Willow Springs, Ca (1977) 7.5' USGS Quad.

Date: 2022

**Scale:** 1:24,000




Primary # HRI# **Trinomial** 

Page 10 of 10

\*Resource Name or #: 4040 Manly Rd

\*Scale: 1:6,000

\*Date of map: September 2021



# PRIMARY RECORD

Primary # HRI # Trinomial

**NRHP Status Code** 

Other Listings Review Code

Paviawar Pa

	Review Code	Reviewer		Date	
Page 1 of 6 P1. Other Identifier:	*Resource Na	me or #: 14101 I	one Avenue		
	Not for Publication ⊠ Unres	tricted			
*a. County: Kern			P2b or P2d. Attach a Location Map as	necessary)	
	/lerhorse Canyon Date 19		•	<b>Sec</b> 08	S.B.B.M.
c. Address 14101 Iron		City Rosar		Zip	93560
	or large and/or linear resources) Zone		373774 mE/	3860360	mN;
	(e.g. parcel#, directions to resource, ele		358-132-10		
	ribe resource and its major elemer	· · · · ·		ze setting and b	oundaries)
• `	comprised of two buildings, a				
foundations, on a flat rec which is enclosed in chair driveway from Irone Aver fence of the southern half bungalow features a cross primary (southern) entry f show wood ornamental s been converted into occup opening had been altered	tangular five-acre parcel. Both n-link fencing. The northern had nue. The residence and garacy of the parcel. The residence is s-gable gray composite shingle ood with a half-moon fixed ins hutters flanking each window, piable space and is immediated to a single standard wood entingle, exposed rafter tails, and	buildings and a walf of the parcel is on the parcel is on the parcel is on the parcel is on the parcel is a roughly L-shaped roof, smooth white et window. There is but no extant shully northwest of the ry door and white walf.	ater tank are situated on the pen and undeveloped. The pelosed by wood and chain-lind single-story California bung stucco cladding, aluminum has also an entry door on the natters were visible during survesidence. Photos from 2012 yood siding. The garage feature	southern half property is according with alow of 1,069 orizontal slider orth façade. Prey. The detact	of the property, essible via a dirt in the chain-link square feet. The windows, and a hotos from 2012 thed garage has garage's two-bay
roof of composite gray sni	ngie, exposed raiter tails, and	smooth white stucc	o cladding.		
P4. Resources Present:	S: (List attributes and codes)  Building Structure   ng (Photograph required for buildings,	•	P5b. Description of Photo 1. Property ove the south façade (Aug	Photo: (view, da erview facing no gust 24, 2021)  ed/Age and Solistoric Both  NETROnline  ress:  Jame, affiliation, A.	ource: th
P10. Survey Type: (Desc	ribe) Intensive, pedestrian	right of way	*P9. Date Recorded:	April 11, 202	22
• •• •	te survey report and other sources				
2022 PaleoWest, LLC. A-CAES Project,	Historic Resources Evaluation Kern County, California (2021	n <i>Report, Addendui</i> ). Prepared for Gol	der Associates.	-	-
	□ Location Map    □ Sketa Sketa Sketa    □ Sketa Sketa    □ District    □ Distri	Record Lines		, Structure, an g Station Reco	

State of California — The Resources Agency
DEPARTMENT OF PARKS AND RECREATION
HRI#
BUILDING, STRUCTURE, AND OBJECT RECORD

\*NRHP Status Code 6Z

\*Resource Name or # (Assigned by recorder)

B1. Historic Name: N/A

B2. Common Name: N/A B3. Original Use: Residential B4. Present Use: Residential Vernacular Califonria bungalow \*B5. Architectural Style: \*B6. Construction History: (Construction date, alterations, and date of alterations) The Kern County Assessor's Office lists a build date of 1958, but a historic aerial from 1963 does not show the extant buildings on the property. The extant buildings are first visible on The next available historic aerial dated 1974. Subsequent aerials do not indicate any alterations and the Assessor property details do not list any building permits that would indicate alterations have been made since its ca. 1970 date of construction. \*B7. Moved? ⊠ No ☐ Yes ☐ Unknown Date: N/A Original Location: N/A \*B8. Related Features: Detached garage B9a. Architect: Unknown Unknown b. Builder: \*B10. Significance: Theme Area: Period of Significance: Residential Applicable Criteria: N/A **Property Type:** (Discuss importance in terms of historical or architectural context as defined by theme, period, and geographic scope. Also address integrity.)

The village of Willow Springs was sold multiple times between 1918 and 1947. The growing accessibility of automobile travel and improvements in water conveyance meant that stopping at Willow Springs, one of the few natural springs in the western Mojave Desert, was no longer a necessary part of travel through the region. Additionally, since WWII, the springs have been severely depleted due to drought. The most recent survey of Willow Springs indicated that the smaller springs had gone entirely dry by 1992 and the others were at risk of running dry. Due to these changes, development and population growth in Willow Springs and its immediate surrounding area was slow throughout much of the twentieth century (Tipton 1988; OHP 2021). Agriculture remained a primary industry in Kern County, but the growth of the aerospace industry has been a major change to the economic landscape of the region in the twentieth century. Agriculture in Willow Springs and its immediate surrounding area has remained a steady yet small contributor to the industry of the region (Caltrans 2007: 17-18, Dunne 2016, Tipton 1988, Greene and Knight 1992).

B11. Additional Resource Attributes: (List attributes and codes)

HP4. Ancillary building


\*B12. References:

See page 3.

\*B14. Evaluator: Lisa Demarais, M.A., PaleoWest, LLC

\*Date of Evaluation: April 23, 2022

(This space reserved for official comments.)



State of California — The Resources Agency
DEPARTMENT OF PARKS AND RECREATION
CONTINUATION SHEET

Primary # HRI#		
Trinomial		

Irone Avenue

Page 3 of 6	*Resource Name or # (Assigned by recor	der) 14101 Irone A
Recorded by:	Lisa Demarais, PaleoWest Dat	e: April 23, 2022

□ Continuation □ Update

\*B10. Significance: (continued)

Although Willow Springs remained predominantly unchanged during much of the twentieth century, two new developments were completed nearby during this period that affected the settlement. Muroc Army Air Field was established approximately 15 miles east of Willow Springs and Rosamond. The base, which would later become Edwards Air Force Base (EAFB), opened in 1932 and helped to bring more traffic to the Willow Springs area despite the loss of its main draws for long-range travelers and local visitors. In subsequent years EAFB attracted settlers and investment in infrastructure, providing an economic boon to the region; however, central Rosamond and Lancaster saw the greatest economic benefits and population growth (Tipton 1988; OHP 2021). Due to the population boom during the 1930s, the demand for reliable infrastructure increased. Much like other parts of the United States, the Willow Springs area needed electricity in order to grow and thrive. Due to this country-wide demand, President Roosevelt signed the Rural Electrification Act (REA) into law in 1936 (Barnes 2007). The Willow Springs area received electricity shortly after the REA was enacted.

In 1953, the Willow Springs International Raceway opened approximately 1.25 miles west of Willow Springs. At the time, there was little residential or commercial development around Willow Springs or the racetrack, save for a few farms that had installed irrigation equipment and a few small desert homesteaders. During the 1960s, a series of new grided streets were cut in the area around Willow Spring and the raceway, apparently in anticipation for increased residential growth. Ultimately, very few residences were built, the majority of which are centered in a small area in the Project area bound by Irone Avenue, Melody Lane, 145th Street W and 140th Street West and were constructed between 1960 and 1965. New residences built during this period were primarily single-story single-family vernacular residences on parcels of five acres or less. Although most of these residences are devoid of a particular recognizable architectural style, they reflect common materials and basic forms used throughout Southern California, giving many a distinct rural vernacular Californian appearance commonly identified in similar communities (UCSB 1952a, 1952b; HistoricAerials.com 1959, 1963; Kern County Recorder 1960).

#### \*B12. References:

Barnes, D.F.

2007. The Challenge of Rural Electrification: Strategies for Developing Countries. RFF Press, Washington D.C.

California Department of Transportation (Caltrans)

A Historical Context and Archaeological Research Design for Agricultural Properties in California. Division of Environmental Analysis, Sacramento, California.

Dunne, Kerry

"Boomtimes Again: Twentieth-Century Mining in the Mojave Desert," Primary Source Sets, Digital Public Library of 2016 America, Massachusetts. https://dp.la/primary-source-sets/boomtimes-again-twentieth-century-mining-in-the-mojavedesert, accessed April 2022.

Greene, Andry and Albert Knight

1992 "P-15-000129 Supplement, Trinomial CA\_KER-129), California Landmark #130 Willow Springs," Western Mojave Survey Association, North Hollywood, California.

HistoricAerials.com

1959 Willow Springs, CA. Aerial imagery. 1963 Willow Springs, CA. Aerial imagery.

Kern County Recorder

Tract No. 2355 [map]. Record of Survey Book 7, Page 191. 1960

Office of Historic Preservation (OHP)

2021 "Willow Springs – Historical Landmark." California State Parks, Office of Historic Preservation. Available: https://ohp.parks.ca.gov/ListedResources/Detail/130. Accessed September 2021.

Tipton, Karla

1988 "Willow Springs: An Oasis in Antelope Valley" from Antelope Valley Press in The Gold Ledge. Available: https://www.karlatipton.com/portfolio/Antelope-Valley-Press-Willow-Springs-May-1988.pdf. Accessed September 2021.

University of Santa Barbara (UCSB) Library

1952a Flight ID ABL-1952, Frame 3K-89. October 12.

1952b Flight ID ABL-1952, Frame 4K-39. October 12.

State of California — The Resources Agency DEPARTMENT OF PARKS AND RECREATION	Primary # HRI#
CONTINUATION SHEET	Trinomial

CONTINUATION SHEET			1 IIXI#	
			Trinomial	
Page 4 of 6	*Resource Name or # (Assigned	l by recorder)	14101 Irone Avenue	
Recorded by:	Lisa Demarais, PaleoWest	Date:	April 23, 2022	
				□ Continuation □ Update

### California Register of Historical Resources Eligibility

The subject property at 14101 Irone Avenue (358-132-10) was evaluated for historical significance under California Register of Historical Resources (CRHR) Criteria 1-4.

Under Criterion 1, the subject property was evaluated for an association with significant historical events or broad patterns of history at the local, regional, state, or national level. The property lies within an unincorporated area of the Antelope Valley, a region of the Mojave Desert that has a rich history of American exploration, migration, and settlement unique to the California and the high desert region during the nineteenth and early twentieth centuries; however, based on a review of historical aerial photographs, the buildings on the property were constructed c. 1970, well after the period of significance for this theme of American Settlement in the Antelope Valley and the broader exploration and settlement of California. As such, the subject property cannot be directly associated with significance of exploration and settlement at the regional (Antelope Valley), state (California), or local level. PaleoWest also considered whether 14101 Irone Avenue may be significant for an association with the theme of Community Development of the Antelope Valley, 1918-1975 and the sub-theme of Rural Residential Development of the valley. Although the residence and garage date to the period of significance for the theme and sub-theme, the subject property is not a rare, unique, or exemplary example of a property associated with twentieth century community development and rural residential development of the Antelope Valley. It does provide a recognizable representation of broad patterns of residential development in the valley. Additionally, the property is within an unincorporated area of Kern County and the Antelope Valley that does not have a strong cohesive pattern of community history that would include the property's period of construction for which it might be considered historically significant. The property is near the communities of Willow Springs and Rosamond but lacks an immediate connection with the development of these communities. In summary, no direct associations between 14101 Irone Avenue and historically significant events or broad patterns of history at the local, region, state, or national level could be established. As such, the subject property is recommended not eligible under CRHR Criterion 1.

Research was conducted to determine if the subject property is significant under Criterion 2 for associations with the lives of historically important persons who have made contributions to local, state, or national history. No direct connection to historically important individuals could be identified through historical and archival research of 14101 Irone Avenue. Individuals found to be associated with the property through archival research include Jeffrey R. Williams, Caleb C. Porter, Steven Joel Cooper, Seaneen Tara McArdle, Ricard A. Valenzuela, and Melissa D. Porter. No information was uncovered to confirm these individuals resided at 14101 Irone Avenue during its historic period and research did not suggest the identified individuals made important contributions to history. Historically important persons such as explorers Pedro Fages, Joseph Walker, and John C. Frémont are known to have traveled through the area and to have stopped at nearby Willow Springs, but these events happened well before the construction of the extant buildings on the subject property. Therefore, there is no direct correlation between known significant historical figures and the property. As 14101 Irone Avenue does not appear to be illustrative of the accomplishments of historically important persons within a local, state, or national historical context, the property is recommended not eligible under Criterion 2.

To evaluate the subject property under Criterion 3, PaleoWest considered whether it embodies distinctive characteristics of a type, period, or method of construction and whether it represents the work of a master architect or possesses high artistic value. The residence and converted garage building at 14101 Irone Avenue are vernacular renditions of the California Bungalow stve which is very common to rural areas of Southern California. As an unadorned example of the California Bungalow style, the property does not embody enough of the distinctive characteristics of this style to be considered an exemplary or unique iteration of a California Bungalow. While vernacular architecture can be considered historically significant, 14101 Irone Avenue is not a distinctive, rare, or exemplary vernacular California Bungalow which is a common type and style throughout rural areas of Southern California. PaleoWest also considered whether the subject property may be significant for an association with a master builder or architect; however, no record of a builder or architect was found through property and document search engines of the Kern County Tax Assessor's Office nor through archival research. In summary, the subject property is not a distinctive or rare example of a vernacular California Bungalow residence in rural Southern California or a specific period or method of construction, nor is it associated with a significant master architect or builder. As such, 14101 Irone Avenue is recommended not eligible under Criterion 3.

The subject property is a common property type that is unlikely to provide vital information about history or prehistory that is not readily available through historical and archival research. As such, the property is recommended not eligible under CRHR Criterion 4.

The subject property is not within a designated or previously identified historic district. As a very sparsely developed and unincorporated area, the immediate vicinity of the property also lacks architectural cohesion and a defined shared historical narrative to be considered a historic district. Thus, 14101 Irone Avenue is not recommended eligible as a contributor to a CRHR-eligible or listed historic district.

## **CONTINUATION SHEET**

Page 5 of 6\*Resource Name or # (Assigned by recorder)Recorded by:Lisa Demarais, PaleoWestDate:

Primary # HRI# Trinomial

14101 Irone Avenue

April 23, 2022

□ Continuation □ Update



Photo 2. North façade of the residence and north and west façades of the garage, view to the southeast.



Photo 3. South (primary) and west façades of the residence, view to the northeast (2020 Redfin)

State of California — The Resources Agency
DEPARTMENT OF PARKS AND RECREATION
LOCATION MAP

Primary HRI

Trinomial

**Scale:** 1:24,000 Page # of # **Resource Name or #:** 358-132-10

Map Name: Tylerhorse Canyon, Ca (1966) 7.5' USGS Quad.



# PRIMARY RECORD

Primary # HRI # Trinomial

**NRHP Status Code** 

Other Listings

Naviawa ....

	Review Code		Revie	wer		Date	
Page 1 of 5 P1. Other Identifier:	*Resource	Name or	#: <u>14</u>	070 Lodesta	r Avenue		
*P2. Location:	t for Publication 🗵 Un	restricted	i				
*a. County: Kern		and	P2c, P2	e, and P2b or P	2d. Attach a Location Map as i	necessary.)	
*b. USGS 7.5' Quad Tyle	rhorse Canyon Date	1965	Т	R	SE 1/4 of SE of	Sec	S.B.B.M.
c. Address 14070 Lodest	ar Avenue		City _	Rosamond		Zip	93560
d. UTM: (give more than one for la	rge and/or linear resources) Z	one _	11N	373829	mE/	3860664	mN;
e. Other Locational Data: (e.g	g. parcel#, directions to resource	e, elevation, e	etc.)	APN 358-13	32-07		
*P3a. Description: (Describe	e resource and its major ele	ements. Inc	lude des	sign, materials	, condition, alterations, size	e, setting, and b	oundaries)
The subject property (14070 The vernacular Ranch style property and a small grouping gable asphalt shingle roof with a vertension entry porch with a vertens	e was constructed in 19 ng of trees and shrubs ith rectangular attic vent '-beam wood support con windows, and stucco escreen exterior door. The a one-by-one vinyl horizying space. The south (rhere are two outbuildin	946. Lands planted ar- s beneath plumns, on xterior wal e east faç zontal slidi rear) façad	scaping ound the each genover- lls. The ade feat ade feature	consists of ne residence pable, a rece one metal fr main entryw atures a rece dow beneath ires a wing e	grasses and shrubs of the residence feature assed carport with wood ame double hung window is on the north and of the gable on the east extension, a secondary	growing freely an L-shape support colund ows, decorative consists of a should be which entrance with	throughout the d plan, a cross- nns, a shed roof the shutters, one- single entry-door support columns in may indicate a concrete steps,
P3b. Resource Attributes:	,			Family Prope		☐ Other (Isc	plates, etc.)
P5a. Photograph or Drawing		<del>-</del>					,
		-			P5b. Description of P	hoto: (view, dat	e, accession #)
					Photo 1. Property over	view facing sc	uthwest
201				1	*P6. Date Constructe  Historic Prehin 1946  Kern County Tax Asse	storic  Bot	
			×11.11		Trom County Tax 71000	5001	
			YVV	We see	*P7. Owner and Addre	ess:	
		200			John Barrios		04.00500
	A WATER TO A VALUE OF THE PARTY		A STATE	ALTA PARTY	14070 Lodestar Avenu	e, Rosamono	CA 93560
			WW)		* <b>P8. Recorded by:</b> (Na Lisa C. Demarais, M.A		and address)
		-			Evan Mills, M.A., RPA		
in at the second	NI MEDIA	100			PaleoWest, LLC.		
		生物		K. Calab	571 S. Ivy Avenue, Mo	nrovia, CA 91	016
TMO Summer Turner (Describe		a de la companya de l			P9. Date Recorded:	April 23, 202	2
P10. Survey Type: (Describ	·			- "\			
A-CAES Project, Ke	istoric Resources Evalua ern County, California (2	ation Repo 021). Prep	ort, Adde pared fo	endum to: Co r Golder Ass	ociates.	•	-
*Attachments: ☐ NONE Record ☐ Archaeological R ☐ Artifact Record ☒ Photo	Record District Reco				nuation Sheet		ure, and Object Rock Art Record

State of California — The Resources Agency Primary #

Page 2 of 5		*NRHP \$	Status Code	6Z					
	*Resource Na	ame or # (A	ssigned by reco	der)	1	4070 L	odestar A	venue	
B1. Historic Name:	N/A	(		,	_				
B2. Common Name:	N/A								
B3. Original Use:	Residential								
B4. Present Use:	Residential								
*B5. Architectural Style:	Ranch								
*B6. Construction Histor	ry: (Construction date, alt	terations, and d	late of alterations)	Coi	nstructed in	n 1946.	No buildin	g permits a	re available in
public tax appraiser re	cords but the window	ws have be	en updated to vi	nyl.					
*B7. Moved? ⊠ No ☐	Yes 🗆 Unknown	Date:	N/A	Orio	ginal Loca	tion:	N/A		
*B8. Related Features:	Detached garage	<b>D</b> uto	14// (	<b>U</b>	jiliai 200a		14/71		
B9a. Architect: Unknow			b. Builde	r: l	Jnknown				
*B10. Significance: Then				_	Area:				
Period of Significance:	-		Property Type:		Residentia	al	Applicab	le Criteria:	N/A
(Discuss importance in te	erms of historical or arc	chitectural co	ntext as defined by	them	ne, period, a	nd geog	raphic scop	e. Also addr	ess integrity.)
The village of Willow Sprimprovements in water cowas no longer a necessar drought. The most recent at risk of running dry. Due was slow throughout mucbut the growth of the aero Agriculture in Willow Spriregion (Caltrans 2007: 17-	nveyance meant that ry part of travel throus urvey of Willow Speto these changes, of the twentieth cospace industry has ngs and its immedia	at stopping a ugh the regi rings indicated development entury (Tipto been a ma ate surround	at Willow Springs ion. Additionally, ted that the sma at and population on 1988; OHP 2 ajor change to the ding area has re	s, one sinc ler sport grow 21). The economic economic sport grow 21). The economic economic economic sport grow and the economic	e of the few e WWII, th prings had vth in Willo Agriculture onomic lan ned a stea	natura e sprin gone e w Sprir e remai	Il springs in gs have be ntirely dry ngs and its ned a prin e of the reg	n the wester een severel by 1992 and immediate nary industrigion in the	rn Mojave Desert y depleted due to d the others were surrounding area y in Kern County twentieth century
								(con	tinued on page 3
B11. Additional Resource	Attributes: (List attrib	outes and cod	les) HP4	. And	cillary build	_		acth arrow	

\*B12. References:

See page 3.

Lisa Demarais, M.A., PaleoWest, LLC. \*B14. Evaluator:

April 23, 2022 \*Date of Evaluation:

(This space reserved for official comments.)

(Sketch Map with north arrow required.)



State of California — The Resources Agency DEPARTMENT OF PARKS AND RECREATION			Primary # HRI#				
CONTINU	JATION SHEET		Trinomial				
Page 3 of 5	*Resource Name or # (Assigned by	recorder)	14070 Lodestar Avenue				
Recorded by:	Lisa Demarais	Date:	April 23, 2022				
				☐ Continuation ☐ Indate			

#### \*B10. Significance: (continued)

Although Willow Springs remained predominantly unchanged during much of the twentieth century, two new developments were completed nearby during this period that affected the settlement. Muroc Army Air Field was established approximately 15 miles east of Willow Springs and Rosamond. The base, which would later become Edwards Air Force Base (EAFB), opened in 1932 and helped to bring more traffic to the Willow Springs area despite the loss of its main draws for long-range travelers and local visitors. In subsequent years EAFB attracted settlers and investment in infrastructure, providing an economic boon to the region; however, central Rosamond and Lancaster saw the greatest economic benefits and population growth (Tipton 1988; OHP 2021). Due to the population boom during the 1930s, the demand for reliable infrastructure increased. Much like other parts of the United States, the Willow Springs area needed electricity in order to grow and thrive. Due to this country-wide demand, President Roosevelt signed the Rural Electrification Act (REA) into law in 1936 (Barnes 2007). The Willow Springs area received electricity shortly after the REA was enacted.

In 1953, the Willow Springs International Raceway opened approximately 1.25 miles west of Willow Springs. At the time, there was little residential or commercial development around Willow Springs or the racetrack, save for a few farms that had installed irrigation equipment and a few small desert homesteaders. During the 1960s, a series of new grided streets were cut in the area around Willow Spring and the raceway, apparently in anticipation for increased residential growth. Ultimately, very few residences were built, the majority of which are centered in a small area in the Project area bound by Irone Avenue, Melody Lane, 145<sup>th</sup> Street W and 140<sup>th</sup> Street West and were constructed between 1960 and 1965. New residences built during this period were primarily single-story single-family vernacular residences on parcels of five acres or less. Although most of these residences are devoid of a particular recognizable architectural style, they reflect common materials and basic forms used throughout Southern California, giving many a distinct rural vernacular Californian appearance commonly identified in similar communities (UCSB 1952a, 1952b; HistoricAerials.com 1959, 1963; Kern County Recorder 1960).

#### \*B12. References:

Barnes, D.F.

2007. The Challenge of Rural Electrification: Strategies for Developing Countries. RFF Press, Washington D.C.

California Department of Transportation (Caltrans)

A Historical Context and Archaeological Research Design for Agricultural Properties in California. Division of Environmental Analysis, Sacramento, California.

Dunne, Kerry

2016 "Boomtimes Again: Twentieth-Century Mining in the Mojave Desert," Primary Source Sets, Digital Public Library of America, Massachusetts. https://dp.la/primary-source-sets/boomtimes-again-twentieth-century-mining-in-the-mojave-desert, accessed April 2022.

Greene, Andry and Albert Knight

1992 "P-15-000129 Supplement, Trinomial CA\_KER-129), California Landmark #130 Willow Springs," Western Mojave Survey Association, North Hollywood, California.

HistoricAerials.com

1959 Willow Springs, CA. Aerial imagery.1963 Willow Springs, CA. Aerial imagery.

Kern County Recorder

1960 Tract No. 2355 [map]. Record of Survey Book 7, Page 191.

Office of Historic Preservation (OHP)

2021 "Willow Springs – Historical Landmark." California State Parks, Office of Historic Preservation. Available: https://ohp.parks.ca.gov/ListedResources/Detail/130. Accessed September 2021.

Tipton, Karla

1988 "Willow Springs: An Oasis in Antelope Valley" from Antelope Valley Press in The Gold Ledge. Available: <a href="https://www.karlatipton.com/portfolio/Antelope-Valley-Press-Willow-Springs-May-1988.pdf">https://www.karlatipton.com/portfolio/Antelope-Valley-Press-Willow-Springs-May-1988.pdf</a>. Accessed September 2021.

University of Santa Barbara (UCSB) Library

1952a Flight ID ABL-1952, Frame 3K-89. October 12.1952b Flight ID ABL-1952, Frame 4K-39. October 12.

State of California — The Resources Agency DEPARTMENT OF PARKS AND RECREATION			Primary # HRI#		
CONTINU	JATION SHEET		Trinomial		
Page 4 of 5	*Resource Name or # (Assigned by	recorder)	14070 Lodestar Avenue		
Recorded by:	Lisa Demarais	Date:	April 23, 2022		

□ Continuation □ Update

#### California Register of Historical Resources Eligibility

The subject property at 14070 Lodestar Avenue (358-132-07) was evaluated for historical significance under California Register of Historical Resources (CRHR) Criteria 1-4.

Under Criterion 1, the subject property was evaluated for an association with significant historical events or broad patterns of history at the local, regional, state, or national level. The property lies within an unincorporated area of the Antelope Valley, a region of the Mojave Desert that has a rich history of American exploration, migration, and settlement unique to the California and the high desert region during the nineteenth and early twentieth centuries. According to the Kern County Property Appraiser records the single-family residence was built in 1946, which is well past settlement at the regional (Antelope Valley), state (California), or local level. PaleoWest also considered whether 14070 Lodestar Avenue may be significant for an association with the theme of Community Development of the Antelope Valley, 1918-1975 and the sub-theme of Rural Residential Development of the valley. Although the residence and outbuilding may date to the period of significance for the theme and sub-theme, the subject property is not a rare, unique, or exemplary example of a property associated with twentieth century community development and rural residential development of the Antelope Valley. It does provide a recognizable representation of broad patterns of residential development in the valley. Additionally, the property is within an unincorporated area of Kern County and the Antelope Valley that does not have a strong cohesive pattern of community history that would include the property's period of construction for which it might be considered historically significant. The property is near the communities of Willow Springs and Rosamond but lacks an immediate connection with the development of these communities. In summary, no direct associations between 14070 Lodestar Avenue and historically significant events or broad patterns of history at the local, region, state, or national level could be established. As such, the subject property is recommended not eligible under CRHR Criterion 1.

Research was conducted to determine if the subject property is significant under Criterion 2 for associations with the lives of historically important persons who have made contributions to local, state, or national history. No direct connection to historically important individuals could be identified through historical and archival research of 14070 Lodestar Avenue. Individuals found to be associated with the property through archival research include Veterans Affairs, Jacob Daniels, 360 Mortgage Group, Zeive Brodnax & Steel LLP, Steven Jermaine Lowrey, and Feliciano Garcia. No information was uncovered to confirm these individuals or organizations resided at 14070 Lodestar Avenue during its historic period and research did not suggest the identified individuals made important contributions to history. Historically important persons such as explorers Pedro Fages, Joseph Walker, and John C. Frémont are known to have traveled through the area and to have stopped at nearby Willow Springs, but these events happened well before the construction of the extant buildings on the subject property. Therefore, there is no direct correlation between known significant historical figures and the property. As 14070 Lodestar Avenue does not appear to be illustrative of the accomplishments of historically important persons within a local, state, or national historical context, the property is recommended not eligible under Criterion 2.

To evaluate the subject property under Criterion 3, PaleoWest considered whether it embodies distinctive characteristics of a type, period, or method of construction and whether it represents the work of a master architect or possesses high artistic value. The residence at 14070 Lodestar Avenue are vernacular renditions of the California Ranch style which is very common to rural areas of Southern California. As an unadorned example of the California Ranch style, the property residence does not embody enough of the distinctive characteristics of this style to be considered an exemplary or unique iteration of a California Ranch. While vernacular architecture can be considered historically significant, the residence at 14070 Lodestar Avenue is also not a distinctive, rare, or exemplary vernacular California Ranch which is a common type and style throughout rural areas of Southern California. PaleoWest also considered whether the subject property may be significant for an association with a master builder or architect; however, no record of a builder or architect was found through property and document search engines of the Kern County Tax Assessor's Office nor through archival research. In summary, the residence of the subject property is not a distinctive or rare example of a vernacular California Ranch residence in rural Southern California. Additionally, this building does not represent a specific period or method of construction, are they associated with a significant master architect or builder. As such, 14070 Lodestar Avenue is recommended not eligible under Criterion 3.

The subject property is a common property type that is unlikely to provide vital information about history or prehistory that is not readily available through historical and archival research. As such, the property is recommended not eligible under CRHR Criterion 4.

The subject property is not within a designated or previously identified historic district. As a very sparsely developed and unincorporated area, the immediate vicinity of the property also lacks architectural cohesion and a defined shared historical narrative to be considered a historic district. Thus, 14070 Lodestar Avenue is not recommended eligible as a contributor to a CRHR-eligible or listed historic district.


State of California — The Resources Agency
DEPARTMENT OF PARKS AND RECREATION
LOCATION MAP

Primary HRI

**Trinomial** 

**Scale:** 1:24,000 Page 5 of 5 **Resource Name or #:** 358-132-07

Map Name: Tylerhorse Canyon, Ca (1966) 7.5' USGS Quad.



### PRIMARY RECORD

Primary # HRI # Trinomial NRHP Status Code

Other Listings
Review Code


**Review Code** Reviewer Date Page 1 of 6 \*Resource Name or #: 10145 Hamilton Road P1. Other Identifier: \*P2. Location: ☐ Not for Publication ☐ Unrestricted \*a. County: and (P2c, P2e, and P2b or P2d. Attach a Location Map as necessary.) \*b. USGS 7.5' Quad 1965 т SE 1/4 of SE 1/4 of Sec S.B.B.M. Willow Springs Date 01 10145 Hamilton Road City 93560 c. Address Rosamond d. UTM: (give more than one for large and/or linear resources) Zone 11N 380137 mE/ 3862071 mN; APN 358-052-08 e. Other Locational Data: (e.g. parcel#, directions to resource, elevation, etc.) \*P3a. Description: (Describe resource and its major elements. Include design, materials, condition, alterations, size, setting, and boundaries) The subject property (10145 Hamilton Road) is comprised of a vernacular California Bungalow one-story single-family residence with a single ancillary outbuilding. The property is currently vacant and is accessible from Hamilton Road to the south and from 90th Avenue to the east. Landscaping consists of natural landscaping with native trees, shrubs, and grasses growing freely across the property. The residence has a rectangular plan, a metal front-gable roof with rectangular attic vents and exposed rafter tails in the roof eaves, a frontgable roof enclosed entry extension, two-over-two double-hung wooden windows with missing glass, and a large entry bay with an opening which is missing a door (or doors). The exterior walls of the main house are primarily clad in flat stucco, except for the enclosed porch entry which has horizontal wood plank siding. The south façade is the only elevation visible from the right-of-way and appears to serve as the primary entrance. The ancillary barn, located directly to the west of the single-family residence features a rectangular-shaped plan, a tin front-gable roof, wood siding, and a window wall on the east and west façades. HP2. Single Family Property; HP4. Ancillary Building \*P3b. Resource Attributes: (List attributes and codes) \*P4. Resources Present: ⊠ Building ☐ Structure ☐ Object ☐ Site ☐ District ☐ Element of District ☐ Other (Isolates, etc.) P5a. Photograph or Drawing (Photograph required for buildings, structures, and objects.) P5b. Description of Photo: (view, date, accession #) Photo 1. Property overview facing north August 27, 2021 \*P6. Date Constructed/Age and Source: ☐ Historic ☐ Prehistoric ☐ Both ca. 1960 Historic aerials, NETROnline \*P7. Owner and Address: 10145 Hamilton Road \*P8. Recorded by: (Name, affiliation, and address) Emma Keethler, M.A. Gena Granger, M.A., RPA PaleoWest, LLC. 571 S. Ivy Avenue, Monrovia, CA 91016 \*P9. Date Recorded: April 19, 2022 \*P10. Survey Type: (Describe) Intensive, pedestrian right-of-way \*P11. Report Citation: (Cite survey report and other sources, or enter "none.") 2022 PaleoWest, LLC. Historic Resources Evaluation Report, Addendum to: Cultural Resources Technical Report for the Hydrostor A-CAES Project, Kern County, California (2021). Prepared for Golder Associates. \*Attachments: 
NONE □ Location Map ☐ Sketch Map □ Continuation Sheet □ Building, Structure, and Object Record Archaeological Record District Record Linear Feature Record Milling Station Record Rock Art Record ☐ Artifact Record ☐ Photograph Record ☐ Other (List):

State of California — The Resources Agency
DEPARTMENT OF PARKS AND RECREATION
HRI#
BUILDING, STRUCTURE, AND OBJECT RECORD

Page 2 of 6
\*NRHP Status Code 62

BUILDING, ST	RUCTURE, AND UB	JECT RECO	עא	
Page 2 of 6	*NRHP	Status Code	6Z	
_	*Resource Name or # (/	Assigned by recorder	r) 10145	Hamilton Road
B1. Historic Name:	N/A	,	, <u> </u>	
B2. Common Name:	N/A			
B3. Original Use:	Residential			
B4. Present Use:	Residential			
*B5. Architectural Styl				
	Ory: (Construction date, alterations, and	′ <u>—</u>		constructed ca. 1960. It is first visible
	t no earlier aerials of the property			permits for the property publicly
available. Many of the	ne windows and doors are absen	t but the fenestration	openings remain.	
*B7. Moved? ⊠ No ☐ *B8. Related Features:		N/A Or	riginal Location:	N/A
B9a. Architect: Unknown	own	b. Builder:	Unknown	
*B10. Significance: Th	eme		Area:	
Period of Significance	·	Property Type:	Residential	Applicable Criteria: N/A
(Discuss importance in	terms of historical or architectural co	ontext as defined by the	eme, period, and geo	graphic scope. Also address integrity.)
was slow throughout me but the growth of the ac Agriculture in Willow Sp	uch of the twentieth century (Tipe erospace industry has been a m	ton 1988; OHP 2021 ajor change to the ending area has rema	). Agriculture rema conomic landscap ained a steady yet	ings and its immediate surrounding area ained a primary industry in Kern County, e of the region in the twentieth century. small contributor to the industry of the
				(continued on page 3)
B11. Additional Resour	ce Attributes: (List attributes and co	des) N/A		
*B12. References:			(Sketch	Map with north arrow required.)
See page 3.	Emma Keethler		553-651-65 553-651-40 553-651-60	838-032-01 838-032-01
*B14. Evaluator:			A STATE OF THE STA	
*Date of Evaluation:	April 19, 2022			815-060-01
			553-051-05 553-051-07	3033400 B 8 3134030-02

(This space reserved for official comments.)



State of California — The Resources Agency
DEPARTMENT OF PARKS AND RECREATION
CONTINUATION SHEET

HRI#
Trinomial

CONTIN	JATION SHEET	Trinomial				
Page 3 of 6	*Resource Name or # (Assigned by	recorder)	10145 Hamilton Road			
Recorded by:	Emma Keethler	Date:	April 19, 2022			
				□ Continuation □ Update		

#### \*B10. Significance: (continued)

Although Willow Springs remained predominantly unchanged during much of the twentieth century, two new developments were completed nearby during this period that affected the settlement. Muroc Army Air Field was established approximately 15 miles east of Willow Springs and Rosamond. The base, which would later become Edwards Air Force Base (EAFB), opened in 1932 and helped to bring more traffic to the Willow Springs area despite the loss of its main draws for long-range travelers and local visitors. In subsequent years EAFB attracted settlers and investment in infrastructure, providing an economic boon to the region; however, central Rosamond and Lancaster saw the greatest economic benefits and population growth (Tipton 1988; OHP 2021). Due to the population boom during the 1930s, the demand for reliable infrastructure increased. Much like other parts of the United States, the Willow Springs area needed electricity in order to grow and thrive. Due to this country-wide demand, President Roosevelt signed the Rural Electrification Act (REA) into law in 1936 (Barnes 2007). The Willow Springs area received electricity shortly after the REA was enacted.

In 1953, the Willow Springs International Raceway opened approximately 1.25 miles west of Willow Springs. At the time, there was little residential or commercial development around Willow Springs or the racetrack, save for a few farms that had installed irrigation equipment and a few small desert homesteaders. During the 1960s, a series of new grided streets were cut in the area around Willow Spring and the raceway, apparently in anticipation for increased residential growth. Ultimately, very few residences were built, the majority of which are centered in a small area in the Project area bound by Irone Avenue, Melody Lane, 145<sup>th</sup> Street W and 140<sup>th</sup> Street West and were constructed between 1960 and 1965. New residences built during this period were primarily single-story single-family vernacular residences on parcels of five acres or less. Although most of these residences are devoid of a particular recognizable architectural style, they reflect common materials and basic forms used throughout Southern California, giving many a distinct rural vernacular Californian appearance commonly identified in similar communities (UCSB 1952a, 1952b; HistoricAerials.com 1959, 1963; Kern County Recorder 1960).

#### \*B12. References:

Barnes, D.F.

2007. The Challenge of Rural Electrification: Strategies for Developing Countries. RFF Press, Washington D.C.

California Department of Transportation (Caltrans)

2007 A Historical Context and Archaeological Research Design for Agricultural Properties in California. Division of Environmental Analysis, Sacramento, California.

Dunne, Kerry

2016 "Boomtimes Again: Twentieth-Century Mining in the Mojave Desert," Primary Source Sets, Digital Public Library of America, Massachusetts. https://dp.la/primary-source-sets/boomtimes-again-twentieth-century-mining-in-the-mojave-desert, accessed April 2022.

Greene, Andry and Albert Knight

1992 "P-15-000129 Supplement, Trinomial CA\_KER-129), California Landmark #130 Willow Springs," Western Mojave Survey Association, North Hollywood, California.

HistoricAerials.com

1959 Willow Springs, CA. Aerial imagery.1963 Willow Springs, CA. Aerial imagery.

Kern County Recorder

1960 Tract No. 2355 [map]. Record of Survey Book 7, Page 191.

Office of Historic Preservation (OHP)

2021 "Willow Springs – Historical Landmark." California State Parks, Office of Historic Preservation. Available: https://ohp.parks.ca.gov/ListedResources/Detail/130. Accessed September 2021.

Tipton, Karla 1988

"Willow Springs: An Oasis in Antelope Valley" from Antelope Valley Press in The Gold Ledge. Available: <a href="https://www.karlatipton.com/portfolio/Antelope-Valley-Press-Willow-Springs-May-1988.pdf">https://www.karlatipton.com/portfolio/Antelope-Valley-Press-Willow-Springs-May-1988.pdf</a>. Accessed September 2021.

University of Santa Barbara (UCSB) Library

1952a Flight ID ABL-1952, Frame 3K-89. October 12.1952b Flight ID ABL-1952, Frame 4K-39. October 12.

	ornia — The Resources Agency T OF PARKS AND RECREATION	Primary # HRI#	•					
CONTINU	JATION SHEET	Trinomial						
Page 4 of 6	*Resource Name or # (Assigned by record	ler) 10145 Hamilton Road						
Recorded by:	Emma Keethler Date	e: April 19, 2022						
			□ Continuation □ Update					

#### California Register of Historical Resources Evaluation

The subject property at 10145 Hamilton Road (358-052-08) was evaluated for historical significance under California Register of Historical Resources (CRHR) Criteria 1-4.

Under Criterion 1, the subject property was evaluated for an association with significant historical events or broad patterns of history at the local, regional, state, or national level. The property lies within an unincorporated area of the Antelope Valley, a region of the Mojave Desert that has a rich history of American exploration, migration, and settlement unique to California and the high desert region during the nineteenth and early twentieth centuries; however, there is no build date provided by the Kern County Assessor's Office records, and the earliest available aerial photography is 1963, which is well past settlement at the regional (Antelope Valley), state (California), or local level. As such, the subject property cannot be directly associated with significance of exploration. PaleoWest also considered whether 10145 Hamilton Road may be significant for an association with the theme of Community Development of the Antelope Valley, 1918-1975 and the sub-theme of Rural Residential Development of the valley. Although the residence and outbuilding may date to the period of significance for the theme and sub-theme, the subject property is not a rare, unique, or exemplary example of a property associated with twentieth century community development and rural residential development of the Antelope Valley. It does provide a recognizable representation of broad patterns of residential development in the valley. Additionally, the property is within an unincorporated area of Kern County and the Antelope Valley that does not have a strong cohesive pattern of community history that would include the property's period of construction for which it might be considered historically significant. The property is near the communities of Willow Springs and Rosamond but lacks an immediate connection with the development of these communities. In summary, no direct associations between 10145 Hamilton Road and historically significant events or broad patterns of history at the local, region, state, or national level could be established. As such, the subject property is recommended not eligible under CRHR Criterion 1.

Research was conducted to determine if the subject property is significant under Criterion 2 for associations with the lives of historically important persons who have made contributions to local, state, or national history. No direct connection to historically important individuals could be identified through historical and archival research of 10145 Hamilton Road. Individuals found to be associated with the property through archival research include Josephina Padilla and Luzviminda Padilla. No information was uncovered to confirm these individuals resided at 10145 Hamilton Road during its historic period and research did not suggest the identified individuals made important contributions to history. Historically important persons such as explorers Pedro Fages, Joseph Walker, and John C. Frémont are known to have traveled through the area and to have stopped at nearby Willow Springs, but these events happened well before the construction of the extant buildings on the subject property. Therefore, there is no direct correlation between known significant historical figures and the property. As 10145 Hamilton Road does not appear to be illustrative of the accomplishments of historically important persons within a local, state, or national historical context, the property is recommended not eligible under Criterion 2.

To evaluate the subject property under Criterion 3, PaleoWest considered whether it embodies distinctive characteristics of a type, period, or method of construction and whether it represents the work of a master architect or possesses high artistic value. The residence at 10145 Hamilton Road is a vernacular rendition of the California Bungalow stye which is very common to rural areas of Southern California. As an unadorned example of the California Bungalow style, the residence does not embody enough of the distinctive characteristics of this style to be considered an exemplary or unique iteration of a California Bungalow. While vernacular architecture can be considered historically significant, the residence at 10145 Hamilton Road is also not a distinctive, rare, or exemplary vernacular California Bungalow. The ancillary barn is a typical wooden utilitarian barn that does not embody a specific style, nor is it a rare, distinct, or excellent iteration of a rural farm building warranting historical significance for its architecture. PaleoWest also considered whether the subject property may be significant for an association with a master builder or architect; however, no record of a builder or architect was found through property and document search engines of the Kern County Tax Assessor's Office nor through archival research. In summary, the residence of the subject property is not a distinctive or rare example of a vernacular California Bungalow residence in rural Southern California and the ancillary barn is also not a unique or rare example of a rural utilitarian barn or farm building. Additionally, neither building clearly represents a specific period or method of construction, nor are they associated with a significant master architect or builder. As such, 10145 Hamilton Road is recommended not eligible under Criterion 3.

The subject property is a common property type that is unlikely to provide vital information about history or prehistory that is not readily available through historical and archival research. As such, the property is recommended not eligible under CRHR Criterion 4.

The subject property is not within a designated or previously identified historic district. As a very sparsely developed and unincorporated area, the immediate vicinity of the property also lacks architectural cohesion and a defined shared historical narrative to be considered a historic district. Thus, 10145 Hamilton Road is not recommended eligible as a contributor to a CRHR-eligible or listed historic district.

State of California — The Resources Agency DEPARTMENT OF PARKS AND RECREATION **CONTINUATION SHEET** 

Primary # HRI#

Trinomial

Page 5 of 6

Recorded by: Emma Keethler

10145 Hamilton Road \*Resource Name or # (Assigned by recorder)

April 19, 2022

□ Continuation □ Update



Photo 2. Property overview facing north.

State of California — The Resources Agency
DEPARTMENT OF PARKS AND RECREATION
LOCATION MAP


Primary HRI Trinomial

Page 6 of 6**Resource Name or #:** 358-052-08

**Date:** 2022

**Scale:** 1:24,000

Map Name: Willow Springs, Ca (1977) 7.5' USGS Quad.



# PRIMARY RECORD

Primary # HRI# **Trinomial** 

**NRHP Status Code** 

Other Listings Review Code

Poviowor

			Review	Code		Re	viewe	r			Date		
Page 1 of 3			*Re	esourc	e Name	or #:	1008	85 Har	milton R	Road			
P1. Other Ide		☐ Not for F	Dubliosti s	n 🖂 i	Inroctr!	otod							
P2. Location a. County:	: Ker	<del></del>	นมแนสเด	лі 🖂 (	Hestri		o P2a 1	and Da	h or P2d	Attach a Location Map as	necessor	ny )	
•		Tylerhorse		D-1	4005	_				·		-	0.0.0.4
b. USGS 7.5'		Canyon, C		Date	1965	T	9N		14W	NE ¼ of SE of	Sec	08	S.B.B.M.
. Address	Meold					City	Rosa	amon				_ Zip	93560
d. UTM: (give m						11N			0245	mE/	3862	2101	mN;
e. Other Locat		, , ,							8-052-0				
	•							-		ondition, alterations, sizes single-family resider			
he property. exterior walls way. It is uncl with stucco si property; how County Prope	The rescaled in ear who lis belo ever, north ty Apple	sidence has stucco. This ether the prim w and a stud one of the an raiser records	an irregu residence nary entra co lintel a cillary bu . Addition	lar receis set ince or above. ildings al deta	etangular back a n the ea Aerials are visi ails are ir	distand distand st or w from 2 ble from discer	with acce on the est faç on the interval of th	dditior he pa ade. dicate right-om th	ns, a si arcel an The sou e that the of-way to be publice	ve trees, shrubs and de-gable roof, two down dide-gable roof, two down dide-gable roof, two down dide-gable roof, two visually assess a control right-of-way due to	brick mally as two wire ancilland	nasonry ssess f ndows ary out e are li	y chimneys, and rom the right-of of unknown type buildings on the
P3b. Resourc		•				P2. Sin							
			•			•			strict	☐ Element of Distric	t 🗌 Ot	her (Is	olates, etc.)
P5a. Photogra	ph or D	rawing (Photog	graph require	ed for bu	ıildings, str	uctures,	and obje	cts.)		The December of L	N1		
										<b>5b. Description of I</b> hoto 1. Property ove			
										ugust 27, 2021			
										P6. Date Construct	_		
										〗Historic  □ Preh 940	ISTOFIC	П во	uri
			4						Ke	ern County Tax Asse	essor		
- AND MARKET STATE OF THE PARKET STATE OF THE		West 1	L		Luite	All d				7. Owner and Addr ohn J. Barrios	ess:		
A SECOND	A STATE OF THE STA			mi Me				-	10	0085 Hamilton Road	, Rosar	nond, (	CA 93560
					1					<b>B. Recorded by:</b> (Nsa C. Demarais, M.A		filiation,	and address)
									_	van Mills, M.A., RPA	ı		
									_	aleoWest, LLC. 17 S. Ivy Avenue, M	onrovio	CA 04	1016
									5	ir S. ivy Averlue, Mi	Ji II OVIA	, CA 9	1010
									*P9	). Date Recorded:	April :	23, 202	22
P10. Survey 1	Гуре: ([	Describe)	Reconna	issand	e, CEQ/	A comp	liance						
P11. Report (	Citatior	: (Cite survey						)					
4-CAES Proje	ct, Keri	n County, Cal	ifornia (20	)21). P	repared	for Gol	der As	socia	tes.	ural Resources Tech		-	-
*Attachments Record	chaeolo	gical Record		rict Re	cord					ation Sheet			ture, and Objec Rock Art Record

State of California — The Resources Agency DEPARTMENT OF PARKS AND RECREATION **CONTINUATION SHEET** 

Page 2 of 3

Primary # HRI#

**Trinomial** 

10085 Hamilton Road

\*Resource Name or # (Assigned by recorder) Recorded by: Lisa Demarais, Evan Mills

April 23, 2022

□ Continuation □ Update



Photo 2. Northerly view toward the residence from the right-of-way.


State of California — The Resources Agency
DEPARTMENT OF PARKS AND RECREATION
LOCATION MAP

Primary HRI Trinomial

Page 3 of 3**Resource Name or #:** 358-052-07

**Scale:** 1:24,000

Map Name: Willow Springs, Ca (1977) 7.5' USGS Quad.



## **PRIMARY RECORD**

Primary # HRI# **Trinomial** 

**NRHP Status Code** 

Other Listings

	Review Code	Revie	ewer		Date	
Page 1 of 3 P1. Other Identifier:	*Resource Name or	#: <u>1</u>	0057 Hamilt	on Road		
	or Publication 🛛 Unrestricte	d				
*a. County: Kern	an	<b>d</b> (P2c, F	2e, and P2b or	P2d. Attach a Location Map as	necessary.)	
	Springs, CA Date 1965	<b>T</b> 91	N R 14	W SE ¼ of SE of	<b>Sec</b> 01	S.B.B.M.
c. Address 10057 Hamilton	Road	City	Rosamond		Zip	93560
d. UTM: (give more than one for large	e and/or linear resources) Zone	9N	380301	mE/	3861871	mN;
e. Other Locational Data: (e.g. p	arcel#, directions to resource, elevation	etc.)	APN 358-0	)52-06		
*P3a. Description: (Describe re	esource and its major elements. In	clude de	esign, materia	ls, condition, alterations, size	e, setting, and b	ooundaries)
and located on a 9.78-acre pa the right-of-way. Aerials show references one residential buil ranch of concrete construction residence has rough stucco e detached stucco two-bay gara	familton Road) is comprised of rcel. The single-family residence that there are multiple structured ding. The property is enclosed in with a composite shingle root exterior cladding, wood eaves, ge, at least two ancillary building none are listed in the Kern Come setback.	e is se es on to in chair of and of and alungs, and	t back appro he property, in-link fencin concrete slat uminum hori: d livestock o	oximately 425 feet from the but the Kern County Tales. Real estate records in foundation. Real estate zontal sliding windows. Storrals. None of the build	ne road and is x Assessor p ndicate that th e photos from The 2017 pho ings are visib	s not visible from ublic record only the residence is a 2017 show the stos also show a le from the right-
*P3b. Resource Attributes: (L	ist attributes and codes) HP2.	Single	Family Prop	erty; HP33. Farm/Ranch	1	
'P4. Resources Present: 🛛 🗈	•			ct	Other (Iso	olates, etc.)
P5a. Photograph or Drawing (P	Photograph required for buildings, structu	ires, and	objects.)			
	427			P5b. Description of P		
	Sec. 1			Photo 1. Property over August 27, 2021	view racing n	ortri
				*P6. Date Constructe	storic Bo	
Town April						
The state of the s				*P7. Owner and Addre Rodolfo Gamino Gueri		
	Jed Jed			10057 Hamilton Road,		^A 03560
	And Andreas An			*P8. Recorded by: (N. Lisa C. Demarais, M.A	ame, affiliation,	
				Gena Granger, M.A., F	RPA	
				PaleoWest, LLC.		
			5.18	571 S. Ivy Avenue, Mo	nrovia, CA 91	016
		55.1	50 70	*P9. Date Recorded:	April 23, 202	22
*D40 C T (5 - " )						
*P10. Survey Type: (Describe)						
P11. Report Citation: (Cite sur	• •		,	0 % 10 = - :		
A-CAES Project, Kerr	oric Resources Evaluation Rep n County, California (2021). Pre	pared f	or Golder As	ssociates.		•
*Attachments: NONE Record Archaeological Record Artifact Record Photogr				inuation Sheet ☐ B ord ☐ Milling Station		ture, and Object Rock Art Record

**CONTINUATION SHEET** 

\*Resource Name or # (Assigned by recorder)

Page 2 of 3 Recorded by: Lisa Demarais and Gena Granger Primary # HRI# **Trinomial** 

10057 Hamilton Road

April 23, 2022

□ Continuation □ Update



Photo 2. Property overview, facing northwest.



Photo 3. Detail view of rear covered porch (Realtor.com 2017).

#### References:

Realtor.com. 10057 Hamilton Road, News Corp, www.realtor.com/realestateandhomes-detail/10057-Hamilton-Rd\_Rosamond\_CA\_93560\_M25595-68480, accessed April 2022.

State of California — The Resources Agency
DEPARTMENT OF PARKS AND RECREATION
LOCATION MAP

Page 3 of 3


Primary HRI Trinomial

**Resource Name or #:** 358-052-06

Map Name: Willow Springs, Ca (1977) 7.5' USGS Quad.

**Date:** 2022

**Scale:** 1:24,000



# PRIMARY RECORD

Primary # HRI# **Trinomial** 

**NRHP Status Code** 

Other Listings

	Review Code	Revi	ewer		Date	
Page 1 of 5 P1. Other Identifier:	*Resource Name	e or #: <u>9</u>	9714 Rosamo	ond Boulevard		
*P2. Location:	or Publication 🛭 Unrestri	cted				
*a. County: Kern		and (P2c, F	P2e, and P2b or	P2d. Attach a Location Map as r	necessary.)	
*b. USGS 7.5' Quad Little Bu	uttes <b>Date</b> 1965	<b>T</b> 9	N R 13	W NE ¼ of NW of	<b>Sec</b> 19	S.B.B.M.
c. Address 9714 Rosamond I	Boulevard	City	Rosamond		Zip	93560
d. UTM: (give more than one for large	and/or linear resources) Zone	11N	380843	mE/	3858643	mN;
e. Other Locational Data: (e.g. pa	arcel#, directions to resource, eleva	ition, etc.)	APN 374-0	)42-03		
*P3a. Description: (Describe re	source and its major elements	. Include d	esign, material	ls, condition, alterations, size	e, setting, and b	ooundaries)
The subject property (9714 Ro 828 square feet. The residence Rosamond Boulevard and east freely across the property. The rectangular attic vents beneath The entryway is on the south accessed via concrete steps a exterior screen door. The east f	e was constructed in 1919 from an unnamed adjacen e residence has a rectan the gables, horizontal sliding façade and consists of a sand a ramp. The west faç	and is on t dirt road. gular plar ng vinyl wi single fibe ade featu	a 2.26-acre Landscaping oriented no indows cover rglass entry- res two wind	parcel. The property is a g consists of native trees, orth-south with a front-g ed with exterior screens, door behind an exterior slows and a side-entry definition.	accessible from shrubs, and able compose and tan stuck screen door.	om the south via grasses growing ite shingle roof, to exterior walls. The entrance is by an additional
*P3b. Resource Attributes: (Lis	et attributes and codes)	D2 Single	S Family Prop	oertv		
*P4. Resources Present: 🛛 B					Other (Iso	plates etc.)
P5a. Photograph or Drawing (Pf		=		ct 🔲 Element of District	☐ Other (isc	nates, etc.)
Tod. I notograph of Drawing (i)	lotograph required for buildings, st	idotales, and	objects.)	P5b. Description of P	hoto: (view de	to accession #\
	47	100		Photo 1. Property over		
			100	Rosamond Boulevard (		
					<u> </u>	- ,
				*P6. Date Constructe	d/Age and S	ource:
					storic 🔲 Bot	
W			A A A A A A	1919		
		F	1000	Kern County Tax Asse	ssor	
			186	*P7. Owner and Addre	ess:	
		500		9714 Rosamond Boule	vard, Rosam	ond, 93650
				*P8. Recorded by: (Na Emma Keethler, M.A.	ame, affiliation,	and address)
				Gena Granger, M.A., R	PA.	
	Land and the	4	-	PaleoWest, LLC.		
				571 S. Ivy Avenue, Mo	nrovia, CA 91	016
				*P9. Date Recorded:	April 23, 202	2
*D40 Curvey Trees (Describe)	Intonoiso madaatsiaa si	abt of	,			
*P10. Survey Type: (Describe)	Intensive, pedestrian ri	• •				
P11. Report Citation: (Cite sur			,			
	oric Resources Evaluation I County, California (2021).				nical Report fo	or the Hydrostor
*Attachments: ☐ NONE ☐ Record ☐ Archaeological Record ☐ Photogram	ord  District Record					ture, and Object Rock Art Record

State of California — The Resources Agency Primary # DEPARTMENT OF PARKS AND RECREATION HRI# BUILDING, STRUCTURE, AND OBJECT RECORD Page 2 of 5 \*NRHP Status Code \*Resource Name or # (Assigned by recorder) 9714 Rosamond Boulevard B1. Historic Name: N/A B2. Common Name: N/A B3. Original Use: Residential B4. Present Use: Residential \*B5. Architectural Style: Vernacular California ranch \*B6. Construction History: (Construction date, alterations, and date of alterations) Constructed 1919. No record of building permits. Windows have been updated to vinyl and cladding is updated post-World War II replacement stucco. \*B7. Moved? ⊠ No ☐ Yes ☐ Unknown Date: N/A Original Location: N/A \*B8. Related Features: B9a. Architect: Unknown Unknown b. Builder: \*B10. Significance: Theme Area: N/A Period of Significance: **Property Type:** Applicable Criteria: (Discuss importance in terms of historical or architectural context as defined by theme, period, and geographic scope. Also address integrity.) The village of Willow Springs was sold multiple times between 1918 and 1947. The growing accessibility of automobile travel and improvements in water conveyance meant that stopping at Willow Springs, one of the few natural springs in the western Mojave Desert, was no longer a necessary part of travel through the region. Additionally, since WWII, the springs have been severely depleted due to drought. The most recent survey of Willow Springs indicated that the smaller springs had gone entirely dry by 1992 and the others were at risk of running dry. Due to these changes, development and population growth in Willow Springs and its immediate surrounding area was slow throughout much of the twentieth century (Tipton 1988; OHP 2021). Agriculture remained a primary industry in Kern County, but the growth of the aerospace industry has been a major change to the economic landscape of the region in the twentieth century. Agriculture in Willow Springs and its immediate surrounding area has remained a steady yet small contributor to the industry of the region (Caltrans 2007: 17-18, Dunne 2016, Tipton 1988, Greene and Knight 1992). (continued on page 3) N/A B11. Additional Resource Attributes: (List attributes and codes) \*B12. References: (Sketch Map with north arrow required.)

See page 3.

\*B14. Evaluator: Emma Keethler, M.A.

\*Date of Evaluation: April 23, 2022

(This space reserved for official comments.)



State of California — The Resources Agency DEPARTMENT OF PARKS AND RECREATION CONTINUATION SHEET

Primary # HRI# Trinomial

9714 Rosamond Boulevard

Page 3 of 5 \*Resource Name or # (Assigned by recorder)

Recorded by: Emma Keethler, M.A. Date:

April 23, 2022

□ Continuation □ Update

#### \*B10. Significance: (continued)

Although Willow Springs remained predominantly unchanged during much of the twentieth century, two new developments were completed nearby during this period that affected the settlement. Muroc Army Air Field was established approximately 15 miles east of Willow Springs and Rosamond. The base, which would later become Edwards Air Force Base (EAFB), opened in 1932 and helped to bring more traffic to the Willow Springs area despite the loss of its main draws for long-range travelers and local visitors. In subsequent years EAFB attracted settlers and investment in infrastructure, providing an economic boon to the region; however, central Rosamond and Lancaster saw the greatest economic benefits and population growth (Tipton 1988; OHP 2021). Due to the population boom during the 1930s, the demand for reliable infrastructure increased. Much like other parts of the United States, the Willow Springs area needed electricity in order to grow and thrive. Due to this country-wide demand, President Roosevelt signed the Rural Electrification Act (REA) into law in 1936 (Barnes 2007). The Willow Springs area received electricity shortly after the REA was enacted.

In 1953, the Willow Springs International Raceway opened approximately 1.25 miles west of Willow Springs. At the time, there was little residential or commercial development around Willow Springs or the racetrack, save for a few farms that had installed irrigation equipment and a few small desert homesteaders. During the 1960s, a series of new grided streets were cut in the area around Willow Spring and the raceway, apparently in anticipation for increased residential growth. Ultimately, very few residences were built, the majority of which are centered in a small area in the Project area bound by Irone Avenue, Melody Lane, 145<sup>th</sup> Street W and 140<sup>th</sup> Street West and were constructed between 1960 and 1965. New residences built during this period were primarily single-story single-family vernacular residences on parcels of five acres or less. Although most of these residences are devoid of a particular recognizable architectural style, they reflect common materials and basic forms used throughout Southern California, giving many a distinct rural vernacular Californian appearance commonly identified in similar communities (UCSB 1952a, 1952b; HistoricAerials.com 1959, 1963; Kern County Recorder 1960).

#### \*B12. References:

Barnes, D.F.

2007. The Challenge of Rural Electrification: Strategies for Developing Countries. RFF Press, Washington D.C.

#### California Department of Transportation (Caltrans)

A Historical Context and Archaeological Research Design for Agricultural Properties in California. Division of Environmental Analysis, Sacramento, California.

#### Dunne, Kerry

2016 "Boomtimes Again: Twentieth-Century Mining in the Mojave Desert," Primary Source Sets, Digital Public Library of America, Massachusetts. https://dp.la/primary-source-sets/boomtimes-again-twentieth-century-mining-in-the-mojave-desert, accessed April 2022.

#### Greene, Andry and Albert Knight

1992 "P-15-000129 Supplement, Trinomial CA\_KER-129), California Landmark #130 Willow Springs," Western Mojave Survey Association, North Hollywood, California.

#### HistoricAerials.com

1959 Willow Springs, CA. Aerial imagery.1963 Willow Springs, CA. Aerial imagery.

#### Kern County Recorder

1960 Tract No. 2355 [map]. Record of Survey Book 7, Page 191.

#### Office of Historic Preservation (OHP)

2021 "Willow Springs – Historical Landmark." California State Parks, Office of Historic Preservation. Available: https://ohp.parks.ca.gov/ListedResources/Detail/130. Accessed September 2021.

#### Tipton, Karla 1988

"Willow Springs: An Oasis in Antelope Valley" from Antelope Valley Press in The Gold Ledge. Available: <a href="https://www.karlatipton.com/portfolio/Antelope-Valley-Press-Willow-Springs-May-1988.pdf">https://www.karlatipton.com/portfolio/Antelope-Valley-Press-Willow-Springs-May-1988.pdf</a>. Accessed September 2021.

#### University of Santa Barbara (UCSB) Library

1952a Flight ID ABL-1952, Frame 3K-89. October 12. 1952b Flight ID ABL-1952, Frame 4K-39. October 12.

State of California — The Resources Agency DEPARTMENT OF PARKS AND RECREATION	Primary # HRI#
CONTINUATION SHEET	Trinomial

CONTINU	JATION SHEET		Trinomial	
Page 4 of 5	*Resource Name or # (Assigned by	recorder)	9714 Rosamond Boulevard	
Recorded by:	Emma Keethler, M.A.	Date:	April 23, 2022	
				□ Continuation □ Update

#### California Register of Historical Resources Eligibility

The subject property at 9714 Rosamond Road (374-042-03) was evaluated for historical significance under California Register of Historical Resources (CRHR) Criteria 1-4.

Under Criterion 1, the subject property was evaluated for an association with significant historical events or broad patterns of history at the local, regional, state, or national level. The property lies within an unincorporated area of the Antelope Valley, a region of the Mojave Desert that has a rich history of American exploration, migration, and settlement unique to the California and the high desert region during the nineteenth and early twentieth centuries. According to the Kern County Property Appraiser records 9714 Rosamond Boulevard was constructed circa 1919, which suggests the residence may be significant for an association with the theme of Community Development of the Antelope Valley, 1918-1975 and the sub-theme of Rural Residential Development of the valley. Although the residence and outbuilding may date to the period of significance for the theme and sub-theme, the subject property is not a rare, unique, or exemplary example of a property associated with twentieth century community development and rural residential development of the Antelope Valley. It does not provide a recognizable representation of broad patterns of residential development in the valley. Additionally, the property is within an unincorporated area of Kern County and the Antelope Valley that does not have a strong cohesive pattern of community history that would include the property's period of construction for which it might be considered historically significant. The property is near the communities of Willow Springs and Rosamond but lacks an immediate connection with the development of these communities. In summary, no direct associations between 9714 Rosamond Boulevard and historically significant events or broad patterns of history at the local, region, state, or national level could be established. As such, the subject property is recommended not eligible under CRHR Criterion 1.

Research was conducted to determine if the subject property is significant under Criterion 2 for associations with the lives of historically important persons who have made contributions to local, state, or national history. No direct connection to historically important individuals could be identified through historical and archival research of 9714 Rosamond Boulevard. Individuals found to be associated with the property through archival research include Dixie Lee Noel and Roy Leo Noel. No information was uncovered to confirm these individuals resided at 9714 Rosamond Boulevard during its historic period and research did not suggest the identified individuals made important contributions to history. Historically important persons such as explorers Pedro Fages, Joseph Walker, and John C. Frémont are known to have traveled through the area and to have stopped at nearby Willow Springs, but these events happened well before the construction of the extant buildings on the subject property. Therefore, there is no direct correlation between known significant historical figures and the property. As 10145 Hamilton Road does not appear to be illustrative of the accomplishments of historically important persons within a local, state, or national historical context, the property is recommended not eligible under Criterion 2.

To evaluate the subject property under Criterion 3, PaleoWest considered whether it embodies distinctive characteristics of a type, period, or method of construction and whether it represents the work of a master architect or possesses high artistic value. The residence, not including the modern utilitarian shed type outbuilding, at 9714 Rosamond Boulevard is a vernacular rendition of the California Ranch type which is very common to rural areas of Southern California. As an unadorned example of the California Ranch type, the property residence does not embody enough of the distinctive characteristics of this style to be considered an exemplary or unique iteration of a California Ranch. While vernacular architecture can be considered historically significant, the residence at 9714 Rosamond Boulevard is also not a distinctive, rare, or exemplary vernacular California Ranch which is a common type and style throughout rural areas of Southern California. The ancillary barn is a typical wooden utilitarian barn that does not embody a specific style, nor is it a rare, distinct, or excellent iteration of a rural farm building warranting historical significance for its architecture. PaleoWest also considered whether the subject property may be significant for an association with a master builder or architect; however, no record of a builder or architect was found through property and document search engines of the Kern County Tax Assessor's Office nor through archival research. In summary, the residence of the subject property is not a distinctive or rare example of a vernacular California Ranch residence in rural Southern California and the ancillary modern shed is also not a unique or rare example of a rural utilitarian farm building. Additionally, neither building clearly represents or a specific period or method of construction, nor are they associated with a significant master architect or builder. As such, 9714 Rosamond Boulevard is recommended not eligible under Criterion 3.


The subject property is a common property type that is unlikely to provide vital information about history or prehistory that is not readily available through historical and archival research. As such, the property is recommended not eligible under CRHR Criterion 4.

The subject property is not within a designated or previously identified historic district. As a very sparsely developed and unincorporated area, the immediate vicinity of the property also lacks architectural cohesion and a defined shared historical narrative to be considered a historic district. Thus, 9714 Rosamond Boulevard is not recommended eligible as a contributor to a CRHR-eligible or listed historic district.

State of California — The Resources Agency	Primary
DEPARTMENT OF PARKS AND RECREATION	HRI
LOCATION MAP	Trinomial

**Page** 5 **of** 5 **Scale:** 1:24,000 **Resource Name or #:** 374-042-03

Map Name: Little Buttes, Ca (1975) 7.5' USGS Quad.



# **PRIMARY RECORD**

Primary # HRI# **Trinomial** 

**NRHP Status Code** 

Other Listings Review Code

Reviewer

Review Code Reviewer	Date
Page 1 of 6 *Resource Name or #: 9668 Rosamo	ond Boulevard
P1. Other Identifier:	
P2. Location: ☐ Not for Publication ☐ Unrestricted	
	P2d. Attach a Location Map as necessary.)
b. USGS 7.5' Quad Little Buttes Date 1965 T 9N	R_13W
c. Address 9668 Rosamond Boulevard City Rosamond	Zip <u>93560</u>
d. UTM: (give more than one for large and/or linear resources) Zone 11N 380926	mE/ <u>3858636</u> mN;
e. Other Locational Data: (e.g. parcel#, directions to resource, elevation, etc.)  APN 374-0	042-04
P3a. Description: (Describe resource and its major elements. Include design, material	ls, condition, alterations, size, setting, and boundaries)
The subject property (9668 Rosamond Boulevard) is comprised of a one-story was ingle-family residence was constructed in 1921 and sits within a 0.49-acre property. The residence has a rectangular plan and front gable roof with a small rear addition has a shed roof, and the enclosed porch has a hipped roof, rectangular attic vents, one-by-one vinyl horizontal sliding windows of varying anodular metal. The primary entrance is on the north façade and consists of a single states of the primary buildings in varying states of disrepair are visible from the right-of-way.	parcel. The property is accessible from the south via shrubs, and grasses growing freely throughout the I rear addition and enclosed entry porch addition. The Other features include a composite shingle roofing, size, and exterior walls which are clad in stucco and agle vinyl entry door with concrete steps. The west and
P3b. Resource Attributes: (List attributes and codes) HP2. Single Family Propert. Resources Present: ⊠ Building □ Structure □ Object □ Site □ Distriction	
P5a. Photograph or Drawing (Photograph required for buildings, structures, and objects.)	
P5a. Photo or Drawing (Photo required for buildings, structures, and objects.)	P5b. Description of Photo: (view, date, accession #)
	Photo 1. Property overview facing southeast August 30, 2021
	August 30, 2021
	*P6. Date Constructed/Age and Source:
	1921
	Kern County Tax Assessor
90	*D7 Owner and Address:
	*P7. Owner and Address: Ronald E Smillie and Gilberto A Nevarez
	9668 Rosamond Boulevard, Rosamond, CA 93560
	*P8. Recorded by: (Name, affiliation, and address) Emma Keethler, M.A.
TTP 是我们的特别是一个人的一个人。	Grena Granger, M.A., RPA
	PaleoWest, LLC.
	571 S. Ivy Avenue, Monrovia, CA 91016
	*P9. Date Recorded:April 23, 2022
240 Common Tomas (Dagarika)	
P10. Survey Type: (Describe) Intensive, pedestrian right-of-way	
P11. Report Citation: (Cite survey report and other sources, or enter "none.")	Outtoned December 15 and 15 an
2022 PaleoWest, LLC. Historic Resources Evaluation Report, Addendum to: Of A-CAES Project, Kern County, California (2021). Prepared for Golder As	
	inuation Sheet
Record Archaeological Record District Record Linear Feature Rec	
☐ Artifact Record ☑ Photograph Record ☐ Other (List):	

State of California — The Resources Agency
DEPARTMENT OF PARKS AND RECREATION
BUILDING, STRUCTURE, AND OBJECT RECORD

\*NRHP Status Code

\*Resource Name or # (Assigned by recorder)

B1. Historic Name:
B2. Common Name:

N/A

N/A

9668 Rosamond Boulevard B2. Common Name: B3. Original Use: Residential B4. Present Use: Residential Vernacular California Bungalow \*B5. Architectural Style: \*B6. Construction History: (Construction date, alterations, and date of alterations) The residence was constructed in 1921. No public record of building permits were located, but replacement vinyl windows have been installed and the original cladding has been replaced with post-World War II concrete-based stucco. Based on the region and building type, it is likely the original cladding was also stucco. \*B7. Moved? ⊠ No ☐ Yes ☐ Unknown Date: Original Location: N/A N/A \*B8. Related Features: N/A B9a. Architect: Unknown Unknown b. Builder: \*B10. Significance: Theme Area: N/A Period of Significance: Residential **Applicable Criteria: Property Type:** (Discuss importance in terms of historical or architectural context as defined by theme, period, and geographic scope. Also address integrity.) The village of Willow Springs was sold multiple times between 1918 and 1947. The growing accessibility of automobile travel and improvements in water conveyance meant that stopping at Willow Springs, one of the few natural springs in the western Mojave Desert, was no longer a necessary part of travel through the region. Additionally, since WWII, the springs have been severely depleted due to drought. The most recent survey of Willow Springs indicated that the smaller springs had gone entirely dry by 1992 and the others were at risk of running dry. Due to these changes, development and population growth in Willow Springs and its immediate surrounding area was slow throughout much of the twentieth century (Tipton 1988; OHP 2021). Agriculture remained a primary industry in Kern County, but the growth of the aerospace industry has been a major change to the economic landscape of the region in the twentieth century. Agriculture in Willow Springs and its immediate surrounding area has remained a steady yet small contributor to the industry of the region (Caltrans 2007: 17-18, Dunne 2016, Tipton 1988, Greene and Knight 1992). (continued on page 3) HP4. Ancillary building B11. Additional Resource Attributes: (List attributes and codes) \*B12. References: See page 3. (Sketch Map with north arrow required.) Lisa Demarais, M.A. \*B14. Evaluator: April 23, 2022 \*Date of Evaluation:

(This space reserved for official comments.)

State of California — The Resources Agency DEPARTMENT OF PARKS AND RECREATION	Primary # HRI#
CONTINUATION SHEET	Trinomial
	0669 Pagamand Paulovard

CONTIN	UATION SHEET		Trinomial	
Page 3 of 6	*Resource Name or # (Assigned by	recorder)	9668 Rosamond Boulevard	
Recorded by:	Emma Keethler	Date:	April 23, 2022	
				□ Continuation □ Update

#### \*B10. Significance: (continued)

Although Willow Springs remained predominantly unchanged during much of the twentieth century, two new developments were completed nearby during this period that affected the settlement. Muroc Army Air Field was established approximately 15 miles east of Willow Springs and Rosamond. The base, which would later become Edwards Air Force Base (EAFB), opened in 1932 and helped to bring more traffic to the Willow Springs area despite the loss of its main draws for long-range travelers and local visitors. In subsequent years EAFB attracted settlers and investment in infrastructure, providing an economic boon to the region; however, central Rosamond and Lancaster saw the greatest economic benefits and population growth (Tipton 1988; OHP 2021). Due to the population boom during the 1930s, the demand for reliable infrastructure increased. Much like other parts of the United States, the Willow Springs area needed electricity in order to grow and thrive. Due to this country-wide demand, President Roosevelt signed the Rural Electrification Act (REA) into law in 1936 (Barnes 2007). The Willow Springs area received electricity shortly after the REA was enacted.

In 1953, the Willow Springs International Raceway opened approximately 1.25 miles west of Willow Springs. At the time, there was little residential or commercial development around Willow Springs or the racetrack, save for a few farms that had installed irrigation equipment and a few small desert homesteaders. During the 1960s, a series of new grided streets were cut in the area around Willow Spring and the raceway, apparently in anticipation for increased residential growth. Ultimately, very few residences were built, the majority of which are centered in a small area in the Project area bound by Irone Avenue, Melody Lane, 145<sup>th</sup> Street W and 140<sup>th</sup> Street West and were constructed between 1960 and 1965. New residences built during this period were primarily single-story single-family vernacular residences on parcels of five acres or less. Although most of these residences are devoid of a particular recognizable architectural style, they reflect common materials and basic forms used throughout Southern California, giving many a distinct rural vernacular Californian appearance commonly identified in similar communities (UCSB 1952a, 1952b; HistoricAerials.com 1959, 1963; Kern County Recorder 1960).

#### \*B12. References:

Barnes, D.F.

2007. The Challenge of Rural Electrification: Strategies for Developing Countries. RFF Press, Washington D.C.

California Department of Transportation (Caltrans)

A Historical Context and Archaeological Research Design for Agricultural Properties in California. Division of Environmental Analysis, Sacramento, California.

Dunne, Kerry

2016 "Boomtimes Again: Twentieth-Century Mining in the Mojave Desert," Primary Source Sets, Digital Public Library of America, Massachusetts. https://dp.la/primary-source-sets/boomtimes-again-twentieth-century-mining-in-the-mojave-desert, accessed April 2022.

Greene, Andry and Albert Knight

1992 <sup>\*</sup>P-15-000129 Supplement, Trinomial CA\_KER-129), California Landmark #130 Willow Springs," Western Mojave Survey Association, North Hollywood, California.

HistoricAerials.com

1959 Willow Springs, CA. Aerial imagery.1963 Willow Springs, CA. Aerial imagery.

Kern County Recorder

1960 Tract No. 2355 [map]. Record of Survey Book 7, Page 191.

Office of Historic Preservation (OHP)

2021 "Willow Springs – Historical Landmark." California State Parks, Office of Historic Preservation. Available: https://ohp.parks.ca.gov/ListedResources/Detail/130. Accessed September 2021.

Tipton, Karla 1988

"Willow Springs: An Oasis in Antelope Valley" from Antelope Valley Press in The Gold Ledge. Available: <a href="https://www.karlatipton.com/portfolio/Antelope-Valley-Press-Willow-Springs-May-1988.pdf">https://www.karlatipton.com/portfolio/Antelope-Valley-Press-Willow-Springs-May-1988.pdf</a>. Accessed September 2021.

University of Santa Barbara (UCSB) Library

1952a Flight ID ABL-1952, Frame 3K-89. October 12.1952b Flight ID ABL-1952, Frame 4K-39. October 12.

State of California — The Resources Agency DEPARTMENT OF PARKS AND RECREATION			Primary # HRI#	
CONTINU	JATION SHEET		Trinomial	
Page 4 of 6	*Resource Name or # (Assigned by red	corder)	9668 Rosamond Boulevard	
_	Emma Keethler	Date:	April 23, 2022	
				□ Continuation □ Update

#### California Register of Historical Resources Eligibility:

The subject property at 9668 Rosamond Boulevard (374-042-04) was evaluated for historical significance under California Register of Historical Resources (CRHR) Criteria 1-4.

Under Criterion 1, the subject property was evaluated for an association with significant historical events or broad patterns of history at the local, regional, state, or national level. The property lies within an unincorporated area of the Antelope Valley, a region of the Mojave Desert that has a rich history of American exploration, migration, and settlement unique to the California and the high desert region during the nineteenth and early twentieth centuries. According to the Kern County Assessor's Office records, the residence was constructed circa 1921, which is past the period for settlement at the regional (Antelope Valley), state (California), or local level. PaleoWest also considered whether 9668 Rosamond Boulevard may be significant for an association with the theme of Community Development of the Antelope Valley, 1918-1975 and the sub-theme of Rural Residential Development of the valley. Although the residence may date to the period of significance for the theme and sub-theme, the subject property is not a rare, unique, or exemplary example of a property associated with twentieth century community development and rural residential development of the Antelope Valley. It does provide a recognizable representation of broad patterns of residential development in the valley. Additionally, the property is within an unincorporated area of Kern County and the Antelope Valley that does not have a strong cohesive pattern of community history that would include the property's period of construction for which it might be considered historically significant. The property is near the communities of Willow Springs and Rosamond but lacks an immediate connection with the development of these communities. In summary, no direct associations between 9668 Rosamond Boulevard and historically significant events or broad patterns of history at the local, region, state, or national level could be established. As such, the subject property is recommended not eligible under CRHR Criterion 1.

Research was conducted to determine if the subject property is significant under Criterion 2 for associations with the lives of historically important persons who have made contributions to local, state, or national history. No direct connection to historically important individuals could be identified through historical and archival research of 9668 Rosamond Boulevard. Individuals found to be associated with the property through archival research include Ronald Smillie, Gilberto Navarez, Vicky Gale Carrer, Dixie Noel, and Douglas Arnold Middleton. No information was uncovered to confirm these individuals resided at 9668 Rosamond Boulevard during its historic period and research did not suggest the identified individuals made important contributions to history. Historically important persons such as explorers Pedro Fages, Joseph Walker, and John C. Frémont are known to have traveled through the area and to have stopped at nearby Willow Springs, but these events happened well before the construction of the extant buildings on the subject property. Therefore, there is no direct correlation between known significant historical figures and the property. As 9668 Rosamond Boulevard does not appear to be illustrative of the accomplishments of historically important persons within a local, state, or national historical context, the property is recommended not eligible under Criterion 2.

To evaluate the subject property under Criterion 3, PaleoWest considered whether it embodies distinctive characteristics of a type, period, or method of construction and whether it represents the work of a master architect or possesses high artistic value. The residence at 9668 Rosamond Boulevard is a vernacular rendition of the California Bungalow stye which is very common to rural areas of Southern California. As an unadorned example of the California Bungalow style, the property residence does not embody enough of the distinctive characteristics of this style to be considered an exemplary or unique iteration of a California Bungalow. While vernacular architecture can be considered historically significant, the residence at 9668 Rosamond Boulevard is also not a distinctive, rare, or exemplary vernacular California Bungalow which is a common type and style throughout rural areas of Southern California. The utilitarian outbuildings are typical wooden utilitarian buildings that do not embody a specific style, nor are they a rare, distinct, or excellent iteration of a rural farm building warranting historical significance for its architecture. PaleoWest also considered whether the subject property may be significant for an association with a master builder or architect; however, no record of a builder or architect was found through property and document search engines of the Kern County Tax Assessor's Office nor through archival research. In summary, the residence of the subject property is not a distinctive or rare example of a vernacular California Bungalow residence in rural Southern California and the ancillary barn is also not a unique or rare example of a rural utilitarian barn or farm building. Additionally, neither building clearly represents or a specific period or method of construction, nor is itare they associated with a significant master architect or builder. As such, 9668 Rosamond Boulevard is recommended not eligible under Criterion 3.

The subject property is a common property type that is unlikely to provide vital information about history or prehistory that is not readily available through historical and archival research. As such, the property is recommended not eligible under CRHR Criterion 4.

The subject property is not within a designated or previously identified historic district. As a very sparsely developed and unincorporated area, the immediate vicinity of the property also lacks architectural cohesion and a defined shared historical narrative to be considered a historic district. Thus, 9668 Rosamond Boulevard is not recommended eligible as a contributor to a CRHR-eligible or listed historic district.

#### **CONTINUATION SHEET**

Page 5 of 6

\*Resource Name or # (Assigned by recorder)

Recorded by: Emma Keethler Date:

Primary # HRI# Trinomial

9668 Rosamond Boulevard

April 23, 2022

□ Continuation □ Update



Photo 2. North (primary) façade, view facing south.



Photo 3. North and east façades, view facing southwest.

State of California — The Resources Agency	
DEPARTMENT OF PARKS AND RECREATION	
I OCATION MAP	


Trinomial

Primary HRI

**Scale:** 1:24,000 Page 6 of 6**Resource Name or #:** 374-042-04

Map Name: Little Buttes, Ca (1975) 7.5' USGS Quad.

**Date:** 2022



### PRIMARY RECORD

Primary # HRI # Trinomial

**NRHP Status Code** 

Other Listings Review Code

s Reviewer

Date

Page 1 of 6	*Resource Name	or #:	9650 W. Ros	amond Boule	evard				
P1. Other Identifier: *P2. Location: Not for Pu	ıblication 🛛 Unrestric	tod							
	<del></del>		DO L DOL	DO 1 A# 1 1		,			
*a. County: Kern  *b. USGS 7.5' Quad Little Buttes			c, P2e, and P2b or		-			20	CDDM
*b. USGS 7.5' Quad Little Buttes c. Address 9650 W. Rosamond B	Date 1965	_ T _ City	9N Rosamond	_ <b>R</b> _13W	_ NE ¼ <b>of</b> N		_	20 3560	S.B.B.M
d. UTM: (give more than one for large and/or		-	-				. —		NI.
e. Other Locational Data: (e.g. parcel#,		11N	<u>382418</u> APN 374-		mE/	38585	02	— '''	N;
*P3a. Description: (Describe resource					alterations, size	e. setting. :	and bou	ndaries	3)
The subject property (9650 W Rosar	•								<u> </u>
1.47-acre parcel. The single-family re Boulevard. Landscaping consists of Oak tree within the front yard near the residence has a rectangular plan, a confaçades, faux-divided lite vinyl sliding stucco walls. The primary entrance is and a metal exterior security door. To two windows, and the west façade fee	esidence was construct a planted row of shrubs ne northern property bot composite shingle jerking windows, a small meta s on the north façade at the north façade feature	ed in 19 along undary. The ad read read read read consister the second read read read read read read read rea	952. The prop the chain-link Other smalle oof with rectainey stack extensions sists of a single vindows and re	erty is acces fence facing r trees and sl ngular attic vending from the entry-door ectangular fo	sible from the Rosamond B hrubs grow frents below the central pebeneath a rocundation ven	e south vi Boulevard eely acro e eaves ak of the of overha ts. The e	ia Rosa I along voss the pon the ending, con	mond with a proper east are extended as the ex	large ty. The nd west erior steps,
P3b. Resource Attributes: (List attri			gle Family Pro		controle step	<i>3</i> 3.			
P4. Resources Present: Buildin					ent of District	☐ Othe	r (Isolat	es et	<u>c)</u>
P5a. Photograph or Drawing (Photogra	<del>-</del>				on District		i (isolat	00, 01	o.,
Toda i notograpii or Drawing (i notogra	apri roquirou for bullulingo, ottu	otaroo, a	114 05,0000.)	P5h Desi	cription of P	hoto: (vie	w date a	ncessio	n #)
					Property over				
					d Boulevard (				
				-					
				*P6. Date	e Constructe	d/Age ar	nd Sou	rce:	
		(I) IV	Ya.		c 🗌 Prehis	storic _	] Both		
	(4)	WY		1950					
		WI		Kern Cou	nty Tax Asse	ssor			
		1/4		*P7 Own	er and Addre	266.			
			N. P. Inda	17. 0	or and Addit				
				9650 W. F	Rosamond Bo	oulevard			
		A Paris			erded by: (Na ethler, M.A.	ame, affilia	ation, and	d addre	ess)
				Gena Gra	nger, M.A., R	RPA			
				PaleoWes	st, LLC.				
				571 S. Ivy	Avenue, Mo	nrovia, C	A 9101	6	
				*P9. Date F	Recorded:	April 23,	, 2022		
				J					
P10. Survey Type: (Describe)	ntensive, pedestrian rig	ht-of-wa	ay						
P11. Report Citation: (Cite survey re	•		,						
2022 PaleoWest, LLC. Historic R A-CAES Project, Kern Coul	nty, California (2021). P				ources Techr	nical Repo	ort for tl	ne Hyd	drostor
*Attachments: ☐ NONE ☐ Loc Record ☐ Archaeological Record ☐ Artifact Record ☐ Photograph R		Linea	p ⊠ Con ar Feature Red	tinuation She cord ☐ Mi	eet 🛚 B	uilding, S Record			Object Record

Page 2 of 6	*NR	HP Status Code _	6Z				
	*Resource Name or	# (Assigned by record	der)	9650 V	V. Rosamond Bo	oulevard	
B1. Historic Name:	N/A						
B2. Common Name:	N/A						
B3. Original Use:	Residential						
B4. Present Use:	Residential	ala					
*B5. Architectural Sty	<b>le:</b> Vernacular California ra <b>tory:</b> (Construction date, alterations,		Tho	rocidoneo was	constructed in 1	050 Thor	o aro no
	nits available or visible feature	_				330. THE	e ale lio
*B7. Moved? ⊠ No [ *B8. Related Features	: N/A			inal Location:	N/A		
B9a. Architect: <u>Unkr</u> *B10. Significance: Th		b. Builder:	_	nknown Area:			
Period of Significance		Property Type:		Residential	_ Applicable C	riteria:	N/A
(Discuss importance i	n terms of historical or architectur	al context as defined by	theme	e, period, and geo	graphic scope. Al	so address	s integrity.)
region (Caltrans 2007:	17-18, Dunne 2016, Tipton 19	88, Greene and Knigh	nt 199	92).			
						(contin	ued on page 3)
B11. Additional Resour	rce Attributes: (List attributes an	d codes) N/A					
*B12. References:							
See page 3.				(Sketch	Map with north	arrow red	quired.)
	<b>-</b>						
*B14. Evaluator:	Emma Keethler			-		14	THE PARTY
*Date of Evaluation:	April 23, 2022			Et Creat	374-042-39	<b>5730725</b> 9	374-042-07

(This space reserved for official comments.)



# State of California — The Resources Agency DEPARTMENT OF PARKS AND RECREATION HRI# CONTINUATION SHEET Trinomial Page 2 of 6 \*\*Resource Name or # (Assigned by recently) 9650 W. Rosamond Boulevard

CONTINU	JATION SHEET		Trinomial	
Page 3 of 6	*Resource Name or # (Assigned by	recorder)	9650 W. Rosamond Boulevard	
Recorded by:	Emma Keethler	Date:	April 23, 2022	
				□ Continuation □ Update

#### \*B10. Significance: (continued)

Although Willow Springs remained predominantly unchanged during much of the twentieth century, two new developments were completed nearby during this period that affected the settlement. Muroc Army Air Field was established approximately 15 miles east of Willow Springs and Rosamond. The base, which would later become Edwards Air Force Base (EAFB), opened in 1932 and helped to bring more traffic to the Willow Springs area despite the loss of its main draws for long-range travelers and local visitors. In subsequent years EAFB attracted settlers and investment in infrastructure, providing an economic boon to the region; however, central Rosamond and Lancaster saw the greatest economic benefits and population growth (Tipton 1988; OHP 2021). Due to the population boom during the 1930s, the demand for reliable infrastructure increased. Much like other parts of the United States, the Willow Springs area needed electricity in order to grow and thrive. Due to this country-wide demand, President Roosevelt signed the Rural Electrification Act (REA) into law in 1936 (Barnes 2007). The Willow Springs area received electricity shortly after the REA was enacted.

In 1953, the Willow Springs International Raceway opened approximately 1.25 miles west of Willow Springs. At the time, there was little residential or commercial development around Willow Springs or the racetrack, save for a few farms that had installed irrigation equipment and a few small desert homesteaders. During the 1960s, a series of new grided streets were cut in the area around Willow Spring and the raceway, apparently in anticipation for increased residential growth. Ultimately, very few residences were built, the majority of which are centered in a small area in the Project area bound by Irone Avenue, Melody Lane, 145<sup>th</sup> Street W and 140<sup>th</sup> Street West and were constructed between 1960 and 1965. New residences built during this period were primarily single-story single-family vernacular residences on parcels of five acres or less. Although most of these residences are devoid of a particular recognizable architectural style, they reflect common materials and basic forms used throughout Southern California, giving many a distinct rural vernacular Californian appearance commonly identified in similar communities (UCSB 1952a, 1952b; HistoricAerials.com 1959, 1963; Kern County Recorder 1960).

#### \*B12. References:

Barnes, D.F.

2007. The Challenge of Rural Electrification: Strategies for Developing Countries. RFF Press, Washington D.C.

California Department of Transportation (Caltrans)

2007 A Historical Context and Archaeological Research Design for Agricultural Properties in California. Division of Environmental Analysis, Sacramento, California.

Dunne, Kerry

2016 "Boomtimes Again: Twentieth-Century Mining in the Mojave Desert," Primary Source Sets, Digital Public Library of America, Massachusetts. https://dp.la/primary-source-sets/boomtimes-again-twentieth-century-mining-in-the-mojave-desert, accessed April 2022.

Greene, Andry and Albert Knight

1992 "P-15-000129 Supplement, Trinomial CA\_KER-129), California Landmark #130 Willow Springs," Western Mojave Survey Association, North Hollywood, California.

HistoricAerials.com

1959 Willow Springs, CA. Aerial imagery.1963 Willow Springs, CA. Aerial imagery.

Kern County Recorder

1960 Tract No. 2355 [map]. Record of Survey Book 7, Page 191.

Office of Historic Preservation (OHP)

2021 "Willow Springs – Historical Landmark." California State Parks, Office of Historic Preservation. Available: https://ohp.parks.ca.gov/ListedResources/Detail/130. Accessed September 2021.

Tipton, Karla 1988

"Willow Springs: An Oasis in Antelope Valley" from Antelope Valley Press in The Gold Ledge. Available: <a href="https://www.karlatipton.com/portfolio/Antelope-Valley-Press-Willow-Springs-May-1988.pdf">https://www.karlatipton.com/portfolio/Antelope-Valley-Press-Willow-Springs-May-1988.pdf</a>. Accessed September 2021.

University of Santa Barbara (UCSB) Library

1952a Flight ID ABL-1952, Frame 3K-89. October 12.1952b Flight ID ABL-1952, Frame 4K-39. October 12.

#### State of California — The Resources Agency

	<u> </u>			<b>/</b>
DEPARTMEN	T OF PARKS AND RECREATION		HRI#	
CONTINU	JATION SHEET		Trinomial	
Page 4 of 6	*Resource Name or # (Assigned by rec	order)	9650 W. Rosamond Boulevard	
Recorded by:	Emma Keethler D	ate:	April 23, 2022	
		-		□ Continuation □ Update

Primary #

#### California Register of Historical Resources Eligibility

The subject property at 9650 Rosamond Boulevard (374-042-39) was evaluated for historical significance under California Register of Historical Resources (CRHR) Criteria 1-4.

Under Criterion 1, the subject property was evaluated for an association with significant historical events or broad patterns of history at the local, regional, state, or national level. The property lies within an unincorporated area of the Antelope Valley, a region of the Mojave Desert that has a rich history of American exploration, migration, and settlement unique to the California and the high desert region during the nineteenth and early twentieth centuries. According to the Kern County Assessor's Office records, the residence was constructed circa 1952, which is well past the period for settlement at the regional (Antelope Valley), state (California), or local level. PaleoWest also considered whether 9650 Rosamond Boulevard may be significant for an association with the theme of Community Development of the Antelope Valley, 1918-1975 and the sub-theme of Rural Residential Development of the valley. Although the residence may date to the period of significance for the theme and sub-theme, the subject property is not a rare, unique, or exemplary example of a property associated with twentieth century community development and rural residential development of the Antelope Valley. It does provide a recognizable representation of broad patterns of residential development in the valley. Additionally, the property is within an unincorporated area of Kern County and the Antelope Valley that does not have a strong cohesive pattern of community history that would include the property's period of construction for which it might be considered historically significant. The property is near the communities of Willow Springs and Rosamond but lacks an immediate connection with the development of these communities. In summary, no direct associations between 9650 Rosamond Boulevard and historically significant events or broad patterns of history at the local, region, state, or national level could be established. As such, the subject property is recommended not eligible under CRHR Criterion 1.

Research was conducted to determine if the subject property is significant under Criterion 2 for associations with the lives of historically important persons who have made contributions to local, state, or national history. No direct connection to historically important individuals could be identified through historical and archival research of 9650 Rosamond Boulevard. Individuals found to be associated with the property through archival research include Dominga Moreno, Lydia Holton, and Michael Moreno. No information was uncovered to confirm these individuals resided at 9650 Rosamond Boulevard during its historic period and research did not suggest the identified individuals made important contributions to history. Historically important persons such as explorers Pedro Fages, Joseph Walker, and John C. Frémont are known to have traveled through the area and to have stopped at nearby Willow Springs, but these events happened well before the construction of the extant buildings on the subject property. Therefore, there is no direct correlation between known significant historical figures and the property. As 9650 Rosamond Boulevard does not appear to be illustrative of the accomplishments of historically important persons within a local, state, or national historical context, the property is recommended not eligible under Criterion 2.

To evaluate the subject property under Criterion 3, PaleoWest considered whether it embodies distinctive characteristics of a type, period, or method of construction and whether it represents the work of a master architect or possesses high artistic value. The residence at 9650 Rosamond Boulevard is a vernacular rendition of the California Ranch style which is very common to rural areas of Southern California. As an unadorned example of the California Ranch style, the property residence does not embody enough of the distinctive characteristics of this style to be considered an exemplary or unique iteration of a California Ranch. While vernacular architecture can be considered historically significant, the residence at 9650 Rosamond Boulevard is also not a distinctive, rare, or exemplary vernacular California Ranch which is a common type and style throughout rural areas of Southern California. PaleoWest also considered whether the subject property may be significant for an association with a master builder or architect; however, no record of a builder or architect was found through property and document search engines of the Kern County Tax Assessor's Office nor through archival research. In summary, the residence of the subject property is not a distinctive or rare example of a vernacular California Ranch residence in rural Southern California and the ancillary barn is also not a unique or rare example of a rural utilitarian barn or farm building. Additionally, neither building clearly represents or a specific period or method of construction, nor is it associated with a significant master architect or builder. As such, 9650 Rosamond Boulevard is recommended not eligible under Criterion 3.

The subject property is a common property type that is unlikely to provide vital information about history or prehistory that is not readily available through historical and archival research. As such, the property is recommended not eligible under CRHR Criterion 4.

The subject property is not within a designated or previously identified historic district. As a very sparsely developed and unincorporated area, the immediate vicinity of the property also lacks architectural cohesion and a defined shared historical narrative to be considered a historic district. Thus, 9650 Rosamond Boulevard is not recommended eligible as a contributor to a CRHR-eligible or listed historic district.

State of California — The Resources Agency DEPARTMENT OF PARKS AND RECREATION **CONTINUATION SHEET** 

Page 5 of 6

Primary # HRI#

**Trinomial** 

\*Resource Name or # (Assigned by recorder) Recorded by: Emma Keethler

April 23, 2022

9650 W. Rosamond Boulevard

□ Continuation □ Update



Photo 2. North (primary) façade, view facing south.




Photo 3. Property overview facing southeast.

State of California — The Resources Agency	Primary
DEPARTMENT OF PARKS AND RECREATION	HRI
LOCATION MAP	Trinomial

**Scale:** 1:24,000 Page 6 of 6**Resource Name or #:** 374-042-39

Map Name: Little Buttes, Ca (1975) 7.5' USGS Quad.



# PRIMARY RECORD

Primary # HRI#

Trinomial **NRHP Status Code** 

Other Listings

	Review Code	F	Reviewer			Date	
Page 1 of 6	*Resource Name	or #:	9580 Ro	osamo	and Boulevard		
P1. Other Identifier:							
	Publication 🛭 Unrestri	cted					
*a. County: Kern		•			P2d. Attach a Location Map as r	necessary.)	
*b. USGS 7.5' Quad Little But				R 13\	NE ¼ of NW of	Sec 19	_ S.B.B.M.
c. Address <u>9580 Rosamond Bo</u> d. UTM: (give more than one for large at		_ City			DO 5/	Zip	93560
e. Other Locational Data: (e.g. pard		111_		38102 374-0	•	3858632	mN;
			· —				houndarios)
*P3a. Description: (Describe reso	ource and its major elements.	. Inclu	de design, rr	nateriai	s, condition, alterations, size	e, setting, and	boundaries)
The subject property (9580 Rosa style single-family residence consminimal. Much of the landscape i planted adjacent to the residence flat roof extension on the east factype covered in dark screen, and to obscure the property from view projection which obscures much	structed in 1955. The props open loose sandy soil we on each side. The reside ade, a tall metal chimney exterior stucco walls. The right-of-way, may	erty is ith an nce h pipe o parco	s accessible area of han as a rectan extending frelis surroun	e from rdscap igular   rom th nded b	Rosamond Boulevard to bing and intermittent gras plan, a composite shingle e north-facing roof slope by tall privacy fencing with	the south. Leses. There are hipped roof, windows of hintermitten	andscaping is are small trees an acarport with a an unknown t plastic paneling
						/aantina	d \
P3b. Resource Attributes: (List	attributes and codes) H	P2. Si	ngle Family	v Prop	ertv	(continue	o on page )
P4. Resources Present: X Bui						Other (Is	solates, etc.)
P5a. Photograph or Drawing (Pho	tograph required for buildings, str	uctures	, and objects.)	)			
					P5b. Description of P		
					Photo 1. Property over		
	No a la l	-			Rosamond Boulevard	(August 30, 2	2021)
					*P6. Date Constructe	d/Age and S	Source:
						storic 🔲 Bo	
	No.				1955		_
- Alleria		NA STATE	11	W.L	Kern County Tax Asse	ssor	
			467		*P7. Owner and Addre Reinaldo De Larosa	ess:	
PERSONAL PROPERTY AND ADDRESS OF THE PERSONAL PR					9580 Rosamond Boule	vard, Rosan	nond, CA 93560
					*P8. Recorded by: (Na Emma Keethler, M.A.	ame, affiliation	, and address)
					Evan Mills, M.A., RPA		
					PaleoWest, LLC.		
			-	-	571 S. Ivy Avenue, Mo	nrovia, CA 9	1016
					*P9. Date Recorded:	April 23, 20	22
P10. Survey Type: (Describe)	Intensive, pedestrian rig	aht of	way				
P11. Report Citation: (Cite surve							
- '	ic Resources Evaluation F		,	m to: (	Sultural Resources Techn	nical Report	or the Hydrostor
	County, California (2021). I					ποαι πορυπ	or the rightoster
	Location Map Ske	etch N		Conti	inuation Sheet 🛛 B		cture, and Object Rock Art Record

# **BUILDING, STRUCTURE, AND OBJECT RECORD**

Page 2 of 6	*NRHP Status Co	de		
	*Resource Name or # (Assigned b	v recorder)	9580 Rosamo	nd Boulevard
B1. Historic Name:	N/A	,		
B2. Common Name:	N/A			
B3. Original Use:	Residential			
B4. Present Use:	Residential			
*B5. Architectural Sty	e: Vernacular California Ranch			
*B6. Construction His	tory: (Construction date, alterations, and date of alterations)	ions) Residence	constructed in 1	955. No publicly available
building permit reco	rds to confirm alterations, and no alterations	are readily appare	ntly from right-o	f-way field survey.
*B7. Moved? ⊠ No [ *B8. Related Features		Original Lo	ocation: N/A	
B9a. Architect: Unkn	own b.	Builder: Unknow	n	
*B10. Significance: Th	eme	Area:		
Period of Significance	: Property	Type: Reside	ntial Appl	icable Criteria: N/A
(Discuss importance i	n terms of historical or architectural context as def	fined by theme, period	d, and geographic	scope. Also address integrity.)
was slow throughout m but the growth of the a Agriculture in Willow S	ue to these changes, development and popuch of the twentieth century (Tipton 1988; Cerospace industry has been a major changorings and its immediate surrounding area 17-18, Dunne 2016, Tipton 1988, Greene and	OHP 2021). Agriculte to the economic has remained a st	ture remained a landscape of the	primary industry in Kern County, e region in the twentieth century.
B11. Additional Resour	ce Attributes: (List attributes and codes)			(continued on page 3)
<b>*B12. References:</b> See page 3.				
*B14. Evaluator: *Date of Evaluation:	Emma Keethler, M.A. April 23, 2022		(Sketch Map w	vith north arrow required.)

(This space reserved for official comments.)



# State of California — The Resources Agency DEPARTMENT OF PARKS AND RECREATION HRI# CONTINUATION SHEET Trinomial Page 3 of 6 \*Resource Name or # (Assigned by recorder) 9580 Rosamond Boulevard

Page 3 of 6	*Resource Name or # (Assigned by re	ecorder)	9580 Rosamond Boulevard	
Recorded by:	Emma Keethler	Date:	April 23, 2022	
				□ Continuation □ Update

#### \*B10. Significance: (continued)

Although Willow Springs remained predominantly unchanged during much of the twentieth century, two new developments were completed nearby during this period that affected the settlement. Muroc Army Air Field was established approximately 15 miles east of Willow Springs and Rosamond. The base, which would later become Edwards Air Force Base (EAFB), opened in 1932 and helped to bring more traffic to the Willow Springs area despite the loss of its main draws for long-range travelers and local visitors. In subsequent years EAFB attracted settlers and investment in infrastructure, providing an economic boon to the region; however, central Rosamond and Lancaster saw the greatest economic benefits and population growth (Tipton 1988; OHP 2021). Due to the population boom during the 1930s, the demand for reliable infrastructure increased. Much like other parts of the United States, the Willow Springs area needed electricity in order to grow and thrive. Due to this country-wide demand, President Roosevelt signed the Rural Electrification Act (REA) into law in 1936 (Barnes 2007). The Willow Springs area received electricity shortly after the REA was enacted.

In 1953, the Willow Springs International Raceway opened approximately 1.25 miles west of Willow Springs. At the time, there was little residential or commercial development around Willow Springs or the racetrack, save for a few farms that had installed irrigation equipment and a few small desert homesteaders. During the 1960s, a series of new grided streets were cut in the area around Willow Spring and the raceway, apparently in anticipation for increased residential growth. Ultimately, very few residences were built, the majority of which are centered in a small area in the Project area bound by Irone Avenue, Melody Lane, 145<sup>th</sup> Street W and 140<sup>th</sup> Street West and were constructed between 1960 and 1965. New residences built during this period were primarily single-story single-family vernacular residences on parcels of five acres or less. Although most of these residences are devoid of a particular recognizable architectural style, they reflect common materials and basic forms used throughout Southern California, giving many a distinct rural vernacular Californian appearance commonly identified in similar communities (UCSB 1952a, 1952b; HistoricAerials.com 1959, 1963; Kern County Recorder 1960).

#### \*B12. References:

Barnes, D.F.

2007. The Challenge of Rural Electrification: Strategies for Developing Countries. RFF Press, Washington D.C.

California Department of Transportation (Caltrans)

2007 A Historical Context and Archaeological Research Design for Agricultural Properties in California. Division of Environmental Analysis, Sacramento, California.

Dunne, Kerry

2016 "Boomtimes Again: Twentieth-Century Mining in the Mojave Desert," Primary Source Sets, Digital Public Library of America, Massachusetts. https://dp.la/primary-source-sets/boomtimes-again-twentieth-century-mining-in-the-mojave-desert, accessed April 2022.

Greene, Andry and Albert Knight

1992 "P-15-000129 Supplement, Trinomial CA\_KER-129), California Landmark #130 Willow Springs," Western Mojave Survey Association, North Hollywood, California.

HistoricAerials.com

1959 Willow Springs, CA. Aerial imagery.1963 Willow Springs, CA. Aerial imagery.

Kern County Recorder

1960 Tract No. 2355 [map]. Record of Survey Book 7, Page 191.

Office of Historic Preservation (OHP)

2021 "Willow Springs – Historical Landmark." California State Parks, Office of Historic Preservation. Available: https://ohp.parks.ca.gov/ListedResources/Detail/130. Accessed September 2021.

Tipton, Karla 1988

"Willow Springs: An Oasis in Antelope Valley" from Antelope Valley Press in The Gold Ledge. Available: <a href="https://www.karlatipton.com/portfolio/Antelope-Valley-Press-Willow-Springs-May-1988.pdf">https://www.karlatipton.com/portfolio/Antelope-Valley-Press-Willow-Springs-May-1988.pdf</a>. Accessed September 2021.

University of Santa Barbara (UCSB) Library

1952a Flight ID ABL-1952, Frame 3K-89. October 12.1952b Flight ID ABL-1952, Frame 4K-39. October 12.

State of California — The Resources Agency

alifornia — The Resources Agency	Primary #
RKS AND RECREATION	HRI#
N SHEET	Trinomial
*Resource Name or # (Assigned by recorder)	9580 Rosamond Boulevard
Keethler Date:	April 23, 2022
	☐ Continuation ☐ Update

#### California Register of Historical Resources Eligibility

DEPARTMENT OF PARKS AND RECREATION

CONTINUATION SHEET

Recorded by: Emma Keethler

Page 4 of 6

The subject property at 9580 Rosamond Boulevard (374-042-07) was evaluated for historical significance under California Register of Historical Resources (CRHR) Criteria 1-4.

Under Criterion 1, the subject property was evaluated for an association with significant historical events or broad patterns of history at the local, regional, state, or national level. The property lies within an unincorporated area of the Antelope Valley, a region of the Mojave Desert that has a rich history of American exploration, migration, and settlement unique to the California and the high desert region during the nineteenth and early twentieth centuries. According to the Kern County Assessor's Office records, the residence was constructed circa 1955, which is well past the period for settlement at the regional (Antelope Valley), state (California), or local level. PaleoWest also considered whether 9580 Rosamond Boulevard may be significant for an association with the theme of Community Development of the Antelope Valley, 1918-1975 and the sub-theme of Rural Residential Development of the valley. Although the residence may date to the period of significance for the theme and sub-theme, the subject property is not a rare, unique, or exemplary example of a property associated with twentieth century community development and rural residential development of the Antelope Valley. It does provide a recognizable representation of broad patterns of residential development in the valley. Additionally, the property is within an unincorporated area of Kern County and the Antelope Valley that does not have a strong cohesive pattern of community history that would include the property's period of construction for which it might be considered historically significant. The property is near the communities of Willow Springs and Rosamond but lacks an immediate connection with the development of these communities. In summary, no direct associations between 9580 Rosamond Boulevard and historically significant events or broad patterns of history at the local, region, state, or national level could be established. As such, the subject property is recommended not eligible under CRHR Criterion 1.

Research was conducted to determine if the subject property is significant under Criterion 2 for associations with the lives of historically important persons who have made contributions to local, state, or national history. No direct connection to historically important individuals could be identified through historical and archival research of 9580 Rosamond Boulevard. Individuals found to be associated with the property through archival research includes Reinaldo De La Rosa. No information was uncovered to confirm this individual resided at 9580 Rosamond Boulevard during its historic period and research did not suggest the identified individuals made important contributions to history. Historically important persons such as explorers Pedro Fages, Joseph Walker, and John C. Frémont are known to have traveled through the area and to have stopped at nearby Willow Springs, but these events happened well before the construction of the extant buildings on the subject property. Therefore, there is no direct correlation between known significant historical figures and the property. As 9580 Rosamond Boulevard does not appear to be illustrative of the accomplishments of historically important persons within a local, state, or national historical context, the property is recommended not eligible under Criterion 2.

To evaluate the subject property under Criterion 3, PaleoWest considered whether it embodies distinctive characteristics of a type, period, or method of construction and whether it represents the work of a master architect or possesses high artistic value. The residence at 9580 Rosamond Boulevard is a vernacular rendition of a California Ranch residence. As an unadorned example of a vernacular California Ranch, the property's residence does not embody enough of the distinctive characteristics of this style to be considered an exemplary or unique iteration of a vernacular California Ranch. While vernacular architecture can be considered historically significant, the residence at 9580 Rosamond Boulevard is also not a distinctive, rare, or exemplary vernacular California Ranch which is a common type and style throughout rural areas of Southern California. The utilitarian outbuildings are typical wooden utilitarian buildings that do not embody a specific style, nor are they a rare, distinct, or excellent iteration of a rural farm building warranting historical significance for its architecture. PaleoWest also considered whether the subject property may be significant for an association with a master builder or architect; however, no record of a builder or architect was found through property and document search engines of the Kern County Tax Assessor's Office nor through archival research. In summary, the residence of the subject property is not a distinctive or rare example of a vernacular California Ranch residence in rural Southern California and the ancillary barn is also not a unique or rare example of a rural utilitarian barn or farm building. Additionally, neither building clearly represents or a specific period or method of construction, nor are they associated with a significant master architect or builder. As such, 9580 Rosamond Boulevard is recommended not eligible under Criterion 3.

The subject property is a common property type that is unlikely to provide vital information about history or prehistory that is not readily available through historical and archival research. As such, the property is recommended not eligible under CRHR Criterion 4.

The subject property is not within a designated or previously identified historic district. As a very sparsely developed and unincorporated area, the immediate vicinity of the property also lacks architectural cohesion and a defined shared historical narrative to be considered a historic district. Thus, 9580 Rosamond Boulevard is not recommended eligible as a contributor to a CRHR-eligible or listed historic district.

#### **CONTINUATION SHEET**

Page 5 of 6 \*Resource Name or # (Assigned by recorder)
Recorded by: \_Emma Keethler Date:

Primary # HRI# Trinomial

9580 Rosamond Boulevard

April 23, 2022

□ Continuation □ Update



Photo 2. Property overview facing south.




Photo 3. Property overview facing southeast.

State of California — The Resources Agency	Primary
DEPARTMENT OF PARKS AND RECREATION	HRI
LOCATION MAP	Trinomial

**Page** 6 **of** 6 **Resource Name or #:** 374-042-07 **Scale:** 1:24,000

**Date:** 2022

Map Name: Little Buttes, Ca (1975) 7.5' USGS Quad.



State of California — The	Resources Agency	Primary #	
DEPARTMENT OF PARK	S AND RECREATION	HRI#	
<b>LOCATION MAP</b>		Trinomial	
Page 3 of	*Resource Name or # (A	ssigned by recorder)	
*Map Name:	*Scale:	*Date of Map:	

### PRIMARY RECORD

Primary # HRI # Trinomial

**NRHP Status Code** 

Other Listings Review Code

Listings v Code Poviewer

	Review Code	R	eviewer		Date	
Page 1 of 6 P1. Other Identifier:	*Resourc	ce Name or #:	9009 Rosan	ond Boulevard		
*P2. Location:	Not for Publication ⊠	Unrestricted				
*a. County: Kern		and (P	2c, P2e, and P2b c	r P2d. Attach a Location Map as	necessary.)	
*b. USGS 7.5' Quad L	ittle Buttes, CA Date amond Boulevard	1965 <b>T</b> City	9N R 1	SE ¼ of SE of	<b>Sec</b> 18 Zip	<b>S.B.B.M.</b> 93560
d. UTM: (give more than one for	or large and/or linear resources)	Zone 11N	3819	63 mE/	3858709	mN;
e. Other Locational Data:	(e.g. parcel#, directions to resou	urce, elevation, etc.	.) APN 252	352-33		
*P3a. Description: (Desc	cribe resource and its major	elements. Includ	de design, materi	als, condition, alterations, siz	e, setting, and b	oundaries)
The subject property is or residence) constructed in use, and a secondary re Avenue to the east. Lan plantings of trees along the shaped plan, a cross-gal windows with decorative and an open porch with vorofs near the main resisoutheast corner of the windows, and an irregular	1959, two concrete blocksidence constructed c. 2 dscaping consists of name southern property bord ble composite shingle rowood shutters, and yellowinyl-clad support columnidence. A rectangular plearcel. The gas station	ck ancillary build	ildings of unknoperty is accessubs, and grasseast of the resion masonry chincrete block externo ancillary corommercial bund brick vener	own use, a one-story combible from Rosamond Bouses growing freely across dence. The 1,237 squareney on the west façade, rior walls. The south faça acrete block outbuildings vilding, that once operate or cladding, metal securi	nmercial buildinulevard to the sthe property foot main resid, faux dividedde features the with low-pitch stars a gas stars screen cover	ng that is not in south and 90th with windbreak dence has an L-lite vinyl sliding a main entrance side-gable metal tation, is at the ered doors and
P3b. Resource Attribute P4. Resources Present: P5a. Photograph or Draw	Building ☐ Structure	e Object	Site Dist	P5b. Description of F	Other (Iso	e, accession #)
A Toward	Show Miles			Photo 1. Property over		
				*P7. Owner and Addresses Luis Vargas TR, Gloria Family Trust 9009 Rosamond Bould  *P8. Recorded by: (N Emma Keethler, M.A. Evan Mills, M.A., RPA PaleoWest, LLC.  571 S. Ivy Avenue, Mo	ed/Age and So istoric	ond, CA 93560 and address)
1740 0 - 7 (7	1 \ 1 \			*P9. Date Recorded:	April 24, 202	2
P10. Survey Type: (Desc			-			
A-CAES Project,	. Historic Resources Eva , Kern County, California	<i>luation Report,</i> (2021). Prepar	Addendum to: ed for Golder A		•	-
*Attachments: ☐ NONE Record ☐ Archaeologica ☐ Artifact Record ☐ Ph	al Record 🔲 District Re		lap ⊠ Cor ear Feature Re	ntinuation Sheet 🔲 B cord 🗌 Milling Station	uilding, Struct Record	ure, and Object Rock Art Record

State of California — The Resources Agency DEPARTMENT OF PARKS AND RECREATION Primary # HRI# **BUILDING, STRUCTURE, AND OBJECT RECORD** 

,	•				
Page 2 of 6	*NRHP Stat	us Code 6Z			
	*Resource Name or # (Assig	ned by recorder)	9009	Rosamond Boulevard	
B1. Historic Name:	N/A				
B2. Common Name:	N/A				
B3. Original Use:	Residential, commercial				
B4. Present Use:	Residential, commercial				
<del>-</del>	le: Vernacular ranch (residence), ut				
	tory: (Construction date, alterations, and date of	· -		tructed 1959 and secondary dwell	
	. The commercial building was constru		<u> </u>		
	the property was altered either with a	n addition or remode	el, but specific	alteration details were not availab	ole or
readily apparent.					
*B7. Moved? ⊠ No 🏾	☐ Yes ☐ Unknown Date: N/A	Origin	nal Location:	N/A	
*B8. Related Features	: Miscellaneous ancillary buildings (	(2), secondary reside	ence		
B9a. Architect: Unkn		b. Builder: Un	known		•
*B10. Significance: Th	eme		rea:		
Davied of Cinnificance	Duan		esidential,	Amplicable Cuitaria: N/A	
Period of Significance	-	, ,,	ommerical	Applicable Criteria: N/A	
,	n terms of historical or architectural context Springs was sold multiple times betw	•		• • • • • • • • • • • • • • • • • • • •	
but the growth of the a Agriculture in Willow S	uch of the twentieth century (Tipton 1 erospace industry has been a major of prings and its immediate surrounding 17-18, Dunne 2016, Tipton 1988, Gree	change to the econg area has remained	omic landsca d a steady ye	pe of the region in the twentieth of	century.
				(continued on page	3)
B11. Additional Resour	ce Attributes: (List attributes and codes)	HP4. Ancilla	ary building		
*B12. References:					
See page 3			(Sketc	h Map with north arrow required.)	
		100	(0.1010	map	
*B14. Evaluator: *Date of Evaluation:	Emma Keethler, M.A., PaleoWest April 23, 2022	825258753	123:523 114:35:23	222-222-222 (17-222-222)  Decreases 222 (17-222-222)  Decreases 223 (17-222-222)  Decreases 223 (17-222-222)  Decreases 223 (17-222-222)  Decreases 223 (17-222-222)	252-3 <u>.</u>
/This co.	ace reserved for official comments.)	88988	255352	25255253 25255253 25255253	25743
(This spa	ace reserved for official confinents.)				



State of California — The Resources Agency DEPARTMENT OF PARKS AND RECREATION CONTINUATION SHEET

Primary # HRI# Trinomial

	SATION OTILL!		Tillolliai	
Page 3 of 6	*Resource Name or # (Assigned by r	ecorder)	9009 Rosamond Boulevard	
Recorded by:	Emma Keethler	Date:	April 25, 2022	
				□ Continuation □ Update

#### \*B10. Significance: (continued)

Although Willow Springs remained predominantly unchanged during much of the twentieth century, two new developments were completed nearby during this period that affected the settlement. Muroc Army Air Field was established approximately 15 miles east of Willow Springs and Rosamond. The base, which would later become Edwards Air Force Base (EAFB), opened in 1932 and helped to bring more traffic to the Willow Springs area despite the loss of its main draws for long-range travelers and local visitors. In subsequent years EAFB attracted settlers and investment in infrastructure, providing an economic boon to the region; however, central Rosamond and Lancaster saw the greatest economic benefits and population growth (Tipton 1988; OHP 2021). Due to the population boom during the 1930s, the demand for reliable infrastructure increased. Much like other parts of the United States, the Willow Springs area needed electricity in order to grow and thrive. Due to this country-wide demand, President Roosevelt signed the Rural Electrification Act (REA) into law in 1936 (Barnes 2007). The Willow Springs area received electricity shortly after the REA was enacted.

In 1953, the Willow Springs International Raceway opened approximately 1.25 miles west of Willow Springs. At the time, there was little residential or commercial development around Willow Springs or the racetrack, save for a few farms that had installed irrigation equipment and a few small desert homesteaders. During the 1960s, a series of new grided streets were cut in the area around Willow Spring and the raceway, apparently in anticipation for increased residential growth. Ultimately, very few residences were built, the majority of which are centered in a small area in the Project area bound by Irone Avenue, Melody Lane, 145<sup>th</sup> Street W and 140<sup>th</sup> Street West and were constructed between 1960 and 1965. New residences built during this period were primarily single-story single-family vernacular residences on parcels of five acres or less. Although most of these residences are devoid of a particular recognizable architectural style, they reflect common materials and basic forms used throughout Southern California, giving many a distinct rural vernacular Californian appearance commonly identified in similar communities (UCSB 1952a, 1952b; HistoricAerials.com 1959, 1963; Kern County Recorder 1960).

#### \*B12. References:

Barnes, D.F.

2007. The Challenge of Rural Electrification: Strategies for Developing Countries. RFF Press, Washington D.C.

#### California Department of Transportation (Caltrans)

2007 A Historical Context and Archaeological Research Design for Agricultural Properties in California. Division of Environmental Analysis, Sacramento, California.

#### Dunne, Kerry

2016 "Boomtimes Again: Twentieth-Century Mining in the Mojave Desert," Primary Source Sets, Digital Public Library of America, Massachusetts. https://dp.la/primary-source-sets/boomtimes-again-twentieth-century-mining-in-the-mojave-desert, accessed April 2022.

#### Greene, Andry and Albert Knight

1992 "P-15-000129 Supplement, Trinomial CA\_KER-129), California Landmark #130 Willow Springs," Western Mojave Survey Association, North Hollywood, California.

#### HistoricAerials.com

1959 Willow Springs, CA. Aerial imagery.1963 Willow Springs, CA. Aerial imagery.

#### Kern County Recorder

1960 Tract No. 2355 [map]. Record of Survey Book 7, Page 191.

#### Office of Historic Preservation (OHP)

2021 "Willow Springs – Historical Landmark." California State Parks, Office of Historic Preservation. Available: https://ohp.parks.ca.gov/ListedResources/Detail/130. Accessed September 2021.

#### Tipton, Karla

1988 "Willow Springs: An Oasis in Antelope Valley" from Antelope Valley Press in The Gold Ledge. Available: https://www.karlatipton.com/portfolio/Antelope-Valley-Press-Willow-Springs-May-1988.pdf. Accessed September 2021.

#### University of Santa Barbara (UCSB) Library

1952a Flight ID ABL-1952, Frame 3K-89. October 12. 1952b Flight ID ABL-1952, Frame 4K-39. October 12.

State of California — The Resources Agency Primary #
DEPARTMENT OF PARKS AND RECREATION HRI#
CONTINUATION SHEET Trinomial

CONTINU	JATION SHEET		Trinomial	
Page 4 of 6	*Resource Name or # (Assigned b	y recorder)	9009 Rosamond Boulevard	
Recorded by:	Emma Keethler	Date:	April 25, 2022	
				□ Continuation □ Update

#### California Register of Historical Resources Eligibility

The subject property at 9009 Rosamond Boulevard (252-352-33) was evaluated for historical significance under California Register of Historical Resources (CRHR) Criteria 1-4.

Under Criterion 1, the subject property was evaluated for an association with significant historical events or broad patterns of history at the local, regional, state, or national level. The property lies within an unincorporated area of the Antelope Valley, a region of the Mojave Desert that has a rich history of American exploration, migration, and settlement unique to the California and the high desert region during the nineteenth and early twentieth centuries. According to the Kern County Assessor's Office records, the residence was constructed circa 1959, which is well past the period for settlement at the regional (Antelope Valley), state (California), or local level. PaleoWest also considered whether 9009 Rosamond Boulevard may be significant for an association with the theme of Community Development of the Antelope Valley, 1918-1975 and the sub-theme of Rural Residential Development of the valley. Although the residence may date to the period of significance for the theme and sub-theme, the subject property is not a rare, unique, or exemplary example of a property associated with twentieth century community development and rural residential development of the Antelope Valley. It does provide a recognizable representation of broad patterns of residential development in the valley. Additionally, the property is within an unincorporated area of Kern County and the Antelope Valley that does not have a strong cohesive pattern of community history that would include the property's period of construction for which it might be considered historically significant. The property is near the communities of Willow Springs and Rosamond but lacks an immediate connection with the development of these communities. In summary, no direct associations between 9009 Rosamond Boulevard and historically significant events or broad patterns of history at the local, region, state, or national level could be established. As such, the subject property is recommended not eligible under CRHR Criterion 1.

Research was conducted to determine if the subject property is significant under Criterion 2 for associations with the lives of historically important persons who have made contributions to local, state, or national history. No direct connection to historically important individuals could be identified through historical and archival research of 9668 Rosamond Boulevard. Individuals found to be associated with the property through archival research include Ronald Smillie, Gilberto Navarez, Vicky Gale Carrer, Dixie Noel, and Douglas Arnold Middleton. No information was uncovered to confirm these individuals resided at 9009 Rosamond Boulevard during its historic period and research did not suggest the identified individuals made important contributions to history. Historically important persons such as explorers Pedro Fages, Joseph Walker, and John C. Frémont are known to have traveled through the area and to have stopped at nearby Willow Springs, but these events happened well before the construction of the extant buildings on the subject property. Therefore, there is no direct correlation between known significant historical figures and the property. As 9009 Rosamond Boulevard does not appear to be illustrative of the accomplishments of historically important persons within a local, state, or national historical context, the property is recommended not eligible under Criterion 2.

To evaluate the subject property under Criterion 3, PaleoWest considered whether it embodies distinctive characteristics of a type, period, or method of construction and whether it represents the work of a master architect or possesses high artistic value. The residence at 9009 Rosamond Boulevard is a vernacular rendition of the California Ranch style which is very common to rural areas of Southern California. As an unadorned example of the California Ranch style, the property residence does not embody enough of the distinctive characteristics of this style to be considered an exemplary or unique iteration of a California Ranch. While vernacular architecture can be considered historically significant, the residence at 9009 Rosamond Boulevard is also not a distinctive, rare, or exemplary vernacular California Ranch which is a common type and style throughout rural areas of Southern California. The utilitarian outbuildings are typical wooden utilitarian buildings that do not embody a specific style, nor are they a rare, distinct, or excellent iteration of a rural farm building warranting historical significance for its architecture. PaleoWest also considered whether the subject property may be significant for an association with a master builder or architect; however, no record of a builder or architect was found through property and document search engines of the Kern County Tax Assessor's Office nor through archival research. In summary, the residence of the subject property is not a distinctive or rare example of a vernacular California Ranch residence in rural Southern California and the modern commercial building (gas station) on the property is not an exemplary sample of commercial design or construction. It should also be noted that there are two additional age eligible utilitarian outbuildings located on the property which are of a vernacular masonry design which are not exemplary samples of vernacular ancillary building design. Additionally, none of the buildings clearly represents or a specific period or method of construction, nor are they associated with a significant master architect or builder. As such, 9009 Rosamond Boulevard is recommended not eligible under Criterion 3.

The subject property is a common property type that is unlikely to provide vital information about history or prehistory that is not readily available through historical and archival research. As such, the property is recommended not eligible under CRHR Criterion 4.

The subject property is not within a designated or previously identified historic district. As a very sparsely developed and unincorporated area, the immediate vicinity of the property also lacks architectural cohesion and a defined shared historical narrative to be considered a historic district. Thus, 9009 Rosamond Boulevard is not recommended eligible as a contributor to a CRHR-eligible or listed historic district.

#### **CONTINUATION SHEET**

Page 5 of 6

\*Resource Name or # (Assigned by recorder)

Recorded by: Emma Keethler Date:

Primary # HRI# Trinomial

9009 Rosamond Boulevard

April 25, 2022

□ Continuation □ Update



Photo 1. South (primary) façade of main residence, view facing north.




Photo 2. Overview of ancillary buildings, facing northeast.

State of California — The Resources Agency
DEPARTMENT OF PARKS AND RECREATION
I OCATION MAP

Primary HRI Trinomial

**Scale:** 1:24,000 Page 6 of 6**Resource Name or #: 252-352-33** 

Map Name: Little Buttes, Ca (1975) 7.5' USGS Quad.



# PRIMARY RECORD

Primary # HRI# **Trinomial** 

**NRHP Status Code** 

Other Listings Review Code


Reviewer

	Review Code	Rev	iewer		Date	
Page 1 of 7	*Resource Name	or #:	3045 90th Sti	reet West		
_	ligh Desert Cellars	_				
*P2. Location:	for Publication ⊠ Unrestric	ted				
*a. County: Kern	a	<b>nd</b> (P2c,	P2e, and P2b or	P2d. Attach a Location Map as r	necessary.)	
b. USGS 7.5' Quad Little I	Buttes <b>Date</b> 1965	T 9	9N <b>R</b> 13	W SE ¼ of SE ¼ of	<b>Sec</b> 16	S.B.B.M.
c. Address 3045 90th Str	eet West	City	Rosamond		Zip	93560
d. UTM: (give more than one for larg	ge and/or linear resources) Zone	11N	3819	59 mE/	3858761	mN;
e. Other Locational Data: (e.g.	parcel#, directions to resource, elevation	on, etc.)	APN 252-3	352-32		
*P3a. Description: (Describe	resource and its major elements.	Include	design, materia	ls, condition, alterations, size	e, setting, and b	ooundaries)
building) on a 9.68-acre parce feet, and is surrounded by an north and west of the buildi surrounded by separate chair has a rectangular plan, a flat be doors on the east (primary) fa and glass doors a recessed a south and north façades are buildings along the north pro	20th Street West) is comprise el accessible from the east via asphalt parking lot to the east ing partially lined with trees. In-link fencing, excluding the east ouilt-up roof, stucco cladding, a açade. A narrow flat roofed bliappearance. The windows and absent of windows or second operty boundary and set backappear to be small rectangular.	a 90th Set and set and set astern center and a waited doors lary entite approximation.	Street West outh. Other la es, trees, and ommercially-call of steel-fra de projection of the east fa ry doors. Aeri kimately 800	The building was constructed and scape features included shrubs grow freely the developed portion of the pared fixed windows and two extends from the east factorial photos from 2020 should be a constructed.	cted in 1956, a a grass fend oughout the property. The wo steel-fram acade, giving tel exterior so w at least tw	is 3,050 square ced-in lawn area parcel which is subject building e glass entrance the window wall ecurity bars. The o small ancillary
	List attributes and codes) HP					
	Building 🗌 Structure 🗌 Obje			ct  Element of District	Other (Iso	olates, etc.)
P5a. Photograph or Drawing (	Photograph required for buildings, stru	ctures, an	d objects.)	İ		
	Control of the Contro			P5b. Description of P		
	23		1 1	Photo 1. Property over	view racing no	ortnwest
	A STATE OF THE STA			August 24, 2021		
				*P6. Date Constructe	2 has and\h	ource:
	and the while				storic    Bot	
The same of the sa	MICHIGAN AND AND AND AND AND AND AND AND AND A	1.		1956	Storic 🗀 Boi	,11
AL PROPERTY OF THE PARTY OF THE	Han	THE		Kern County Tax Asses	ssor	
The latest	The Part of the		gh Douert Collers			
			havez Vineyarda	*P7. Owner and Addre	ess:	
				Luis Vargas Trust	D	04.00500
				3045 90th Street West,	, Rosamona,	CA 93560
				* <b>P8. Recorded by:</b> (Na Lisa C. Demarais, M.A.		
				Evan Mills, M.A., RPA	-	
The same of the sa				PaleoWest, LLC.		
				571 S. Ivy Avenue, Mor	nrovia, CA 91	016
			Walter Town	*P9. Date Recorded:	April 26, 202	22
P10. Survey Type: (Describe	) Intensive, pedestrian rigi	nt-of-wa	V	I		
• • • •	urvey report and other sources, or					
2022 PaleoWest, LLC. <i>Hi</i> s	storic Resources Evaluation Rern County, California (2021). P	eport, A	ddendum to: (		nical Report fo	or the Hydrostor
*Attachments:  NONE Record Archaeol Art Record Artifa		cord	⊠ Continuat □ Linear Fea □ Other (List)	ature Record	Structure, an Station Reco	

# **BUILDING, STRUCTURE, AND OBJECT RECORD**

Page 2 of 7	*NRHP Status Code	6Z		
	*Resource Name or # (Assigned by re	ecorder)	3045 90	Oth Street West
B1. Historic Name:	N/A	ŕ		
B2. Common Name:	High Desert Cellars			
B3. Original Use:	Commercial			
B4. Present Use:	Commercial			
*B5. Architectural Styl	e: Vernacular Spanish Revival			
	tory: (Construction date, alterations, and date of alterations			lo building permits to indicate there
	ial alterations, though the steel frame glass win	dow wa	lls on the primary	façade appear to be a recent
alteration.				
*B7. Moved? ⊠ No ☐ *B8. Related Features	<del></del>	Ori	ginal Location:	N/A
B9a. Architect: Unkn	own b. Buil	lder:	Unknown	
*B10. Significance: Th	eme		Area:	
Period of Significance	: Property Ty	pe:	Commercial	Applicable Criteria: N/A
(Discuss importance in	n terms of historical or architectural context as defined	d by ther	ne, period, and geog	graphic scope. Also address integrity.)
at risk of running dry. D was slow throughout m but the growth of the a Agriculture in Willow S	nt survey of Willow Springs indicated that the si ue to these changes, development and populat uch of the twentieth century (Tipton 1988; OHF erospace industry has been a major change to prings and its immediate surrounding area had 17-18, Dunne 2016, Tipton 1988, Greene and K	tion gro 2021) the eds remai	wth in Willow Spri Agriculture rema onomic landscape ned a steady yet	ngs and its immediate surrounding area lined a primary industry in Kern County, e of the region in the twentieth century.
				(continued on page 3)
B11. Additional Resour	ce Attributes: (List attributes and codes)	N/A		
*B12. References:				
See page 4				
*B14. Evaluator:	Caity Chandler		(Sketch	Map with north arrow required.)
*Date of Evaluation:	April 26, 2022	_	(OKetOII	map mai notal allow required.)
21 21 <b>213311</b>		-	352-23 352-23	EL E

(This space reserved for official comments.)



State of California — The Resources Agency DEPARTMENT OF PARKS AND RECREATION	Primary # HRI#
CONTINUATION SHEET	Trinomial

CONTIN	DATION SHEET		Trinomiai	
Page 3 of 7	*Resource Name or # (Assigned b	y recorder)	3045 90th Street West	
Recorded by:	Lisa Demarais and Caity Chandler	Date:	April 26, 2022	
				□ Continuation □ Update

#### \*B10. Significance: (continued)

Although Willow Springs remained predominantly unchanged during much of the twentieth century, two new developments were completed nearby during this period that affected the settlement. Muroc Army Air Field was established approximately 15 miles east of Willow Springs and Rosamond. The base, which would later become Edwards Air Force Base (EAFB), opened in 1932 and helped to bring more traffic to the Willow Springs area despite the loss of its main draws for long-range travelers and local visitors. In subsequent years EAFB attracted settlers and investment in infrastructure, providing an economic boon to the region; however, central Rosamond and Lancaster saw the greatest economic benefits and population growth (Tipton 1988; OHP 2021). Due to the population boom during the 1930s, the demand for reliable infrastructure increased. Much like other parts of the United States, the Willow Springs area needed electricity in order to grow and thrive. Due to this country-wide demand, President Roosevelt signed the Rural Electrification Act (REA) into law in 1936 (Barnes 2007). The Willow Springs area received electricity shortly after the REA was enacted.

In 1953, the Willow Springs International Raceway opened approximately 1.25 miles west of Willow Springs. At the time, there was little residential or commercial development around Willow Springs or the racetrack, save for a few farms that had installed irrigation equipment and a few small desert homesteaders. During the 1960s, a series of new grided streets were cut in the area around Willow Spring and the raceway, apparently in anticipation for increased residential growth. Ultimately, very few residences were built, the majority of which are centered in a small area in the Project area bound by Irone Avenue, Melody Lane, 145<sup>th</sup> Street W and 140<sup>th</sup> Street West and were constructed between 1960 and 1965. New residences built during this period were primarily single-story single-family vernacular residences on parcels of five acres or less. Although most of these residences are devoid of a particular recognizable architectural style, they reflect common materials and basic forms used throughout Southern California, giving many a distinct rural vernacular Californian appearance commonly identified in similar communities (UCSB 1952a, 1952b; HistoricAerials.com 1959, 1963; Kern County Recorder 1960).

#### California Register of Historical Resources of Eligibility

The subject property at 3045 90<sup>th</sup> Street West (252-352-32) was evaluated for historical significance under California Register of Historical Resources (CRHR) Criteria 1-4.

Under Criterion 1, the subject property was evaluated for an association with significant historical events or broad patterns of history at the local, regional, state, or national level. The property lies just outside of Willow Springs a former resort community in Southern California. PaleoWest also considered whether 3025 90<sup>th</sup> Street West may be significant for an association with the theme of Community Development. Although this commercial property may date to the period of significance for the theme, the subject property is not a rare, unique, or exemplary example of a property associated with twentieth century community development. The property is near the communities of Willow Springs and Rosamond but lacks an immediate connection with the development of these communities. Thus, there is no direct association between 3045 90<sup>th</sup> Street West and historically significant events or broad patterns of history at the local, region, state, or national level could be established. As such, the subject property is recommended not eligible under CRHR Criterion 1.

Under Criterion 2, the subject property was evaluated for associations with the lives of historically important persons who have made contributions to local, state, or national history. No direct connection to historically important individuals could be identified. Therefore, there is no direct correlation between any known significant historical figures and the property. 3045 90<sup>th</sup> Street West is recommended not eligible under Criterion 2.

To evaluate the subject property under Criterion 3, PaleoWest considered whether it embodies distinctive characteristics of a type, period, or method of construction and whether it represents the work of a master architect or possesses high artistic value. The building at 3045 90<sup>th</sup> Street West is a one-story vernacular Spanish Revival commercial building, which is very common to Southern California. As an unadorned example of the Spanish Revival style, this commercial property does not embody enough of the distinctive characteristics of this style to be considered exemplary or unique. While vernacular architecture can be considered historically significant, the commercial building at 3045 90<sup>th</sup> Street West is not a distinctive, rare, or exemplary vernacular Spanish Revival. The building does not clearly represent a specific period or method of construction, nor is it associated with a significant master architect or builder. As such, 3045 90<sup>th</sup> Street West is recommended not eligible under Criterion 3.

The subject property at 3045 90<sup>th</sup> Street West is a common property type that is unlikely to provide vital information about history or prehistory that is not readily available through historical and archival research. As such, the property is recommended not eligible under CRHR Criterion 4.

# State of California — The Resources Agency DEPARTMENT OF PARKS AND RECREATION CONTINUATION SHEET

Primary #
HRI#
Trinomial

9911111	STATION OFFICE		Tillolliai	
Page 4 of 7	*Resource Name or # (Assigned b	y recorder)	4040 Manly Road	
Recorded by:	Lisa Demarais	Date:	May 3, 2022	
				□ Continuation □ Update

\*B12. References: (continued)

Barnes, D.F.

2007. The Challenge of Rural Electrification: Strategies for Developing Countries. RFF Press, Washington D.C.

California Department of Transportation (Caltrans)

2007 A Historical Context and Archaeological Research Design for Agricultural Properties in California. Division of Environmental Analysis, Sacramento, California.

Dunne, Kerry

2016 "Boomtimes Again: Twentieth-Century Mining in the Mojave Desert," Primary Source Sets, Digital Public Library of America, Massachusetts. https://dp.la/primary-source-sets/boomtimes-again-twentieth-century-mining-in-the-mojave-desert, accessed April 2022.

Greene, Andry and Albert Knight

1992 <sup>"P-15-000129 Supplement, Trinomial CA\_KER-129), California Landmark #130 Willow Springs," Western Mojave Survey Association, North Hollywood, California.</sup>

HistoricAerials.com

1959 Willow Springs, CA. Aerial imagery.1963 Willow Springs, CA. Aerial imagery.

Kern County Recorder

1960 Tract No. 2355 [map]. Record of Survey Book 7, Page 191.

Office of Historic Preservation (OHP)

2021 "Willow Springs – Historical Landmark." California State Parks, Office of Historic Preservation. Available: https://ohp.parks.ca.gov/ListedResources/Detail/130. Accessed September 2021.

Tipton, Karla 1988

"Willow Springs: An Oasis in Antelope Valley" from Antelope Valley Press in The Gold Ledge. Available: <a href="https://www.karlatipton.com/portfolio/Antelope-Valley-Press-Willow-Springs-May-1988.pdf">https://www.karlatipton.com/portfolio/Antelope-Valley-Press-Willow-Springs-May-1988.pdf</a>. Accessed September 2021.

University of Santa Barbara (UCSB) Library

1952a Flight ID ABL-1952, Frame 3K-89. October 12. 1952b Flight ID ABL-1952, Frame 4K-39. October 12.

#### **CONTINUATION SHEET**

Page 5 of 7 \*Resource Name or # (Assigned by recorder)

Recorded by: Lisa Demarais and Caity Chandler Date:

Primary # HRI#

Trinomial

April 26, 2022

3045 90th Street West

□ Continuation □ Update



Photo 2. East (primary) and south façades, view facing northwest.



Photo 3. Partial property overview facing west.

#### **CONTINUATION SHEET**

Page 6 of 7

\*Resource Name or # (Assigned by recorder)

Recorded by: Lisa Demarais and Caity Chandler Date:

Primary # HRI#

Trinomial

3045 90th Street West April 26, 2022

□ Continuation □ Update



Photo 4. North façade, view facing southwest.




Photo 5. East (primary) façade, view facing west.

State of California — The Resources Agency
DEPARTMENT OF PARKS AND RECREATION
I OCATION MAP

Primary HRI Trinomial

**Scale:** 1:24,000 Page 7 of 7**Resource Name or #: 252-352-32** 

Map Name: Little Buttes, Ca (1975) 7.5' USGS Quad.



# **PRIMARY RECORD**

Primary # HRI# **Trinomial** 

**NRHP Status Code** 

Other Listings Review Code

	Review Code	F	Revie	wer	<u> </u>	ate		
Page 1 of 5 P1. Other Identifier:	*Resource I	Name or	#: _	2973 95 <sup>th</sup> S	treet			_
*P2. Location:	t for Publication 🛭 Unr	estricte	d					
*a. County: Kern		and	<b>d</b> (P2c,	P2e, and P2b	or P2d. Attach a Location Map as	necessar	y.)	
*b. USGS 7.5' Quad Little		1965 <b>1</b>	_ '	R	NE 1/4 of NW of	Sec	19	S.B.B.M.
c. Address 2973 95 <sup>th</sup> Stree	et		City	Rosamon	d		Zip	93560
d. UTM: (give more than one for large	and/or linear resources) Zone	e <u>1</u>	11N	381	132 mE/	3858	3641	mN;
e. Other Locational Data: (e.g. p	arcel#, directions to resource, el	evation, etc	c.)	APN 374	-042-08			
*P3a. Description: (Describe re	esource and its major eleme	nts. Inclu	ide des	sign, material	s, condition, alterations, size,	setting,	and bou	ındaries)
The subject property (2973 95 built in 1942. The property is consists of a predominantly cleares growing freely. The resignectangular attic vents beneath divided-lite vinyl sliding window below a roof overhang and with vehicles, and debris but appeadjacent structure is adjoined window and a set of glass viny composite shingle front-gable resignation.	accessible from Rosam ared lawn with varieties dence has a rectangular the gable peaks. There ws, and stucco exterior win a partially enclosed pars to feature at least for the main residence of the design of the student of the main residence of the student of t	ond Bou of plante plan, a is an ado walls. Th orch. Thi our windo by a roo	ulevar ed gra clay dition ne prir is nort ows. of exte ed two	d to the so sses, trees tile side-gal along the w mary entran th façade is The west fa ension from o-door garag	uth and from the west vialong the western façade ble roof with shed extens rest façade which has a loce of the residence is on partially obscured from the açade features an addition the western addition. The lies northeast of the magnification of the magnification is a second to the second to th	a 95th of the r ion at t w pitch the no e right-o n with a e east	Street. esidendhe sou side-garth faça single façade dence a	Landscaping ce, and native ath (rear), and able roof, faux ade, recessed by vegetation, e window. An includes one and features a
FP3b. Resource Attributes: (Li FP4. Resources Present: ⊠ B P5a. Photograph or Drawing (P	uilding	Object [	Site	e Distric	Element of District [ P5b. Description of Ph	oto: (vie	w, date,	accession #)
					Photo 1. Property overvi	ew facii	ng sout	<u>:h</u>
A.					March 28, 2022			
A Aller	, on A	4			<b>*P6. Date Constructed</b> ⊠ Historic □ Prehist 1942	oric _		rce:
		100			Kern County Tax Assess	sor		
					*P7. Owner and Addres			_
		1000	THE REAL PROPERTY.		2973 9th Street, Rosamo	nd, CA	93560	
		-			*P8. Recorded by: (Nan Emma Keethler, M.A.	ne, affilia	ition, an	d address)
	1	J.			Evan Mills, M.A., RPA			
	A L	1			PaleoWest, LLC.			
1					571 S. Ivy Avenue, Mon	rovia, C	A 9101	6
					*P9. Date Recorded:	April 25	, 2022	
*P10. Survey Type: (Describe)	Intensive, pedestriar	right-of-	-way					
		n Report	t, Add	endum to: C	Cultural Resources Technic sociates.	cal Rep	ort for t	the Hydrostor
*Attachments: NONE Record Archaeological Record Artifact Record Photogra	cord District Record		Лар near F	⊠ Conti eature Reco	nuation Sheet ⊠ Bui ord ☐ Milling Station Re	lding, S ecord		re, and Object ock Art Record

State of California — The Resources Agency
DEPARTMENT OF PARKS AND RECREATION
HRI#
BUILDING, STRUCTURE, AND OBJECT RECORD

Page 2 of 5	*NRHF	Status Code	6Z		
	*Resource Name or # (	Assigned by recor	rder)	2973 9	95 <sup>th</sup> Street
B1. Historic Name:	N/A				
B2. Common Name:	N/A				
B3. Original Use:	Residential				
B4. Present Use:	Residential				
*B5. Architectural Sty	le: Vernacular bungalow				
	tory: (Construction date, alterations, and rindows at an unknown date.	I date of alterations)	Constructed	d 1942. \	/isible alterations include installation of
*B7. Moved? ⊠ No [ *B8. Related Features		N/A d garage	Original Lo	cation:	N/A
B9a. Architect:	Unknown	b. Builder	r:	Unkno	own
*B10. Significance: Th	ieme		Area:		
Period of Significance	»:	Property Type:	Reside	ntial	Applicable Criteria: N/A
(Discuss importance i	n terms of historical or architectural of	context as defined by	theme, period	l, and geo	ographic scope. Also address integrity.)
Agriculture in Willow S		inding area has re	emained a st		be of the region in the twentieth century. It small contributor to the industry of the
					(continued on page 3)
B11. Additional Resour	ce Attributes: (List attributes and co	odes) HP4	. Ancillary bu	ilding	
*B12. References:					
See page 3.					
	F		252:152:26	(Sketch	n Map with north arrow required.) 25245225 25245225 252
*B14. Evaluator:	Emma Keethler, M.A.		osamond Blvd		Rosamond Blvd Rosamond Blvd
*Date of Evaluation:	April 25, 2022		8741042407	374042-07	574-042-03 574-042-03 574-042-03

(This space reserved for official comments.)



	The Resources Agency RKS AND RECREATION	Primary # HRI#		
CONTINUATIO	ON SHEET	Trinomial		
Daga 2 of F	*Descripe Name of # (Assigned by recorder)	2973 95th Street		

CONTIN	DATION OTILL!		Timomai	
Page 3 of 5	*Resource Name or # (Assigned by rec	order)	2973 95 <sup>th</sup> Street	
Recorded by:	Emma Keethler Da	ate:	April 25, 2022	
				□ Continuation □ Update

#### \*B10. Significance: (continued)

Although Willow Springs remained predominantly unchanged during much of the twentieth century, two new developments were completed nearby during this period that affected the settlement. Muroc Army Air Field was established approximately 15 miles east of Willow Springs and Rosamond. The base, which would later become Edwards Air Force Base (EAFB), opened in 1932 and helped to bring more traffic to the Willow Springs area despite the loss of its main draws for long-range travelers and local visitors. In subsequent years EAFB attracted settlers and investment in infrastructure, providing an economic boon to the region; however, central Rosamond and Lancaster saw the greatest economic benefits and population growth (Tipton 1988; OHP 2021). Due to the population boom during the 1930s, the demand for reliable infrastructure increased. Much like other parts of the United States, the Willow Springs area needed electricity in order to grow and thrive. Due to this country-wide demand, President Roosevelt signed the Rural Electrification Act (REA) into law in 1936 (Barnes 2007). The Willow Springs area received electricity shortly after the REA was enacted.

In 1953, the Willow Springs International Raceway opened approximately 1.25 miles west of Willow Springs. At the time, there was little residential or commercial development around Willow Springs or the racetrack, save for a few farms that had installed irrigation equipment and a few small desert homesteaders. During the 1960s, a series of new grided streets were cut in the area around Willow Spring and the raceway, apparently in anticipation for increased residential growth. Ultimately, very few residences were built, the majority of which are centered in a small area in the Project area bound by Irone Avenue, Melody Lane, 145<sup>th</sup> Street W and 140<sup>th</sup> Street West and were constructed between 1960 and 1965. New residences built during this period were primarily single-story single-family vernacular residences on parcels of five acres or less. Although most of these residences are devoid of a particular recognizable architectural style, they reflect common materials and basic forms used throughout Southern California, giving many a distinct rural vernacular Californian appearance commonly identified in similar communities (UCSB 1952a, 1952b; HistoricAerials.com 1959, 1963; Kern County Recorder 1960).

#### \*B12. References:

Barnes, D.F.

2007. The Challenge of Rural Electrification: Strategies for Developing Countries. RFF Press, Washington D.C.

California Department of Transportation (Caltrans)

A Historical Context and Archaeological Research Design for Agricultural Properties in California. Division of Environmental Analysis, Sacramento, California.

Dunne, Kerry

2016 "Boomtimes Again: Twentieth-Century Mining in the Mojave Desert," Primary Source Sets, Digital Public Library of America, Massachusetts. https://dp.la/primary-source-sets/boomtimes-again-twentieth-century-mining-in-the-mojave-desert, accessed April 2022.

Greene, Andry and Albert Knight

1992 <sup>\*</sup>P-15-000129 Supplement, Trinomial CA\_KER-129), California Landmark #130 Willow Springs," Western Mojave Survey Association, North Hollywood, California.

HistoricAerials.com

1959 Willow Springs, CA. Aerial imagery.1963 Willow Springs, CA. Aerial imagery.

Kern County Recorder

1960 Tract No. 2355 [map]. Record of Survey Book 7, Page 191.

Office of Historic Preservation (OHP)

2021 "Willow Springs – Historical Landmark." California State Parks, Office of Historic Preservation. Available: https://ohp.parks.ca.gov/ListedResources/Detail/130. Accessed September 2021.

Tipton, Karla

1988 "Willow Springs: An Oasis in Antelope Valley" from Antelope Valley Press in The Gold Ledge. Available: https://www.karlatipton.com/portfolio/Antelope-Valley-Press-Willow-Springs-May-1988.pdf, Accessed September 2021.

University of Santa Barbara (UCSB) Library

1952a Flight ID ABL-1952, Frame 3K-89. October 12.1952b Flight ID ABL-1952, Frame 4K-39. October 12.

State of California — The Resources Agency DEPARTMENT OF PARKS AND RECREATION CONTINUATION SHEET		Primary # HRI#					
			Trinomial				
Page 4 of 5	*Resource Name or # (Assigned by red	corder)	2973 95th Street				
Recorded by:	Emma Keethler	Date:	April 25, 2022				
		•		□ Continuation □ Update			

#### California Register of Historical Resources Eligibility

The subject property at 2973 95<sup>th</sup> Street (374-042-08) was evaluated for historical significance under California Register of Historical Resources (CRHR) Criteria 1-4.

Under Criterion 1, the subject property was evaluated for an association with significant historical events or broad patterns of history at the local, regional, state, or national level. The property lies within an unincorporated area of the Antelope Valley, a region of the Mojave Desert that has a rich history of American exploration, migration, and settlement unique to the California and the high desert region during the nineteenth and early twentieth centuries. According to the Kern County Assessor's Office records, the residence was constructed circa 1942, which is well past the period for settlement at the regional (Antelope Valley), state (California), or local level. PaleoWest also considered whether 2973 95th Street may be significant for an association with the theme of Community Development of the Antelope Valley, 1918-1975 and the sub-theme of Rural Residential Development of the valley. Although the residence may date to the period of significance for the theme and sub-theme, the subject property is not a rare, unique, or exemplary example of a property associated with twentieth century community development and rural residential development of the Antelope Valley. It does provide a recognizable representation of broad patterns of residential development in the valley. Additionally, the property is within an unincorporated area of Kern County and the Antelope Valley that does not have a strong cohesive pattern of community history that would include the property's period of construction for which it might be considered historically significant. The property is near the communities of Willow Springs and Rosamond but lacks an immediate connection with the development of these communities. In summary, no direct associations between 2973 95th Street and historically significant events or broad patterns of history at the local, region, state, or national level could be established. As such, the subject property is recommended not eligible under CRHR Criterion 1.

Research was conducted to determine if the subject property is significant under Criterion 2 for associations with the lives of historically important persons who have made contributions to local, state, or national history. No direct connection to historically important individuals could be identified through historical and archival research of 2973 95th Street. Individuals found to be associated with the property through archival research include Ronald Smillie, Gilberto Navarez, Vicky Gale Carrer, Dixie Noel, and Douglas Arnold Middleton. No information was uncovered to confirm these individuals resided at 2973 95th Street during its historic period and research did not suggest the identified individuals made important contributions to history. Historically important persons such as explorers Pedro Fages, Joseph Walker, and John C. Frémont are known to have traveled through the area and to have stopped at nearby Willow Springs, but these events happened well before the construction of the extant buildings on the subject property. Therefore, there is no direct correlation between known significant historical figures and the property. As 2973 95th Street does not appear to be illustrative of the accomplishments of historically important persons within a local, state, or national historical context, the property is recommended not eligible under Criterion 2.

To evaluate the subject property under Criterion 3, PaleoWest considered whether it embodies distinctive characteristics of a type, period, or method of construction and whether it represents the work of a master architect or possesses high artistic value. The residence and detached garage building at 2973 95th Street is a vernacular rendition of the California Ranch stye which is very common to rural areas of Southern California. As an unadorned example of the California Ranch style, the property residence does not embody enough of the distinctive characteristics of this style to be considered an exemplary or unique iteration of a California Ranch. While vernacular architecture can be considered historically significant, the residence at 2973 95th Street is also not a distinctive, rare, or exemplary vernacular California Ranch which is a common type and style throughout rural areas of Southern California. The detached garage and utilitarian outbuilding are typical wooden utilitarian buildings that do not embody a specific style, nor are they a rare, distinct, or excellent iteration of a rural farm building warranting historical significance for its architecture. PaleoWest also considered whether the subject property may be significant for an association with a master builder or architect; however, no record of a builder or architect was found through property and document search engines of the Kern County Tax Assessor's Office nor through archival research. In summary, the residence of the subject property is not a distinctive or rare example of a vernacular California Ranch residence in rural Southern California and the ancillary barn is also not a unique or rare example of a rural utilitarian barn or farm building. Additionally, neither building clearly represents or a specific period or method of construction, nor are they associated with a significant master architect or builder. As such, 2973 95th Street is recommended not eligible under Criterion 3.

The subject property is a common property type that is unlikely to provide vital information about history or prehistory that is not readily available through historical and archival research. As such, the property is recommended not eligible under CRHR Criterion 4.

The subject property is not within a designated or previously identified historic district. As a very sparsely developed and unincorporated area, the immediate vicinity of the property also lacks architectural cohesion and a defined shared historical narrative to be considered a historic district. Thus, 2973 95th Street is not recommended eliqible as a contributor to a CRHR-eliqible or listed historic district.

State of California — The Resources Agency DEPARTMENT OF PARKS AND RECREATION	Primary HRI
LOCATION MAP	Trinomial

**Page** 5 **of** 5 **Scale:** 1:24,000 **Resource Name or #:** 374-042-08

Map Name: Little Buttes, Ca (1975) 7.5' USGS Quad.



# PRIMARY RECORD

Primary # HRI # Trinomial

NRHP Status Code

Other Listings Review Code


	Review Code	Reviewei	•		Date	
Page 1 of 6	*Resource Na	me or #:2860	W. 100th Stre	eet		
P1. Other Identifier:  *P2. Location:	or Publication 🛭 Unres	tricted				
*a. County: Kern	or Publication \( \triangle \)		nd D2h or D2d	Attach a Location Map as	nocossany)	
*b. USGS 7.5' Quad Little Buc. Address 2860 W. 100 <sup>th</sup> St		65 <b>T</b> 9N	<b>R</b> 13' amond	•	• •	19 <b>S.B.B.M</b> 93560
d. UTM: (give more than one for large e. Other Locational Data: (e.g. pa			80321 N 374-041-0	mE/	3857171	mN;
*P3a. Description: (Describe re		· · · · —			ze setting and h	ooundaries)
The subject property (2860 W. acre parcel. The 960 square-for Street. Landscaping consists of as well as along another windblue a side-gable asphalt shingle root simple support columns, one-benefit primary entrance is a single endoor. The entrance is flanked by steps and five windows. The immediately south of the main freestanding flat-roofed shelter and street	not residence was constructurally occurring grass eak planting of trees aloof with rectangular attic vy-one vinyl sliding windoutry-door on the north fay two windows on each swest façade is not visib residence and an ancill	ructed in 1940, see and shrubs wing the western by tents beneath earns and faux divided accessed with the south falle from the rightary building is so	and the propith a planting order of the ch gable, a sided-lite viny is the cover açade feature of way. A putheast of the coverties of way.	perty is accessible of trees along the parcel. The resident shed-pent roof extern sliding windows, and extern porch and es a single secondar gazebo with a aspect main residence.	from the west east of the resi ce features a resion covered and stucco ex concrete step ry entrance do halt shingle p Southeast of	via West 100th idential structure rectangular plan, entry porch with terior walls. The is leading to the for with concrete the yramidal roof is
P3b. Resource Attributes: (List P4. Resources Present: ⊠ But P5a. Photograph or Drawing (Pt	uilding Structure 0	• —	District ts.)	_	_ `	,
				<b>ib. Description of I</b> noto 1. Property ove		
			Au	igust 30, 2021		
			19 Ke	40 rn County Tax Asses	istoric Bot	
THE RESERVE AND THE				<ul> <li>Owner and Addr strick Ladd</li> </ul>	ess:	
			_	60 W. 100 <sup>th</sup> Street,	Rosamond, C	A 93560
			*P8	. Recorded by: (Nonma Keethler, M.A.	·	
			Ev	an Mills, M.A., RPA	1	
	And the felt of the same		- 127 -	leoWest, LLC.		
2000年11日			57	1 S. Ivy Avenue, Mo	onrovia, CA 91	016
			*P9	. Date Recorded:	April 23, 202	2
*P10. Survey Type: (Describe)	Intensive, pedestrian	right-of-way				
	rey report and other sources ric Resources Evaluation County, California (2021	n Report, Addend			nnical Report fo	or the Hydrostor
	Location Map Sord District Record	Sketch Map  Linear Feat	□ Continuation     □ Co			ture, and Object Rock Art Record

State of California — The Resources Agency Primary #
DEPARTMENT OF PARKS AND RECREATION HRI#

BLIII DING STRUCTURE AND OBJECT RECORD

Page 2 of 6	*!	NRHP Status Code	6Z	
	*Resource Name	or # (Assigned by rece	order)2860 V	V. 100 <sup>th</sup> Street
B1. Historic Name:	N/A			
B2. Common Name:	N/A			
B3. Original Use:	Residential			
B4. Present Use:	Residential			
*B5. Architectural Styl				
	tory: (Construction date, alteratio	· · · · · · · · · · · · · · · · · · ·		was constructed in 1940. There are
			•	the original windows have been
<u>-</u>	. The concrete slab entry po	orch also appears to n	ave been recently repla	aced.
*B7. Moved? ⊠ No ☐ *B8. Related Features		ate: N/A	_ Original Location:	N/A
B9a. Architect: Unkn		b. Builde		
*B10. Significance: Th			Area:	NI/A
Period of Significance		Property Type		_ Applicable Criteria: N/A
(Discuss importance in	n terms of historical or archited	tural context as defined by	by theme, period, and geo	ographic scope. Also address integrity.)
but the growth of the a Agriculture in Willow S	erospace industry has bee	en a major change to t surrounding area has	the economic landscap remained a steady ye	ained a primary industry in Kern County, be of the region in the twentieth century. It small contributor to the industry of the
				(continued on page 3)
B11. Additional Resour	ce Attributes: (List attributes	and codes) HF	P4. Ancillary building	
*B12. References:				
See page 3			(Sketch	n Map with north arrow required.)
*B14. Evaluator:	Emma Keethler		39:051:50	574011·02 574011·03
*Date of Evaluation:	April 23, 2022			
			45.70	Schara Are

(This space reserved for official comments.)



CONTIN	UATION SHEET		Trinomial	
Page 3 of 6	*Resource Name or # (Assigned by re	corder)	2860 W. 100th Street	
Recorded by:	Emma Keethler	Date:	April 23, 2022	
				□ Continuation □ Update

#### \*B10. Significance: (continued)

Although Willow Springs remained predominantly unchanged during much of the twentieth century, two new developments were completed nearby during this period that affected the settlement. Muroc Army Air Field was established approximately 15 miles east of Willow Springs and Rosamond. The base, which would later become Edwards Air Force Base (EAFB), opened in 1932 and helped to bring more traffic to the Willow Springs area despite the loss of its main draws for long-range travelers and local visitors. In subsequent years EAFB attracted settlers and investment in infrastructure, providing an economic boon to the region; however, central Rosamond and Lancaster saw the greatest economic benefits and population growth (Tipton 1988; OHP 2021). Due to the population boom during the 1930s, the demand for reliable infrastructure increased. Much like other parts of the United States, the Willow Springs area needed electricity in order to grow and thrive. Due to this country-wide demand, President Roosevelt signed the Rural Electrification Act (REA) into law in 1936 (Barnes 2007). The Willow Springs area received electricity shortly after the REA was enacted.

In 1953, the Willow Springs International Raceway opened approximately 1.25 miles west of Willow Springs. At the time, there was little residential or commercial development around Willow Springs or the racetrack, save for a few farms that had installed irrigation equipment and a few small desert homesteaders. During the 1960s, a series of new grided streets were cut in the area around Willow Spring and the raceway, apparently in anticipation for increased residential growth. Ultimately, very few residences were built, the majority of which are centered in a small area in the Project area bound by Irone Avenue, Melody Lane, 145th Street W and 140th Street West and were constructed between 1960 and 1965. New residences built during this period were primarily single-story single-family vernacular residences on parcels of five acres or less. Although most of these residences are devoid of a particular recognizable architectural style, they reflect common materials and basic forms used throughout Southern California, giving many a distinct rural vernacular Californian appearance commonly identified in similar communities (UCSB 1952a, 1952b; HistoricAerials.com 1959, 1963; Kern County Recorder 1960).

#### \*B12. References:

Barnes, D.F.

2007. The Challenge of Rural Electrification: Strategies for Developing Countries. RFF Press, Washington D.C.

California Department of Transportation (Caltrans)

A Historical Context and Archaeological Research Design for Agricultural Properties in California. Division of Environmental Analysis, Sacramento, California.

Dunne, Kerry

"Boomtimes Again: Twentieth-Century Mining in the Mojave Desert," Primary Source Sets, Digital Public Library of 2016 America, Massachusetts. https://dp.la/primary-source-sets/boomtimes-again-twentieth-century-mining-in-the-mojavedesert, accessed April 2022.

Greene, Andry and Albert Knight

"P-15-000129 Supplement, Trinomial CA\_KER-129), California Landmark #130 Willow Springs," Western Mojave Survey 1992 Association, North Hollywood, California.

HistoricAerials.com

1959 Willow Springs, CA. Aerial imagery.

1963 Willow Springs, CA. Aerial imagery.

Kern County Recorder

1960 Tract No. 2355 [map]. Record of Survey Book 7, Page 191.

Office of Historic Preservation (OHP)

2021 "Willow Springs – Historical Landmark." California State Parks, Office of Historic Preservation. Available: https://ohp.parks.ca.gov/ListedResources/Detail/130. Accessed September 2021.

Tipton, Karla

1988 "Willow Springs: An Oasis in Antelope Valley" from Antelope Valley Press in The Gold Ledge. Available: https://www.karlatipton.com/portfolio/Antelope-Valley-Press-Willow-Springs-May-1988.pdf. Accessed September 2021.

University of Santa Barbara (UCSB) Library

1952a Flight ID ABL-1952, Frame 3K-89. October 12. 1952b Flight ID ABL-1952, Frame 4K-39. October 12.

State of California — The Resources Agency DEPARTMENT OF PARKS AND RECREATION		Primary # HRI#					
CONTIN	UATION SHEET		Trinomial				
Page 4 of 6	*Resource Name or # (Assigned by re	corder)	2860 W. 100th Street				
Recorded by:	Emma Keethler	Date:	April 23, 2022				
				☐ Continuation ☐Update			

#### California Register of Historical Resources Eligibility

The subject property at 2860 W. 100th Street (374-041-09) was evaluated for historical significance under California Register of Historical Resources (CRHR) Criteria 1-4.

Under Criterion 1, the subject property was evaluated for an association with significant historical events or broad patterns of history at the local, regional, state, or national level. The property lies within an unincorporated area of the Antelope Valley, a region of the Mojave Desert that has a rich history of American exploration, migration, and settlement unique to the California and the high desert region during the nineteenth and early twentieth centuries. According to the Kern County Assessor's Office records, the residence was constructed circa 1940, which is well past the period for settlement at the regional (Antelope Valley), state (California), or local level. PaleoWest also considered whether 2860 W. 100th Street may be significant for an association with the theme of Community Development of the Antelope Valley, 1918-1975 and the sub-theme of Rural Residential Development of the valley. Although the residence may date to the period of significance for the theme and sub-theme, the subject property is not a rare, unique, or exemplary example of a property associated with twentieth century community development and rural residential development of the Antelope Valley. It does provide a recognizable representation of broad patterns of residential development in the valley. Additionally, the property is within an unincorporated area of Kern County and the Antelope Valley that does not have a strong cohesive pattern of community history that would include the property's period of construction for which it might be considered historically significant. The property is near the communities of Willow Springs and Rosamond but lacks an immediate connection with the development of these communities. In summary, no direct associations between 2860 W, 100th Street and historically significant events or broad patterns of history at the local, region, state, or national level could be established. As such, the subject property is recommended not eligible under CRHR Criterion 1.

Research was conducted to determine if the subject property is significant under Criterion 2 for associations with the lives of historically important persons who have made contributions to local, state, or national history. No direct connection to historically important individuals could be identified through historical and archival research of 2860 W. 100th Street. Individuals found to be associated with the property through archival research include Patrick Ladd, Knollwood Inv Capital LLC, John Rehlkau, Ralph De Leon, Old Canal Financial. No information was uncovered to confirm these individuals or organizations resided at 9668 Rosamond Boulevard during its historic period and research did not suggest the identified individuals made important contributions to history. Historically important persons such as explorers Pedro Fages, Joseph Walker, and John C. Frémont are known to have traveled through the area and to have stopped at nearby Willow Springs, but these events happened well before the construction of the extant buildings on the subject property. Therefore, there is no direct correlation between known significant historical figures and the property. As 2860 W. 100th Street does not appear to be illustrative of the accomplishments of historically important persons within a local, state, or national historical context, the property is recommended not eligible under Criterion 2.

To evaluate the subject property under Criterion 3, PaleoWest considered whether it embodies distinctive characteristics of a type, period, or method of construction and whether it represents the work of a master architect or possesses high artistic value. The residence and ancillary buildings at 2860 W. 100th Street are vernacular renditions of the California Ranch stye which is very common to rural areas of Southern California. As an unadorned example of the California Ranch style, the residence does not embody enough of the distinctive characteristics of this style to be considered an exemplary or unique iteration of a California Ranch. While vernacular architecture can be considered historically significant, the residence at 2860 W. 100th Street is also not a distinctive, rare, or exemplary vernacular California Ranch which is a common type and style throughout rural areas of Southern California. The utilitarian ancillary outbuildings are typical wooden utilitarian buildings that do not embody a specific style, nor are they a rare, distinct, or excellent iteration of a rural farm building warranting historical significance for its architecture. It should also be noted that there appears to be a secondary residential structure located on this parcel, also a California Ranch style; however, there is no record of this secondary residential on the Kern County Property Appraiser records and it is not clearly visible from the right of way for assessment. PaleoWest also considered whether the subject property may be significant for an association with a master builder or architect; however, no record of a builder or architect was found through property and document search engines of the Kern County Tax Assessor's Office nor through archival research. In summary, the residence of the subject property is not a distinctive or rare example of a vernacular California Ranch residence in rural Southern California and the ancillary outbuildings are also not a unique or rare example of a rural utilitarian or farm building. Additionally, neither building clearly represents or a specific period or method of construction, nor are they associated with a significant master architect or builder. As such, 2860 W. 100th Street is recommended not eligible under Criterion 3.

The subject property is a common property type that is unlikely to provide vital information about history or prehistory that is not readily available through historical and archival research. As such, the property is recommended not eligible under CRHR Criterion 4.

The subject property is not within a designated or previously identified historic district. As a very sparsely developed and unincorporated area, the immediate vicinity of the property also lacks architectural cohesion and a defined shared historical narrative to be considered a historic district. Thus, 2860 W. 100th Street is not recommended eligible as a contributor to a CRHR-eligible or listed historic district.

State of California — The Resources Agency DEPARTMENT OF PARKS AND RECREATION **CONTINUATION SHEET** 

HRI#

**Trinomial** 

2860 W. 100th Street

Primary #

Page 5 of 6

\*Resource Name or # (Assigned by recorder) Recorded by: Emma Keethler

April 23, 2022

□ Continuation □ Update



Photo 2. Property overview facing east, gazebo and residence in foreground with ancillary building in background.




Photo 3. Ancillary structure situated south of the main residence, view facing east.

State of California — The Resources Agency DEPARTMENT OF PARKS AND RECREATION	Primary HRI
LOCATION MAP	Trinomial

Page 6 of 6**Scale:** 1:24,000 **Resource Name or #:** 374-041-09

Map Name: Little Buttes, Ca (1975) 7.5' USGS Quad.



State of California — The DEPARTMENT OF PARK	<u> </u>	Primary # HRI#	
<b>LOCATION MAP</b>		Trinomial	
Page 3 of	*Resource Name or # (Assi	gned by recorder)	
*Map Name:	*Scale:	*Date of Map:	

# PRIMARY RECORD

Primary # HRI # **Trinomial** 

**NRHP Status Code** 

	Other Listing Review Code		Re	viev	ver			Date		
Page 1 of 2	*Resourc	e Name	or #:	AP	N 358-	131-02	2			
P1. Other Identifier:										
*P2. Location:	or Publication 🛛 l	Unrestri	cted							
*a. County: Kern			and (P2	c, P26	e, and P2	2b or P2d	d. Attach a Location Map	as necessar	y.)	
*b. USGS 7.5' Quad Tylerho		1965	Т	9N	R	14W	NE 1/4 of SE o	f Sec	80	S.B.B.M.
c. Address Meoldy Lane			City	Ro	osamor	nd			Zip	93560
d. UTM: (give more than one for large	e and/or linear resources)	Zone	11N			3709	mE/	3860		mN;
e. Other Locational Data: (e.g. p	arcel#, directions to resou	urce, elevat	tion, etc.)	_	Parcel	is app	roximately 340 feet	east of 14	5 <sup>th</sup> Str	eet West
*P3a. Description: (Describe r	esource and its major	elements.	. Include	e des	ign, mat	terials,	condition, alterations, s	size, settin	g, and l	boundaries)
The subject property (APN 358-131-02) was identified through reconnaissance survey but was not accessible for intensive survey onsite or from the right-of-way due to safety hazards. The rectangular 3-acre property is bounded on the north Melody Lane (a dirt road also known as Avenue of the Stars) and to the south, west, and east by single-family properties. The property is accessible from the north via a dirt driveway. The eastern and western parcel boundaries are each lined with a row of trees forming privacy screens and windbreaks. The Kern County Tax Assessor lists one building on the property, a 1,342 square-foot square foot residence with one bedroom and one and a half bathrooms. The extant residence is approximately 2,500 square feet, including a large addition to the south façade of the building performed at an unknown date between 1989 and 2003 (historicaerials.com 1963, 1974, 1989, 2003, 2018). The alteration transformed the residence from an L-shaped plan to an irregular plan with a vaguely rectangular form. The residence is setback approximately 210 feet from the road. A rectangular ancillary building lies west of the residence. No address for the property could be identified. Additional details are indiscernible from the public right-of-way due to the setback and safety concerns during the survey.										
P3b. Resource Attributes: (L P4. Resources Present: ⊠ E P5a. Photograph or Drawing (F	Building   Structure	e Ob uildings, str	uctures, a	Site and ob	; D	istrict	☐ Element of Distri  P5b. Description of  Aerial view of subject	f <b>Photo:</b> (	view, da	•
		Avenue	Of The St	ars			Kern County GIS (20	020)		_
			A Cal			<b>,</b>	*P6. Date Construc	cted/Age	and S	Source:
		\$	N. S.	Ė				historic		
	10000000000000000000000000000000000000		363			-	Kern County Tax As	sessor		
	358-131-02						P7. Owner and Add Evelyn Baxter			
		A 3	1	3	100		14151 Brightstar Ave	enue, Ros	samon	d, CA 93560
358-131-01							<b>P8. Recorded by:</b> Lisa C. Demarais, M		iliation,	and address)
			4	358-	131-28	-	Evan Mills, M.A., RP	PA		
<b>多工作 数据 199</b>			210			_	PaleoWest, LLC.	4	04.0	1040
			ME.			<u>:</u>	517 S. Ivy Avenue, N	vionrovia,	CA 9	1016
8	8 4.			10		*F	9. Date Recorded:	April 2	27, 202	22
*P10. Survey Type: (Describe)	Reconnaissand	ce, CEQA	A comp	lianc	e					
P11. Report Citation: (Cite survey report and other sources, or enter "none.") 2022 PaleoWest, LLC. Historic Resources Evaluation Report, Addendum to: Cultural Resources Technical Report for the Hydrostor A-CAES Project, Kern County, California (2021). Prepared or Golder Associates.										
			Line							ture, and Object Rock Art Record
DDD 500A (4/05)		•						*D		

State of California — The Resources Agency
DEPARTMENT OF PARKS AND RECREATION
LOCATION MAP

Primary HRI Trinomial

Page 2 of 2**Resource Name or #:** 358-131-02

**Scale:** 1:24,000

