DOCKETED	
Docket Number:	23-IEPR-04
Project Title:	Accelerating Bulk Grid Connection
TN #:	249973
Document Title:	Presentation - Improving Bulk Grid Interconnection, Expansion, and Utilization
Description:	6.A Will Gorman, LBNL
Filer:	Raquel Kravitz
Organization:	Lawrence Berkeley National Lab (LBNL)
Submitter Role:	Public Agency
Submission Date:	5/3/2023 1:40:31 PM
Docketed Date:	5/3/2023





Improving Bulk Grid Interconnection, Expansion, and Utilization

Will Gorman

Research Scientist Electricity Markets and Policy Department


CEC Panel May 4th, 2023

The views and opinions of the authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof, or The Regents of the University of California.

Photo source: Licensed from Shutterstock




There has been a substantial increase in annual interconnection requests since 2013 (not just in CA); Over 2 TW of capacity active at end of 2022






BERKELEY LAB

Active capacity in grid interconnection queues (~2,000 GW) exceeds the installed capacity of the entire U.S. power plant fleet (~1,250 GW)




More than 95% of active capacity in interconnection queues is zero-carbon



BERKELEY LAP


Notes: (a) Hybrid storage in queues is estimated for some projects. (b) Total installed capacity from EIA-860, December 2022.

Only 21% of projects that applied for interconnection prior to 2018 have been built – 72% have been withdrawn (7% are still actively trying!)




One consequence of high withdrawal rates is the need to restudy the projects that remain in the queue, increasing uncertainty in cost outcomes and further elongating the process

Evidence of a Problem #1: Projects are taking longer to complete interconnection studies and connect to the grid – from 2 years in 2005 to 5 years in 2022



Source: Berkeley Lab, "Queued Up". 2023

Typical duration from IA to commercial operations date (COD) has increased modestly since 2007, except in CAISO where recently built solar projects took 4-6 years *after* securing an IA






Notes: (1) Data were only available for 737 projects across 5 ISO/RTOs and one utility (Southern Company), out of 3,846 total "operational" projects in the full dataset. (2) Not all data used in this analysis are publicly available.

6

Evidence of a Problem #2: Grid connection costs are increasing due largely to network upgrades, and are higher for wind, solar, and storage – driving project withdrawals



- Interconnection costs have grown across regions
- These trends are largely driven by network upgrade costs
- Wind, solar & storage interconnection costs are often higher than natural gas
- High & unpredictable interconnection costs likely lead to higher queue entry and more withdrawals



Mission: To enable a **simpler**, **faster**, and **fairer** interconnection of clean energy resources while enhancing the **reliability**, **resiliency**, and **security** of our **distribution** and **bulk-power electric grids**



Stakeholder Engagement

- Nation-wide engagement platform and collaborative exchanges
- Generate innovative solutions from discussion with utilities, grid operators, state/local governments, clean energy industry, non-profits



Data & Analytics

- Collect and analyze interconnection data to inform solutions development
- Increase transparency of interconnection process



Strategic Roadmap

- Create roadmap to inform interconnection process improvements
- Identify both near- and long-term opportunities and solutions



Technical Assistance

- Leverage DOE laboratory expertise to directly support stakeholders
- Focus on requests targeting key problems identified in roadmap



